

ADDENDUM NO. 1
TO THE PLANS AND SPECIFICATIONS FOR
Birchim Lane Overlay Project

May 17, 2019

This addendum is being issued to notify bidders that the following change has been made to the Project bid documents: The requirement that the paving material be stockpiled for a minimum of 2 weeks has been deleted. Please reference Section 39-1.02 on page 33 of the Birchim lane Overlay Project – Special Provisions

39-1.02 MATERIALS - Amend the Standard Specifications to read as follows: Cold Asphalt Concrete (CAC): Provide an asphalt concrete mixture composed of crushed stone or gravel and asphalt cement mixed in an approved plant. Ensure that the gradation and quality of the aggregate Birchim Lane Overlay Project- Special Provisions 32 and the grade and quality of asphalt binder conform to those normally used in the construction of highways by Federal or State agencies. The grade of asphalt cutback for this work shall be slow-cure, conforming to ASTM D 2026 [SC-3000]. The aggregate must comply with 1/2 inch grading. Asphalt Concrete shall be stored in a stockpile in a clean area to prevent contamination. ~~The completed mixture shall be stockpiled, unless otherwise directed by the Engineer, for a minimum of 2 weeks prior to placement on the road surface.~~

Receipt of this addendum should be acknowledged by **inserting the number and the date of receipt of Addendum on page 6** of the Bid Proposal Form. Failure to acknowledge receipt of this addendum on the Bid Proposal Form may be considered grounds for rejection of the bid.

If a bid is submitted, it should be with the understanding that the revisions contained herein are incorporated into the plans and specifications for the project and form a part of the contract to be executed for this work. It is requested that any contractors or subcontractors that may have been given plans or specifications for this project be advised of these contract revisions.

Inyo County
Department of Public Works



Mike Errante
Public Works Director

May 17, 2019

Date