

Appendix N

Water Supply Assessment



Water Supply Assessment

Bonanza Peak Energy Project

PREPARED FOR
Bonanza Peak Solar, LLC


DATE
06 April 2026

REFERENCE
0756349



Water Supply Assessment

Bonanza Peak Energy ProjectBonanza Peak Energy Project
0756349




Meg O'Donnell

Senior Consultant, Scientist




Jeff Brizendine

Principal Technical Consultant, Water Resources



Ian Todd

Partner



Chris Noddings

Project Manager

Environmental Resources Management, Inc.

1340 Treat Boulevard

Suite 550

Walnut Creek, CA 94597

T +1 925 946 0455

© Copyright 2026 by The ERM International Group Limited and/or its affiliates ('ERM'). All Rights Reserved.

No part of this work may be reproduced or transmitted in any form or by any means, without prior written permission of ERM.



CONTENTS

EXECUTIVE SUMMARY	ES-1
1. PROJECT DESCRIPTION	1
1.1 OVERVIEW	1
1.2 PROJECT LOCATION AND GROUNDWATER BASIN	1
1.3 PROJECT CONSTRUCTION AND OPERATIONS	1
1.3.1 Operation and Maintenance Building	2
1.3.2 Temporary Water Storage Ponds	2
1.4 WATER DEMAND	2
1.4.1 Construction Water Assumptions	5
1.4.2 Operational Water Assumptions	5
1.4.3 Decommissioning Water Assumptions	7
2. SENATE BILL 610 APPLICABILITY	7
2.1 IS THE PROPOSED PROJECT SUBJECT TO CALIFORNIA ENVIRONMENTAL QUALITY ACT?	7
2.2 IS THE PROPOSED PROJECT A “PROJECT” UNDER SENATE BILL 610?	7
2.2.1 Residential Development	7
2.2.2 Shopping Center or Business Establishment	8
2.2.3 Commercial Office Building	8
2.2.4 Hotel or Motel	8
2.2.5 Industrial, Manufacturing, or Processing Plant or Industrial Park	8
2.3 IS THERE A PUBLIC WATER SYSTEM THAT WILL SERVE THE PROPOSED PROJECT?	8
2.4 IS THERE A CURRENT URBAN WATER MANAGEMENT PLAN THAT ACCOUNTS FOR THE PROJECT DEMAND?	8
2.5 IS GROUNDWATER A COMPONENT OF THE SUPPLIES FOR THE PROJECT?	9
2.6 ARE THERE SUFFICIENT SUPPLIES TO SERVE THE PROJECT OVER THE NEXT TWENTY YEARS?	9
3. RENEWABLE ENERGY GENERAL PLAN AMENDMENT APPLICABILITY	9
3.1 WATER RESOURCES POLICIES	9
3.2 MITIGATION MEASURES HYD-2: CONDUCT SITE-SPECIFIC GROUNDWATER INVESTIGATIONS	10
4. WATER SUPPLY	11
4.1 SOUTH LAHONTAN HYDROLOGIC REGION	11
4.2 PAHRUMP VALLEY GROUNDWATER BASIN	12
4.2.1 Basin Characteristics: Pahrump Valley Groundwater Basin	12
4.2.2 Basin Management: Pahrump Valley Groundwater Basin	15
5. WATER SUPPLY RELIABILITY	15
6. CONCLUSIONS	16
7. REFERENCES	18

APPENDIX A	BAI 2005 PRELIMINARY INVESTIGATION	
APPENDIX B	AMEC 2006 STUDY	
APPENDIX C	CARDNO ENTRIX 2012 REPORT	
APPENDIX D	USGS 2020 REPORT	

LIST OF TABLES

TABLE 1	PROJECT WATER DEMAND SUMMARY	2
TABLE 2	PROJECT WATER DEMAND – OPERATIONS	6

LIST OF FIGURES

FIGURE 1	REGIONAL OVERVIEW	3
FIGURE 2	GROUNDWATER BASIN	4

ACRONYMS AND ABBREVIATIONS

Acronym	Description
AF	acre-feet
AFY	acre-feet per year
APT	aquifer performance tests
BAI	Broadbent and Associates, Inc.
bgs	below ground surface
CEQA	California Environmental Quality Act
DWR	Department of Water Resources
mg/L	milligrams per liter
O&M	operations and maintenance
Project	Bonanza Peak Energy Project
PV	photovoltaic
REGPA	Renewable Energy General Plan Amendment
SB	Senate Bill
SEDA	Solar Energy Development Area
USGS	United States Geological Survey
WSA	Water Supply Assessment

EXECUTIVE SUMMARY

Bonanza Peak Solar, LLC, a wholly owned subsidiary of 174 Power Global, LLC, which is a wholly owned subsidiary of Hanwha Energy USA Holdings Corp. (Applicant), requests a Renewable Energy Permit from Inyo County, California, to construct, own, operate, and maintain a utility scale solar photovoltaic (PV) energy generating facility on private lands. The requested term for the Renewable Energy Permit is 50 years.

The Bonanza Peak Energy Project (Project) will include solar PV arrays, access roads, and an approximately 0.5-mile generation tie-line corridor within unincorporated Inyo County, California. While the generation tie-line corridor will continue into Nevada to the northeast, only the portion of the Project within California is considered within this scope. The Project Area encompasses approximately 3,387 acres with a Developed Area of no greater than 2,400 acres, as dictated by the Inyo County Renewable Energy General Plan Amendment (REGPA). Groundwater usage and supply are assessed in this Water Supply Assessment (WSA). The hydrology and water quality characteristics of the Project, including stormwater analysis and the impacts of construction and regular operations on groundwater and surface water quality, are assessed in the *Hydrology and Water Quality Assessment* (Environmental Resources Management, Inc. [ERM] 2025).

California Senate Bill (SB) 610 and SB 221 were introduced in 2001 as an amendment to the California Water Code. These SBs require certain projects to complete an assessment on water reliability and availability in the area and report to the city or county decision makers before the project can be approved. The WSA identifies water reliability and water supply over a 20-year projection period. The purpose of such an assessment is to collaborate the planning of the project between local water availability and project water needs/proposed land use. The Project qualifies as a "Project" under Water Code Section 10912 due to its industrial use and footprint exceeding 40 acres. Accordingly, a WSA has been prepared in compliance with SB 610 requirements.

The construction phase is anticipated to take 18 months to complete and would require an estimated 723 acre-feet (AF) of water per year for a total of 1,085 AF during the construction period. The main activity in this phase that produces a water demand is dust suppression during ground-disturbing activities. During the 50-year operation phase, the Project is estimated to use about 0.014 AF of water per year for operations and maintenance. The decommissioning phase is anticipated to require water, with a significant portion of the demand driven by dust suppression during ground-disturbing activities. Exact volumes have not yet been determined and are not included within this WSA due to the uncertainty associated with, and the extended time frame before, decommissioning would occur (after the useful life of the Project).

The Project will source the water needed by extracting groundwater from the Pahrump Valley Groundwater Basin (Basin 6-028). The basin has had several studies previously completed based on research and to analyze previously proposed projects, producing a substantive amount of data regarding groundwater availability. Additionally, the basin is historically considered a very low priority, and thus has no current state-regulated pumping rates.

The California Environmental Quality Act (CEQA) environmental impact questions for hydrology and water quality were addressed for the Project in a separate report, and Inyo County REGPA



Environmental Impact Report Mitigation Measure HYD-2 and New Water Resources Policy WR-3.5 and WR-3.7 are included as part of this analysis. Following a review of water supply as well as water demand during construction and operations, it is ERM's opinion that the Project's impact to water supply, including down-watershed biological resources that include special-status plants, wildlife, and their habitats (including the Amargosa Watershed), will be less than significant. This conclusion is supported by:

- Based on a review of existing data from previously proposed projects and other sources, the proposed 723 AF per year (AFY) (1,085 AF total) for construction would be approximately 8.1 percent of lowest annual recharge data point (8,872 AFY) in the southern Pahrump Valley, where the proposed Project is located, modeled in the existing studies that were reviewed.
- The proposed 0.014 AFY for operations is 0.00016 percent of that same lowest annual recharge data point.
- The basin in question (i.e., Pahrump Valley Groundwater Basin) is considered very low priority by the state due to relatively limited use currently, and there are no current state regulations on pumping rates, indicating a low level of concern for water availability from the basin under current conditions.
- Consistent with Policy WR-3.5, measures will be incorporated to minimize water consumption as well as the use of potable water throughout all phases of the Project.
- Water rights adequate to support the annual water requirements for construction and operations are held within the land lease.
- Consistent with Policy WR-3.7, the Applicant will purchase and retire water rights along the same flow path for the water that will be used for the Project (both construction and maintenance) at a minimum of a 1 to 1 ratio.
- REGPA Mitigation Measure HYD-2 will be implemented.

Furthermore, it should be noted that by incorporating an analysis of the 1.5-year construction period along with the 50-year operational horizon (for a 51.5-year projection analysis), this WSA exceeds the statutory 20-year projection requirement, thereby offering a more rigorous and forward-looking evaluation.

1. PROJECT DESCRIPTION

1.1 OVERVIEW

Bonanza Peak Solar, LLC, a wholly owned subsidiary of 174 Power Global, LLC, which is a wholly owned subsidiary of Hanwha Energy USA Holdings Corp. (Applicant), requests a Renewable Energy Permit from Inyo County, California, to construct, own, operate, and maintain a utility scale solar photovoltaic (PV) energy generating facility on private lands. The requested term for the Renewable Energy Permit is 50 years.

The Bonanza Peak Energy Project (Project) would be located in the Charleston View Solar Energy Development Area (SEDA) in southeastern Inyo County, adjacent to the Nevada state line, just north of Old Spanish Trail Highway.

The solar generation facility, including the PV arrays, substation, and other electrical equipment, would be within a 3,382-acre Project Area with a Developed Area of no greater than 2,400 acres, as dictated by the Inyo County Renewable Energy General Plan Amendment (REGPA; Inyo County 2015). The Project has a planned net generating capacity of up to 500 megawatts alternating current.

The PV electrical generation facility includes installation of fencing, access roads, PV modules, single axis tracker racking, inverters, electrical distribution equipment, overhead and underground power lines, substation, interconnection switchyard, and an overhead transmission line racking system. While the generation tie-line corridor will continue into Nevada to the northeast, only the portion of the Project within California is considered within this scope.

Construction is anticipated to begin as early as January 2027. The Project may be built in one or more phases within an approximately 18-month construction period.

1.2 PROJECT LOCATION AND GROUNDWATER BASIN

Figure 1 provides a regional overview, illustrating the broader geographic context relevant to the study area. The Project is within the Pahrump Valley Groundwater Basin (Basin 6-028), which extends across the California-Nevada border (Figure 2).

1.3 PROJECT CONSTRUCTION AND OPERATIONS

Construction is anticipated to begin as early as January 2027. The Project may be built in one or more phases within an approximately 18-month construction period. Operations will begin immediately after construction is completed in 2028. The number of workers during each construction phase may vary, reaching up to 450 depending on the phase of construction.

The proposed Project will be remotely operated, therefore not requiring full-time employees onsite. Occasional deliveries and maintenance will be required throughout the operation of the proposed Project and is expected to be approximately 100 visits per year. The visits would primarily be related to maintenance of infrastructure, testing, repairs, and vegetation management (e.g., grass and weed trimming). After the useful life of the Project, which is anticipated to be 50 years, the panels would be disassembled from the mounting frames and

recycled according to current regulations at the time. The Project would be restored to its pre-development condition.

1.3.1 OPERATION AND MAINTENANCE BUILDING

An onsite operations and maintenance (O&M) building will provide plumbing and sanitation (including a septic system) for employee use. There will be no full-time employees on the property, but personnel will be there as needed. For a conservative estimate of the water demand, it is assumed that one person will be onsite for an equivalent of a normal 40-hour work week over 26 weeks (one half of a year).

1.3.2 TEMPORARY WATER STORAGE PONDS

It is anticipated that temporary water storage ponds would be needed during construction. Each construction water storage pond would be lined with a plastic and/or rubber liner and would have a slight pitch to the corner closest to the transfer pump. Their locations will be identified on a more detailed Project design. Water from existing wells in the Project area would be pumped into temporary construction water storage ponds with 723 acre-feet per year (AFY) needed for construction activities (1,085 acre-feet [AF] for the entire construction period). Any surface water discharge would be in compliance with water quality and sediment management regulations.


1.4 WATER DEMAND

The water demand for this Project includes both temporary demand in the construction phase, as well as long-term demand during O&M of the solar facility. The estimated construction water demand as provided by the Applicant is approximately 723 AF of water per year over the proposed 18-month construction period (1,085 AF total) and based on other projects of similar size and type in the area. The estimated construction water demand as provided by the Applicant is approximately 723 AF of water per year over the proposed 18-month construction period (1,085 AF total) and based on other projects of similar size and type in the area. The estimated annual water demand for O&M is up to 0.014 AFY, which would occur as a result of non-potable water use at the O&M building. Some conservative assumptions have been made for the Project's O&M water demand, and the estimated demand is consistent with other projects of this size and type. Table 1 summarizes the overall Project water demand.

TABLE 1 PROJECT WATER DEMAND SUMMARY

Phase	Construction Water Demand (AF)	Annual Water Demand (AFY)
Construction Demand (18 months)	1,085	
O&M Demand (Annually)		0.014

Note: The Renewable Energy Permit term is 50 years, plus construction at 1.5 years. Decommissioning is not considered in these water demand calculations.



Legend


- Gen-tie Corridor
- Developed Area
- Project Area

Figure 1
Bonanza Peak Energy Project
Regional Overview



M:\US\Projects\A-C\174 Power Global\Bonanza Peak\ArcGIS\Bonanza Peak.aprx\Groundwater Basins, REVISED: 12/01/2025, SCALE: 1:360,000 when printed at 8.5x11

Drawn By: Henrik.Westerkam



Legend

- Gen-tie Corridor
- Developed Area
- Project Area
- Groundwater Basin

Figure 2
Bonanza Peak Energy Project
Groundwater Basins



Due to the uncertainty associated with, and the extended time frame before, decommissioning would occur (after the useful life of the Project), decommissioning water is not considered within the water demand.

The following three subsections discuss each phase and the assumptions made in more detail.

1.4.1 CONSTRUCTION WATER ASSUMPTIONS

Construction of similar, utility-scale PV solar projects on more temperate desert sites (with temperatures below 100 degrees Fahrenheit) spanning up to 1 square mile have typically entailed the use of approximately 20 water truck fill-ups per day—each carrying 5,000 gallons (approximately 0.015 AF)—during summer periods. For such projects, total water use generally ranged between 0.1 and 0.2 AF per acre.

The proposed Project, however, is located in a hotter and drier climate and therefore will require additional water. To account for the increased water need, it is conservatively assumed that 0.28 to 0.30 AF will be required for each acre of ground-disturbing activity.

The proposed Project has an estimated water demand of 723 AFY (1,085 AF total over 18 months) for the construction phase includes, but is not limited to, the following:

- Up to 0.3 AF of water per acre of ground-disturbing activities
- A total of 2,452 acres of ground-disturbing activities requiring water to minimize dust generation, based on 2,400 acres of Developed Area plus 10 additional acres associated with the Zircon Street access road and the generation tie-line corridor

Water for construction will be sourced from one or more existing private groundwater wells within the Applicant's lease. Water rights adequate to support the annual water requirements for construction are within the land lease held by the Applicant. The identification of Project water supply wells will be determined upon well testing; all Project water supply wells will be reviewed and approved by the Inyo County Environmental Health Department and all appropriate permits will be obtained.

1.4.2 OPERATIONAL WATER ASSUMPTIONS

The main water demand components for the operational phase of the Project consist of fire suppression and water use associated with the O&M building. At the time of this report, the volume of water required for fire suppression has not yet been determined and thus has not been included in any calculations. Excluding fire suppression, the estimated total annual water use during operations is approximately 0.014 AFY over the life of the Project. Table 2 summarizes the total water demand during the operations phase.

Water for operations will be sourced from one or more existing private groundwater wells within the Applicant's lease. Water rights adequate to support the annual water requirements for operation are within the land lease held by the Applicant. The identification of Project water supply wells will be determined upon well testing; all Project water supply wells will be reviewed and approved by the Inyo County Environmental Health Department and all appropriate permits will be obtained.

TABLE 2 PROJECT WATER DEMAND – OPERATIONS

Operations and Maintenance	Yearly Water Demand (acre-feet per year)
O&M Building	0.014
Total	0.014

1.4.2.1 SOLAR PHOTOVOLTAIC PANEL WASHING

Routine panel washing is not anticipated, as occasional rainfall and wind are expected to adequately remove dust and debris under typical site conditions. As a result, there is no anticipated water needed for panel washing during the lifespan of the Project.

1.4.2.2 FIRE SUPPRESSION

In alignment with Policy PSU-8.1, which stipulates that adequate fire protection facilities must be established prior to the approval of development projects in unincorporated areas of Inyo County, we respectfully acknowledge this requirement and its significance in ensuring public safety. Per 2022 California Fire Code, a Hazard Mitigation Analysis will be prepared, and per CA SB 38 an Emergency Response Plan will be prepared, both of which will contain measures related to fire protection and suppression. At this stage of Project planning, we recognize that provisions for onsite water storage to support fire suppression may be necessary. However, the specific volume and configuration of such provisions will be contingent upon the design of the fire protection system and the applicable local regulatory standards. Given the typical scale of on-site fire protection infrastructure, commonly comprising multiple water storage tanks, we anticipate that the current water supply will be sufficient to meet fire protection requirements. This expectation is consistent with standard practices for similar developments in comparable settings.

1.4.2.3 OPERATIONS AND MAINTENANCE BUILDING

The O&M building's main source of water demand is the restroom facilities for the onsite personnel. There will be no full-time employees onsite, but personnel will be onsite as needed. During the operational phase, water usage will remain minimal and be limited to restroom facilities as well as occasional maintenance needs related to the electrical collection lines and switchyard. Sanitary facilities will be supported by a permanent aboveground or subsurface septic tank system. Drinking water will be supplied via a 5-gallon cooler dispenser in the O&M building. As mentioned in Section 1.3.1, it is conservatively assumed that one person will be onsite for the equivalent of half a year, which requires up to 25 gallons of water per person per shift for sanitary purposes (International Association of Plumbing and Mechanical Officials 2022). The O&M building is estimated to have a water demand of 0.014 AFY as seen in the calculation below:

$$(25 \text{ gallons per worker per shift}) \times (1 \text{ worker per day}) = 25 \text{ gallons per day}$$

$$(25 \text{ gallons per day}) \times (182 \text{ days per year}) = 4,550 \text{ gallons per year}$$

$$(4,550 \text{ gallons per year}) / (325,851 \text{ gallons per AF}) = 0.014 \text{ AFY}$$

1.4.3 DECOMMISSIONING WATER ASSUMPTIONS

A detailed, Project-specific decommissioning and reclamation plan will be developed and approved prior to the start of decommissioning activities. Water use during decommissioning will be primarily for dust suppression purposes. These measures will ensure that dust generated from equipment removal, site grading (if necessary), and soil disturbance is adequately controlled in accordance with applicable air quality and health standards. Exact volumes have not yet been determined and are not included within this Water Supply Assessment (WSA) due to the uncertainty associated with, and the extended time frame before, any decommissioning that would occur (after the useful life of the Project).

2. SENATE BILL 610 APPLICABILITY

SB 610 was amended to the California Water Code in 2002 and requires a detailed WSA to be completed for all projects that are subject to the California Environmental Quality Act (CEQA) and meet specific criteria. The purpose of the bill is to integrate the local water supply and quality with the future/proposed land use to minimize negative impacts on the groundwater supply and quality. Larger development projects must make certain that the local groundwater can handle the water demands of the proposed project or propose and analyze other options to reduce the impacts of water draw in the area.

The sections below address the questions posed by SB 610 to determine if it is subject to CEQA and in need of a WSA.

2.1 IS THE PROPOSED PROJECT SUBJECT TO CALIFORNIA ENVIRONMENTAL QUALITY ACT?

According to the California Water Code Section 10910, any city or county that determines the proposed project meets the definition of a “project”, as defined in Section 10912, is subject to CEQA and must complete a WSA. Any projects that require a discretionary permit by a public agency, are undertaken by a public agency, and/or are funded by public agencies are subject to CEQA. The Project requires a Conditional Use Permit from Inyo County and, therefore, is subject to CEQA.

2.2 IS THE PROPOSED PROJECT A “PROJECT” UNDER SENATE BILL 610?

A project, as defined by the California Water Code Section 10912 under SB 610, can fall under one of five different categories. Each category is defined so that it is equivalent to or greater in water consumption than 500 dwelling units. The five categories are defined below and their applicability to the Project is addressed. As noted below, the Project is included in one of the categories (Industrial) and is, therefore, defined as a Project under SB 610. This WSA has been completed for the proposed Project in compliance with the California Water Code.

2.2.1 RESIDENTIAL DEVELOPMENT

A proposed residential development project is defined in SB 610 to be 500 dwellings or larger. This Project is not a residential development.



2.2.2 SHOPPING CENTER OR BUSINESS ESTABLISHMENT

A proposed shopping center or business establishment project is defined by SB 610 to be an office building employing more than 1,000 persons or having more than 500,000 square feet of floor space. This Project is not a shopping center or business establishment.

2.2.3 COMMERCIAL OFFICE BUILDING

A proposed commercial office building project is defined by SB 610 to be an office building employing more than 1,000 persons or having more than 250,000 square feet of floor space. This Project is not a commercial office building.

2.2.4 HOTEL OR MOTEL

A proposed project that is a hotel or motel, or a combination of the two, is defined by SB 610 to be more than 500 rooms. This Project is not a hotel or motel, or a combination of the two.

2.2.5 INDUSTRIAL, MANUFACTURING, OR PROCESSING PLANT OR INDUSTRIAL PARK

A proposed industrial, manufacturing, processing plant, or industrial park project is defined by SB 610 to house more than 1,000 persons, occupy more than 40 acres of land, or have more than 650,000 square feet of floor area. The proposed Project is not a manufacturing, processing plant, or industrial park. However, the Project is an industrial facility that would occupy more than 40 acres of land; therefore, it is determined to be a Project under Water Code Section 10912. A WSA has been completed in compliance with the requirements of SB 610.

2.3 IS THERE A PUBLIC WATER SYSTEM THAT WILL SERVE THE PROPOSED PROJECT?

A “public water system” is defined in California Water Code Section 10912 as a system that has 3,000 or more service connections that provides piped water to the public for human consumption. The Project is located within the unincorporated community of Charleston View, which does not receive municipal water from the Inyo County Water Department. Instead, water services are managed by private utility companies. While Inyo County’s Water Service Districts database states that Charleston View falls within the Hidden Springs Water District, Hidden Springs Water District is a private water utility company that dissolved in 1983 (Inyo County Local Agency Formation Commission 2011). The Project does not have a public water system that will service it, as residents receive water from private wells; therefore, Project water supply would come from the Pahrump Valley Groundwater Basin.

2.4 IS THERE A CURRENT URBAN WATER MANAGEMENT PLAN THAT ACCOUNTS FOR THE PROJECT DEMAND?

According to California Water Code Sections 10610-10656 and 10608, urban water suppliers that provide over 3,000 AF of water annually or have more than 3,000 service connections are required to submit an Urban Water Management Plan. This plan details the reliability of the water source over a 20-year period under normal-year (non-drought), single-dry year (drought), and

multiple-dry year (extended drought) scenarios. The Urban Water Management Plan must be updated and approved by the Department of Water Resources (DWR) every 5 years.

The Project is not located in an area that has an existing Urban Water Management Plan; however, it falls within the boundaries of the Inyo-Mono Integrated Regional Water Management Region, which encompasses Inyo and Mono counties. Due to very low priority status of Pahrump Valley Groundwater Basin, it is not included in the Inyo-Mono Integrated Regional Water Management.

2.5 IS GROUNDWATER A COMPONENT OF THE SUPPLIES FOR THE PROJECT?

Groundwater is a component of the water supply related to the Project. Groundwater supplies will come from the Pahrump Valley Groundwater Basin via water rights granted through a land lease and are discussed in further detail in Sections 2.6 and 4.

2.6 ARE THERE SUFFICIENT SUPPLIES TO SERVE THE PROJECT OVER THE NEXT TWENTY YEARS?

The water supply options proposed for this Project are discussed in more detail in Section 4 of this WSA. As discussed in the following sections, based on the most current data for the water supply options, there are no indications that the Project would have an insufficient water supply during the construction, operations, and decommissioning phases through both the next 20 years (analysis period per regulations) and the anticipated lifetime of the Project (51.5 years). Section 6 provides a more in-depth discussion of the conclusions drawn from the WSA.

3. RENEWABLE ENERGY GENERAL PLAN AMENDMENT APPLICABILITY

The County of Inyo REGPA (Inyo County 2015), adopted in 2015, establishes policies for the siting and development of renewable energy projects, including guidelines that impact groundwater resources. Groundwater management is a critical consideration under the REGPA, as large-scale solar developments can affect local hydrology through water use for dust suppression, panel washing, and site preparation. The *Final Program Environmental Impact Report* associated with the REGPA (Inyo County 2015) evaluates these impacts, emphasizing the need for sustainable water use practices in designated SEDAs.

The following subsections address applicable policies and mitigation measures from the REGPA.

3.1 WATER RESOURCES POLICIES

Two new water resources policies from the REGPA (Inyo County 2015), and associated commentary, are provided as follows:

Policy WR-3.5: Sustainable Renewable Energy Solar Development. The County shall require renewable energy solar facility development to incorporate measures to minimize water consumption and use of potable water and encourage the use of reclaimed water and/or practices that do not require water during construction, the life of the facility, and during reclamation.

Measures will be incorporated to minimize water consumption and the use of potable water throughout all phases of the Project, including construction, operation, and reclamation. The use of reclaimed water and waterless practices will be prioritized wherever feasible to align with the County's sustainability objectives.

Policy WR-3.7: Charleston View. Projects proposed in Charleston View shall be water sustainable and shall require project applicants to purchase and retire water rights along the same flow path for the water that will be used for the project (construction and maintenance) at a minimum of a 1 to 1 ratio.

Water rights are held within the land lease, and an onsite well is available for Project use. The requirements of the Charleston View SEDA, including the 1:1 water rights retirement obligation, are fully recognized and will be met. Coordination with the County is ongoing to ensure alignment with all applicable water sustainability objectives.

3.2 MITIGATION MEASURES HYD-2: CONDUCT SITE-SPECIFIC GROUNDWATER INVESTIGATIONS

MM HYD-2 reads as follows:

Site-specific groundwater investigations will be completed for all proposed solar facility development projects within the individual SEDAs and the OVSA proposing to utilize groundwater resources, prior to final project design approval. These investigations will identify site-specific criteria related to considerations such as local aquifer volumes and hydrogeologic characteristics, current/proposed withdrawals, inflow/recharge capacity, and potential effects to local aquifer and well levels from proposed project withdrawals. All applicable results and recommendations from these investigations will be incorporated into the associated individual project design documents to address identified potential impacts to groundwater resources (per applicable regulatory standards), with all related requirements to be included in associated engineering/design drawings and construction contract specifications. A summary of the types of remedial measures typically associated with identified potential effects to groundwater resources is provided below. The remedial measures identified/recommended as part of the described site-specific groundwater investigations will take priority over the more general types of standard measures listed below.

Recommended mitigation measures for HYD-2 (Inyo County 2015), and associated commentary, are provided as follows:

Aquifer/Well drawdown: (1) monitor local aquifer and private/production well levels to verify the presence or absence of project-related effects during pre-construction, construction, and operation periods (based on methodology and monitoring schedule approved by Regional Water Quality Control Board [RWQCB] and County); (2) document background and pre-construction groundwater conditions and comparable project-related construction and operation trends, along with related factors such as precipitation levels and groundwater budgets; (3) prepare scaled maps depicting the associated site(s), existing and proposed monitoring well locations, relevant natural (e.g., springs and groundwater dependent vegetation) and other features (e.g., reservoirs) and pre-/post-

project groundwater contours, along with a description of cumulative water level changes; (4) restrict project related groundwater withdrawals to appropriate levels to avoid significant adverse effects to local aquifers/wells and/or other groundwater-dependent uses (e.g., vegetation, springs or other related surface water features), based on thresholds approved by the RWQCB and County; and (5) provide mitigation for affected wells or other uses/resources where applicable, potentially including well modifications (e.g., deepening pumps or wells), financial compensation, and compensatory mitigation for impacts to groundwater dependent surface water features and habitats.

Groundwater Recharge Capacity: (1) reduce the area of onsite impervious surface, if appropriate, through increased use of surfacing materials such as gravel, decomposed granite, or pervious pavement; and (2) use facilities such as retention/percolation basin and unlined drainage facilities to increase local infiltration and groundwater recharge. The County may employ water injection as a method of groundwater recharge as deemed appropriate on a case-by-case basis. This decision would be made during project-specific CEQA analysis for a given solar energy development proposal.

Additional groundwater pumping data has been identified as relevant to the analysis presented in this report. This data may contain information that could enhance the understanding of the existing groundwater sources or inform future water resource management decisions. At the time of this report finalization and publication, this dataset was not available for review and therefore was not incorporated. If there is interest in reviewing or integrating this supplementary dataset into future updates or analyses, it can be provided upon request once it is made available. Permit evaluators are encouraged to reach out if further detail or access to this data would support ongoing planning, regulatory review, or technical evaluation efforts.

Current site plans outline the PV structures that will be installed individually at existing grade, without the need for mass grading of the Developed Area. Maintaining the natural grading of the land preserves its permeability, allowing for effective water infiltration and reducing surface runoff. This process supports natural filtration, as soil and vegetation help absorb and filter stormwater runoff before it reaches groundwater reserves. By promoting groundwater recharge, the ungraded land contributes to the long-term sustainability of local water resources. During the final design phase, the Project will evaluate the remaining Groundwater Recharge Capacity measures outlined above and implement appropriate strategies as necessary.

4. WATER SUPPLY

The water supply for the proposed Project is expected to be sourced from one or more of the following options that meet the Project's water demand: onsite or offsite groundwater extracted from the Pahrump Valley Groundwater Basin. The following subsections discuss the potential water sources and the capacity of each source.

4.1 SOUTH LAHONTAN HYDROLOGIC REGION

The proposed Project is in the South Lahontan Hydrologic Region and overlies the Pahrump Valley Groundwater Basin specifically. The northern section of the South Lahontan Hydrologic Region drains toward the Great Basin and terminal lakes (Mono, Owens, Searles, and China Lakes). The

southern section flows toward the Mojave River Basin, Death Valley Basin, Antelope Valley, and El Mirage Dry Lake (DWR 2013). The water demands for the Project could be met by onsite or offsite groundwater wells in the Pahrump Valley Groundwater Basin.

4.2 PAHRUMP VALLEY GROUNDWATER BASIN

The Project overlies the Pahrump Valley Groundwater Basin (Basin 6-028) and is the expected location of the groundwater wells. The subbasin is bounded by the Nopah and Resting Spring Mountain Ranges to the west; the Spring Mountains located to the north and to the east separating Pahrump Valley from the Las Vegas Valley. The following subsections describe the subsurface characteristics and management of the Pahrump Valley Groundwater Basin (DWR 2024).

4.2.1 BASIN CHARACTERISTICS: PAHRUMP VALLEY GROUNDWATER BASIN

The Pahrump Valley Groundwater Basin spans about 93,100 acres or 145 square miles. The basin is bounded by non-water-bearing rocks of the Resting Springs and Nopah Mountain Ranges on the west and northwest and by the Kingston Mountain Range on the south.

Water Bearing Formations

Quaternary alluvium, which forms the primary water-bearing unit within the basin, includes unconsolidated younger alluvial fan material underlain by semi-consolidated, older alluvium. Maximum thickness of the alluvium is at least 800 feet (DWR 2004).

Recharge and Connectivity

Recharge of the Pahrump Valley Groundwater Basin is derived from the percolation of runoff through alluvial deposits at the base of the bordering mountains, and from the infiltration of precipitation that falls to the valley floor. Groundwater in the alluvium moves toward either Stewart Lake or into Nevada toward Pahrump Lake. Groundwater is confined near the margins of the dry lakes and along the base of the alluvial deposits originating from the Spring Mountains in the Nevada portion of the basin (DWR 2004). The California DWR estimates that the storage capacity is approximately 690,000 AF (DWR 2004). Other studies analyzed in the 2006 study by AMEC Earth & Environmental, Inc. (AMEC) showed storage estimates from 6,000,000 to 22,500,000 AF.

Aquifer Water Quality

The character of the groundwater varies from calcium-magnesium bicarbonate to magnesium-calcium bicarbonate. The quality of the groundwater is suitable for all beneficial uses. Total dissolved solids concentrations range from about 145 to 540 milligrams per liter (mg/L), with an average concentration of about 340 mg/L. Fluoride content ranges from 0.1 to 0.8 mg/L and averages about 0.4 mg/L. Boron content averages about 0.1 mg/L (DWR 2004).

Groundwater Level Trends

The state records of groundwater levels within the California portion of the basin intermittently span a period from 1952 through 1984. In the southern part of the basin, records show that groundwater levels declined by nearly 60 feet at one well during 1952 through 1975; although at

another well, water levels declined by 0.6 foot from 1956 through 1972. Along the southeast margin of the basin, water levels declined in one well by approximately 2.3 feet during 1959 through 1977, and by approximately 5.1 feet at another well during 1959 through 1984. Depth-to-water ranged from approximately 98 to 123 feet below the surface. Near Stewart Lake in the northern portion of the basin, water levels declined by approximately 2.7 feet at one location during 1960 through 1976, and by approximately 2.1 feet at another location during 1976 through 1984. Depth-to-water ranged between approximately 20 to 40 feet below the surface. Near Pahrump Lake in the central part of the basin, records indicate water levels remained relatively unchanged from 1959 through 1976; water levels remained approximately 55 feet below the surface (DWR 2004). It is assumed that the noted fluctuations were due to environmental factors such as rain, temperature, the natural movements of the basin groundwater, and undocumented water draws.

Prior Studies

Results of Preliminary Hydrogeologic Investigation and Test Well Construction at the Wiley Trust Property in Inyo County, California (Broadbent and Associates, Inc.[BAI] 2005)

BAI was contracted by Sagebrush Enterprises to conduct a water supply investigation of the Wiley Trust Property located in eastern Inyo County, California (Appendix A). The Property was located near the California-Nevada state line in the Pahrump Valley Groundwater Basin approximately. BAI was contracted to drill, install, develop, and test a groundwater production well on the property for a potential residential development.

Drilling activities reached a total depth of 1,514 feet below ground surface (bgs); however, the drilling conditions became too difficult, encountering very hard cemented layers. The lithologic log indicated the boring has a high percentage of fines from approximately 110 to 1,514 feet bgs. The geophysical logs indicated a high percentage of fines without significant areas of coarse material that would produce larger amounts of water. Based on the observations, BAI assumed if the boring was completed as a production well it would produce between 200 to 700 gallons per minute, which equates to approximately 322.5 to 1,129.2 AFY (BAI 2005).

Water Supply Potential for New Development in Inyo County, California; Recharge Assessment and Water Supply Potential for New Subdivision, Inyo County, California (AMEC Earth & Environmental, Inc. 2006)

Related to the above study by BAI (2005) and on the same property, AMEC completed an assessment for the water supply potential for the proposed Hidden Valley Ranch area. This report focused on the available water resources in the Pahrump Valley that could be used to support development of a municipal water supply.

This extensive study reviewed existing data as well as conducted original modelling on the basin's ability to provide a water supply via groundwater. Research within the report quoted previous studies showing an estimated recharge ranging from 17,650 to 26,000 AFY with an average of 22,312 AFY. Using these prior studies and empirical methods, the authors estimated an annual recharge of 10,486 AFY for the southern valley watershed, where this Project is located. The

authors then employed two variations of the Maxey-Eakin method to develop the net recharge infiltration model of the southern valley. The two variations produced estimates of 8,872 and 9,740 AFY of infiltration recharge. Combining with the earlier estimate from prior studies, this produces an average estimated infiltration recharge of approximately 9,700 AFY. It should be noted that this proposed project was not constructed and the analysis was published in “Draft” form (Appendix B).

Long-Term Aquifer Performance Test Report 2 (Cardno ENTRIX, 2012)

Cardno ENTRIX performed a long-term aquifer performance test (APT) designated as APT-2 in support of a prior similar test, APT-1, connected with the proposed Hidden Hills Solar Electric Generating System. This proposed solar thermal generating plant would have used mirrors to reflect and focus sunlight onto a boiler pod mounted on a tower. This reflected solar energy would have boiled the water inside the boiler pod to generate, generating steam to engage generating turbines, similar to boiler power generation using conventional fuel sources such as natural gas. This solar thermal system would have required a significantly higher volume of yearly operating water than the currently proposed photovoltaic system, though the exact amount anticipated was not stated.

According to the report, the test well was able to produce a constant rate of 45 gallons per minute (72.6 AFY) over a 14-day period and was considered to be sufficient to supply the reported required yearly volumes over the 28-year project construction and operating period (i.e., 25-year operating period and the 3-year construction period combined).

Additionally, the report (Appendix C) stated:

“Moreover, based upon these data and also consistent with the results of APT-1, off-site water level drawdowns are not expected to occur and therefore there won’t be project associated drawdown caused at either the nearby private domestic wells for at Stump Spring.

While it is not possible to predict future development in the Pahrump Valley, the historic water level data provided by Nye County indicates the water levels west of the State Line Fault system have been relatively stable over the last 20 years. Barring unforeseen changes in the pumping pattern in the valley, it is unlikely that regional pumping could substantially impact the aquifer at the project site or substantially change the prediction of this analysis”

Ultimately, however, the Hidden Hills Solar Electric Generating System was not constructed.

This proposed project was not constructed.

Groundwater Characterization and Effects of Pumping in the Death Valley Regional Groundwater Flow System, Nevada and California, with Special References to Devils Hole (United States Geological Survey [USGS] 2020)

This is a detailed study conducted by the USGS regarding, among other things, the effects of groundwater pumping in the Death Valley regional flow system. The Pahrump to Death Valley South basin is one of four groundwater basins in the system. One of the purposes of this study is



to estimate the potential future (2019-2100) effects of groundwater development on water levels and spring discharges (Appendix D).

Findings of significance relative to the proposed Project are:

1. Pahrump Valley is hydraulically connected to a 26-mile perennial reach of the Amargosa River between Shoshone, California, and Dumont Dunes (Malmberg, 1967; Harrill, 1986), which has been designated as a National Wild and Scenic River (Interagency Wild and Scenic Rivers Coordinating Council 2018).
2. The Pahrump Valley is not hydrologically connected to Devils Hole.
3. The Pahrump Valley is one of the principal areas noted in the modeled/simulated groundwater development analysis.
4. Groundwater levels declined in Pahrump Valley from 1960-1980 during the period of largest groundwater withdrawals, with recovery noted after 2004 based on reduced pumping.
5. Total recharge volume to the Pahrump to Death Valley South basin was just over 22,000 AFY.
6. Pre-development inter-basin migration of groundwater from Pahrump Valley to other basins totaled 7,920 AFY with 20,280 AFY entering the Pahrump Valley study area.

4.2.2 BASIN MANAGEMENT: PAHRUMP VALLEY GROUNDWATER BASIN

The Inyo County Water Department oversees groundwater extraction activities and requires permits and monitoring for withdrawals that may have a significant environmental impact or exceed sustainable yield thresholds, rather than based on a fixed volume. This ensures that extraction aligns with sustainable yield estimates and prevents over-extraction. The Pahrump Valley Groundwater Basin has historically been classified as a very low priority basin exempting it from the Sustainable Groundwater Management Act requirements. Currently, the basin does not have any legal regulations on the amount of groundwater that can be pumped per well with minimal management.

5. WATER SUPPLY RELIABILITY

This section assesses the reliability of the water source within the Pahrump Valley Groundwater Basin based on publicly available data.

The Pahrump Valley Groundwater Basin, within the South Lahontan Hydrologic Region, is the sole groundwater option for the Project. While much information is known about some of the groundwater basins in the South Lahontan region, comprehensive information that could provide a realistic water reliability budget to determine groundwater sustainability in the region is largely unknown (DWR 2013).

The Pahrump Valley Groundwater Basin is historically a very low priority basin and there are no current state restrictions on the pumping rates in this subbasin. In light of these conditions and the analyses in Section 4, the available evidence does not indicate:

1. that local water supplies would be unable to meet the Project's demands;
2. that the proposed water use would impose long-term negative impacts on the groundwater basin; or

3. that the proposed water use could cause significant down-watershed impacts to biological resources that include special-status plants, wildlife, and their habitats (including the Amargosa Watershed).

6. CONCLUSIONS

This WSA evaluated the water demands for two phases of the Project's lifetime: construction and operations. The construction phase is anticipated to take 18 months to complete and would require an estimated 723 AF of water per year, with a total of 1,085 AF during the 18-month construction period. The main activity in this phase that produces a water demand is dust suppression during ground-disturbing activities. While this is a water demand, some return flow and infiltration will occur. During the 50-year operation phase, the Project is estimated to use about 0.014 AF of water per year. The decommissioning phase is anticipated to require water, with a significant portion of the demand driven by dust suppression during ground-disturbing activities. Exact volumes have not yet been determined and are not included within this WSA due to the uncertainty associated with, and the extended time frame before, any decommissioning would occur (after the useful life of the Project).

While a project-specific study/analysis was not completed for the proposed Project, a substantive amount of analysis has previously occurred for research and to analyze previously proposed projects that were not constructed. These hydrology studies and literature from the California DWR, Inyo County, the USGS, and other contractors serve as the basis for the water supply and water reliability section of this report. Based on the information reviewed, the Pahrump Valley Groundwater Basin was found to be viable for water production for previous projects of much larger demands. Although groundwater testing has not been performed to confirm expectations, based on review of existing literature, it is ERM's opinion that the Pahrump Valley Basin has the capacity to produce enough water for the construction phase and operations phase without significant negative impacts to the basin or down-watershed biological resources that include special-status plants, wildlife, and their habitats (including the Amargosa Watershed). It should also be noted that, based on historic groundwater level trends discussed in Section 4, the area where the Project is located may have water shortages and/or see a decrease in the groundwater due to environmental stresses not associated with the Project. In addition to the above, the following also supports this opinion:

1. The basin in question (i.e., Pahrump Valley Groundwater Basin [Basin 6-028]) is considered very low-priority due to relatively limited use currently.
2. There are no current regulations on pumping rates that would indicate a concern in the basin.
3. Consistent with Policy WR-3.5 (discussed in Section 3.1), measures will be incorporated to minimize water consumption, as well as the use of potable water, throughout all phases of the project.
4. Three water rights are held within the land lease.
5. Consistent with Policy WR-3.7 (also discussed in Section 3.1), the Applicant will purchase and retire water rights along the same flow path for the water that will be used for the Project (both construction and maintenance) at a minimum of a 1 to 1 ratio.
6. REGPA Mitigation Measure HYD-2 will be implemented.



Per the previous discussions, this WSA has concluded that, based on currently available data, there are no indications that the water supply in the area will not be able to meet the Project water demands nor impose long-term negative impacts on the groundwater basin or on down-watershed biological resources. Based on that finding, it is ERM's opinion that the Project's impact to the basin's water supplies will be less than significant. Furthermore, it should be noted that by incorporating analysis of a combined 1.5-year construction period and a 50-year operational horizon for a 51.5-year analysis period, this WSA exceeds the statutory 20-year projection requirement, thereby offering a more rigorous and forward-looking evaluation.

7. REFERENCES

- AMEC Earth & Environmental, Inc. 2006. Water Supply Potential for New Development (Draft). Inyo County, California.
- Broadbent & Associates, Inc. (BAI). 2005. *Results of Preliminary Hydrogeologic Investigation and Test Well Construction at the Wiley Trust Property in Inyo County, California*.
- Cardno Entrix. 2012. Long-Term Aquifer Performance Test Report: Hidden Hills Solar Electric Generating System Site, Prepared for BrightSource Energy.
- Department of Water Resources (DWR). 2004. *Pahrump Valley groundwater basin description* (Bulletin 118). Accessed: 10 March 2025. Retrieved from https://water.ca.gov/-/media/DWR-Website/Web-Pages/Programs/Groundwater-Management/Bulletin-118/Files/2003-Basin-Descriptions/6_028_PahrumpValley.pdf.
- DWR. 2013. *South Lahontan hydrologic region groundwater update* (Chapter 11, Groundwater Update 2013). Accessed: 10 March 2025. Retrieved from https://water.ca.gov/-/media/DWR-Website/Web-Pages/Programs/Groundwater-Management/Bulletin-118/Files/Statewide-Reports/GWU2013_Ch11_SouthLahontan_Final.pdf.
- DWR. 2024. *Final Draft: Semi-annual groundwater conditions report* (October 2024). Accessed: 10 March 2025. Retrieved from https://s3.amazonaws.com/og-production-open-data-cnra-892364687672/resources/7dec17f2-6674-42bc-a743-24b4edce9261/finaldraft_oct_2024_semi_annual_groundwater_conditions_report.pdf.
- Environmental Resources Management, Inc. (ERM). 2025. *Hydrology and Water Quality Assessment for the Bonanza Peak Energy Project*.
- Harrill, J.R. 1986. Ground-water storage depletion in Pahrump Valley, Nevada-California, 1962–75: U.S. Geological Survey Water Supply Paper 2279, 53 p., <https://doi.org/10.3133/wsp2279>.
- Interagency Wild and Scenic Rivers Coordinating Council., 2018. National Wild and Scenic Rivers System—Amargosa River, California: National Wild and Scenic Rivers System web page, accessed January 2, 2018, at <http://www.rivers.gov/rivers/amargosa.php>.
- International Association of Plumbing and Mechanical Officials. 2022. *2022 California Plumbing Code (Title 24, Part 5)*. Accessed: 20 March 2025. Retrieved from: 2022 California Plumbing Code
- Inyo County Local Agency Formation Commission. 2011. *Dissolution No. 2011-01 – Hidden Springs Water District [Notice of Exemption]*. Inyo County Clerk/Recorder's Office. Accessed: 13 March 2025. Retrieved from: <https://www.inyocounty.us/icContent/environmentalDocuments/documents/11-015.pdf>
- Inyo County. 2015. *Renewable Energy General Plan Amendment (REGPA). Final Environmental Impact Report*. Inyo County Planning Department. Accessed: 12 March 2025. Retrieved from: <https://ceganet.opr.ca.gov/2014061039/3>

- Malmberg, G.T. 1967. Hydrology of the valley-fill and carbonate-rock reservoirs, Pahrump Valley, Nevada-California: U.S. Geological Survey Water Supply Paper 1832, 47 p., <https://doi.org/10.3133/wsp1832..>
- USGS. 2020. Groundwater characterization and effects of pumping in the Death Valley regional groundwater flow system, Nevada and California, with special reference to Devils Hole: U.S. Geological Survey Professional Paper 1863, 178 p., <https://doi.org/10.3133/pp1863>.



APPENDIX A BAI 2005 PRELIMINARY INVESTIGATION

**RESULTS OF PRELIMINARY
HYDROGEOLOGIC INVESTIGATION AND
TEST WELL CONSTRUCTION AT THE WILEY
TRUST PROPERTY IN INYO COUNTY,
CALIFORNIA**

**RESULTS OF PRELIMINARY
HYDROGEOLOGIC INVESTIGATION AND
TEST WELL CONSTRUCTION AT THE WILEY
TRUST PROPERTY IN INYO COUNTY,
CALIFORNIA**

Prepared for:
Sagebrush Enterprises
4730 South Fort Apache Rd. Suite 300
Las Vegas, Nevada

Prepared by
BROADBENT & ASSOCIATES, INC.
8 West Pacific Ave
Henderson, NV 89015
(702) 563-0600
www.broadbentinc.com

November 2005

Project No. 05-01-149-001

Broadbent & Associates, Inc.
8 West Pacific Avenue
Henderson, Nevada 89015
Voice (702) 563-0600
Fax (702) 563-0610



November 9, 2005

Project No. 05-01-149-001

Mr. Jim Rhodes
Sagebrush Enterprises
4730 South Fort Apache Rd., Suite 300
Las Vegas, Nevada

Re: CLIENT FINAL REPORT
Results of Preliminary Hydrogeologic Investigation of the Wiley Trust Property
in Pahrump Valley, California

Dear Mr. Rhodes:

Presented herein are the results of the Broadbent and Associates, Inc. (BAI) water supply investigation of the Wiley Trust Property in Pahrump Valley, California. Fieldwork on the site was carried out by Jonathan Bell, Project Geologist with BAI. Analysis of the data was performed by Lonnie Roy P.E., Mark Kazleskis P.G., and Bob Broadbent of BAI. Overall project management was by Lonnie Roy, P.E. The drilling contractor for the project was the Layne Christensen Company of Fontana, California.

INTRODUCTION

BAI was contracted by Sagebrush Enterprises (Sagebrush) to conduct a water supply investigation of the Wiley Trust Property (Property) located in eastern Inyo County California. The Property is located near the California - Nevada State Line in the Pahrump Valley water basin. BAI was contracted to drill, install, develop, and test a ground water production well on the Property for a potential residential development.

METHODS OF INVESTIGATION

Activities conducted during this investigation include the following:

- Reviewed reasonably obtainable maps and literature from the United States Geological Survey (USGS), The Nevada Division of Water Resources (NDWR), the California Department of Water Resources (CDWR), the Southern Nevada Water Authority (SNWA) and the Desert Research Institute (DRI). BAI also reviewed previous work conducted by a variety of contractors in the vicinity of the Property.
- Prepared a Well Specifications for Water Production Well document used by the drilling companies for bidding purposes;
- Coordinated with the selected drilling contractor and appropriate governmental agencies to obtain the appropriate permits required for the installation and testing of the production well. A copy of the well installation exemption permit is provided in Appendix A;
- Observed and reviewed the geophysical logs of the boring to an approximate depth of 1,347 feet bgs. The geophysical logs consisted of composite electric logs, temperature and conductivity logs, and a caliper log. Copies of the logs are provided in Appendix B;
- Coordinated and observed the drilling of one boring to an approximate depth of 1,514 feet below ground surface (bgs). Logged contractor samples collected during the drilling of the boring. A copy of the lithologic log field notes is provided in Appendix C.
- Designed a production well to be used as a test well at the Wiley property. A copy of the well design is provided in Appendix D.
- Consulted with Sagebrush on Production expectations of proposed well.

LOCAL GEOLOGY

Generally, the lithology encountered within the borings consisted of loosely consolidated silty sand and gravels from ground surface to a depth of approximately 110 feet below ground surface (bgs), from 110 feet bgs to approximately 1,050 feet bgs lithology consisted of 80% to 100% fine sand, silt and clay mixtures, from 1,050 to 1,417 feet bgs a slight decrease in 70% to 80% fine sand, silt, and clay mixture, the lithology at 1,417 consists of 55% fine to medium sand, 25% silt, 15% coarse sand, and 10% fine gravel and is a very hard layer approximately 6 to 12 inches thick. The lithology from

1,418 bgs to 1,470 feet bgs consisted of 45% fine to medium sand, 30% silt, 10% coarse sand, and 15% fine to coarse gravels, and 1,470 to the 1,514 feet bgs consist of 40% fine to medium sand, 35% silt, 15% fine to coarse gravels, and 5% clay.

FIELD ACTIVITIES

On May 23, 2005 BAI arrived on-site to observe the installation of a fifty foot conductor casing at the location selected for the installation of the Wiley water well. The conductor casing was installed approximately 320 feet west and 850 feet south of the north east corner of Section 11, T21N, R10E, San Bernardino B & M. On May 31, 2005 Layne Christensen began drilling an 18.5 inch boring through the conductor casing. Static groundwater was anticipated to be encountered between 140 bgs to 160 bgs. The boring was initially going to extend 1,000 feet bgs, but the lithology from approximately 110 feet bgs to 1,000 feet bgs was comprised of a high percentage fines (fine sand, silt, and clays). The high percentage of fines indicated a low water yield, so Mr. Jim Rhodes with Sagebrush Enterprises was contacted and he approved the drilling of an additional 350 feet of boring.

An additional 347 feet of boring was drilled, at which point drilling was stopped in order to run the geophysical logs. On June 6, 2005, COLOG Borehole Geophysics & Hydrophysics arrived on-site to run the geophysical logs (logs consisted of composite electric logs, temperature and conductivity logs, and a caliper log). A copy of the geophysical logs is attached in Appendix B.

On June 6, 2005 the lithologic logs and geophysical logs were reviewed by Lonnie Roy P.E., Robert Broadbent, Mark Kazelskis P.G., and Jonathan Bell with BAI. Both the lithologic and geophysical logs were reviewed and indicated that a large percentage of the boring lithology was comprised of fine sand, silt, and clay. The logs did not indicate significant areas with high percentages of coarse sands or gravel material. The logs did indicate a slight increase in the percentage of coarser sands and gravels (55% to 65%) from approximately 1,150 to 1,347 feet bgs, but a high percentage of silt was still present (30% to 45%). Based on these observations, and BAI's opinion that the well, if constructed at this depth, would not produce the required water, Mr. Jim Rhodes approved the drilling of an additional 300 feet of boring.

Drilling was continued after the geophysical log was completed and the boring was extended to a total depth of 1,514 feet bgs. At depth of approximately 1,417 bgs, the drilling conditions became more difficult and some very hard cemented layers were encountered. These hard cemented layers increased in frequency and at a depth of approximately 1,514 feet bgs the boring was terminated. The drilling conditions had become too difficult, and in order to continue drilling a new type of drill bit would need to be utilized.

DATA REDUCTION

On June 9, 2005 in a meeting between Lonnie Roy P.E., Robert Broadbent, Mark Kazelskis P.G., and Jonathan Bell with BAI, the boring lithology and the amount of water typically produced in this type of lithology was discussed. The lithologic log indicated the boring has a high percentage of fines from approximately 110 feet bgs to 1,514 feet bgs. The geophysical logs indicate a high percentage of fines without significant areas of coarse material that would produce larger amounts of water. Based on these observations BAI assumed if the boring was completed as a production well it would produce between 200gpm to 700 gpm. The amount of water necessary for this project according to Sage Brush Enterprises was between 1,000gpm and 2,000 gpm per well. In a discussion with Mr. Jim Rhodes this information was discussed and the decision was made to stop drilling and abandon the boring.

On June 14, 2005, the Layne Christensen Company completed the abandonment of the test well. The work was complete by a California licensed driller.


CLOSURE

This report has been prepared for the exclusive use of Sagebrush Enterprises. Limited data was used in the performance of this study. Findings presented in this report are based upon observations of field personnel and points of investigation and information supplied to BAI from Sagebrush Enterprises and G.C. Wallace, Inc.


No warranty, expressed or implied, is intended. It is possible that variations in conditions could exist beyond the points explored in this investigation. Also, changes in site conditions could occur at some time in the future due to variations in rainfall, temperature, regional water usage, or other factors.

Sincerely,

BROADBENT & ASSOCIATES, INC.




Mark E. Kazelskis, P.G.
Senior Geologist



Lonnie C. Roy, P.E.
Principal Engineer



Appendix A
Test Boring Location Map



Test Boring Location Map
Rhodes Study
Pahrump, Nevada

Drawing No. 1

Prepared by: SES Approved By: JB Date: 08/23/05

Project No. 05-01-149-001


Appendix B
Water Well Permit

Notice of Exemption - Inyo County *Amendment*

To: ☒ Office of Planning and Research
1400 Tenth Street, Room 121
Sacramento, CA 95814

☒ County Clerk
County of Inyo
P.O. Drawer F
Independence, CA 93526

From: (Public Agency): Inyo County Environmental Health Services Dept.
P.O. Box 427
Independence, CA 93526



Project Title: Pump Test, Domestic Water Well, Rhodes Holmes Development Proposal

Project Location - Specific Address: Charleston View, Section 11, T21N, R10E, San Bernardino B & M; Lat. 35° 56' 33.2217" N, Long. 115° 51' 50.77213" W.

Project Location - City: Charleston View

Project Location - County: Southeast portion of Inyo County, near California-Nevada state line.

Description of Nature, Purpose, and Beneficiaries of Project: Pump test to determine water availability for proposed subdivision and associated facilities and amenities.

Name of Public Agency Approving Project: Inyo County

Name of Person or Agency Carrying Out Project: Inyo County

Exempt Status: (check one)

- ☐ Ministerial (Sec. 21080(b)(1); 15268);
☒ Categorical (Sec. 21080(b)(9); 15301-15329);
☐ Declared Emergency (Sec. 21080(b)(3); 15269(a));
☐ Emergency Project (Sec. 21080(b)(4); 15269(b)(c));

Reasons why project is exempt: The project is new construction of limited small new facilities; installation of small, new equipment and facilities in small structures (drilling a domestic supply water well and conducting a pump test). Discharge water will be piped to an existing natural drainage, with no potential impact to the environment. Section 15303 of the CEQA Guidelines specifically exempts such projects (Class 3 Exemption).

Lead Agency

Contact Person: Marvin Moskowitz, Director, Environmental Health Services

Area Code/Telephone/Extension: 760-878-0264

If filed by applicant:

1. Attach certified document of exemption finding.
2. Has a Notice of Exemption been filed by the public agency approving the project?

☐ Yes ☐ No ☐

Signature: Marvin Moskowitz Date: 5/24/05 Title: Dir of EHS

Date received for filing at OPR:


Appendix C
Geophysical Logs


COLOG


BOREHOLE GEOPHYSICS & HYDROPHYSICS A DIVISION OF LAYNE CHRISTENSEN COMPANY


11001 Etiwanda Avenue, Fontana CA. 92337 Ph. (909) 390-2833 Fax (909) 390-6097


CO RHODES HOMES WELL WILEY SUPPLY WELL FLD RHODES HOMES CTY INYO STE CALIFORNIA FILING No	COMPANY RHODES HOMES						
	WELL ID WILEY SUPPLY WELL						
	FIELD RHODES HOMES						
	COUNTRY USA		STATE CALIFORNIA				
LOCATION		OTHER SERVICES					
N 35° 56' 26.2" W 115° 51' 54.2" 11 S 0602369 UTM 3977955		ELOG GLOG CALIPER					
SEC	TWP	RGE					
PERMANENT DATUM	GS	ELEVATION	K.B.				
LOG MEAS FROM	GS	ABOVE PERM. DATUM	D.F.				
DRILLING MEAS. FROM	GS		G.L.				
DATE	05 Jun 05	TYPE FLUID IN HOLE	WATER				
RUN No	1	SALINITY					
TYPE LOG	TEMP FLUID CONDUCTIVITY	DENSITY					
DEPTH-DRILLER	1347'	LEVEL					
DEPTH-LOGGER	1347'	MAX. REC. TEMP.					
BIT LOGGED INTERVAL	1347'						
TOP LOGGED INTERVAL	0'						
OPERATING RIG TIME							
RECORDED BY	D. WALKER						
WITNESSED BY	R. HACKER/J. BELL						
RUN		BOREHOLE RECORD		CASING RECORD			
NO.	BIT	FROM	TO	SIZE	WGT.	FROM	TO
1	26"	0'	50'	20"		0'	50'
2	18.5"	50'	1347'				













COLOG


BOREHOLE GEOPHYSICS & HYDROPHYSICS A DIVISION OF LAYNE CHRISTENSEN COMPANY


11001 Etiwanda Avenue, Fontana CA. 92337 Ph. (909) 390-2833 Fax (909) 390-6097


CO RHODES HOMES WELL WILEY SUPPLY WELL FLD RHODES HOMES CTY INYO STE CALIFORNIA FILING No	COMPANY RHODES HOMES						
	WELL ID WILEY SUPPLY WELL						
	FIELD RHODES HOMES						
	COUNTRY USA	STATE CALIFORNIA					
	LOCATION N 35° 56' 26.2" W 115° 51' 54.2" 11 S 0602369 UTM 3977955	OTHER SERVICES ELOG GLOG CALIPER					
	SEC	TWP	RGE				
PERMANENT DATUM	GS	ELEVATION					
LOG MEAS. FROM	GS	ABOVE PERM. DATUM					
DRILLING MEAS. FROM	GS	K.B.					
DATE	05 Jun 05	TYPE FLUID IN HOLE					
RUN No	2&3	WATER					
TYPE LOG	ELOG COMPOSITE	SALINITY					
DEPTH-DRILLER	1347'	DENSITY					
DEPTH-LOGGER	1347'	LEVEL					
BTM LOGGED INTERVAL	1347'	MAX. REC. TEMP.					
TOP LOGGED INTERVAL	0'						
OPERATING RIG TIME							
RECORDED BY	D. WALKER						
WITNESSED BY	R. HACKER/J. BELL						
RUN	BOREHOLE RECORD			CASING RECORD			
NO.	BIT	FROM	TO	SIZE	WGT.	FROM	TO
1	26"	0'	50'	20"		0'	50'
2	18.5"	50'	1347'				












COLOG


BOREHOLE GEOPHYSICS & HYDROPHYSIC


A DIVISION OF LAYNE CHRISTENSEN COMPANY


11001 Etiwanda Avenue, Fontana CA. 92337 Ph. (909) 390-2833 Fax (909) 390-6097

CO RHODES HOMES WELL WILEY SUPPLY WELL FLD RHODES HOMES CTY INYO STE CALIFORNIA FILING No	COMPANY RHODES HOMES		WELL ID WILEY SUPPLY WELL		
	FIELD RHODES HOMES		COUNTRY USA		
	STATE CALIFORNIA		LOCATION		
	N 35° 56' 26.2" W 115° 51' 54.2" 11 S 0602369 UTM 3977955		OTHER SERVICES ELOG GLOG TEMP FLUID COND		
SEC	TWP	RGE	PERMANENT DATUM GS		
ELEVATION			K.B.		
LOG MEAS. FROM GS			D.F.		
DRILLING MEAS. FROM GS			G.L.		
DATE	05 Jun 05	TYPE FLUID IN HOLE	WATER		
RUN No	4	SALINITY			
TYPE LOG	CALIPER	DENSITY			
DEPTH-DRILLER	1347'	LEVEL			
DEPTH-LOGGER	1347'	MAX. REC. TEMP.			
BTM LOGGED INTERVAL	1318'				
TOP LOGGED INTERVAL	0'				
OPERATING RIG TIME					
RECORDED BY	D. WALKER				
WITNESSED BY	R. HACKER/J. BELL				
RUN NO.	BOREHOLE RECORD			CASING RECORD	
NO.	BIT	FROM	TO	SIZE	WGT.
1	26"	0'	50'	20"	3'
2	18.5"	50'	1317'		









Appendix D
Lithologic Logs

Interval or Depth and Time	% of total sample: Size of distribution # Rock type % Color Roundness	% of total sample: Size of distribution # Rock type % Color Roundness
25'	Coarse Fraction - larger than coarse sand Yellowish ore Gravels 1-2 feet	Fine Fraction - coarse sand and finer Yellowish orange fine sand and silts 20% Yellowish fine sand & silts (60%) clay 10% other 10% (sand)
50		
50-60	Light Brown fine sands (30%) silts (40%) clay (5%) coarse sand (15%) sand is sub rounded to rounded and consist of silts (70%), limestone (20%) Qtz (5%), other (5%)	
60-70	Light Brown fine-coarse sand (80%), silts (10%) fine gravels (10%) sand & gravel consist of siltstone limestone (gray & red) (25%), quartz (5%) clasts are subrounded to rounded	70%
70-80	Light Brown fine sand (20%) silts (70%) clay (5%) med-coarse sands (5%)	
80-90	Light Brown silts (60%) fine sand (35%) clay (5%) med-coarse sand (2%) sand is siltstone & limestone	
90-100	Similar to 80-90	
100-110	Similar to 80-100	

Interval or Depth and Time	% of total sample: Size of distribution # Rock type % Color Roundness	% of total sample: Size of distribution # Rock type % Color Roundness
110-120	Coarse Fraction - larger than coarse sand light Brown silt 35% & fine sand (40%) clay (5%) med - coarse sands 10% sands are subround - round & are silt/sand stone (50%) limestone 35% volcanic (5%) Qtz 5%.	Fine Fraction - coarse sand and finer
*	118-133 Drillers added & 1 Bag of Driscine.	10 Bags of Bentonite
120-130	light Brown 40% fine sand 30% silt, 20% med to coarse sand (sands are subround to round, silt/sandstone 45% limestone, volcanic 5% other (etc etc.) 5%.	45
130-140	Similar to 120-130	
140-150	Similar to 120-130 clay	Slight increase in
150-160	light Brown silt 55% clay 35% fine sand 8% med - coarse sand 2% (subround to round) 60% limestone, 10% volcanic, 5% Qtz 5% other	
160-170		
170-180		
180-190	light Brown silt 50% clay 40% fine sand 8% med - coarse sand 2% (sub same as 150-160)	
190-200	Similar to 180-190	

Interval or Depth and Time	% of total sample: Size of distribution # Rock type % Color Roundness	% of total sample: Size of distribution # Rock type % Color Roundness
200-210	Coarse Fraction - larger than coarse sand light Brown silt 50% med-coarse sand 10% 80% limestone, 15% volcanic, 5% QZ.	Fine Fraction - coarse sand and finer fine sand 25% clay 15% sand sub round - rounded
210-220	light Brown med-coarse sand 50%, silts 25%, fine gravels 20%, coarse gravels (5%) clasts are subround to rounded 80% limestone, 10% volcanic 5% calcite 5% QZ.	
220-230	light Brown silt 50% med sand - fine sands 5% clast sub round - round 80% limestone 10% volcanic, calcite 5%, QZ 5%	Fine sand 40% clay 5%
230-240	Similar	
240-250	light Brown silt 60% med sands - fine gravels 5%	clay 25% fine sand 10%
250-260		
260-270	light Brown silt 50% med sand - fine gravel 5%	clay 40% fine sand 5%
270-280	light Brown clay 70% silt 20% fine sand 10%	
↓ 310-320		

Interval or Depth and Time	% of total sample: Size of distribution # Rock type % Color Roundness	% of total sample: Size of distribution # Rock type % Color Roundness
	Coarse Fraction - larger than coarse sand	Fine Fraction - coarse sand and finer
320-330	light Brown clay 50% silt 40% fine sand 10%	
330-340	light Brown clay 40% silt 35% fine sand 20% 50% med sand - fine gravel	
340-350	light Brown clay 45% silt 40% fine sand 15%	
350-360		
360-390	light Brown clay 85% silt 10% fine sand 5% med clay has med plasticity	
390-440	light Brown clay 80% silt 15% fine sand 5% med plasticity	
440-490	light Brown 85% clay 10% silt 5% fine sand medium plasticity	
490-550	slightly darker Brown 80% clay 15% silt 5% fine sand, slight decrease in plasticity low-med	
550-570	light Brown 80% clay 15% silt 5% fine sand med plasticity	
570-600	light Brown 75% clay 2% med silt 15% silt 8% fine sand sand - fine gravel slight plasticity	
600-730	light Brown 80% clay 15% silt 5% fine sand low plasticity	


Interval or Depth and Time	% of total sample: Size of distribution # Rock type % Color Roundness	% of total sample: Size of distribution # Rock type % Color Roundness
730-770	Coarse Fraction - larger than coarse sand light Brown clay 65% silt 25% fine sand 10% slight plasticity	Fine Fraction - coarse sand and finer
770-830	light Brown clay 60% silt 30% fine sand 10% slight plasticity	
830-890	light Brown silt 45% clay 35% fine sand 20% no plasticity	
*	* found some Hard cemented and pieces Approximately 2" in size. They consist of Cemented fine-med sand. (in the 830-840 sample)	
890-950	light Brown 70% silt 20% fine sand clay 10%	
*	* found some Hard cemented pieces. They also consist of fine-med sand. some evidence H ₂ O (ie cement of clasts, small void spaces)	
950-980	light Brown 65% silt 25% fine sand clay 10%	
980-1000	light Brown 60% silt 35% fine sand 5% clay	
1000-1050	light Brown fine sand 55% 35% silt 5% clay 5% med sand	
1050-1080	light Brown fine-med sand 50% 45% silt 5% clay	
1080-1130	light Brown fine-med sand 45% 45% silt 5% coarse sand 5% clay	

Interval or Depth and Time	% of total sample: Size of distribution # Rock type % Color Roundness	% of total sample: Size of distribution # Rock type % Color Roundness
1130-1160	Coarse Fraction - larger than coarse sand light Brown fine-med sand 45% silt 45% 10% coarse sand	Fine Fraction - coarse sand and finer
1160-1180	light Brown silt 45% fine-med sand 40% clay 10% coarse sand 5%	
1180-1200	light Brown silt 50% fine-med sand 35% coarse sand 10% clay 5%	
1200-1310	light Brown silt 40% fine-med sand 35% coarse sand 15% fine gravel 5% clay 5% clastic sub round to round.	
1310-1347	light Brown silt 30% fine-med sand 40% silt 30% coarse sand 15% fine gravel 10% clay 5%	
1400-1470	light Brown fine-med sand 55% silt 25% coarse sand 15% fine gravel 10% clasts are sub angular to rounded, coarsest of cemented silty sandstone 50%, limestone 30%, volcanic 20%	
1477'	*Very hard layer approx 6" thick	
1470-1470	light Brown fine-med sand 45% silt 30% coarse sand 10% fine gravel 10% coarse gravel 5% clay 5%	
1448-1458	*Very hard layer drilled said feels like Rx approx 10' thick	

Interval or Depth and Time	% of total sample: Size of distribution # Rock type % Color Roundness	% of total sample: Size of distribution # Rock type % Color Roundness
1470- 1514 TD	Coarse Fraction - larger than coarse sand Light Brown fine-med sand 40% silt 35% Coarse sand 10% fine gravels 10% coarse gravels 5% clay 5%	Fine Fraction - coarse sand and finer

Appendix E
Wiley Production Well Design

Plan View
Not to Scale



Drawing No. 1

Prepared by: JEH Approved by: JB Date: 4/14/05

Production Well Design Detail
Wiley Supply Well

Inyo County, California

Project No. 05-01-149



BAI

BROADBENT & ASSOCIATES, INC.
ENGINEERING, WATER RESOURCES & ENVIRONMENTAL

Draft
Pahrump Environmental Feasibility Report

Prepared for:
G.C. Wallace, Inc
1555 South Rainbow Boulevard
Las Vegas, Nevada 89146

Prepared by:
SWCA Environmental Consultants
2820 W. Charleston Boulevard, Suite 15
Las Vegas, NV 89102

June 2005

Table of Contents

Introduction.....	1
Biological Resources	1
Summary.....	1
Project Area Description.....	1
General Project Area Vegetation Description.....	1
Creosote-Bursage Scrub.....	2
Mojave Desert Mixed Scrub	2
Salt Desert Scrub.....	3
Developed Areas	3
Noxious Weeds	3
General Project Area Wildlife Description.....	4
Mammals.....	4
Birds.....	4
Reptiles and Amphibians	5
Summary of Federal Laws Affecting Biological Resources.....	6
Bald Eagle Protection Act, 16 U.S.C. Sec. 668, 668 note, 668a-668d.	6
Endangered Species Act, as amended, 16 U.S.C. 1531, et seq. Section 7 (16 U.S.C. 1536).	6
Migratory Bird Treaty Act of 1918 as amended, 16 U.S.C. 703-711, et seq.....	6
National Environmental Policy Act of 1969, 42 U.S.C. Sections 4321-4347.	6
Clean Water Act, 33 U.S.C. 1251 et. seq.....	7
Fish and Wildlife Coordination Act, as amended, 16 U.S.C. 661, et seq.....	7
North American Wetlands Conservation Act, 16 U.S.C.; 4401 et seq.....	7
Protection of Wetlands (Executive Order 11990).....	8
Nevada Special Status Species.....	8
Special Status Plants	8
Cacti and Yucca	9
Special Status Species.....	9
Desert Tortoise.....	9
Pahrump Valley buckwheat.....	10
Biological Recommendations for the Nevada Sites.....	11
California Threatened, Endangered and Sensitive Species.....	12
California Laws And Regulations.....	14
Biological Recommendations for the California Sites.....	14
Cultural Resources	14
Known Cultural Resources in the Proposed Project Area	15
Laws, Regulations, and Guidelines for Cultural Resources	16
Federal Laws, Regulations, and Guidelines.....	16
California Laws, Regulations, and Guidelines	17
Nevada Laws, Regulations, and Guidelines	19
Identification, Evaluation, and Mitigation Measures.....	19
To Identify Unknown Cultural Resources in the Project Area.....	19
Known Cultural Resources in the Project Area	20
Summary.....	21
Paleontological Resources	21

Contributors	21
References	22
Appendix A. Nevada Natural Heritage Program Database Search Results	1

INTRODUCTION

SWCA Environmental Consultants (SWCA) was contracted by G.C. Wallace to evaluate and identify potential environmental issues on approximately 2,000 acres of land in Clark and Nye Counties, Nevada, and Inyo County, California. The evaluation was accomplished by gathering data on threatened, endangered, and sensitive species that could potentially occur within the project areas, a preliminary review for potential jurisdictional waters, a cultural resources Class 1 literature search, a preliminary review for potential paleontological resources, and a field visit to identify potential environmental issues.

BIOLOGICAL RESOURCES

SUMMARY

This section focuses on the biological resources that could potentially occur in the project area, and includes:

- Project Area Description
 - Vegetation
 - Wildlife
- Federal Laws And Regulations
- Nevada Laws And Regulations
- California Laws And Regulations
- Nevada Threatened, Endangered, and Sensitive Species
- California Threatened, Endangered, and Sensitive Species
- Clean Water Act and Potential Jurisdictional Waters

PROJECT AREA DESCRIPTION

The project area consists of several parcels located in Nye and Clark Counties, Nevada and Inyo County, California. The parcels are located in the following Townships, Ranges and Sections:

- Township 22 South, Range 54 East, Sections: 24, 25, 26, and 27
- Township 23 South, Range 55 East, Sections: 6 and 7
- Township 21 South, Range 10 East, Sections: 10, and 11

Highway 160 is located northeast of the project area, and all parcels can be accessed by traveling southwest on the Old Spanish Trail Highway to each parcel's appropriate access road. The Hidden Hills Landing Strip is located in several of the Nye County parcels, and an unnamed landing strip is located in the Clark County parcels. Both landing strips are abandoned and no longer in use. SWCA biologists visited the project area on June 1, 2005. At the time of the field visit, there was water flowing in Stump Spring, located southeast of the Clark County site. The town of Pahrump is northwest, the Spring Mountains are northeast, and the Nopah Range is southwest of the project area.

GENERAL PROJECT AREA VEGETATION DESCRIPTION

The project area is located within the Mojave Desert region. Low, widely spaced shrubs dominate the vegetation. The species composition of the Mojave Desert has common

elements with the Great Basin to the north, and many succulent species common to the Sonoran Desert to the south and east. The most widely distributed plant, the creosote bush (*Larrea tridentata*), covers extensive areas in nearly pure stands, and is often closely associated with white bursage (*Ambrosia dumosa*). Several distinct communities exist within the project area, including:

- Creosote-Bursage Scrub
- Mojave Desert Mixed Scrub
- Salt Desert Scrub
- Developed Areas
- Noxious Weeds

CREOSOTE-BURSAGE SCRUB

The most extensive natural vegetation community in the project area and surrounding region consists of creosote-bursage scrub. This community is principally dominated by creosote bush, with white bursage as a common co-dominant. It occurs on alluvial slopes, valley floors, and mountain slopes below 4,000 feet (1,220 meters) in elevation. This community is usually found on well-drained soils, often on bajadas and low hills, and is conspicuously absent around playas because of high salinity (Wallace and Romney 1972), and/or dense fine-textured basin soils low in oxygen (Lunt et al. 1973). Areas without dense concentrations of this community are steep and rocky slopes, dry washes, saltbush flats, and dry lakebeds.

Primary associated shrub species include blackbrush (*Coleogyne ramosissima*), Nevada tea (*Ephedra nevadensis*), indigo bush (*Psoralea fremontii*), shadscale (*Atriplex confertifolia*), hopsage (*Grayia spinosa*), spiny menodora (*Menodora spinescens*), desert thorn (*Lycium* spp.), ratany (*Krameria parvifolia*), honey mesquite (*Prosopis glandulosa*), and brittlebush (*Encelia farinosa*). Other associated species include Joshua tree (*Yucca brevifolia*), Mojave yucca (*Yucca schottigera*), prickly pear (*Opuntia engelmannii*), Schockley's goldenhead (*Acamptopappus schockleyi*), and turpentine-broom (*Thamnosma montana*).

MOJAVE DESERT MIXED SCRUB

The Mojave Desert mixed scrub community occurs on the midslopes of the bajadas, generally below the blackbrush scrub community and above the creosote-bursage scrub community. The typical elevation range is 2,000–5,000 feet (610–1,524 meters). The sites where this community occurs typically have very shallow, overly drained, often rolling to steep soils, usually derived from granitic parent materials. These sites have extremely low water holding capacity, mild alkalinity, and low salinity.

The Mojave mixed desert scrub community is a heterogeneous assemblage of shrubs that also occur in other nearby communities. The lack of a dominant shrub species makes it difficult to clearly categorize this scrub type into the more common communities. It is typically considered a scrub community comprised of a highly variable mixture of shrubs with several species sharing dominance. Although the dominant species in this community varies from place to place, it is usually characterized by the occurrence of creosote bush in association with several possible species, including white bursage, indigo bush, desert thorn, shadscale, hopsage, ratany and Nevada tea. Primary associated

shrub species include blackbrush, brittlebrush, bebbia (*Bebbia juncea*), allscale (*Atriplex polycarpa*) and desert holly (*Atriplex hymenelytra*). Other associated species include Joshua tree, Mojave yucca, cacti (*Echinocereus* spp.) and teddybear cholla (*Opuntia biglovii*).

SALT DESERT SCRUB

The salt desert scrub vegetation community is associated with moderately alkaline soils toxic enough to inhibit most desert shrubs that occur in the creosote-bursage scrub. Typically, one strongly dominant species of saltbush is found in association with several additional species in a particular area (possibly including other species of saltbush). This community is often composed of a nearly uniform stand of shrubs about 3 feet (1 meter) tall forming a more complete cover than the creosote-bursage scrub community.

The salt desert scrub community, also commonly referred to as saltbush or shadscale scrub, is characterized by the dominance of one or more of the following species: shadscale, Torrey saltbush (*Atriplex torreyi*), fourwing saltbush (*A. canescens*), desert holly, Bailey's greasewood (*Sarcobatus baileyi*), desert thorn, winterfat (*Ceratoides lanata*), budsage (*Artemisia spinescens*), Nevada tea, horsebrush (*Tetradymia canescens*) and snakeweed. Primary associated shrub species include greasewood (*Sarcobatus vermiculatus*), sagebrush (*Artemisia* spp.), blackbrush, iodine bush (*Allenrolfea occidentalis*) and creosote bush.

DEVELOPED AREAS

The ground surface in developed/urban areas are generally paved with asphalt and concrete, or overbuilt with structures that generally do not support vegetation. These areas can be broadly defined as anthropogenic (man-made) plant communities that have replaced many of the native, natural plant communities found within the project area. Plants that grow in these areas include many species of ornamental trees and shrubs planted as landscaping around buildings and other developed areas, turf grass associated with private residences, and non-native annual and ruderal grassland species associated with disturbed or cleared areas. The developed portions within the project area consist of abandoned home sites and landing strips. Noxious weeds have invaded most of these areas.

NOXIOUS WEEDS

Noxious weeds, as defined by the Nevada Revised Statutes (NRS), are "any species of plant which is, or is likely to be, detrimental or destructive and difficult to control or eradicate" (NRS 1999). They out-compete native vegetation and can spread quickly in a short time span. Many noxious weeds can be found dominating the areas along Nevada's borders (BLM 1999). These weeds tend to thrive in areas with 8 to 12 inches (20 to 30 centimeters) of precipitation and have the potential to expand their range into Nevada if they are not controlled or eradicated.

The following noxious weeds are found in southern Nevada: camelthorn (*Alhagi maurorum*), Russian knapweed (*Acroptilon repens*), yellow starthistle (*Centaurea solstitialis*), perennial pepperweed (tall whitetop) (*Lepidium latifolium*), cheatgrass (*Bromus tectorum*), saltcedar and puncturevine (*Tribulus terrestris*) (BLM 2000).

Camelthorn is a common weed along streams and ditches. Puncturevine is ubiquitous, but is most common on farms and rangelands. Yellow starthistle is common along roads and waste areas, but it can also be found growing on a variety of soil types. Saltcedar infests riparian areas, often in dense thickets that can out-compete and replace native species in riparian areas. Perennial pepperweed can be found in wet areas, ditches, along roads, on croplands and in waste areas (UDOT 2001). Russian knapweed is not limited to specific habitat types, but it is typically found in disturbed areas and tends to avoid healthy, natural habitats (Carpenter and Murray 1998).

GENERAL PROJECT AREA WILDLIFE DESCRIPTION

MAMMALS

Most mammals in the Project Area and surrounding region are nocturnal, but occasionally a few may be seen during the day. Small mammals that could occur in the project area include the black-tailed jackrabbit (*Lepus californicus*), desert cottontail (*Sylvilagus audubonii*), desert woodrat (*Neotoma lepida*), long-tailed pocket mouse (*Chaetodipus formosus*), desert pocket mouse (*Chaetodipus penicillatus*), little pocket mouse (*Perognathus longimembris*), cactus mouse (*Peromyscus eremicus*), Merriam's kangaroo rat (*Dipodomys merriami*), house mouse (*Mus musculus*) and white-tailed antelope squirrel (*Ammospermophilus leucurus*). Larger mammal species may include the grey fox (*Urocyon cinereoargenteus*), desert kit fox (*Vulpes velox*), coyote (*Canis latrans*), bobcat (*Lynx rufus*), striped skunk (*Mephitis mephitis*), and spotted skunk (*Spilogale gracilis*).

Although no information is available specifically for bats, a number of bat species have the potential to occur within or near the project area. Mines and natural caves, as well as crevices associated with buildings, bridges and trees located on and near the project area provide potential roosting habitat for bats. The Yuma myotis (*Myotis yumanensis*), California myotis (*M. californicus*), western pipistrelle (*Pipistrellus hesperus*), palid bat (*Artrozous pallidus*) and little brown bat (*Myotis lucifugus*) are the species most likely to inhabit the project area and the surrounding region.

BIRDS

A checklist of birds for Clark County confirms that several hundred species have been observed near the project area and/or in the surrounding region either as residents or as migrants/transients (NDOW 2005). Most bird species that occur in the project area and surrounding region are associated with either riparian-wetland or creosote-bursage scrub habitat. Within the riparian habitat type, common bird species that are typically found in the winter include the yellow-rumped warbler (*Dendroica coronata*), verdin (*Auriparus flaviceps*), Abert's towhee (*Pipilo aberti*), black phoebe (*Sayornis nigricans*), black-tailed gnatcatcher (*Polioptila melanura*), marsh wren (*Cistothorus palustris*) and phainopepla (*Phainopepla nitens*). In the spring, common riparian bird species include the red-winged blackbird (*Agelaius phoeniceus*), brown-headed cowbird (*Molothrus ater*), cliff swallow (*Hirundo rustica*), morning dove (*Zenaida macroura*), verdin, common yellowthroat (*Geothlypis trichas*) and Abert's towhee.

Common bird species that are associated with creosote-bursage scrub habitat include the greater roadrunner (*Geococcyx californianus*), horned lark (*Eremophila alpestris*), scrub

jay (*Aphelocoma coerulescens*), common raven (*Corvus corax*), black-throated sparrow (*Amphispiza bilineata*) and sage sparrow (*Amphispiza belli*). Game birds that utilize this habitat type include mourning dove (*Zenaida macroura*) and Gambel's quail (*Callipepla gambelii*).

While the project area itself does not appear to contain open water or riparian areas the agricultural fields and the open water in the nearby town of Pahrump may attract the bird species associated with these areas.

Birds associated with permanent sources of open water include the yellow-headed blackbird (*Xanthocephalus xanthocephalus*), black-crowned night heron (*Nycticorax nycticorax*) and green heron (*Butorides striatus*). Seasonal migratory birds use both permanent and temporary bodies of water for foraging and resting. These birds include a number of waterfowl species such as the ruddy duck (*Oxyura jamaicensis*), northern mallard (*Anas platyrhynchos*), northern pintail (*Anas acuta*), cinnamon teal (*Anas cyanoptera*), American coot (*Fulica americana*) and Canada goose (*Branta canadensis*).

Numerous birds could occur as winter or summer residents or migrants within the project area for brief periods in the spring and fall. Some common species include the yellow-rumped warbler (*Dendroica coronata*), Hutton's vireo (*Vireo huttoni*), cliff swallow (*Hirundo pyrrhonata*), ruby-crowned kinglet (*Regulus calendula*) and white-crowned sparrow (*Zonotrichia leucophrys*).

Red-tailed hawks (*Buteo jamaicensis*), northern harriers (*Circus cyaneus*), golden eagles (*Aquila chrysaetos*) and prairie falcons (*Falco mexicanus*) are some of the raptors that may occur within the project area. Many raptor species use large trees, cliff faces and rocky ledges as sites to roost or nest. Owl species that may occur in the project area include the western burrowing owl (*Athene cunicularia*), great-horned owl (*Bubo virginianus*) and barn owl (*Tyto alba*).

REPTILES AND AMPHIBIANS

Reptiles are especially adapted to drought conditions and extreme temperatures and are therefore well represented in the project area and surrounding region. Many diurnal lizards are widespread, while others are habitat specialists. Widespread species include the side-blotched lizard (*Uta stansburiana*), desert iguana (*Dipsosaurus dorsalis*), Great Basin fence lizard (*Sceloporus occidentalis biserialis*), desert horned lizard (*Phrynosoma platyrhinos*), western whiptail lizard (*Cnemidophorus tigris*) and western-banded gecko (*Coleonyx variegates*). Other lizard species that are widespread but less abundant include the zebra-tailed lizard (*Callisaurus draconoides*), desert spiny lizard (*Sceloporus magister*) and long-nosed leopard lizard (*Gambelia wislizenii*). Habitat specialists include the collared lizard (*Crotaphytis insularis*), chuckwalla (*Sauromalus obesus*), long-tailed brush lizard (*Urosaurus graciosus*) and common (desert) night lizard (*Xantusia vigilis*).

The desert tortoise (*Gopherus agassizii*) may occur in varying densities in undeveloped areas throughout the project area. This species is listed as threatened by the U. S. Fish and Wildlife Service (FWS) and requires special management considerations. Detailed information on this species is presented in the Special Status Species section.

Representative snake species could include the coachwhip (*Masticophis flagellum*), Great Basin gopher snake (*Pituophis melanoleucus deserticola*), western patch-nosed snake (*Salvadora hexalepis*), glossy snake (*Arizona elegans*), red racer (*Masticophis flagellum piceus*) and the Mojave green rattlesnake (*Crotalus scutulatus*). Unlike lizards, most of which are primarily diurnal, most snake species in the project area are nocturnal.

Amphibians that may occur in the project area include Woodhouse's toad (*Bufo woodhousei*), southwestern toad (*Bufo microscaphus*), Great Plains toad (*Bufo cognates*), Pacific treefrog (*Hyla regilla*) and American bullfrog (*Rana catesbeiana*). The American bullfrog is a problematic, introduced species in the Southwest that feeds on native wildlife, including other amphibians, small reptiles and fish.

SUMMARY OF FEDERAL LAWS AFFECTING BIOLOGICAL RESOURCES

BALD EAGLE PROTECTION ACT, 16 U.S.C. SEC. 668, 668 NOTE, 668A-668D.

This Act prohibits wantonly possessing, selling, transporting, or trading of a bald or golden eagle or eagle part, alive or dead.

ENDANGERED SPECIES ACT, AS AMENDED, 16 U.S.C. 1531, ET SEQ. SECTION 7 (16 U.S.C. 1536).

Section 7 (16 U.S.C. 1536) states that all Federal departments and agencies shall, in consultation with and with the assistance of the Secretary of the Interior, insure that any actions authorized, funded, or carried out by them do not jeopardize the continued existence of any threatened or endangered species, or result in the destruction or adverse modification of habitat of such species which is determined by the Secretary to be critical.

MIGRATORY BIRD TREATY ACT OF 1918 AS AMENDED, 16 U.S.C. 703-711, ET SEQ.

Except as allowed by implementing regulations, this Act makes it unlawful to pursue, hunt, kill, capture, sale, purchase, ship, transport, carry, export any migratory bird, or any part, nest or egg of any such bird.

NATIONAL ENVIRONMENTAL POLICY ACT OF 1969, 42 U.S.C. SECTIONS 4321-4347.

It is a continuing policy of the Federal Government, in cooperation with State and local governments, and other public and private organizations to use all practicable means and measures to create and maintain conditions under which man and nature can exist in productive harmony, and fulfill the social, economic, and other requirements of present and future generations of Americans. Provisions must be made to ensure that environmental information is available to public officials and citizens before decisions are made and before actions are taken.

Note: While the project area does not appear to contain wetlands, jurisdictional waters may be present. If the sites are to be developed, SWCA recommends that surveys specifically for wetlands and or jurisdictional waters be done. If those surveys reveal wetlands or jurisdictional waters the following laws could be applicable.

CLEAN WATER ACT, 33 U.S.C. 1251 ET. SEQ.

The objective of this Act is to restore and maintain the chemical, physical and biological integrity of the Nation's waters (33 U.S.C. 1251). Section 404 requires authorization to place dredged or fill material into water bodies or wetlands. Placement of fill materials within jurisdictional waters of the U.S. requires authorization by the U.S. Army Corps of Engineers (USACE). Several types of USACE permits are available to authorize the placement of fill materials into jurisdictional waters including wetlands, depending upon the type of project and amount of potential disturbance. The limit of the USACE's jurisdiction on a stream channel is defined by the width of the channel at its Ordinary High Water Mark (OHWM), which is referred to as the jurisdictional width. The OHWM for non-tidal streams is defined as "the line on the shore established by the fluctuations of water and is indicated by physical characteristics, such as a clear, natural line impressed on the bank, shelving, changes in the character of the soil, destruction of terrestrial vegetation, the presence of litter or debris, or other appropriate means that consider the characteristics of the surrounding area" (33 CFR Part 328.3). Stream channels provide habitat for various wildlife species, serve as travel corridors for wildlife, convey flood flows, and perform other floodplain functions.

The U.S. Army Corps of Engineers (USACE) has exerted jurisdiction over several tributaries in the Pahrump area (personal communication Gebhart, Richard A. SPK). Many of these tributaries are part of the interstate system (and therefore under the jurisdiction of the USACE) because the California/Nevada border is so close to the project area, and in some cases within the project area. The tributaries from the nearby Spring Mountains flow perennially into California. At the time of the field visit, there was water flowing in Stump Spring. As Stump Spring is near the Clark County parcel, and crosses the Nevada/California border, the Corps could consider any washes or channels within the Clark County parcel that exhibit an OHWM and connect to Stump Spring, jurisdictional.

The project area should be surveyed for jurisdictional waters and the necessary Clean Water Act 404 and 401 permits should be obtained from the USACE and Nevada Division of Environmental Protection prior to construction. If USACE permits are required, the project then has a federal nexus and biological and cultural surveys, permitting, and monitoring may be required. The biological sections, biological recommendations, cultural sections and cultural mitigation sections within this document contain further information regarding these subjects.

FISH AND WILDLIFE COORDINATION ACT, AS AMENDED, 16 U.S.C. 661, ET SEQ.

This Act states that whenever the waters of any stream or other body of water are proposed to be impounded, diverted, the channel deepened or otherwise controlled or modified, the Corps shall consult with the U.S. Fish and Wildlife Service, the National Marine Fisheries Service as appropriate, and the agency administering the wildlife resources of the state.

NORTH AMERICAN WETLANDS CONSERVATION ACT, 16 U.S.C.: 4401 ET SEQ.

This Act establishes the North American Wetlands Conservation Council (16 U.S.C. 4403) (NAWCC) to recommend wetlands conservation projects to the Migratory Bird

Conservation Commission (MBCC). Section 9 of the Act (16 U.S.C. 4408) addresses the restoration, management, and protection of wetlands and habitat for migratory birds on Federal lands. Federal agencies acquiring, managing, or disposing of Federal lands and waters are to cooperate with the FWS to restore, protect, and enhance wetland ecosystems and other habitats for migratory birds, fish and wildlife on their lands, to the extent consistent with their missions and statutory authorities.

PROTECTION OF WETLANDS (EXECUTIVE ORDER 11990).

Federal agencies shall take action to minimize the destruction, loss or degradation of wetlands, and to preserve and enhance the natural and beneficial values of wetlands in carrying out the agencies responsibilities. Each agency, to the extent permitted by law, shall avoid undertaking or providing assistance for new construction located in wetlands unless the head of the agency finds 1) that there is no practicable alternative to such construction, and 2) that the proposed action includes all practicable measures to minimize harm to wetlands that may result from such use. In making this finding the head of the agency may take into account economic, environmental and other pertinent factors. Each agency shall also provide opportunity for early public review of any plans or proposals for new construction in wetlands.

NEVADA SPECIAL STATUS SPECIES

To assess the potential for occurrence of any threatened, endangered or sensitive species, SWCA obtained and reviewed the most current lists of Federal, State and County sensitive species for Nye and Clark Counties from the Nevada Natural Heritage Database, and reviewed relevant habitat information. The full list of Nye County rare species can be found at: <http://heritage.nv.gov/lists/conye.htm>. The full list of Clark County rare species can be found at: <http://heritage.nv.gov/lists/coclark.htm>. Appendix A contains the results of the Nevada Natural Heritage Database search. Special status species include those listed as threatened or endangered under the Federal Endangered Species Act (ESA) of 1973, as amended, species proposed for listing, species of special concern and other species identified either by the FWS, Bureau of Land Management (BLM), Nevada Department of Wildlife (NDOW), or the Nevada Native Plant Society (NNPS) as unique or rare. The BLM sensitive species are taxa that are not already included as BLM Special Status Species under 1) Federally listed, proposed or candidate species; or 2) State of Nevada listed species. The BLM policy is to provide these species with the same level of protection as is provided for candidate species in BLM Manual 6840.06 C, that is to "ensure that actions authorized, funded, or carried out do not contribute to the need for the species to become listed." The BLM Sensitive Species designation is normally used for species that occur on BLM administered lands for which BLM has the capability to significantly affect the conservation status of the species through management. SWCA recommends that prior to construction the developer and/or their consultant meet with the FWS and the BLM to gather any concerns that these agencies may have regarding any listed species.

SPECIAL STATUS PLANTS

State-listed species are protected by the 2001 Nevada Revised Statutes (NRS). State listed plants found in Clark County fall into one of two categories: critically endangered

and cactus/yucca (cactus and yucca are discussed below). Critically endangered plants are species threatened with extinction because of habitat loss, overexploitation, disease or other factors affecting their populations.

CACTI AND YUCCA

In the State of Nevada, cacti and yucca are protected under the NRS. Cactus, yucca and Christmas tree species are legally protected throughout the state of Nevada and include any members of the family Cactaceae and the genus *Yucca*, and all parts of any evergreen tree that has been cut and removed from its original growth place without the foliage being removed. Permits are required to remove these species from the wild and to ship or sell them. Plant salvage activities on BLM administered lands are also coordinated with the State of Nevada. The regulatory statutes may require the salvage, stockpiling, and replanting of cacti and yucca. SWCA recommends that prior to construction the developer and/or their consultant meet with the BLM to gather any concerns that this agency may have regarding the cactus and yucca contained within the project area. Prior to construction the BLM may require that all cacti and yucca meeting BLM salvage requirements would be removed from the defined construction area, and immediately transplanted or stockpiled for transplant following construction. If this is required, specific criteria would be developed by the BLM for determining the type of cacti and yucca that would be salvaged, if they would be immediately transplanted or temporarily stored, and which techniques would be used to replant and ensure survival success.

SPECIAL STATUS SPECIES

The species described below were identified by the Nevada Natural Heritage Program (Appendix A) as recorded in within a three-mile radius of the project area. Habitat may also be available for the chuckwalla (*Sauromalus ater*), the banded Gila monster (*Heloderma suspectum cinctum*), and the Las Vegas bearpoppy (*Arctomecon californica*).

DESERT TORTOISE

The Mojave population of the desert tortoise (*Gopherus agassizii*) is a federally listed threatened species. Critical habitat was designated for the tortoise on February 8, 1994, in California, Nevada, Utah, and Arizona. However, the project area is not located in an area of critical habitat for the desert tortoise.

The Mojave population of the desert tortoise is distributed throughout the southwestern United States in areas below 5,000 feet in elevation. Tortoises are typically found in areas dominated by creosote bush that have firm, but not hard, alluvium for construction of burrows.

No tortoise surveys were conducted in conjunction with the creation of this document, although suitable habitat for desert tortoises does exist within the project area and was observed during the site visit. Presence/absence surveys should be conducted prior to construction commencement. The FWS may require consultation and tortoise clearance surveys prior to construction as well as monitoring or installation of tortoise fencing during construction.

The following are several mitigations that can be taken during construction to lessen any impacts to tortoises that may occur:

- Trash and food items should be disposed of promptly in appropriate predator-proof containers. Trash containers should be removed regularly (at least once per week). This effort will reduce the attractiveness of the area to opportunistic predators such as coyotes, kit foxes, and common ravens.
- A maximum speed limit of 15 miles per hour should be maintained while traveling on the construction site, unpaved access roads, and storage areas. This effort will reduce the potential for vehicle-wildlife related collisions.
- A Worker Environmental Awareness Program (WEAP) should be implemented for construction crews prior to the commencement of construction activities. Training materials and briefings would include, but not be limited to, discussion of the federal ESA, the consequences of noncompliance with this act, identification and values of wildlife and natural plant communities, hazardous substance spill prevention and containment measures, and a review of all required and recommended mitigation measures.
- Any fuel or hazardous waste leaks or spills will be contained immediately and cleaned up at the time of occurrence. Contaminated soil will be removed and disposed of at an appropriate facility.

In Clark County an incidental take of a desert tortoise is covered by the Clark County Multiple Species Habitat Conservation Plan (MSHCP). Prior to construction, Clark County dust control permits will need to be obtained. During this process, a desert tortoise fee is paid. In spite of this, a desert tortoise cannot be knowingly harmed, and if encountered on site during construction the tortoise would need to be removed from the site utilizing the appropriate FWS protocol. However, if there is a federal nexus, i.e. some sort of federal action, such as jurisdictional waters on the site that require permitting activities, then the tortoise is no longer covered under the MSHCP, and a Section 10(a)(1)(B) Incidental Take Permit may need to be acquired. Nye County has begun the development of a Multiple Species Habitat Conservation Plan. As Nye County does not yet have a multiple species habitat conservation plan in place, development in the project area within Nye County may require a Section 10(a)(1)(B) Incidental Take Permit. SWCA recommends that prior to construction the developer and/or their consultant meet with the FWS regarding the desert tortoise. The developer may need to apply for a Section 10(a)(1)(B) Incidental Take Permit from the FWS. Part of this process requires the preparation of a habitat conservation plan. The main criteria for the issuance of a Section 10(a)(1)(B) Incidental Take Permit is that the project must not jeopardize the continued existence of the desert tortoise and all impacts must be mitigated. A full explanation of the Section 10(a)(1)(B) Incidental Take Permit can be found at <http://endangered.fws.gov/hcp/hcpbk7.pdf>.

PAHRUMP VALLEY BUCKWHEAT

Pahrump valley buckwheat (*Eriogonum bifurcatum*) is listed as a species of concern by the U.S. Fish and Wildlife Service (USFWS), and special status by the Nevada and California Bureau of Land Management (BLM) offices. The state rank indicator, based on distribution within Nevada is imperiled, due to rarity or other demonstrable factors. There is not currently any critical habitat designated for this species.

Pahrump valley buckwheat is an annual found growing in Clark and Nye counties, Nevada; also in California. The distribution straddles the Nevada/California state line, from Stewart Valley southeastward to Mesquite Valley.

Habitat is barren, saline, heavy clay, or silty hardpan soils on and near dry playa margins, adjacent shore terraces, and stabilized sand dunes. It is often associated with shadscale saltbush, desert holly, honey mesquite and spiny hopsage. SWCA recommends that prior to construction the developer and/or their consultant meet with the FWS and the BLM to gather any concerns that these agencies may have regarding the Pahrump valley buckwheat.

BIOLOGICAL RECOMMENDATIONS FOR THE NEVADA SITES

SWCA recommends that prior to construction the developer and/or their consultant meet with the FWS and the BLM to gather any concerns that these agencies may have regarding any listed, threatened, endangered or sensitive species that may exist within the project area.

Nye County has begun the development of a Multiple Species Habitat Conservation Plan. As Nye County does not yet have a multiple species habitat conservation plan in place, development in the project area within Nye County may require a Section 10(a)(1)(B) Incidental Take Permit. SWCA recommends that prior to construction the developer and/or their consultant meet with the FWS regarding the desert tortoise. The developer may need to apply for a Section 10(a)(1)(B) Incidental Take Permit from the FWS. Part of this process requires the preparation of a habitat conservation plan.

If the sites are to be developed, SWCA recommends that surveys specifically for wetlands and or jurisdictional waters be done. If those surveys reveal wetlands or jurisdictional waters, the necessary Clean Water Act 404 and 401 permits should be obtained from the USACE and Nevada Division of Environmental Protection prior to construction. As well, consultation with the FWS will be required. In all likelihood, the FWS will call for, at the very least, presence/absence surveys for threatened or endangered species. If threatened or endangered species are discovered during these surveys further mitigations and permitting activities will most likely be required.

If it is determined that the Clark County site has a federal nexus, i.e. some sort of federal action, such as jurisdictional waters, the desert tortoise is no longer covered under the Clark County MSHCP, and a Section 10(a)(1)(B) Incidental Take Permit may need to be acquired from the FWS.

If it is determined that migratory birds, such as burrowing owls, are utilizing the project area for nesting/breeding purposes, the developer should limit development activities to the months in which the migratory birds are normally not present onsite. Generally, late September thru early March is the best time to begin construction to avoid negative impacts to migratory birds.

If there is no federal nexus, the developer may want to have qualified biological and cultural monitors on site during all phases of construction in the event that sensitive biological resources or undiscovered cultural resources are discovered during construction activities.

CALIFORNIA THREATENED, ENDANGERED AND SENSITIVE SPECIES

A compilation of federal and state sensitive plant and wildlife species was prepared for the project from database and literature searches. References searched included the 2005 California Natural Diversity Database (CNDDB) and the California Native Plant Society (CNPS) database. The database searches were performed for the Blackwater Mine, Calvada Springs, Horse Thief Springs, Mound Spring, Nopah Peak, North of Tecopa Pass, Stump Springs, and Tecopa Pass 7.5-minute United States Geological Survey (USGS) quadrangles.

Table 1 contains sensitive plant species that are known to occur or could potentially occur in or near the Inyo County California portion of the project area.

Table 1. Sensitive Plant Species Known to Occur or Potentially Occurring at the Inyo County Project Site (CNDDB and CNPS databases).

Scientific Name	Common Name	Status ¹	Habitat
<i>Achnatherum aridum</i>	Mormon needle grass	- / -; CNPS 2/2-1-1	Joshua tree woodland, pinyon-juniper woodland.
<i>Agave utahensis</i> var. <i>eborispina</i>	Ivory-spined agave	- / -; CNPS 1B/3-1-2	Mojave desert scrub.
<i>Arctomecon merriamii</i>	White bear poppy	- / -; CNPS 2/2-2-1	Chenopod scrub, Mojave desert scrub.
<i>Bouteloua trifida</i>	Red grama	- / -; CNPS 2/3-1-1	Mojave desert scrub.
<i>Calochortus clavatus</i> var. <i>avius</i>	Pleasant Valley mariposa lily	- / -; CNPS 1B/2-2-3	Josephine silt loam and volcanic soils in lower montane coniferous forest.
<i>Camissonia boothii</i> ssp. <i>intermedia</i>	Hairy evening-primrose	- / -; CNPS 2/2-1-1	Sandy soils in Great Basin scrub and Pinyon and juniper woodland
<i>Cymopterus gilmanii</i>	Gilman's cymopterus	- / -; CNPS 2/2-1-1	Mojave desert scrub.
<i>Erioneuron pilosum</i>	Hairy erioneuron	- / -; CNPS 2/2-1-1	Rocky areas, sometimes carbonate soils in pinyon and juniper woodland.
<i>Galium hilendiae</i> ssp. <i>kingstonense</i>	Kingston Mountains bedstraw	- / -; CNPS 1B/3-1-2	Lower montane coniferous forest and rocky areas in pinyon and juniper woodland.
<i>Ivesia patellifera</i>	Kingston Mountains ivesia	- / -; CNPS 1B/3-1-3	Granitic, rocky areas of pinyon and juniper woodland.

<i>Mirabilis coccinea</i>	Red four o'clock	- / -; CNPS 2/2-1-1	Pinyon and juniper woodland.
<i>Penstemon fruticiformis</i> var. <i>amargosae</i>	Death Valley beardtongue	- / -; CNPS 1B/3-1-2	Mojave desert scrub.
<i>Penstemon stephensii</i>	Stephens's beardtongue	- / -; CNPS 1B/2-1-3	Mojave desert scrub; usually carbonate, rocky areas of pinyon and juniper woodland.
<i>Penstemon utahensis</i>	Utah beardtongue	- / -; CNPS 2/2-1-1	Chenopod scrub, Great Basin scrub, Mojave desert scrub, and rocky areas of pinyon and juniper woodland.
<i>Peteria thompsoniae</i>	Spine-noded milk vetch	- / -; CNPS 2/3-1-1	Sandy areas and alluvial fans in Mojave desert scrub.
<i>Sclerocactus johnsonii</i>	Bee-hive cactus	- / -; CNPS 2/2-2-1	Granitic soils in Mojave desert scrub.
<i>Selinocarpus nevadensis</i>	Desert wing-fruit	- / -; CNPS 2/3-1-1	Joshua tree woodland, rocky areas of Mojave desert scrub.

Notes: Sensitivity Status:
 FE = Federally listed as Endangered
 FT = Federally listed as Threatened
 FPE = Federally Proposed for listing as Endangered
 FSC = Federal Species of Concern (U.S. Fish and Wildlife Service)
 CE = California listed as Endangered
 CT = California listed as Threatened
 CNPS List 1B = Plants rare or endangered in California and elsewhere
 List 2 = Plants rare or endangered in California, more common elsewhere
 List 3 = Plants for which more information is needed (a review list).
 List 4 = Plants of limited distribution (a watch list).

Table 2 contains sensitive wildlife species that are known to occur or could potentially occur in or near the Inyo County California portion of the project area.

Table 2. Sensitive Wildlife Species Known or Potentially Occurring at the Inyo County Project Site (CNDDDB and CNPS databases).

Scientific Name ¹	Common Name ¹	Status ²	Habitat
Amphibians			
<i>Rana boylei</i>	Foothill yellow-legged frog	FSC/CSC	Partly shaded, shallow streams and riffles with a rocky substrate in a variety of habitats.
Reptiles			
<i>Gopherus agassizii</i>	Desert tortoise	FT/CT	Most common in desert scrub, desert wash, and Joshua tree habitats; occurs in almost every desert habitat.
<i>Heloderma suspectum cinctum</i>	Banded gila monster	FSC/CSC	Inhabits the lower slopes of rocky canyons and arroyos, but is also found on desert flats

			among scrub and succulents.
Birds			
<i>Accipiter gentilis</i>	Northern goshawk	FSC/CSC	Nesting habitat occurs within and in vicinity of coniferous forest. Uses old nests, and maintains alternate sites.
<i>Falco mexicanus</i>	Prairie falcon	FSC/CSC	Nesting habitat includes dry, open terrain, either level or hilly.
<i>Vireo vicinior</i>	Gray vireo	FSC/CSC	Nesting habitat in the mountains of the Mojave desert associated with stands of juniper and artemisia.
<i>Piranga flava</i>	Hepatic tanager	- /CSC	Nesting habitat includes white fir-pinyon forest on desert peaks, 5300-8100 ft elev. And understory of xerophytic shrubs.
Mammals			
<i>Corynorhinus townsendii pallescens</i>	Pale big-eared bat	FSC/CSC	Lives in a wide variety of habitats but most common in mesic sites.
<i>Tamias panamintinus acrus</i>	Kingston Mountain chipmunk	FSC/CSC	Nests among rocks in fissured cliffs and ledges in arid pinyon-juniper woodlands in the Kingston Mountains.
<i>Ovis canadensis nelsoni</i>	Nelson's bighorn sheep	FSC/CSC	Open, rocky, steep areas with available water and herbaceous forage.

Notes:

¹ Scientific and common names from USFWS, 2001 and CDFG, 2001.² Sensitivity Status:

FE = Federally listed as Endangered

FT = Federally listed as Threatened

FSC = Federal Species of Concern (U.S. Fish and Wildlife Service)

EPA = Eagle Protection Act

CE = California listed as Endangered

CSC = California species of Special Concern (California Department of Fish and Game)

CFP = California Fully Protected species.

CALIFORNIA LAWS AND REGULATIONS

The California Laws and Regulations section is still being developed, and will be included in the final document.

BIOLOGICAL RECOMMENDATIONS FOR THE CALIFORNIA SITES

This section is still being developed, and will be included in the final document.

CULTURAL RESOURCES

This section focuses on the cultural resources in the proposed Pahrump project area, and includes:

- An assessment of resources known to be present as a result of previous cultural resource studies in the proposed project area;

- Extrapolation from known to unknown cultural resources anticipated to be present in the project area;
- An overview of applicable laws, regulations, and guidelines for cultural resources in the area; and
- A summary of possible mitigation efforts, should any be needed.

KNOWN CULTURAL RESOURCES IN THE PROPOSED PROJECT AREA

Records of previous project data in Nevada and California were consulted to determine whether any cultural resources have been identified as a result of previous projects within the proposed project area. For the Nevada parcels, the records search was done by Ms. Susan Murphy of the Harry Reid Center for Environmental Studies at the University of Nevada-Las Vegas on May 16, 2005. For the California parcels, the records search was carried out by Farah Firtha at the Eastern Information Center, University of California, Riverside on May 18, 2005.

Five previous projects have been carried out within the proposed project area or within 1-mile of the proposed project area (Table 3). Previous cultural resources recorded in the vicinity of the project area consist of one prehistoric chipped-stone scatter; one historic Native American cemetery; and one segment of the Old Spanish Trail/Mormon Road. Of these three sites, only the Old Spanish Trail/Mormon Road is within the proposed project area, passing through one of the Nevada parcels considered in this study. The other two sites are all within the 1-mile buffer zone. All of the previously identified sites were located in Nevada, and all have consensus determinations of not eligible for listing on the National Register of Historic Places (NRHP).

Table 3. Previous Projects and Known Cultural Resources in or within 1 mile of the Pahrump Project Area

Report #	Reference; Organization	Sites within proposed project area	Sites within 1 mile of proposed project area
S-84(N)	Williams (no date); Unknown	None	None
S-1043(P)	Rafferty (1982); SERA Archaeology	None	None
S-1950(P)	Myhrer and White (1989); Bureau of Land Management Stateline Resource Area Las Vegas District, Nevada	26CK3848 - Old Spanish Trail/Mormon Road; not eligible	None
S-2369(P)	Kilby and Jones (1998); Lone Mountain Archaeological Services, Inc.	None	26CK5590 -Prehistoric Chipped-stone Scatter; not eligible 26CK5591 – Historic Native American Cemetery; not eligible
IN-0069	Breece and Schliz (1979); WESTEC Services, Inc.	None	None

The Spanish Trail was so named by John C. Fremont who, between 1843-1844, explored the Great Basin for the U.S. Topographic Engineers. During his expedition, he mapped much of the Great Basin, including his route across the Great Basin, using an already

existing trail. The trail was originally used by native groups as a trade route and, later, by both the Spanish Empire and American mountain men for the same purpose. After Fremont's report was published and distributed in 1844, his map and route became the most widely used by emigrants, such as Mormon settlers and California gold seekers, traveling to southern California. Between 1847-1848, the Mormon battalion traveled the route from Salt Lake City, UT to San Bernardino, CA and back again. With the establishment of Mormon missions at Las Vegas, NV, San Bernardino, CA, and other Pacific localities, thousands of Mormons used the trail for travel. Thus, beginning in 1847 and continuing until after 1857, the trail came to be known as the "Mormon Road." Eventually the Las Vegas mission was abandoned. During the early part of the 20th Century, construction of railroads beginning around 1905 and the Arrow Head Trails Highway beginning in the 1920s contributed to decreased use of the Old Spanish Trail/Mormon Road as a major transportation route (Myhrer et al. 1990).

The portion of the Old Spanish Trail/Mormon Road that is located in one of the parcels under consideration here is classified as partially disturbed and lacking integrity, making it ineligible for listing on the NRHP. However, artifacts and features may be associated with this alignment and such resources may retain the potential to provide data about the people who once used the trail.

All of the parcels in the proposed project area are likely to contain as-yet-unidentified prehistoric resources. All as-yet-unidentified cultural resources would have to be evaluated for their significance or uniqueness and whether they are eligible for listing on the NRHP.

LAWS, REGULATIONS, AND GUIDELINES FOR CULTURAL RESOURCES

This review of applicable laws, regulations, and guidelines is organized according to the relevant government agency. Federal laws and regulations are discussed first, followed by California laws and regulations, and then Nevada laws and regulations.

FEDERAL LAWS, REGULATIONS, AND GUIDELINES

No current federal nexus such as federal funding, federal lands, or federal permits is apparent from the land ownership data and the file search data. If this is indeed the case throughout the duration of the project, the main federal law concerning cultural resources that would need to be considered for this project would be the Native American Graves Protection and Repatriation Act of 1990 (NAGPRA) as established in the final rule set forth in 42 CFR Part 10 (1995).

However, it is possible that the proposed project would require a 404 permit from the Army Corps of Engineers because of water-related issues such as alteration of drainages or springs, or impacts to wetlands. In this event, several federal laws and regulations apply. This includes Section 106 of the National Historic Preservation Act of 1966, as amended (NHPA) and its implementing regulations, 36 CFR 800; the National Environmental Policy Act (NEPA); NAGPRA; the Archaeological Data Preservation Act of 1974; and the American Indian Religious Freedom Act (AIRFA) of 1978.

Section 106 of the NHPA specifically requires the lead government agency to identify and evaluate cultural resources that may be affected by the proposed project. In such

cases, pedestrian block surveys should be conducted within the parcel boundaries and pedestrian linear surveys should be conducted along any proposed access road and utility line right-of-ways that will be constructed. Any cultural resources identified as a result of the pedestrian surveys should be evaluated to determine whether they are eligible for listing on the NRHP. Eligibility determinations are typically made in a consensus process among the lead federal agency, consulting federal agencies, and the State Historic Preservation Office. Eligibility determinations are an attempt to assess the integrity of location, design, setting, materials, workmanship, feeling and association of the cultural resources. In order to be eligible for nomination to the NRHP, a resource must retain several aspects of integrity, as well as at least one of the following characteristics:

- (a) Are associated with events that have made a significant contribution to the broad patterns of our history; or
- (b) Are associated with the lives of persons significant in our past; or
- (c) Embody the distinctive characteristics of a type, period, or method of installation, or that represent the work of a master, or that possess high artistic values, or that represent a significant and distinguishable entity whose components may lack individual distinction; or
- (d) Have yielded, or may be likely to yield, information important in prehistory or history. (36 CFR 60.4)

In addition to work required to address Section 106 of the NHPA, NAGPRA requires that "The Federal agency official must take reasonable steps to determine whether a planned activity may result in the excavation of human remains, funerary objects, sacred objects, or objects of cultural patrimony from Federal lands." (42 CFT Part 10 Section 10.3(c)(1). If any NAGPRA issues arise, and if any discoveries of human remains or funerary objects are made, the materials would be dealt with according to the Archaeological Resources Recovery Act (ARPA) (16 U.S.C 470aa et seq.) and its implementing regulations.

When there is a federal nexus for a project and the above-mentioned suite of laws is triggered, archaeological survey, evaluation of resources, and a technical report are typically required. Permits from the lead agency would be required to carry out cultural resources survey. An archaeological survey is usually coordinated with the lead federal agency, with a technical report submitted to the lead federal agency for review. Based on the review, the report is revised and submitted to the State Historic Preservation Office for review, with a final revision to follow. Such reports typically include an assessment of the potential impact of the proposed project on the cultural resources. However, these reports do not typically include plans for the mitigation of the adverse effects of the proposed project on cultural resources. Mitigation plans are typically written after the technical report has been accepted and require another process of review and revision.

CALIFORNIA LAWS, REGULATIONS, AND GUIDELINES

Although no federal agency is currently known to be involved in the proposed project, the project is likely to require permits and/or oversight by local governments for residential construction permits, construction of utilities, and road construction. Because of this permitting and/or oversight role, the California Environmental Quality Act

(CEQA) clearly applies to activities on the parcels located in California, with the local government acting as the lead agency. Additionally, it is explicitly stated in CEQA that, "The lead agency must consider the whole of an action, not simply its constituent parts, when determining whether it will have a significant environmental effect. (Citizens Assoc. For Sensible Development of Bishop Area v. County of Inyo (1985) 172 Cal.App.3d 151)." (Title 14, Chapter 3, Article 1, Section 15003(h). This makes it likely, but not certain, that the entirety of the proposed project will be considered under CEQA, rather than simply the portion in Inyo County, California.

Additionally, if the proposed project is not consistent with the general or specific plans of the local regulatory agency, consultation with Native American groups, the local government agency, and the proponent would be required. If, however, the proposed project is consistent with the existing general or specific plans of the local or state agencies, no such consultation would be required.

CEQA requires a lead agency to determine whether a project may have a significant effect on historical resources. In order to identify cultural resources, a pedestrian survey is typically required.

A *historical resource* is a resource listed in, or determined to be eligible for listing in, the California Register of Historical Resources (CRHR) (Section 21084.1); a resource included in a local register of historical resources (15064.5(a)(2)); or any object, building, structure, site, area, place, record, or manuscript which a lead agency determines to be historically significant (15064.5 (a)(3)).

Public Resources Code SS5024.1 requires evaluation of historical resources to determine their eligibility for listing on the CRHR. The purpose of the CRHR is to maintain listings of the state's historical resources and to indicate which properties are to be protected from substantial adverse change. The criteria for listing resources on the California Register were expressly developed to be in accordance with previously established criteria developed for listing on the NRHP, enumerated above.

According to Section 15064.5(a)(3)(A-D) in the revised CEQA guidelines (Governor's Office of Planning and Research 1998), a resource is considered historically significant if it meets at least one of the following criteria:

- (a) Is associated with events that have made a significant contribution to the broad patterns of California's history and cultural heritage;
- (b) Is associated with the lives of persons important in our past;
- (c) Embodies the distinctive characteristics of a type, period, region or method of installation, or represents the work of an important creative individual, or possesses high artistic values; or
- (d) Has yielded, or may be likely to yield, information important in prehistory or history.

Impacts to significant cultural resources that affect those characteristics of the resource that qualify it for the NRHP or adversely alter the significance of a resource listed on or eligible for listing on the CRHR are considered a significant effect. Impacts to cultural resources are thus considered significant if the project physically destroys or damages all

or part of a resource or changes the character of the use of the resource or physical feature within the setting of the resource.

The disposition of burials falls first under the general prohibition on disturbing or removing human remains under California Health and Safety Code 7050.5. More specifically, remains suspected to be Native American are treated under CEQA at Section 15064.5 and site language found at Public Resources Code SS5097.98 that illustrates the process to be followed in the event that remains are discovered. If human remains are discovered during the construction of the proposed project, no further disturbance to the site shall occur and the Inyo County Coroner must be notified. If the coroner determines the remains to be Native American, the coroner shall notify the Native American Heritage Commission (NAHC) within 24 hours. The NAHC shall identify the person or persons it believes to be the Most Likely Descended (MLD) from the deceased. The MLD may then make recommendations as to the disposition of the remains.

NEVADA LAWS, REGULATIONS, AND GUIDELINES

The Nevada State Historic Preservation Office can recommend that a survey for cultural resources be carried out. If a federal nexus is present, the Nevada SHPO would consult on this project as on any other as described above in the federal section. The Nevada SHPO would provide information about known cultural resources and projects in the proposed project area, consult on the eligibility recommendations for cultural resources, and review the report.

So far as can be determined at this time, the only laws specific to the State of Nevada governing cultural resources concern the disinterment of human remains (Nevada Revised Statutes [NRS] 383.170) and the willful removal, mutilation, defacement, injury to, or destruction of the grave or cairn of a Native American (NRS 383.180). Additionally, NRS 383.180 prohibits the unlawful possession of or selling of goods or human remains from Native American graves and cairns. NRS 383.170 establishes the process to follow upon accidental disturbance of a Native American grave or cairn, and establishes the consequences of not following the process. Additionally, it allows for civil claims by Native American against any individual who violates NRS Statutes 383.170 and 383.180.

IDENTIFICATION, EVALUATION, AND MITIGATION MEASURES

Suggested mitigation measures depend largely on whether the federal government has a role in the project and whether CEQA is extended to the entire project or is restricted to the California portion. The sections below set forth the necessary steps in the event that identification, evaluation, and mitigation of cultural resources is required because of federal involvement or CEQA requirements.

TO IDENTIFY UNKNOWN CULTURAL RESOURCES IN THE PROJECT AREA

In order to fulfill one of the steps required by either federal laws and regulations or by CEQA, cultural resources in the proposed project area should be identified and assessed to determine whether any represent cultural resources eligible for listing on the NRHP or whether they represent "historical resources" eligible for listing on the CRHR. In order to identify cultural resources within the proposed project area, pedestrian block surveys

should be conducted within the parcel boundaries. Additionally, pedestrian linear surveys should be conducted along any proposed access road and utility line right-of-ways that will be constructed outside of the parcel boundaries. Any cultural resources identified as a result of the pedestrian surveys should be evaluated according to either 36 CFR 60.4 or the California Public Resources Code, Division 13, Chapter 2.6, Section 21083.2(g), whichever is applicable. If any of the cultural resources in the project area are deemed to be eligible for nomination to the NRHP, the effect of the proposed project on those resources should be assessed. Cultural resources that are assessed as not eligible for the NRHP do not merit further consideration (California Public Resources Code, Division 13, Chapter 2.6, Section 21083.2(h)).

KNOWN CULTURAL RESOURCES IN THE PROJECT AREA

Although the consensus determination process has concluded that none of the previously identified cultural resources in the project area are eligible for nomination to the NRHP one of the resources merits further consideration: the Old Spanish Trail/Mormon Road.

The Old Spanish Trail/Mormon Road, Site 42CK3848, was the first transportation corridor used across the state of Nevada by Euroamericans and it is listed on the NRHP. Approximately 1,320 feet (0.25 miles) of it passes through one of the parcels in the proposed project area. Approximately 7,100 feet (1.34 miles) of the site also occurs within 1 mile of the proposed project area.

This site was listed on the NRHP because segments of the trail that retain historical integrity and that are physical remnants of the trail are associated with events that have made a significant contribution to the broad patterns of our history in the areas of Transportation and Exploration/Settlement (Criterion A of the NRHP), and because the property has yielded, or is likely to yield information important in prehistory or history (Criterion D). Although significance criteria was met for the trail as a whole, historical and physical integrity were the main factors in the designation of segments listed on the NRHP as the Old Spanish Trail/Mormon Road Historic District (Myhrer et al. 1990).

The segment of the Old Spanish Trail/Mormon Road that passes through the proposed project area and within 1 mile of the proposed project area, from roughly the California border to Stump Spring, was recommended not eligible to the NRHP because this portion of the site is partially disturbed. The disturbance has caused loss of integrity in workmanship, design, feeling, association and materials. Therefore, this segment is considered a non-contributing element to the overall district.

Although this section of the trail has lost much of its integrity and is not a contributing element to the district, monitoring for cultural resources in the vicinity of the trail may be required by the lead agency. Previous survey along the trail has established that numerous artifacts and features are associated with the trail, making its environs an area of high sensitivity for cultural resources. Since these associated artifacts and features have not been fully documented, and since ground-disturbing activities such as those associated with residential development could uncover significant cultural resources, monitoring is likely to be recommended by government agencies involved in the project. Ground disturbing activities include, but are not limited to, the uprooting of vegetation, shovel scraping, using hand tools (e.g., shovels, pick axes, etc.) to dig, using heavy machinery to

scrape, blade, or trench, and even the turning of heavy vehicles or tracked and/or heavy machinery.

Archaeological monitoring of construction in the vicinity of the trail might be avoidable in two ways. The site could be avoided entirely by developing only the southern portion of the parcel in which it is located. Or, the site could be left in place, integrated into part of the housing development, possibly as an interpretive walking trail with information about the trail's history at various kiosks or trail markers.

SUMMARY

Because the proposed project falls under the purview of CEQA, survey for archaeological resources of at least the California parcels and possibly of the entire project area will probably be required. Furthermore, if any cultural resources are identified in the project area, and they are determined to be eligible for the CRHR or NRHP, a determination of the effect of the proposed project on those resources will be required. If the proposed development will have an effect on those resources in some way, mitigation of the effect will probably be required. If mitigation is required, a mitigation plan will probably be required, which would be developed in consultation with the lead and consulting agencies.

The most likely approaches to mitigation of effects on cultural resources include avoidance; deeding the area containing the cultural resources into a conservation easement; capping archaeological sites with soil (in cases where subsurface ground disturbance will not occur); and planning parks, greenspace, or educational exhibits that incorporate the resource. Other types of mitigation measures may also be acceptable, such as data recovery (excavation) or incorporation of the Old Spanish Trail/Mormon Road into the development as an interpretive trail including historical information about the trail.

PALEONTOLOGICAL RESOURCES

The paleontological resources section is still being developed and will be included in the final document.

CONTRIBUTORS

Name	Contribution
Stephanie Pesek	Project Manager, Biological Resources
Eric Koster	Nevada Biological Resources
Lynda Sperry	Nevada Biological Resources
Michael Tuma	California Biological Resources
Heather Stettler	Cultural Resources
Clint Lindsay	Cultural Resources
Patrick Maxon	Cultural Resources
Cara Corsetti	Paleontological Resources
Jessica Debusk	Paleontological Resources

Kelli Nagamine	Administrative

REFERENCES

Breece, William and Allan Schliz

- 1979 Archaeological Survey of the Hidden Hills Ranch Project. Site Inyo County, California. Prepared by WESTEC Services, Inc., Tustin, California, Report No. IN-0069. Prepared for Boyle Engineering, Newport Beach, California.

Kilby, David and Dee Jones

- 1998 Cultural Resource Survey of 64.3 Acres for a Proposed Access Road for the Front Sight Arms Training Facility Near Pahrump, Clark County, Nevada. Lone Mountain Archaeological Services, Inc. Report No. 5-2369(P).

Myhrer, Keith and William White

- 1989 Archaeology of the Old Spanish Trail/Mormon Road from Las Vegas, Nevada to the California Border. Bureau of Land Management, Stateline Resource Area. Las Vegas District, Nevada. Report No. 5-1950(P).

Myhrer, Keith, William White, and Stanton Rolf

- 1990 Contributions to the Study of Cultural Resources: Archaeology of the Old Spanish Trail/Mormon Road from Las Vegas, Nevada to the California Border. Bureau of Land Management, Las Vegas District, Nevada. Technical Report 17.

Rafferty, Kevin

- 1982 Las Vegas – Reno ORV Race, 82-3 (Frontier 500), involving 300 miles of Off-road Vehicle Activity within the Las Vegas District. SERA Archaeology. Report No. 5-1043(P).

Williams, Joseph O.I.

- no date Cultural Resource Survey for Groundshakers Championship Desert Motorcycle Race Application. Report No. 5-84(N).

**APPENDIX A. NEVADA NATURAL HERITAGE PROGRAM DATABASE
SEARCH RESULTS**

Nevada Natural Heritage Program

Department of Conservation and Natural Resources
1550 East College Parkway, Suite 137 * Carson City, Nevada 89706-7921
voice: (775) 687-4245 fax: (775) 687-1288 web: www.heritage.nv.gov/

17 May 2005

Stephanie Pesek
SWCA Environmental Consultants
2820 W. Charleston Blvd., Suite 15
Las Vegas, NV 89102

RE: Data request received 06 May 2005

Dear Ms. Pesek:

We are pleased to provide the information you requested on endangered, threatened, candidate, and/or at risk plant and animal taxa recorded within or near the Wiley Trust project area. We searched our database and maps for the following, a three mile radius around:

Township 22S Range 54E Sections 24, 25, 26, and 27
Township 23S Range 55E Sections 06 and 07

The enclosed printout lists the taxa recorded within the given area. Please be aware that habitat may also be available for: the chuckwalla, *Sauromalus ater*, a Nevada Bureau of Land Management (BLM) Sensitive Species; the banded Gila monster, *Heloderma suspectum cinctum*, a Nevada BLM Special Status Species; and the Las Vegas bearpoppy, *Arctomecon californica*, a Nevada BLM Special Status Species also protected under Nevada state law (NRS 527.260-.300) as critically endangered. We do not have complete data on various raptors that may also occur in the area; for more information contact Ralph Phenix, Nevada Division of Wildlife at (775) 688-1565. Please note that all cacti, yuccas, and Christmas trees are protected by Nevada state law (NRS 527.060-.120), including taxa not tracked by this office.

Please note that our data are dependent on the research and observations of many individuals and organizations, and in most cases are not the result of comprehensive or site-specific field surveys. Natural Heritage reports should never be regarded as final statements on the taxa or areas being considered, nor should they be substituted for onsite surveys required for environmental assessments.

Thank you for checking with our program. Please contact us for additional information or further assistance.

Sincerely,



Eric S. Miskow
Biologist III/Data Manager



APPENDIX B

AMEC 2006 STUDY

**WATER
SUPPLY POTENTIAL FOR NEW DEVELOPMENT
INYO COUNTY, CALIFORNIA**

Submitted to:

**Mary Wily Trust
c/o Mr. Steven Scow Esq.
612 South 7th Street
Las Vegas, Nevada 89101**

Submitted by:

**AMEC Earth & Environmental, Inc.
780 Vista Boulevard, Suite 100
Sparks, Nevada 89434**

**May 2006
AMEC Project No. 5-417-000702**

July, 2006
AMEC Project No. 5-417-000702

Mary Wily Trust
c/o Mr. Steven Scow Esq.
612 South 7th Street
Las Vegas, Nevada 89101

Attention: Mr. Steven Scow

**Re: RECHARGE ASSESSMENT AND WATER SUPPLY POTENTIAL
For New Subdivision, Inyo County, California**

Dear Mr. Scow:

AMEC has completed our assessment of the water supply potential for the Hidden Hills Ranch area, Pahrump Valley, Nevada and California. The enclose report presents a summary of the water resource related documents obtained and reviewed as well as a presentation of our assessment of economically available water quantity.

Respectfully submitted,

AMEC Earth & Environmental, Inc.

Reviewed by,

Brett Whitford
Environmental Services Manager

John Dyer P.G.
Senior Project Manager

BW/mm

Enclosures

J:\Clerical\2006\May_06\5417000702_Mary_Wily_Trust.doc

TABLE OF CONTENTS

SECTION	PAGE
1. INTRODUCTION.....	1
1.1 Background Information	1
2. GENERAL.....	2
2.1 Area Description	2
2.2 Regional Development and Water Use.....	2
2.3 Evaporation.....	5
2.4 Groundwater Development from 1913 through 1998	5
2.5 Environmental Issues Associated with Water Demand	6
3. GENERAL SITE CONDITIONS.....	8
3.1 Geology	8
3.2 Geophysics (Gravity and Magnetic Data).....	9
3.3 State Line Fault System	10
3.4 Topography.....	12
3.5 Climate and Precipitation	12
3.6 Recharge Sources	14
3.7 Discharge Sources	14
3.8 Water Sources.....	15
3.9 Evapotranspiration of Aquifer Storage	15
4. AQUIFER SYSTEMS	16
4.1 Alluvial Aquifer System.....	16
4.2 Carbonate Aquifer System	16
4.3 Regional Flow Regimes (both Shallow and Deep), Gradients and Flow	17
4.4 Groundwater Level Trends (HYDROGRAPHS)	18
4.5 Water Quality.....	19
4.6 Site Specific	20
5. SITE WORK.....	21
5.1 Background/Past Assessments.....	21
5.2 Infiltration/Recharge Model.....	25
5.3 Method.....	26
5.3.1 Method One.....	27
5.3.2 Method Two.....	28
5.4 The Unknown Flow Regime(s).....	29
5.5 Groundwater in Storage.....	29
5.6 Impact of Proposed Demand on Supply	30
5.7 Pumping Wells	33
5.7.1 Demand.....	33
5.7.2 Impact Simulation Output.....	34
5.7.3 100-Year Groundwater Level	34
5.7.4 Modeling Impact Conclusion.....	34
6. ALTERNATIVES.....	35
6.1 Feasibility of Alternatives.....	37
REFERENCES	39

TABLE OF CONTENTS (CONTINUED)

FIGURES

1. Location Map
2. Earth Fissure Map
3. Depth to Bedrock
4. Groundwater Elevation Contour Map
5. Geologic Map
6. Watershed Map
7. Recharge Infiltration Method 1
8. Recharge Infiltration Method 2
9. 5-Year Drawdown
10. 10-Year Drawdown
11. 20-Year Drawdown
12. 30 Year Drawdown

Tables

1. Method One Recharge Input Data
2. Method Two Recharge Input Data
3. Demand Estimate

APPENDICES

- A Precipitation Data
- B Selected Data, Nye County Water Resources Plan
- C Excerpts from Harrill
- D Water Quality Data
- E Aquifer Test Data
- F Winflow Output

1. INTRODUCTION

This report presents AMEC Earth & Environmental, Inc.'s (AMEC) findings regarding a sustainable water resource assessment in the Hidden Hills area of the Pahrump Valley. It has specific focus on the proposed development area in Inyo County, California and Nye County, Nevada (Site), Figure 1. This assessment focuses on the available water resources in the Pahrump Valley that could be utilized to support a municipal water supply development. We understand that the owners of the subject property (Mary Wily Trust (Mary Jane McMonigle and Linda Ekins)), (the Trust) hope to develop a community that consists 20,000-50,000 residential units on about 10,200 acres of land. In order to proceed with development plans, we understand that the Trust desires to assess the water supply resources in the area to be developed in order to aid in future business decisions.

The fundamental concern is the understanding potential impacts of groundwater withdrawals on the groundwater system in order to define the sustainability of the aquifer. In 1999, the U.S. Geological Survey defined groundwater sustainability as *"the development and use of groundwater in a manner that can be maintained for an indefinite time without causing unacceptable environmental, economic or social consequences."* Using this definition, the overall goal of the sustainability assessment is to quantify the amount of groundwater that can be efficiently used without causing unacceptable consequences to the natural and economic system within the Pahrump Valley. The other aspect of this definition is that the quantification of available groundwater is more than a technical issue. Therefore, using this definition, the development of a long-term sustainable yield entails not only understanding the natural system, but also understanding what long-term plan for development of the valley and potential impacts of increased groundwater withdrawal on the existing natural system. These impacts may include loss of riparian habitat and land subsidence. The second important concept is the economics of groundwater recovery. Evaluating quantity of water within the basin based only on natural recharge and aquifer storage will likely indicate a large volume of water that may be available for water supply. However, when economic concerns such as pumping costs and water treatment for potable use are factored into the sustainability analysis, only a fraction of the amount of physical water present may be considered economically viable to utilize as available supply.

Our assessment was performed through the gathering and review of readily available reports and documents, a field reconnaissance visit, along with the development of a recharge model for the subject area. This report presents the information obtained and reviewed along with our assessment of the water resource potential in the area.

1.1 Background Information

The study of water resources in the Pahrump Valley and vicinity has been performed by others of the subject site. The first documentation of water development in the Valley was published by the US Geological Survey in 1921 (Waring, 1921). This document indicated that there were a number of flowing artesian wells in the valley. With in this section we discuss the general geologic framework of the site and surrounding area. This discussion is followed by a

discussion of water resource related reports prepared by others that are site specific then expand outward to valley wide and regional information.

2. GENERAL

2.1 Area Description

The Pahrump Valley drainage basin includes approximately 1,050 square miles in Clark and Nye Counties (southern Nevada), San Bernadino and Inyo and Counties (southeastern California). About 200 square miles of the total drainage basin is in California. The basin extends from Johnnie, Nevada, southeastward approximately 42 miles to a point about 14 miles south of Hidden Valley. The valley is approximately 30 miles wide and extends from the crest of the Nopah Range, the Kingston Range, and the northern part of the Resting Spring Ranges on the southwest, to the crest of the Spring Mountains, on the northeast. The project site is located in the southwestern portion of Pahrump Valley, Figure 1.

Elevation of the Pahrump Valley floor above mean sea level ranges from 2,457 feet at Stewart (dry) Lake to approximately 3,000 feet in the southwestern part of the basin. The mountains range in elevation from about 6,400 feet in the Nopah Range to about 11,900 feet above sea level for the Spring Mountains. This range provides the principal source of recharge to the basin. Pahrump Valley is separated from Mesquite Valley (also called Sandy Valley) to the southeast towards Las Vegas by a topographic rise that divides the two areas into separate hydrographic basins (Malmberg, 1967).

Stewart Lake, located in the northwest part of the valley, covers an area of approximately 6 square miles, and Pahrump (dry) Lake, located in the central part of the valley, covers approximately 10 square miles (Waring 1920, DWR 1964).

2.2 Regional Development and Water Use

The town of Pahrump is located within Pahrump Valley. Currently, it has a population of approximately 32,383. Pahrump has grown by more than 5,100 residents in the past three years for an average of 144 people per month. The town has grown by more than 100 percent in terms of population in the last nine years and by 200 percent since 1990 (Pahrump Valley Times, March, 2005).

The only utilized source of water is the valley fill aquifer. Nevada has issued water rights on 69,000 acre-feet per year (af/y) in Pahrump Valley. This is in excess of the perennial yield of the aquifer (estimated at 12,000 to 19,000 acre-feet per year, sustained yield is 26,000 acre-feet), although actual annual use is only about 23,000 acre-feet (Buqo, 2004). Present use, although significantly less than the amount allotted by water rights, overdrafts the aquifer. The population (and therefore the demand on the aquifer) is expected to increase, reaching a maximum build-out within the next twenty to fifty years. The projected population of Pahrump is 150,000 by 2050, with an annual water demand of approximately 80,000 af/y based on an

estimated per capita use of 486 gallons per day. This is well in excess of both current water rights and perennial yield of the aquifer.

Pahrump Valley was one of the most productive farming districts in southern Nevada. Agricultural products historically have included; cotton, alfalfa, small grains, vegetable, fruits, nuts and grasses. Agriculture, the former principal occupation, was dependent wholly on irrigation from groundwater (The Environmental Data Bank of Independence, 1974).

Historically, irrigation was the prime purpose for groundwater pumpage in Pahrump Valley; over 99 percent of all pumpage was for irrigation purposes prior to 1962. Irrigated land increased from about 1000 acres in the early 1940s to over 3,800 acres in 1958. It peaked in 1968, with approximately 8100 irrigated acres of land. Pumpage rates for the years 1913-1944, 1945-1951, and 1952-1958 were estimated as 4,000, 13,000, and 22,000 acre-feet (averages of 129, 2167, and 3667 acre-feet per year) respectively, based on irregular well and spring discharge measurements from 1913-1958. These data were previously compiled for a groundwater flow model of the valley (Harrill, 1986). By 1962, half of the irrigated land was used to farm cotton, although the 1970's saw the conversion of agricultural land to suburban uses, with a cessation of cotton production by 1982 (Moreo et al, 2003). As the area converted, numbers of domestic wells increased drastically. At the end of August 2001, more than 8,700 domestic wells had been drilled in Pahrump. Yet due to the conversion of agriculture to domestic use, overall water demand in 2000 was the lowest since 1993 (Nye County Water Resources Plan, 2004). As population continues to expand, more domestic wells will be drilled; projections estimate that an additional 25,000 domestic wells will be added with maximum build-out (Buquo, 2004).

Irrigated acreage in Pahrump Valley from 1913 to 1958 was estimated primarily from sporadic measurements of total discharge from wells and springs (Malmberg, 1967) previously compiled for a groundwater flow model of Pahrump Valley (Harrill, 1986). From these measurements, average withdrawals from wells of 4000, 13,000 and 22,000 acre-feet were estimated for the periods 1913-44, 1945-51, and 1952-58, respectively. This undifferentiated groundwater withdrawal in Pahrump Valley was for irrigation. Annual application-rate estimates for alfalfa affected water-use estimates more than any other crop because about 75 percent of the 3 million acre-feet withdrawn from the Death Valley Regional Flow System (DVRFS) during the period 1913 to 1998 was irrigated alfalfa. Alfalfa, grass hay, and turf grass were planted in about 70 percent of irrigated acreage in the southern hydrographic area including Pahrump Valley. Annual application rates for alfalfa, grass hay and turf grass were similar and far exceeded application rates for all other crops. Alfalfa, hay grass and turf grass were classed as high use crops. Application rates for high water-use crops ranged from 5 feet/yr in Penoyer Valley to 9 feet/yr in Pahrump Valley (Moreo, 1999).

Historic water use in the basin grew to 47,100 acre feet in 1968 and then declined to less than 20,000 acre feet in 1986 through 1988. With the increased urbanization in the 1990s, water use increased and by 1996 demand was once again above both the perennial and sustained yields. The conversion of farmland to the Mountain Falls subdivision and the slow growth of that venture has been the primary reason for the decline in water use in 2000. In 2000, the total water demand for irrigation dropped to about 8,000 acre feet, only about 17 percent of the 1968 peak. With the growth of the community, commercial, quasi-municipal, and domestic water

uses have grown significantly over the last two decades, from 2,550 acre feet in 1983 to almost 14,000 acre feet in 2000. Most of the former agricultural acreage in the basin has been converted to subdivisions and parcels. The site of the town cotton gin is now a casino. RV parks, a new bank and office buildings, and other new businesses have been built over the last ten years and construction continues.

Through August 2001, a total of 9,255 wells had been drilled in Pahrump. Well drilling peaked in 1996 when 728 wells were drilled in the basin. Since that time, drilling activity has decreased somewhat but is still significant, with 456 wells drilled in 1999. Almost 300 irrigation wells have been drilled in the valley and 254 municipal, commercial, and industrial wells have been drilled. Of concern is the number of domestic wells (more than 8,700) and the potential for drilling of as many as 25,000 more domestic wells over the coming decades.

The Nevada Department of Water Resources (NDWR) pumpage inventories were available for Pahrump from 1960 to 2000, with the exception of 1979 through 1981. For these three years, irrigation use was estimated using remote sensing data and domestic use was estimated based upon the number of domestic wells in NDWR's well log data base (R.J. LaCamera, U.S. Geological Survey, written commun., 2002). Withdrawals in Pahrump Valley declined from an average of 37,324 acre-feet/year for 1960 to 1979 to 24,629 acre-feet/year for 1990 to 1998. The reduction coincides with a transition from agriculture to municipal water use in Pahrump Valley. Irrigation use declined from about 46,956 acre-feet in 1968 to about 14,818 acre-feet in 1998. Conversely, domestic and municipal use rose from 301 to 7,956 acre-feet in the same period (Modified from Fenelon, 2002). The following chart shows water usage for the period 1990-2000.

YEAR	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000
Irrigation (acre-feet)	15,374	19,257	16,893	14,051	17,046	14,183	16,378	16,723	14,818	11,940	8,000***
Golf Course (Champion) (acre-feet)	1,180	1,180	1,180	1,180	1,180	1,180	1,180	1,183	1,183	1,183	
Cal-Vada* (acre-feet)	1,279	1,087	1,462	1,545	1,817	2,724	3,052	2,988	2,580	2,819	
Commercial/Other, not Cal-Vada (acre-feet)								463	984	918	
Quasi-Municipal, not on Cal-Vada (acre-feet)	3,020**	3,322**	3,754**	4,186**	4,841**	5,534**	6,256**	370	238	307	
Domestic not on Cal-Vada (acre-feet)								7,092	7,718	8,390	
Total	20,853	24,846	23,289	20,962	24,884	23,621	26,866	28,819	27,522	25,558	23,000***
Source: Utley, 2004 * = Including executive golf course, meters commercial, domestic and line losses ** = Quasi-municipal and domestic combined, not on Cal-Vada *** = Nye County Water resources Plan. (Lowest Demand since 1993)											

2.3 Evaporation

The growing season ranges from 210 to 265 days (Galcey, 1968). Six crop cuttings per year. Potential evapotranspiration (ET) is 6.4 feet/year. Application rate minimum is 5 feet/yr, and is most likely is 9 feet/year. The maximum application rate is 14 feet/year. Potential evapotranspiration over the length of a growing season in the southern hydrographic area including Pahrump Valley is 6.4 feet. Estimates of annual potential Evapotranspiration with a modified Penman-Monteith method (Bureau of Reclamation, 2001) differ than less than 10 percent from the modified radiation method in the southern hydrographic area. In Pahrump Valley, where less efficient irrigation methods were practiced, fields were given an irrigation efficiency of 65 percent (Moreo, 1999).

Low water use and mixed water-use crops also were defined in for the southern hydrographic area including Pahrump Valley. Small grains, orchards, and cotton were classed as low water-use crops and assigned annual application rates of 3 to 4 feet (Bureau of Reclamation, 2001). In Pahrump Valley between 1959 and 1978, NDWR estimated irrigation withdrawal as the product of pumping rate and number of days a well was pumped. Averaging their estimates resulted in an application rate of about 5 feet/yr when cotton predominated and about 7 feet/yr when alfalfa predominated (Moreo, 1999).

2.4 Groundwater Development from 1913 through 1998

The first three irrigation wells drilled in Pahrump Valley in 1913 after earlier attempts in 1910 were unsuccessful (Harrill, 1986). Between 1913 and 1916, an additional 27 wells were drilled in Pahrump Valley and annual discharge from wells increased from 500 to 4,000 af/y (Waring, 1921). Groundwater use remained relatively stable prior to 1945 because withdrawals were limited by the amount of water available from flowing wells (Moreo, 1999).

Groundwater withdrawals from Pahrump Valley increased after 1945 with the introduction of high capacity turbine pumps (Harrill, 1986). Irrigated acreage increased from less than 1,000 acres in the early 1940s to about 3,800 in 1958. Irrigate acreage increased after 1952 with the paving of the road to Las Vegas and as people acquired land under the Desert Land Act and Homestead Act (Tim Hafen, land developer, 2003). A maximum of 3,400 acres of cotton were planted in Pahrump Valley during 1962, which was about 50 percent of all irrigated acreage. Irrigated agriculture reached its peak in 1968 with about 8,100 acres under cultivation (Moreo, 1999).

Conversion of Irrigated acreage in Pahrump Valley to suburban communities began after 1970 as economic factors precipitated the decline of cotton production (McCracken, 1990). Cotton was planted on less than 25 percent of the irrigate acreage in Pahrump Valley after 1972 and was not grown after 1982 (Moreo, 1999).

Domestic and public-supply water use in Pahrump Valley increased exponentially between 1960 and 1998. The number of domestic wells increased from less than 50 to 700 between 1962 and 1978 as the population increased from 200 to 2,000 (Harrill, 1986). By 1998, 9,000 acre-feet of

water was used for domestic and public supply to support a population of 20,000 (Hardcastle, 2001). About 75 percent of the domestic and public-supply withdrawal from the DVRFS in 1998 was pumped from Pahrump Valley. The annual groundwater withdrawal for the DVRFS in 1998 was estimated at 90,000 acre-feet/year. The uncertainty (maximum) estimate is 125,000 acre-feet/year to a uncertainty (minimum) estimate of 60,000 af/y. The uncertainty is attributed primarily to uncertainty in irrigation-application rates. Incomplete records of past pumpage, annual acreage estimates, and estimates of water-use coefficients also contribute to the uncertainty, but collectively were less significant than the application rates (Moreo, 1999).

2.5 Environmental Issues Associated with Water Demand

Buqo, 2004, and others have related many of the sensitive issues associated with groundwater withdrawals in the Pahrump Valley area. Several of the key issues include the following:

- Impacts to endemic populations of desert pup fish. These fish are found in isolated springs that are susceptible to drying up due to groundwater withdrawals. At present, the closest documented population of pupfish, to the study area, is located approximately 40 miles to the north, within the Ash Meadows National Wildlife Refuge (Riggs, A.C. & Deacon, J.E., 2002).
- Impacts to phreatophyte vegetation (Bosques). This type of natural vegetation requires shallow groundwater to survive. Relict stands of this type of vegetation exist in Pahrump Valley.
- Earth Fissures. Earth Fissures are caused by land subsidence from groundwater withdrawals. They are commonly found in areas where there is marked contrast in the amount of subsidence, such as along geologic faults and the margins of buried bedrock highs. At least five areas of earth fissures have been documented in Pahrump Valley. Some of these fissures have caused structural damage to homes and infrastructure.

Springs and Fish

Many of the environmentally sensitive areas of Pahrump Valley have already been eliminated by human activities. Before development of groundwater in Pahrump Valley, both Bennetts and Manse Springs (the two largest springs in the study area) discharged continuously, with a combined annual discharge of approximately 10,000 acre-feet. By 1962, Bennetts Spring was dry and Manse Spring only discharged seasonally (Malmberg, 1967). The natural habitat associated with these springs has been destroyed and the native Pahrump killifish had to be relocated by the U.S. Fish and Wildlife to a refuge to protect it from extinction.

In 2006, the Public Broadcast Stats recently presented a documentary on the Death Valley, Nevada, Devils' Hole Pupfish. The hole itself is a fissure in the earth surface that split open 60,000 years ago to reveal a water-filled limestone cavern. "This is the only place on the earth where this fish exist naturally" says Zane Marshal, head diver for the Devil's Hole Pupfish

Recovery Team. Scientists have estimated that this species has been in isolation in excess of 25,000 years.

President Harry Truman, in 1952, designated Devils Hole a disjunct part of Death Valley National Monument. By the late 1960's, development and nearby farming beyond the boundaries of the monument began to take a toll on the water levels in Devil's Hole. What ensued was a bitter contest over water rights that pitted developers against conservationists and the federal government against a corporate farm. In 1976, the U.S. Supreme Court issued a landmark ruling that protected not only the fish but also their fragile habitat specifically stating that water levels in Devils Hole must remain high enough to completely cover a designated spawning shelf at the site. As a result of the ruling, development was halted, and the fish became one of the very first species to be protected under the Endangered Species Act.

Despite 30 years of Federal protection, recent fish counts suggest the fished population is plummeting. Linda Manning, a biologist for the Death Valley National Park reports that the current fish count is the lowest in 32 years of only 123 fish. This time, however, the reasons for their decline are not so clear.

In addition to conducting quarterly counts of the fish, the Park Service has installed monitoring wells near Devils Hole to monitor water levels which have been dropping gradually over the past 14 years. Development and groundwater pumping in nearby Pahrump, Nevada has long been suspected of affecting the water level in Devils Hole, though many Pahrump officials deny the allegations.

Bosques

Additional environmental issue is the potential impact of declining water levels on the mesquite bosques in the southern part of Pahrump Valley. These bosques provide habitat for a number of species of birds and mammals. The groundwater in some of these areas has declined to almost 50 feet below land surface, the limit at which mesquite trees can maintain their vigor. Monitoring of water levels in these areas is needed to determine the rate of water level decline and mitigating measures need to be evaluated. Mitigation could include the application of treated waste water to the bosques or injection of the water immediately up-gradient of the bosques.

Earth Fissures

Groundwater withdrawal has induced surface earth fissuring in portions of Pahrump Valley causing the destruction of roadways and private property. Five principal zones of earth fissures are presently known within Pahrump Valley (Figure 2). They were first noted during field mapping in 1999 at which time several zones were found occurring along fault scarps on the eastern and southwestern margins of the valley. Two discontinuous zones were mapped along north-striking fault scarps in the Hafen Ranch Road area where fissures ranging in length up to 300 feet were observed near the crest of the scarps (dePolo *et al.*, 1999). A similar set of fissures were also mapped along a northwest-trending scarp at the southern end of Pahrump Valley Boulevard and Plantation Street. Owing to a lack of previous investigations, it is

uncertain when the Hafen Ranch and Plantation zones first developed. A fourth zone of fissuring has recently developed in the Homestead Boulevard area where a series of fissures opened following intense rain in the fall of 1997. This zone has continued to develop, with additional fissures opening and structural damage occurring to homes in this area in the fall of 2004.

A fifth zone of recent fissuring also occurs southeast of Pahrump Valley in an area outside of the principal zone of known water-level decline and subsidence. The Front Sight zone consists of large continuous fissures as much as 3 to 6 feet in width and more than 300 feet in length. This area is immediately north of the Mary Wily Trust property.

Prior to the discovery of fissures in Pahrump Valley in 1999, little was known regarding the occurrence of subsidence. Pahrump Valley has no historical benchmark data available for detection of long-term subsidence due to groundwater pumping and water level declines. In an effort to determine the magnitude and spatial pattern in Pahrump Valley a study was initiated (Utley, 2004) designed to detect and measure land subsidence, if any, occurring during the last two decades, and to determine whether the subsidence patterns could be correlated with the distribution of fissure zones.

Based upon GPS surveying of existing USGS benchmarks, as much as 20 cm of subsidence have been recorded in parts of Pahrump Valley since 1981. In addition, Interferometric Synthetic Aperture Radar (InSAR) studies within Pahrump Valley have been conducted to delineate the spatial pattern of subsidence occurring since 1992. Synthetic aperture radar interferometry (InSAR) uses interferometry and global positioning systems (GPS) to detect ground subsidence due to groundwater withdrawal.

There are three main zones of subsidence in Pahrump Valley indicated by InSAR, as well as a general trend of subsidence encompassing the Town of Pahrump. InSAR results can be preferable to GPS because InSAR is a spatially complete study. InSAR indicates subsidence "zones" rather than values at given points as is the case with GPS (Figure 2).

3. GENERAL SITE CONDITIONS

3.1 Geology

The rocks of the region are divided into two generalized groups. The division is based mainly upon the water-bearing character and the relative stratigraphic position of the rocks with respect to the occurrence and movement of groundwater: the consolidated rocks that form the mountain ranges and underlie the valley fill, and the unconsolidated and partially consolidated sedimentary deposits of the valley fill.

A majority of the bedrock topography is concealed by younger valley fill deposits, but is visible in the surrounding mountain ranges, Figure 5. The lithologic units comprising the valley fill deposits consist of younger and older clastic alluvial deposits and include a basal volcanic tuff. The lithologic units comprising the bedrock are primarily limestone, dolomite, sandstone, shale,

and quartzite, with lesser amounts of intrusive igneous rocks, tuff, breccia, and volcanic flows (Malmberg, 1967).

Wells drilled in the valley range from several tens to more than a thousand feet deep. With the exception of one or two wells on the margin of the valley, no reported deep wells within the Pahrump Valley fully penetrate the valley fill and encounter bedrock at depth. Only a few wells have been drilled in excess of 1,000 feet in depth. A three dimensional model of the bedrock basement beneath Pahrump Valley was constructed (Blakely and others, 1988) based upon inversion gravity data. The data presents the thickness of the Valley fill materials up to 2,200 meters or 7,040 feet in depth (Figure 3). The maximum thickness of valley fill materials in the project area based upon the gravity data is estimated at 1,600 meters or 5,120 feet (Figure 3). Harill, 1986, estimated the maximum thickness of the valley fill deposits on prior gravity work at 4,800 feet in the central part of the valley.

3.2 Geophysics (Gravity and Magnetic Data)

Several previous investigators, Healey and Miller (1965), Kane and Carlson (1964), Chapman and others (1971) and Healy (1973) have constructed Bouger gravity anomaly maps that include parts of Pahrump Valley. They give a rough approximation of the subsurface configuration of the valley-fill reservoir. Rough quantitative estimates of the thickness of the valley-fill deposits were developed by making a two-dimensional analysis of the anomalies along four cross sections. In general the analysis shows thickest accumulations of valley fill maximums are along the axis of the Valley south of State Route 372 at approximately 4,800 feet in thickness. The area of maximum thickness was interpreted to be offset towards the south end of valley, which suggests some structural relief in the area, which is now attributed to the State Line Fault System. The shape of the structural depression was interpreted to change from a broad shallow trough north of State route 372 to a composite depression south of State route 372. In this area the basin consists of a broad upper trough that spans the entire width of the valley and has a maximum depth of 2,000 to 2,500 feet, and a second trough 1,000 to 2,000 feet deeper that occupies the central part of the first depression, suggesting the basin probably contains significant internal structures (Harrill, 1986).

A high resolution aeromagnetic survey of the Amargosa Desert and surrounding areas conducted in 1999 by the USGS in cooperation with the U.S. Department of Energy provides insights into the buried geology of the region. The survey covered an area approximately 2,970 miles and includes parts of the Nevada Test Site, Death Valley National Park and includes coverage in Pahrump Valley. The aeromagnetic flight lines were orientated east-west, spaced 0.25 miles apart, and flown at an altitude of 500 feet above terrain (Blakely, 2000). The basement surface is relatively flat and shallow around the margins of the basin, but the surface is interrupted by numerous deep, steep-sided basins. At Pahrump Valley the basement surface is generally flat and within 660 feet below the land surface through out most of the basin, but this gentle topography is punctuated by two prominent, laterally restricted sub-basins. The sub-basins are separated by a gravity ridge that strikes northwest parallel to and north of the California-Nevada state line. The thickness of the deposits exceeds 2 km in the southwestern sub-basin and 5 km in the northeastern sub-basin. Both sub-basins are elongated in the

northwest-southeast direction and have exceptionally steep margins, with dips ranging from 25 degrees along the southwest margin to 65 degrees along the northeast margin, significantly exceeding the average slopes of the surrounding mountain ranges (Blakely, 1998).

The bedrock basement topography of Pahrump Valley is complex. The valley is underlain by two steep, narrow-sided sub-basins separated by a basement ridge that runs approximately parallel to the California-Nevada state line: the State Line, or Pahrump Valley fault zone. It is a right-lateral, strike-slip fault zone, considered to be part of the Walker Lane belt. Blakeley and others (1998) suggest that the region developed as a complex system of transtensional basins transferring strain between an echelon, northwest-striking, right-lateral, strike-slip faults. It is likely that this fault zone serves as a barrier to groundwater flow to the southwest from the Spring Mountains (Lundstrom et al, 2003). Springs and stands of Mesquite along the northeast side of the fault zone support this interpretation (Harrill, 1986).

3.3 State Line Fault Zone

The State Line fault zone (Wright, 1988) in Pahrump Valley and Ash Meadows is a right lateral, strike-slip zone of deformation that lies approximately parallel to the California-Nevada state line and within the Walker Lane belt. Wright (1988) proposed that Pahrump Valley and Ash Meadows are pull-apart basins, transtensional structures caused by right steps in the right-lateral State Line fault zone. Three dimensional models based upon gravity measurements support this interpretation but indicate complex basement structures beneath both Pahrump Valley and Ash Meadows (Blakely and others, 1998, 1999). Pahrump Valley is underlain by two deep, isolated sub-basins lying astride the state line. The intervening basement ridge is apparently a horst-like structure caught between strands of the State Line fault zone. A similar ridge beneath Ash Meadows also separates several sub-basins and is on strike with the Pahrump Valley ridge. Magnetic anomalies over Pahrump Valley are very subdued, as expected for an alluvial filled basin. A cluster of magnetite lineaments follows the State Line fault in Pahrump Valley, where some of the individual anomalies correspond to Quaternary faults mapped by Hoffard (1991) and Lundstrom and others (2000). This general pattern of anastomizing magnetic lineaments continues northwestward along the state line a distance of 62 miles (Blakely, 2000).

Pahrump Valley is cut by a series of late Tertiary to Quaternary aged faults which displace the basin fill deposits. The fault scarps were originally believed to be of compaction origin but are now known to be primarily of tectonic origin. The fault scarps in Pahrump Valley all display down-to-the -west offset and are structurally linked to the right lateral strike slip Pahrump-Sateline fault (Bell and others, 2005).

Due to the tectonic regime in the area, the consolidated bedrock is intensely folded and faulted, with a rugged surface of high relief in the mountainous regions (Malmberg, 1967). The crystalline and clastic units of the bedrock are fractured and likely contain some water, although fractures are generally tight and do not readily transmit water. The carbonate rocks contain fractures and solution channels and are moderate to highly permeable on a local scale. This reservoir type rock permits transmit of water between topographic divides. The consolidated

bedrock aquifer allows for fluid transport down-gradient from the Spring Mountains through Pahrump Valley to the southwest and into Stewart Valley, west of Pahrump Valley. Tests completed at the Nevada Test Site have shown coefficients of transmissibility, defined as the rate flow of water in gallons per day through a 1-foot-wide vertical strip of the aquifer under a hydraulic gradient of 100% (Theis, 1935), ranging from 400 to 900,000 gallons per day per foot (gpd/foot). Due to the depth of the system and possible salt contamination, however, this groundwater resource has not been developed in Pahrump Valley.

The valley fill deposits in Pahrump Valley are primarily alluvial in nature and are characterized by a broad sequence of alluvial fan deposits developed along the western slopes of the Spring Mountains and grading basinward into fine-grained sequence of basin-fill deposits. The oldest recognized deposit in Pahrump Valley is a partially consolidated, highly indurated tuff of Tertiary age with an unknown thickness. Alluvial fans dominate the northeast portion of the valley; prominent fans have formed at the mouths of Wheeler, Wallace, Carpenter, and Trout canyons and have coalesced to form the larger Pahrump and Manse fans (named for the ranches developed at their toes). The deposits consist of boulders, gravel, sand, silt, and clay derived from older fans and exposures of consolidated rock (Malmberg, 1967).

Although the basin fill deposits were originally believed to be of lacustrine origin, they are now known to be largely of paleo-spring origin having formed during wetter climates of the late glacial/pluvial periods (Quade *et al.*, 1995). Much of the material comprising the alluvial deposits is reworked from older paleospring deposits (de Polo *et al.*, 1999). Radiocarbon dates on snails and organic soils in Pahrump Valley place the age of the bulk of these deposits at about 10,000 to 25,000 ka. Arroyos up to 30 meters deep have been incised into the fans; the channel deposits within them consist of unconsolidated, fairly well-sorted gravel, sand, and silt. These deposits, when they lie within the zone of saturation, yield large quantities of water (Malmberg, 1967).

Spring mounds are common around the valley and are composed of fine-grained, calcareous, organic-rich silt, clay, and mud. Non-cemented fluvial sand and mud, as well as interbedded sand, silt, mud, and gravel occupy the top 50 cm to 2 meters of the valley fill (Lundstrom *et al.*, 2003). Estimates by Harrill (1986) indicate that the thickest valley fill deposits lie within the valley center, and measure approximately 1463 meters (4,800 feet).

The valley fill has been grouped into two units based on geology and hydrologic properties: coarse grained alluvial deposits that occupy the margin of the valley, and fine-grained lacustrine and playa deposits occupying the central part of the valley. The coarse-grained deposits generally lie on the perimeter of the valley and provide the most productive aquifers. The most expansive of these deposits lies along the northeast side of the valley, at the foot of the Spring Mountains. Specific capacities of 20 wells along the foot of the Pahrump and Manse fans in 1967 ranged from 5 to 185 gpm (gallons per minute) per foot of drawdown (Malmberg, 1967). Well yields tend to decrease southwest from the fan, as the deposits change from coarse-grained on the valley margin to fine-grained at the valley center. The fine-grained deposits tend to have high amounts of clay, causing them to generally be very poor aquifers (Malmberg, 1967). The town of Pahrump lies in the northeastern portion of the valley, at the foot of the Pahrump fan; most wells in the town tap the coarse-grained valley fill deposits as a groundwater source. There is some interfingering of the coarse-grained valley fill into with the fine-grained

valley fill; some aquifers exist in the center and southwest areas of the valley where few wells have been drilled (Malmberg, 1967).

Within Pahrump Valley water discharges along the northeastern margin of the state-line ridge (fault?) itself. The basement ridges are presumably composed of carbonate rocks and therefore could serve as conduits for groundwater moving northwest to southeast. Perhaps the basement ridge acts like a leaky pipe; water flowing freely northwest–southeast within the ridge is very near the topographic surface relative to water beneath the deep sub-basins, and this may promote the rise of water to the surface where it discharges at springs lying parallel to the subterranean ridge. More likely, reverse faults that bound the northeastern and southwestern margins of the ridge act as barriers to groundwater flow. Water reaching the basement ridge from the north and east may be shunted to the surface. The association of the Pahrump Valley springs and the state-line ridge supports this interpretation. Therefore, it is predicted that water is more abundant along the northern margin of the state line ridge than else where in Pahrump Valley (Blakely, 1998).

3.4 Topography

West of the community of Pahrump, the valley floor is a broad and flat ancient playa or lake bottom. The valley floor slopes gently upward to the toe of the Pahrump fan and has an average gradient of about 15 feet per mile. Storm water runoff reaching this part of the valley generally spreads over a broad area and collects in shallow depressions from which it is eventually discharges by evaporation and transpiration.

The topography of the valley near Hidden Hills Ranch (part of the study area) headquarters, in Nevada, is characterized by low hills, ravines, mesas, and box canyons. Between the northeast edge of the playa and the Manse Ranch, the valley floor slopes upward (northeastward) about 30 feet per mile. Locally the gradient is much steeper, however. The hills and the scarps are breached in several places by deep, southwest-trending arroyos, the largest of which are near Hidden Hills Ranch in Nevada.

The southwest side of the Spring Mountains is characterized by large alluvial fans that head high in the canyons leading from Mount Charleston. The most prominent of these alluvial fans have formed at the mouths of Wheeler, Wallace, Carpenter, Trout and Lovell Canyons, and have coalesced to form three major fans called the Pahrump, Manse, and Lovell fans. The fans extend far into the valley and are among the most notable topographic feature of the valley. (The Environmental Data Bank of Independence, 1974).

3.5 Climate and Precipitation

The climate of southern Nevada ranges from arid to semiarid. Pahrump Valley is arid and is characterized by small amounts of precipitation, low humidity and wide extremes in daily temperatures. Winters are short and mild, and the summers are long and hot. Precipitation occurs mainly during the winter and it generally increases in abundance with altitude. Winter

storms are commonly regional in nature whereas summer storms ordinarily occur as vary localized thunderstorms in the mountains. At the lower altitudes, evaporation rates are high, exceeding 100 inches per year. Strong winds are common throughout the year, but are more prevalent in the spring than in the other seasons.

The average summer high temperature for the summer months of April through September is 95 degrees Fahrenheit (°F). July has a historical 30 year high of 106°F. The months of June, July, and August typically average in excess of 100 F. The average winter low temperature for the months of October through March is 41°F. While the winter low temperature typically occurs in December or January and averages 34°F. All data presented is based upon 30 year historical datum (Wunderground, 2006).

Precipitation in southern Nevada ranges from less than 4 in/yr in some of the low-lying areas, including much of Amargosa Desert and Death Valley, to more than 20 in/yr in high altitude areas of the Spring Mountains and Sheep Range. Precipitation index datum for Spring Mountains from year 1965 to year 2000 show a mean precipitation of 21.24 inches per year (Fenelon, 2002).

Early climatological data have been obtained intermittently at Pahrump Ranch from 1914 through 1962. During the years of record the annual precipitation ranged from 1.88 to 7.26 inches and averaged 4.18 inches (USGS Water Supply Paper-1832).

Subsequently the National Weather Service (NWS) converted the Pahrump Ranch climatological station to an established climate station. The precipitation station location is presented in Figure 4. Available NWS datum ranges from year 1948 through year 2005. The average annual precipitation for the reported years is 4.48 inches. The average precipitation for the last ten years from year 1995 through year 2005 is 5.05 inches (USGS Water Resources Report-01-4195) (Appendix A).

Additionally two precipitation stations were installed on the west slope of the Spring Mountains at Roberts Ranch (A.K.A Trough Springs), elevation 8,500 feet msl, and Red Rock Summit (AKA Clark Canyon Station), elevation 9,000 feet msl (Figure 4). Recorded precipitations for year 1945 through year 1962 are documented. The average annual precipitation for the Trough Springs Station is 11.5 inches and for the Clark Canyon Station is 14.9 inches (Appendix A).

Precipitation patterns for various periods from 1960 to 2000 were compared to trends in groundwater levels and spring discharge. Long-term (30 years) records of precipitation data were compiled and analyzed for selected precipitation stations within the Yucca Mountain region. Three precipitation sites monitored by the NDWR within the Spring Mountains at elevations of 4,000 and 9,000 feet were utilized for precipitation indices (Fenelon, 2002). Locations of the precipitation stations are presented in Figure 4.

3.6 Recharge Sources

The major source of recharge to the Death Valley Regional Groundwater Flow System (DVRGFS) is from precipitation on the highest mountains within the region (D'Agnese et al. 1997, p. 50). The regional flow system is also recharged by interbasinal flow. Some recharge also results from recycled irrigation and domestic waters, as well as seepage of spring discharge back into the groundwater system (Rice 1984, p. 25). However, these recycled components are considered to be small and negligible compared to regional infiltration and interbasinal flux volumes (Waddell 1982, p. 14).

Recharge to the basin is derived from the percolation of runoff through alluvial deposits at the base of the bordering mountains, and from the infiltration of precipitation that falls to the valley floor. Pahrump Valley is a topographically closed basin from which there is no surface-water flow. No perennial streams exist in the area, except for short distances below the springs. Water from larger springs and from snowmelt in the mountains seeps into the gravel of the drainage ways within short distances. Summer thunderstorms, though infrequent, cause these and other washes to carry surface water for only short periods of time. Runoff from precipitations within the basin ends in one of two playas that lie at the base of the Resting Springs and Nopah Ranges on the southwest side of the valley. The northwestern-most playa, lies in Stewart Valley (a small valley between a bedrock spur and the Resting Spring Range which is hydraulically continuous with Pahrump Valley) is the larger of the two playas. It is of irregular shape and includes an area of about 6.5 square miles. The second playa, located about 13 miles southeast of Stewart Valley, about 3.5 miles by 2.5 miles in maximum length and width, lies about 60 feet higher than the larger playa which stands at an elevation of 2,457 feet (The Environmental Data Bank of Independence, 1974).

Runoff from most of the drainage area southeast of the Manse Ranch (in Sec. 4, T.21S, R.54E, MDB&M) flows into the Pahrump Valley playa, and runoff northwest of the ranch flows to the playa in Stewart Valley (The Environmental Data Bank of Independence, 1974).

Groundwater is confined near the margins of the dry lakes and along the base of alluvial deposits originating from the Spring Mountains in the Nevada portion of the basin. Groundwater discharge from the alluvial aquifer occurs mainly through pumpage and spring discharge, or by evapotranspiration (Waring 1920, DWR 1964). Hunt and other (1966) have suggested that some discharge from the basin occurs as inter-basin underflow by way of a deep regional carbonate rock aquifer system that transfers groundwater into the lower lying Amargosa and Death Valley Groundwater basins.

3.7 Discharge Sources

Groundwater discharge from Pahrump Valley occurs by pumping from wells, by evapotranspiration, through spring discharge, and by subsurface outflow principally to areas southwest of the valley. Prior to the construction and use of large capacity wells in about 1912, all discharge was by natural process.

3.8 Water Sources

Presently, the only utilized source of groundwater in Pahrump Valley is the valley-fill aquifer. The current estimated water use is approximately 23,000 acre-feet per year (Bell and others, 2005). The perennial yield of the Valley fill aquifer has been estimated at 12,000 to 19,000 acre feet per year. According to Mr. Bill McCulars (Nevada State Engineers Office) the State of Nevada has appropriated approximately 64,500 acre feet of water for consumptive use in the Pahrump Valley. They are actively rescinding appropriations since estimates prepared by the USGS (Water Supply Paper 1832, 1967) indicate that there are only 12,000 af/y of recharge to the valley. The results of recent re-evaluations of water budgets in southern Nevada suggest that the perennial yield of Pahrump Valley could be higher, on the order of 30,000 acre feet per year or more. But even if the perennial yield were 38,000 acre feet per year (double the U.S. Geological Survey estimate), there is still insufficient recharge to meet the projected demand. Current groundwater withdrawals are distributed throughout much of the basin. Buqo (2004) presented a figure showing the distribution of water use in 1999 (Appendix B). Total groundwater withdrawals are shown for each section of land based upon the Division of Water Resources pumpage inventory and the number of domestic wells in each section.

Practically all discharge of groundwater in the valley is by pumping from wells which are principally located in the north end of Pahrump Valley. From the mid-1940s through 1962, the annual discharge from wells increased from an estimated 10,000 acre-feet to about 28,000 af/y. Montgomery Engineers, 1970, estimated that pumping that year was in the order of 48,000 acre-feet per year.

3.9 Evapotranspiration of Aquifer Storage

Evapotranspiration (ET) occurs primarily in discharge areas, where depths to groundwater are shallow. Three primary natural discharge areas in the area are Ash Meadows, Alkali Flat, and Death Valley, D'Agnese and others, 1997 (p. 45-46). In these areas, evaporation from moist soils and transpiration by phreatophytes account for most of the ET. Shallow groundwater levels can be influenced by ET. In Ash Meadow, (Lacniak and others 1999) analyzed the response of groundwater levels to ET in 27 shallow wells that were 5 to 60 feet deep, and developed the following observations. Annual water level fluctuations caused by ET ranged from about 0.4 to 10 feet. Super imposed on the annual fluctuations in many of the shallow wells were short term responses to local precipitation events that typically attenuated in about 2 weeks or less. The annual maximum depth to water occurred in late summer or fall, shortly after the maximum ET rate for the area. The magnitude of the annual change in water table from the effects of ET is not proportional to the rate of ET because other factors influence water-table declines, such as the depth to the water table, distance to a local surface-water source, and aquifer and soil properties. Additionally, the deeper a well is screened below the water table, the less the water level in the well will respond to ET (Fenelon, 2002).

4. AQUIFER SYSTEMS

Groundwater in Pahrump Valley occurs in two principal aquifers: valley fill and carbonate rocks. The valley fill, as the name implies, fills the saucer-shaped depression which has been formed in the bedrock. The carbonate-rock aquifer underlies the valley fill and extends into the adjacent hills and mountains.

4.1 Alluvial Aquifer System

The water-bearing alluvium covers an area of at least 650 square miles, or approximately two-thirds of the total area of Pahrump Valley and has an average saturated thickness of about 1,000 feet. Confined groundwater occurs along the distal margins of Pahrump, Manse, and Lovell alluvial fans. Fine-grained deposits, those that crop out in an area of about 350 square miles in the central part of Pahrump Valley, are composed principally of silt, clay and fine-grained sand. Principal lithologic units are tuff of Miocene/Pliocene age or older, sand and lacustrine deposits of Pliocene and early Pleistocene age, and younger surficial deposits of Pleistocene and Recent age. The beds of tuff and overlying younger lacustrine deposits are exposed in the central part of the valley, where they have been uplifted and faulted and subsequently exposed by erosion. According to the study made by the U.S. Geological Survey, (USGS) the predominance of clay throughout the fine-grained deposits causes them to be low-production aquifers.

4.2 Carbonate Aquifer System

The carbonate-rock aquifer is composed of carbonate sedimentary rocks from the Cambrian to Permian age that crop out in the Spring Mountains, underlies the valley fill of Pahrump Valley, and extend westward through the Nopah and Resting Springs Ranges into California. The water is generally unconfined and permeability may vary from moderate to high.

No wells in the study area penetrate the carbonate aquifer, so its properties must be inferred from information about other areas. The aggregate stratigraphic thickness of the rock sequence may be as much as 18,000 feet; however the rock have been complexly faulted and folded, and the aggregate vertical thickness at any one place may be substantially more or less (Harrill, 1986). The USGS has estimated a maximum thickness of 20,000 feet for the carbonate aquifer.

Hydraulic continuity is probably achieved through extensive fractures and, to a lesser degree, by localized solution channels. The effective fracture porosity of the lower aquifer was estimated by Winograd and Thordarson (1975) to average less than 1 percent, although locally it may be higher. If these rocks were to be dewatered by pumping or other means, the average specific yield would be low, probably on the order of 0.005.

Reported transmissivity values are highly variable. Winograd and Thordarson presented transmissivities from the results of pumping test of 10 wells that penetrated one or more formations of the lower carbonate aquifer. Values ranged from 130 to 120,000 feet squared per

day (ft²/day). They suggested that the wide range of transmissivity may not be randomly distributed but structurally controlled. Harrill (1986) presented the average transmissivity of the lower carbonate aquifer around and beneath Pahrump Valley to be between 1,500 and 2,500 ft²/day. The estimated hydraulic conductivity from previous modeling studies conducted for the Death Valley regional groundwater flow system (DVRFS) for the carbonate aquifer was presented to range from a minimum of 3.3×10^{-4} feet/day to a maximum of 2,690 feet/day (Belcher, 2002).

4.3 Regional Flow Regimes (both Shallow and Deep), Gradients and Flow

In 1962 the assessed movement of groundwater in the valley-fill aquifer as generally southwestward across the valley. Contours of the water table constructed by the Geological Survey indicate that near the southwest side of the valley the groundwater moves into the Nopah and Resting Spring Ranges that border the subject site. The depth to water varied in 1962 from 21 feet in Stewart Valley, to more than 200 feet, at the base of the Kingston Range. The hydraulic gradient averages about 20 feet per mile along the 35-mile length of the valley trough (USGS Report-1832).

Most groundwater is transmitted from Pahrump Valley southwestward through the Hidden Hills Ranch Mountains to California (The Environmental Data Bank of Independence, 1974). In 2002 the USGS completed a hydrostructural map of the Death Valley region as part of the Nevada Nuclear Test Site evaluation. The Study presented current potentiometric or groundwater water level information for Pahrump Valley. The water level information has been incorporated into Figure 4 (Potter, 2002). Included in the figure are groundwater levels recently acquired by AMEC from project site wells. Both data sets correlate. The overall regional and project site groundwater flow is presented in Figure 4 and depicts a southwesterly flow from the Spring Mountains down into Pahrump Valley.

Water surface is relatively flat in the southern portion of Pahrump Valley, California, and is at an elevation of approximately 2,500 feet. Water levels obtained by AMEC, easterly of the inferred State Line Fault Zone, that parallel the state line, indicate that the water surface in the alluvial aquifer is nearly 200 feet higher in the vicinity of Hidden Hills Ranch. These data also supports previous statements that the State Line Fault system may impact the westerly flow of water towards the Study Area.

Due to a lack of wells completed in the Carbonate reservoir not enough detail is available to derive the overall aquifer flow regime and gradient. It is estimated that all discharge of groundwater from the carbonate-rock reservoir in Pahrump Valley is by subsurface outflow beneath topographic divides to southwest at Chicago and California Valleys and possibly to the north towards Ash Meadows (Figure 4).

4.4 Groundwater Level Trends (HYDROGRAPHS)

Harrill (1986) presented hydrograph data ranging from 1948 through 1975 for select wells throughout Pahrump Valley (Appendix C). Overall Harrill presented that water levels in the wells have been declining since the first wells were constructed in 1913. The annual rate of decline and net change vary at different locations, depending on the distribution of pumping, hydraulic properties of the valley fill, and the depth of the well being measured. Harrill presented hydrographs of six observation wells. Generally the greatest declines occurred along the base of the Pahrump and Manse fans, where maximum declines of about 100 feet were observed. Two wells located away from the fans within the central portion of the valley exhibited substantially lesser rates of water-level decline. Both wells are relatively shallow in depth (about 400 feet deep). One of the 400-foot wells (Well 162 S22 E5301AAA1) is located in the north central portion of the project site. Water level data from this well obtained from 1965 through 1975 depicts a water decline rate of approximately 7.2 inches per year (Harrill, 1986).

Buqo (2004) (Appendix B) presented historical water level declines and rises in Pahrump Valley for the period 1940 through 2000. This figure shows the long-term water level measurements taken by the U.S. Geological Survey at nine wells and supplemental water level data from the Nevada Division of Water Resources. As shown, there are two basic trends in water levels in the northern basin, 1) declining water levels until about 1980 followed by a rise in water levels over the last two decades, and 2) a general decline in water levels over the entire period of development. A reduction in pumping rates since peak withdrawals in 1969 and a number of wet years in the 1980s and 1990s have generally reversed the water level declines along the toe of the alluvial fan in the eastern part of the valley floor. In this area, the groundwater levels have risen by as much as 45 feet from their historic lows in the late 1970s and early 1980s. Water levels have dropped over the last 50 years in wells around the town of Pahrump, and are expected to continue to decline at an average rate of 1 to 3 feet per year (Buqo, 2004).

The United States Geological Survey NWIS Web Database was searched for groundwater levels throughout the entire extent of Pahrump Valley, and into locally adjacent valley's. Water level data for 182 sites were identified within and locally adjacent to Pahrump Valley. The majority of wells presented water level information up until year 1976, but nothing beyond. Eleven wells were identified having consistent historical and current water level measurements, some wells being the same as presented by Harrill (1986) and Buqo (2004). The USGS hydrograph plots and tabular data is presented in Appendix A & C. Locations of the hydrograph wells are presented in Figure 4. The southern half of Pahrump Valley resulted has 17 well sites with groundwater level data. None of the data reviewed depicted a consistent trend or provided a reasonable estimate of water level fluctuations.

Data from four of the eleven wells reviewed are located in the northern portion of Pahrump Valley. These data depict a relatively stagnant to an increase of groundwater levels since the 1975-1976 groundwater level data was presented by Harrill. The four wells have consistent water level datum through year 2003 and 2004. All four wells are situated along the eastern valley-fill alluvium locally adjacent to the Pahrump and Manse Alluvial fans. The hydrographs depict a leveling of water levels in the early 1980's followed by a gradual recovery in water levels of up to 30 feet. The well completion depths range from 395 feet to 800 feet bgs, and

therefore represent both shallow and deeper aquifer conditions locally adjacent to the principal valley recharge infiltration source, the Spring Mountains. One well has consistent water level datum through year 2003 & 2004, and depicts a continued gradual decline. The well is 69 feet in depth and locally central to the Stewart Valley near the Stewart dry lake and is the most distant hydrograph well from the Spring Mountains. The remaining hydrograph wells are more central to the basin and depict a minimal fluctuations in of groundwater levels from 1989 through 1997 at which point water level data is not available.

Withdrawals in Pahrump Valley declined from an average of 37,324 acre-feet/year from 1960 to 1979 to 24,629 acre-feet/year for 1990 to 1998. The reduction coincides with a transition from agriculture to municipal water use in Pahrump Valley. Irrigation use declined from about 46,956 acre-feet per year in 1968 to about 14,818 acre-feet in 1998. Conversely, domestic and municipal use rose from 301 to 7,956 acre-feet per year in the same period (Modified from Fenelon, 2002).

Fenelon (2002) noted that in recent years, a decrease in overall pumping caused water levels to recover in some parts of Pahrump Valley, while water levels in other parts of the valley declined. Withdrawals from Pahrump Valley, and resulting water-level declines, might intercept natural recharge supplied by Spring Mountains to the Ash Meadows groundwater subbasin (Fenelon, 2002).

Water line measurements obtained by AMEC in the Fall of 2005, indicate depth to groundwater level varies from 92 feet to 169 feet in the project area. These data are consistent with other historic data obtained during this study.

Generally, long-term water-level changes local to the project site cannot be inferred from consistent water level measurements. Geotechnical Consultants, Inc (1966) reported that Well 22N 10E 27R1 California San Bernadino Baseline and Meridian reported a water level elevation of 122.5 feet bgs. Comparison of the September 2005 water level measurements shows the water level to have risen approximately 22 feet.

4.5 Water Quality

The United States Geological Survey NWIS Web Database was searched for groundwater quality results within a 383 mile square area surrounding the southern portion of Pahrump valley and locally surrounding the Project area. Analytical results were generated and evaluated (Appendix D). The dates of the data presented range from 1949 to 2002. The majority of results are pre 1970. One site reports recent constituent concentrations from year 2002. Review of the reported constituent levels shows no reported concentrations of concern.

The California Department of Water Resources (CDWR) Bulletin 118 stated "Currently, the overall quality of the groundwater in Pahrump is quite good. The character of the groundwater varies from calcium-magnesium bicarbonate to magnesium-calcium bicarbonate. The quality of groundwater is suitable for all beneficial uses. TDS concentrations range from about 145 to 540

mg/L, with an average concentration of about 340 mg/L. Fluoride content ranges from 0.1 to 0.8 mg/L and averages about 0.4 mg/L. Boron content averages about 0.1 mg/L."

The Geological Survey Water-Supply Paper 1832 Hydrology of the Valley-Fill and Carbonate-Rock Reservoirs Pahrump Valley tabulated chemical analyses made by several agencies for water from 43 wells and 5 springs in Pahrump Valley and vicinity (Appendix C). Of the analysis presented, 18 analysis include primary cations and anions (common chemical elements and compounds) and 30 are partial analysis (specific conductance, chloride, hardness, and pH). Along the northeast side of Pahrump Valley, most groundwater in the Valley-fill reservoir is of calcium-magnesium bicarbonate type. The dissolved solids content of the groundwater increases as the water moves southwestward across the valley. Most of the water samples analyzed were obtained from shallow wells and the quality may not be indicative of water quality in the deeper aquifer. Analysis of water sampled in the vicinity of the California-Nevada boundary showed and increase in magnesium concentration in relation to calcium; magnesium being the principal cation in solution. Northeast of the state line, the total dissolved solids (TDS) content is generally less than 300 parts per million (ppm). Analysis of groundwater sampled along the southwest side of the valley showed a wide variation in the water quality. At the north edge of the Playa in Pahrump Valley, the water in well (N22/9-5abc) is high in magnesium, sodium, sulfate and total dissolved solids content. Else where on the California side of Pahrump Valley, the water is generally of magnesium bicarbonate type, having a TDS solids content less than 500 ppm.

As with most waters from the southern portion of the Basin and Range Physiographic Province, the groundwater is rated as "hard." Water quality local to the project area is generally considered to be "acceptable" based on chemical analyses of water from most wells reviewed indicated that it meets present drinking water standards. However, data presented in the Broadbent and Associates Inc., BIA, (Results of Preliminary Hydrogeologic Investigation of the Wiley Trust Property in Inyo County, California, 5/2003) report indicated that the water sample obtained from a onsite well contained an excessive contration of iron. Further analysis off water samples from the site are needed to assess specific onsite water quality parameters. Additional, historical, water quality analyses for Project wells specific are given in Appendix C. Recent water quality data from Project wells is not currently available.

4.6 Site Specific Studies

Previous hydrogeologic work has been performed at the property by BIA, 2003. This work focused on obtaining and analyzing data that relates to the subsurface conditions and potential yield of water to a production well. We understand from a preliminary review of these reports and discussions with Mt Steven Scow, Attorney, that there are 11 wells on the Site. One of these wells (located in section 24) was tested by BIA. Based on this test the report states that the assessed transmissivity of the aquifer in the vicinity of the well at 625 ft²/day. This report indicated that wells spaced at two mile intervals could provide up to 6,400 acre feet of water. Also additional, tests had been performed on these wells in the past but results of aquifer parameters (if assessed) were not reported by BAI.

The Environmental Data Bank of Independence prepared an Environmental Impact Report for the Site dated 1974 (1974 EIR). This report focused on the issues associated with development of the land into 20 acre agricultural lots. The report indicates that given proposed development in Pahrump Valley at the time that further agricultural development would not be feasible given the available recharge and water supply. However, site reconnaissance performed by AMEC and review of taped interviews of Mr. Al Carpenter (former Owner) indicated that the area was intensively cultivated from the early 1900's through the 1940's.

5. SITE WORK

The following presents an assessment of potential recharge to the Hidden Hills area as performed by AMEC. This assessment utilized data retrieved from published and recognized sources. The assessment described below is a fundamental step in understanding the development potential of the Hidden Hills area.

5.1 Background/Past Assessments

Empirical, water-balance, and distributed-parameter methods have been used to characterize the location and amount of recharge in the Death Valley region. Each method attempts to characterize the complex array of factors controlling recharge; each has limitations (D'Agnese et al. 1997, pp. 50-51).

Maxey and Jameson (1948) utilized an empirical precipitation-recharge relation to estimate the long-term average recharge to Pahrump Valley of 23,000 acre-feet per year. This estimate was based upon variable precipitation infiltration by specific elevation. Below 5,000 feet msl, which correlates to precipitation less than 8 inches per year no precipitation was retained as recharge because it was largely lost to evapotranspiration. Above 5,000 feet msl portions of the precipitation were recovered per 1,000 foot elevation change up to 8,000 feet msl.

The valley recharge was re-evaluated by Eakin and others (1951). The analysis method was also based upon the assumption that a fixed percentage of a given average annual precipitation ultimately infiltrates to groundwater. More elevation zones were used to correspond to actual average amounts of precipitation. No recharge occurred in zones where precipitation was less than 8 inches per year. The estimated average recharge was 22,000 acre-feet/year.

Malmberg (1967, pp. 26, 27) used the method described by Eakin et al. (1951) to reappraise the estimated recharge to Pahrump Valley, Malmberg (1967, pp. 26, 27). The analysis method was similar to the method described by Maxey and Jameson (1948) and was based on the assumption that a fixed percentage of a given average annual rate of precipitation ultimately recharges the groundwater reservoirs. However, Malmberg (1967, pp. 26, 27) uses more altitude zones to correspond more closely to the amounts of precipitation. These altitude zones are the same as the precipitation zones discussed by Malmberg and Eakin (1962, p. 19); however, Malmberg (1967, pp. 26, 27) includes additional precipitation zones of 7,000 to 8,000 feet and above 8,000 feet. Using this method, Malmberg (1967) estimates the average annual

recharge to Pahrump Valley to be 22,000 acre-feet and states that recharge estimated by this method may occur in three ways:

- By direct, infiltration of rainfall in areas that are generally higher than 5,000 feet.
- By seepage loss from streams in the mountains and in the valley.
- By lateral movement from the carbonate-rock reservoir, as well as from fractures in the other consolidated rocks to the valley-fill reservoir.

Because there were many unknown factors in the spatial distribution both of recharge to and of underflow between groundwater reservoirs, Malmberg (1967, pp. 26, 27) did not make direct estimates of recharge to each of the two aquifers (valley-fill aquifer or carbonate-rock aquifer). However, when discussing groundwater discharge of Pahrump Valley, an indirect "probable" division was made that computes annual recharge of 12,000 acre-feet to the valley-fill reservoir and 10,000 acre-feet to the carbonate-rock reservoir (Malmberg, 1967).

Harrill (1986, p. 22) refers to the recharge estimates made by Malmberg (1967, p. 36 page number cited by Harrill) for Pahrump Valley (22,000 acre-feet per year) which were based on a fixed percentage of a given average annual rate of precipitation. Harrill points out that recent techniques of estimating the percentage of precipitation recharge incorporated higher precipitation rates on the side of mountains facing a prevailing storm track and also used different percentage rates of precipitation recharge where there were significant areas of higher altitude. Applying these new techniques, Harrill estimated recharge from precipitation in Pahrump Valley to about 26,000 acre-feet per year. However, because there were insufficient data to determine which set of precipitation recharge was best, a range of recharge from 22,000 to 26,000 acre-feet per year was incorporated into Harrill's model.

The Maxey-Eakin method was modified by D'Agnese et al. (1997, p. 52) to make it more sensitive to the critical factors affecting recharge by using four potential recharge indicators existing within the Geoscientific Information System database. The four potential recharge indicators used by D'Agnese were:

- Altitude
- Slope-aspect
- Relative rock and soil permeability
- Vegetation

Four recharge potential maps created from the recharge indicators of altitude, slope-aspect, relative rock and soil permeability, and vegetation were overlain to produce a map that combined the ratings from each map. The accuracy and appropriateness of the modified Maxey-Eakin method were evaluated by D'Agnese et al. (1997, p. 55) by comparing a map of the new recharge areas with the maps showing locations of low-temperature springs and vegetation types. D'Agnese, et al., indicated that upon inspection, areas uphill from low-temperature springs, regardless of altitude, were found to be coincident with predicted regional recharge areas. Because vegetation constraints were incorporated in the rating criteria, all predicted recharge areas were restricted to vegetation zones classified as either Coniferous

Forests, Pinion-Juniper Woodlands, or Mixed Transition Shrublands. As a result, the refined recharge areas map was considered an improvement to the map based on the traditional Maxey-Eakin method and an acceptable indicator of areas in the region where long-term, regional groundwater recharge may occur. While the modified recharge areas may not exactly describe recharge locations on a local scale, they appear to be appropriate for delineating large-scale zones of recharge that is consistent with previous investigations (Prudic et al. 1993, pp. 23, 24 page numbers cited by D'Agnese et al.). D'Agnese evaluation resulted in a modified Maxey-Eakin method value of 20,247 acre-feet/year. However, it should be noted that even with better defined potential recharge areas, recharge rates are still based on empirical estimates rather than actual measured rates and reflect a significant unknown flux in modeling this region (D'Agnese et al. 1997, p. 55).

In the USGS Water-Resources investigations Report 02-4010, dated 2002, Hevesi presents a comprehensive assessment of recharge in the Death Valley Region of California and Nevada (approximately 39,000 square miles). This report details the estimated annual recharge for the Pahrump Valley using the Net Infiltration Model method. The Net Infiltration method is based upon a water balance grid model of unsaturated flow. The Net Infiltration Model method results were then compared to the empirical modified Maxey-Eakin method.

The USGS net-infiltration model inputs included:

- Precipitation
- Infiltration Inputs: Soils and Bedrock Hydrogeologic Rock Units
- Evapotranspiration Inputs: Solar Radiation, Air Temperature
- Latitude, Longitude, Slope, Elevation, Blocking Angles above a Horizontal Surface (Shading)
- Infiltration Root Zone Water Balance Model
- Vegetation

The USGS Net infiltration method was very comprehensive analysis and included a mass balance of precipitation, water entering the site as run-on, water leaving the site as run-off, change in soil water storage, and evapotranspiration. For the study, the precipitation at some sites was utilized, and estimated for the remaining valley, and soils water storage and evapotranspiration were estimated. Runoff was calculated by the model, and run-on assumed negligible. Energy balance calculations based upon solar radiation and temperature, were incorporated in the overall evapotranspiration calculation which included soil water content and porosity properties. The evapotranspiration model also considered vegetation cover zones and soil thickness which derived the total root density influencing the soil water content, storage and net soil infiltration. The root zone water balance calculations based upon evapotranspiration, change in soil water storage, and net infiltration were made using a two step algorithm applied to each daily time increment of a continuous multi-year time series.

The model did not include snow fall or snow melt, and assumed all precipitation occurred as rain. This assumption increases model uncertainty at higher elevations where there is significant snowfall. The model also assumes that process of vapor flow and temperature effects on water density are negligible. The net infiltration model is an extension of a local-scale

model calibrated to the Yucca mountain site. It was assumed that the conditions at the Yucca mountain site to which the model was field calibrated, and from which the precipitation was distributed was representative of conditions throughout the Death Valley region. The preliminary model is uncalibrated for the Death Valley region as a whole, and model uncertainty is assumed to increase with increasing differences in climate, physiography, geology, soils, and vegetation relative to conditions at the Yucca Mountain Site. Important sources of model uncertainty include input parameters such as hydraulic conductivity of the bedrock, soil thickness, soil hydrologic properties, and vegetation cover. Another important source of model uncertainty is due to limitations in representing the spatial and temporal distribution of precipitation using available climate records.

Major differences in recharge estimates between the preliminary net-infiltration model and the Maxey-Eakin model occur throughout the Death Valley region for specific locations where the underlying bedrock is estimated to be either highly permeable Paleozoic carbonates or highly impermeable granitic intrusives and rhyolitic ash flow tuffs. For example, estimates of potential recharge (net infiltration) are relatively high compared with the Maxey-Eakin results for mountainous locations bordering Death Valley and throughout the region to the east of the Nevada Test Site. These locations consist of bedrock mapped as the Paleozoic carbonate aquifer, and are assigned the highest saturated hydraulic conductivity (36,000 mm/yr) for a consolidated rock type. In contrast, estimates of potential recharge from the net-infiltration model are low relative to recharge estimates from the Maxey-Eakin model for locations in the northern part of the Nevada test Site and for other locations having hydrogeologic rocks with relatively low saturated hydraulic conductivity (40 mm/yr for welded, fractured ash flow tuff or 0.4 mm/yr for granitic intrusives).

Comparison of the Hevesi net infiltration model results with previous estimates of basin recharge suggest that the net-infiltration model may overestimate recharge because of uncertainty in modeled precipitation, bedrock permeability, and soil properties for locations such as the Spring Mountains (Hevesi, 2002). The modified Maxey-Eakin method resulted in 17,650 acre-feet/year and the Net infiltration Model resulted in 25,600 acre-feet/yr recharge.

The following chart summarizes previous authors recharge assessments:

Author	Year	Method	Estimated Recharge (acre-feet/yr)
Maxey and Jameson	1948	Maxey	23,000
Eakin	1951	Maxey- Eakin	22,000
Malmberg	1967	Modified Maxey-Eakin	22,000
Harrill	1986	Modified Maxey-Eakin	22,000-26,000
D'Agnese	1997	Modified Maxey-Eakin	20,247
Hevesi	2002	Modified Maxey-Eakin	17,650
Hevesi	2002	Net Infiltration Model	25,600
Average			22,312

The average estimated recharge for the seven evaluations is 22,312 acre-feet/year. Overall each of the evaluations resulted in similar estimates, except Harrill who presented a range of values based upon uncertainties involved in assumptions for a given technique. Hevesi reported a larger value with the net infiltration model, but substantiates the model is field fit to the Yucca Mountain site, and as such bedrock infiltration through the carbonates may be elevated.

5.2 Infiltration/Recharge Model

Each of the previous infiltration recharge assessments conducted by the various authors sought to improve upon previous work to refine the overall recharge estimate. D'Agnese (1997) was the first author to expand the modeling beyond elevation and precipitation to include basic vegetation, slope, soil and rock permeability influences. Hevesi (2002) advanced D'Agnese work by essentially incorporating multiple detailed sub-modeling evaluations of those additional parameters to derive evapotranspiration and soil saturation, by including vegetation, root mass, soil porosity, and multiple other inputs.

Based upon the previous evaluations, including the overall improvement and diversification of the modeling constraints, additional reconstruction or revaluation of the latest modeling by the USGS would result in recharge estimate within the presented range of previous evaluations and would not substantiate a significant improvement to the multiple previous evaluations. The scope of work to was refocused to address the available project site recharge.

The project site consists of approximately 10,200 acres within the south western portion of Pahrump Valley. The valley and adjoining mountain range drainage patterns were reviewed to identify those drainage patterns that are related to directing surface and groundwater flow specifically from the Spring Mountains as recharge for the site sub-basin.

The Pahrump Valley drainage was evaluated for surface stream drainage patterns with consideration for topography. The purpose was to identify recharge areas that contribute to the northern half of the valley, and those recharge areas that contribute to the southern half of the valley in which the project site is located. The drainage patterns provide a means to define the subsurface flow, but consideration must be given that subsurface flow does not necessarily parallel surface flow patterns.

The evaluation resulted in subdividing the Pahrump Valley into two distinct watershed boundaries using surface drainage patterns and mountain ridge lines. A Geographical Information System (GIS) based model was constructed to assess annual groundwater infiltration rates within the southern watershed area. Data from United States Department of Agriculture, National Resource Conservation Service, United States Geological Service and public GIS sources was utilized to determine elevation contours, rock types and watershed delineations. Two modified Maxey-Eakin method recharge models were generated for the south watershed sub-basin recharge. The model parameters include elevation, precipitation, and included soils and rock type classifications as presented by D'Agnese and Hevesi.

Precipitation data was derived from The United States Department of Agriculture National Cartography and Geospatial Center (USDA/NRCS). The center has developed a modeling application called the Parameter Elevation Regressions on Independent Slopes Model (PRISM) system. PRISM uses point data, a digital elevation model (DEM), and other spatial data sets to generate estimates of annual, monthly and event-based climatic elements that are gridded and GIS-compatible. The strong variation of climate with elevation is the main premise underlying the model formulation. PRISM adopts the assumption that for a localized region, elevation is the most important factor in the distribution of temperature and precipitation. Available station data often do not span the complete range of elevations in an area, especially in mountainous regions. Therefore, vertical extrapolation is required. This is accomplished in PRISM at each DEM grid cell (termed the target grid cell) through a simple linear climate elevation regression. This regression function serves as the main predictive equation in the model. Observed precipitation data were collected from the National Weather Service cooperative network, the NRCS SNOWpack TELelemetry (SNOTEL) network, storage gauges, snow courses, and estimated Apseudo @ stations. The coop data were provided by the National Climatic Data Center (NCDC) and the SNOTEL data by the NRCS National Water and Climate Center (NWCC).

The PRISM Spatial climate layers for Pahrump Annual precipitation were incorporated in the GIS recharge model. Available precipitation station data was verified with PRISM elevation precipitation levels showing strong correlation with the dependent historical elevation gauge results. A fact sheet, metadata about the annual and monthly precipitation models utilized, is presented in Appendix A.

Geologic units were generalized by D'Agnese and others (1997), and Tuner (1996) primarily using saturated hydraulic conductivity, into ten hydrogeologic units that have considerable lateral extent and reasonably distinct hydrologic properties. Estimates of saturated hydraulic conductivity used in the study range from a minimum of 0.4 mm/yr for granitic intrusives to a maximum of 700,000 mm/yr for valley fill deposits. The consolidate hydrogeologic units having high saturated hydraulic conductivity include the Paleozoic age carbonates (36,000 mm/yr) and Mesozoic age sandstones (18,000 mm/yr). Consolidate units having low saturated hydraulic conductivities include PreCambrian age metamorphics (20 mm/yr) and rhyolitic ash flow tuffs (40 mm/yr).

5.3 Method

Two variations of the modified Maxey-Eakin method were employed to develop the net recharge infiltration model of the valley. Both methods assume that a fixed percentage of average annual rates of precipitation ultimately recharges the groundwater (Malmberg, 1967). The first method bases the fixed percentage of recharge on elevation zones, and negates all precipitation below the 5,000 feet elevation (Table 1). The second method classifies the valley into five zones based on the average annual precipitation and assigns fixed recharge percentages based on the amount of average annual precipitation received (Table 2). The Recharge models will be referred to as Method One and Method Two, respectively.

Prior to modeling, watershed boundaries were delineated from elevation contours to establish the area contributing to recharge for Pahrump Valley. After establishing the valley-wide recharge contributing area, the watershed explicit to the southern half of the valley was delineated. Based on our review of existing data it is apparent that the southern half of the Pahrump Valley watershed is responsible for recharging the aquifer underlying the Project Site. Geographically, the Project Site watershed makes up the southern half of the Pahrump Valley watershed and was determined to be approximately 311,372 acres, which represents 44% of the total Pahrump Valley watershed of 713,931 acres (Figure 7). From this watershed delineation, PRISM precipitation data was "clipped" so that only precipitation bands within the project watershed delineation were retained, from this, values of average annual precipitation only contributing to the southern half of Pahrump Valley net recharge could be determined.

Subsequent to identification of the northern basin drainage pattern and the southern basin drainage network, geologic units above 5000 feet msl for the two areas were identified and compiled. The geologic units are based upon previous work by D'Agnese and others (1997), and Tuner (1996) who consolidated the regional lithology primarily by saturated hydraulic conductivity into ten general units. The northern valley has approximately 98,158 acres of soil and bedrock above 5,000 feet msl which provides a component of net recharge. The southern half of the valley has approximately 87,832 acres of available soil and bedrock above 5,000 feet msl which provides a component of net recharge. Comparison of the two infiltration areas results in the southern drainage basin contributing approximately 47% of the total valley recharge. Utilizing the previous studies net infiltration average of 22,312 acre-feet/year; an empirical estimate of 10,486 acre-feet/yr of recharge from the southern watershed can be assumed.

5.3.1 Method One

Expanding on work previously performed by Malmberg and others, Method One required the areas of topography below 5000 feet msl be identified and isolated inside the Project Site watershed. These areas have no significant recharge infiltration contribution due to evapotranspiration, and therefore were disregarded with this analysis. Method One assumed soil and rock above the 5,000 feet msl elevation are the principal sources of recharge for the basin.

Malmberg defined elevation zones and corresponding estimated precipitation recharge rates. The chart below presents a summary of Malmberg's methodology. Focusing on the Project Site watershed, the objective was to determine land areas above 5,000 feet msl and corresponding average annual precipitation rates. To facilitate this, Project PRISM precipitation data was arrayed onto 250 foot topographic contours and zones of precipitation with corresponding elevations and land areas were generated. Figures 6 & 7 present the watershed boundaries and precipitation zones with corresponding elevations respectively. Project PRISM precipitation data is not solely based on elevation. Thus a method to account for precipitation ranges falling outside of defined elevation zones established by Malmberg was developed. The estimated percent of an average annual precipitation band located in the defined precipitation zones were

used to generate weighted formulas. Using the derived weighted formulas, the annual recharge rate was determined to be 8,872 acre-feet for Method One.

Precipitation Zone Based on Elevation (feet)	Estimated Recharge
	Assumed % of Precipitation
Above 8,000	20
7,000 – 8,000	15
6,000 – 7,000	7
5,000 – 6,000	3
Below 5,000	0

Precipitation Zone Based on Annual Precipitation (inches)	Estimated Recharge
	Assumed % of Precipitation
>20	20
15 – 19.9	15
12 – 14.9	7
8 – 11.9	3
<8	0

5.3.2 Method Two

Method Two's estimated precipitation recharge rates were ascertained by considering the land area in the Project Site watershed that corresponded with distinct precipitation zones based on previous work conducted by Hevesi (2002), Figure 7. This report classified the valley into five distinct recharge zones based on the amount of average annual precipitation received. The chart above also presents input to the Hevesi method. Similar to Method One, PRISM precipitation data was arrayed onto the Project Site watershed with GIS software and land areas that corresponded with the defined precipitation zones were established so that recharge rates could be assigned. As shown in the chart on the right, areas in the Project Site watershed that received less than 8 inches of precipitation were assumed to have no positive contribution to groundwater recharge, due to excessive evapotranspiration, and were thus excluded. Table 2 presents the land areas of the Project Site watershed with respective precipitation towards groundwater recharge and related precipitation zones. Using precipitation zones to define Project Site net infiltration recharge, the estimated annual recharge rate was determined to be 9,740 acre-feet

In summary, Method One resulted in approximately 8,872 acre-feet/yr of infiltration recharge to the southern watershed. Method Two resulted in approximately 9,740 acre-feet/yr of infiltration recharge. Utilizing the average estimated recharge from previous studies based upon a ratio of valley watershed acreage (47%) results in an approximate recharge infiltration rate of 10,486 acre-feet/year. The combined average of all three approximations is 9,700 acre-feet/year.

5.4 The Unknown Flow Regime(s)

Areas where basement rocks are in direct hydraulic communication with overlying valley-fill sediments are of key concern. In the eastern tributary basins of Rock Valley, Mercury Valley, and Pahrump Valley, groundwater fluxes through the basement rock are largely horizontal, contributing underflow to the Amargosa Desert. These fluxes are possibly the largest component of recharge to the area within the conceptual model. Vertical leakage from basement rocks upward into valley fill deposits is probably the second largest source of recharge to the valley fill sediments. An upward vertical gradient exists at Yucca Mountain well UE-25e-P1 and several Yucca Mountain Early Warning Drilling Program (EWDP) locations. The magnitude of groundwater flux is not accurately known, but could be appreciable. Upward leakage is probably greatest via faults through valley-fill deposits (Nye County Nuclear Waste Repository Project Office, 2001).

Contact relationships between basement rocks and valley-fill sediments have a pronounced effect on groundwater levels. Most valley-fill sediments are fine grained and act as relatively impermeable "plugs" in the regional flow regime. In some areas, groundwater flow that once discharged from Paleozoic rock into the vast lakes during early tertiary time is now impeded by clay-rich valley-fill sediments. This water now rises to the surface at locations such as Ash Meadows and Devils Hole, upgradient of the boundary between the sequences of Paleozoic and the thick "plug" of tertiary sediments in the Amargosa Trough (Nye County Nuclear Waste Repository Project Office, 2001).

Fluxes across basin boundaries are important in the Amargosa Desert, since most recharge to the basin is derived from subsurface flow from upgradient basins. Water movement through individual compartments is poorly understood because of a lack of observation wells and aquifer test throughout most of the region. The original inter-flow basin estimates were based on water budget imbalances (Nye County Nuclear Waste Repository Project Office, 2001).

Walker and Eakin (1963, p. 21) also discuss groundwater recharge to the Ash Meadows spring system in terms of interbasin underflow. Underflow from Spring Mountain was estimated to be 13,000 acre-feet per year. Groundwater underflow from Paleozoic age carbonate rocks located to the northeast of Ash Meadows was estimated to be 4,000 acre-feet per year. Discharge by subsurface outflow has been estimated at 2,000 acre-feet per year by the U.S.G.S. Bulletin 1832.

5.5 Groundwater in Storage

The valley-fill aquifer system in Pahrump Valley contains a large amount of groundwater which represents water accumulated during past eons. The amount of water contained in selected volume of the valley-fill aquifer is computed by multiplying the volume of saturated material by the specific yield of the material.

Malmberg (1967), in calculating the groundwater in storage in the Pahrump aquifer, indicates that storage in the upper 100 feet of the saturated zone amounts to 6,000,000 acre-feet. Indications that the fill is much deeper (perhaps 1,000 feet, at least in some places) would substantially increase Malmberg's figure. Malmberg (1967) indicates that the annual recharge to the basin from precipitation, estimated from data by Maxey and Jameson (1948), gives the figure of 23,000 acre-feet.

Montgomery Engineers, 1971, gives a figure for annual recharge to the underground basin of 22,000 acre-feet. Montgomery Engineers, in one of their alternative plans for export of water to Las Vegas, has indicated that 4.2 million acre-feet are available for that purpose. It is assumed that export of that volume of water would be dependent on a no-increase (or limited increase) in local consumption. The Montgomery Engineers report states that, "... The water level in wells is shallow (few to several tens of feet) and is dropping at the rate of about two feet per year in areas of concentrated pumpage. The pumping levels of 15 selected wells range from 60 feet to 218 feet with an average of 218 feet. Discharges range from 275 GPM to 1,225 GPM with an average of 730 GPM." It is not known for certain, but these figures may have been derived primarily or totally from well data on the Nevada side of the border. However, since underground conditions are expected to be similar in California and Nevada, it is assumed that the figures given potentially represent the basin (The Environmental Data Bank of Independence, 1974).

The estimates of groundwater in storage in Pahrump Valley made by Montgomery Engineers appear to be based on earlier estimates made by the USGS. The USGS and Montgomery Engineers apparently used the same surface area for the saturated sediments and the same Specific Yield value. Montgomery considered storage in the upper 300 feet of alluvium to arrive at their figure of 22 million acre-feet, whereas the USGS included only 100 feet of saturated alluvium in their calculations.

The USGS Bulletin 1832 assigned a specific yield value of 15 percent for the valley-fill deposits in Pahrump Valley. The aquifer is about 650 square miles in extent or about 400,000 acres; the upper 300 feet of saturated aquifer has a specific yield of 15 percent. The estimated groundwater in storage is the product of these three values or about 18,000,000 acre-feet. Montgomery Engineers (1970) estimated that 22,500,000 acre-feet of groundwater are in storage in Pahrump Valley and the USGS estimated that 60,000 acre-feet of groundwater was in storage for each foot of saturated aquifer material. Stated another way, it will require the extraction of at least 60,000 acre-feet of water in order to lower the water table by one foot. If the total extraction for the valley is 48,000 acre-feet per year as determined by Montgomery Engineers in 1970, this represents a decline of the water table of approximately 0.8 feet per year, considering no recharge by subsurface inflow (The Environmental Data Bank of Independence, 1974).

5.6 Impact of Proposed Demand on Supply

Physical availability of groundwater supply was evaluated by simulating the impacts of the proposed groundwater demand on the aquifer system. The impact on the regional aquifer was

estimated by inputting calculated aquifer coefficients into the WINFLOW™ mathematical groundwater flow model to estimate the drawdown after 100 years. The calculated project 100-aquifer impact was then combined with current water levels to establish the projected 100-year depth to water in the aquifer underlying the area.

The WINFLOW™ analytical element model was used to simulate 2-dimensional, transient groundwater flow. The steady-state module of the model simulates groundwater flow in a horizontal plane using the analytical functions developed by Strack (1989). The transient module uses equations developed by Theis (1935) and by Hantush and Jacob (1955) for confined and leaky aquifers, respectively. Each module uses the principle of superposition to evaluate the effects from multiple analytical functions (wells, etc.) in a uniform regional flow field. The input parameters for the model include: (1) hydraulic conductivity; (2) top of aquifer; (3) bottom of aquifer; (4) reference elevation; (5) regional hydraulic gradient; and (6) storage coefficient.

The model grid values are in units of feet in the Universal Transverse Mercator (Zone 12, NAD 1927) coordinate system utilizing (0, 0) as the ordinate control. Model grids were projected to meters in the Universal Transverse Mercator (Zone 12, NAD 1927) for display in Arc GIS.

The aquifer parameters used in the simulation were based on work performed by the Geotechnical Consultants, Inc in a private report entitled "*Groundwater Investigation Southern Portion of Pahrump Valley County of Inyo, California for S.V.H. Investments*" 1966. Also used were data presented in the USGS report entitled, "*Groundwater Storage Depletion In Pahrump Valley, Nevada-California, 1962-75*", 1986 and "*Probability Distributions of Hydraulic Conductivity for the Hydrogeologic Units of the Death Valley regional Groundwater Flow System, Nevada and California*", 2002.

The physical limits of the aquifer were based on the unconsolidated valley-fill alluvium contact with consolidated bedrock. All existing wells are screened within the valley-fill alluvium. The regional dip of the valley-fill aquifer basin is southeast. The regional direction of groundwater flow within the valley-fill alluvium is to the southwest.

Aquifer parameters were estimated from literature research, previous modeling and available aquifer pump testing results. The estimated hydraulic conductivity from previous modeling studies conducted for the Death Valley Regional Groundwater Flow System (DVRFS) for the alluvial aquifer was presented to range from a minimum of 2.0×10^{-4} feet/day to a maximum of 427 feet/day (Belcher, 2002).

Faunt (1997) presents a summary of the estimated hydraulic conductivity of hydrogeologic units in the Death Valley region based upon previously present work by Wadell (1982) and Bedinger and Others (1989a, 1989b). The alluvial valley-fill deposits of Quaternary-Tertiary age were assigned an approximate hydraulic conductivity of 0.33 feet/day.

Geotechnical Consultants, Inc (1966, private consultants report) presented aquifer pump testing results conducted on one well within the project site. Well 27R1 (22N/10E Sec 27) (reported total depth of 800+ feet) was test pumped at an average rate of 275 gpm. An observation well

approximately 34 feet away, Well 27R2, (reported total depth of 300 feet) was monitored for water level drawdown during the pumping and recovery test period.

The pumping test analysis of observation Well 27R2 presented an estimated pumping transmissivity of 8,250 gpd/feet and a storage coefficient of 6.4 percent. Report test data are included in Appendix E. Observation Well 27R2 recovery data presented an estimated transmissivity of 6,200 gpd/feet. The pumping test analysis of the recovery data for primary pumping Well 27R1 presented a transmissivity of 6,600 gpd/feet. The average of the observation well test analysis for pumping and recovery is 7,225 gpd/feet. Utilizing the average observation well transmissivity of 7,225 gpd/feet, a recorded depth to water of 121 feet, a total well depth of 800 feet, results in a saturated aquifer thickness of 679 feet, and an estimated hydraulic conductivity of approximately 10.6 feet/day ($79.3 \text{ gal/day-ft}^2$).

The aquifer pump test transmissivity results are within the range of values presented by previous authors based upon local and regional work. A hydraulic conductivity value of 10.6 feet/day was calculated from the local pump test results and is within the range of previously presented values used as a regional estimate for the hydraulic conductivity of the valley fill aquifer. Storativity (specific yield) from the aquifer pump testing was 6.4 percent (unitless). For this simulation a conservative value of 5 percent (0.05) was used.

Harrill (1986) presented that in Pahrump Valley, the thickness of the saturated valley ranges from about 200 to 4,000 feet. If no appreciable fine-grained deposits were present, the storage coefficient for these thicknesses would be 0.0002 to 0.003. The percentage of the fine-grained materials present ranges from a very small amount around the margins of the valley to possibly as much as 80 percent in the central valley. In the quantitative parts of his study, Harrill used values in the range 0.0002 to 0.003 for coarse grained deposits around the margins of the valley and values in the range 0.001 and 0.04 for fine-grained deposits in the central part of the valley.

The regional direction of flow and current depth to water were estimated from correlation of current USGS NWIS Web regional groundwater elevation values for years 2001 through year 2003 with regional groundwater elevation contours as presented by Potter (2002), and available data from the USGS NWIS groundwater level database (Figure 4). Based upon the regional groundwater elevation map, the groundwater surface gradient is estimated to be 0.0030 feet per foot, or approximately 16 feet per mile along the valley axis. In comparison, the hydraulic gradient averages about 20 feet per mile along the 35-mile length of the valley trough (USGS Report, 1832. One groundwater surface reference elevation was set at a distance not to be influenced by the pumping wells and was calibrated to measured water level elevations in Project site Well 22N 10E 27R1 California San Bernadino Baseline and Meridian. The well site was visited on September 28, 2005, and a water level depth of 99.8 feet bgs was measured. The land surface elevation is 2580 feet msl resulting in a water level elevation of 2,480 feet msl. A second calibration groundwater elevation was established at Well S21 E54 Sec 10 AAC1 Nevada Mount Diablo Baseline and Meridian. The land surface elevation is 2,885 feet msl. The USGS NWGIS website reports on July 20, 2004 the reported depth to groundwater was 71.5 feet bgs resulting in a water level elevation of 2,813.5 feet msl. The overall groundwater gradient between the reference head point and calibration point is southwest through the project site, having an overall gradient of 0.0075 feet per foot.

5.7 Pumping Wells

5.7.1 Demand

The project site consists of approximately 10,200 acres. Preliminary estimates of the water demand to develop the property are presented in Table 3. Three population scenerios are presented. Residential single family indoor and outdoor use was combined with estimated non-residential schools to present preliminary estimated development water demands. A rate of 200 gallons per day per capita, and three capita per domestic home site were utilized in the demand calculations. A population of approximately 20,000 domestic units (du) utilizing 200 gallons per day per capita, having an average of 3 capita per household would require approximately 15,995 acre-feet/yr of water. This value is slightly smaller than the estimated average infiltration for the entire Pahrump Valley of 22,312 acre-feet/year and equates to approximately one home per half acre. Based on these figures, reduced development demand was evaluated. The developable domestic units (du) for the project were reduced to 10,000 and 5,000 homes for subsequent water demand evaluation. Utilizing 10,000 du resulted in a water demand of 8,427 acre-feet/yr and results in approximately one home per project acre. Utilizing 5,000 du resulted in a water demand of 3,360 acre-feet/year and results in approximately one home per project two acres. The estimated water demands do not include additional water demands for business development, hospitals, golf courses or provide for recharge credits from waste water treatment.

The infiltration recharge average of 9,700 acre-feet/year for the project southern water shed was considered the maximum water withdrawal constraint. The estimated demand scenario of 10,000 du (30,000 capita) resulted in an approximate demand of 8,427 acre-feet/yr, slightly lower than the net infiltration a recharge estimate average and was utilized as the base build-out population for the project and pumping analysis. The 10,000 domestic unit estimated project demand of 8,427 acre-feet/year equates to a 24-hour pumping rate of 5,250 gpm. Ten project wells pumping at an average rate of 525 gpm were utilized in the pumping analysis. The controlling criteria for the well pumping analysis was consideration for the groundwater level drawdown impact on the southern watershed. No specific state impact requirement is defined. To minimize the northern water shed groundwater extraction all pumping scenario wells were located at existing well sites within the southern portions of the project bounds as distant as possible from the northern watershed boundary, Figure 9

The nature of the contact between the carbonate and valley-fill sediments within the Pahrump valley at depth is not known. Previous authors have estimated that a felsic rhyolite ash flow is present, situated basal to the valley fill sediments. The basal ash is presented to act as an aquitard, limiting the amount of recharge between the two aquifers. Overall, depending on valley location, some areas of the basal contact between the valley-fills sediments and the carbonate aquifer may be in recharge, loss or equilibrium. The potential of a contact aquitard, whether extensive or limited in valley extent, would change the basin water sub-flow system.

The full dynamics of the contact between the two aquifers is not understood, and a lack of any physical data does not assist in a reliable interpretation. Therefore, a very small leakage factor of 0.0001 feet was used for modeling the contact of the carbonate aquifer and the over-lying valley fill aquifer.

5.7.2 Impact Simulation Output

The drawdown after 30 years of pumping was calculated assuming that all wells continuously pump at the assigned pumping rates. All wells pumped for 24-hours per day at the established rates of 525 gpm per well. Delayed transient time pumping starts for the future wells was not conducted. The drawdown impact from pumping the well was evaluated over 5-year time steps up to thirty years. The 5, 10, 20 and 30-year impact contours are presented in Figures 9-12, respectively.

The maximum calculated drawdown after 30-years of pumping was 351 feet, occurring at Well P5. The WinFlow V.3.0 analysis output results for the scenario is presented in Appendix F.

5.7.3 100-Year Groundwater Level

The maximum depth to water after 30 years of pumping was calculated by adding the current depth to water to the water level decline trend, which was estimated to be 1.5 feet/year. The 100-year depth to water calculation is shown below.

Static Groundwater Level (Site Well 22N 10E 27R1)	100 feet bgs
Maximum Drawdown (Well P5)	351 feet
30-Year Groundwater Trend @ -1.5 feet/yr	45 feet
100-Year Depth to Water	496 feet bgs

Results of the simulation indicate that after 30 years of pumping at 8,427 acre-feet/yr (5,250 gpm) results in a maximum water level depth below surface along the central project area local to Well P5 of 496 feet bgs, or a elevation of approximately 2,084 feet msl. The average drawdown for a single well pumping 525 gpm, for a 30-year timeframe, is approximately 220 feet bgs. Well P5 is situated central to the well field and is subject to additional drawdown impacts from each of the adjacent pumping wells. The presented estimate is based upon a water level decline of 1.5 feet/year. Note: Since 1980 groundwater elevations have shown a recovery (rebound) of aquifer local to the eastern recharge source, and indication of a stabilization and leveling of groundwater elevations in the central valley.

5.7.4 Modeling Impact Conclusion

The results present a drawdown impact based upon project development demands limited by the estimated south water shed infiltration recharge amount of 9,700 acre-feet/year. The project demand of 8,427 acre-feet/year is based upon approximately 1 domestic home per acre and

represents 87% of the infiltration recharge. Refinement in the estimated development demand based upon master planning would be required. In addition, existing, non-owner, local wells are protected by drawdown impact regulations, which may reduce presented project well pumping rate(s) and/or require adjustment to the presented preliminary well location(s). Committed water rights users in the area will need to be considered as a consumer of the net watershed infiltration recharge and will reduce the total available water supply for the project. The impacts of wastewater effluent recharge were not taken into account, and would potentially reduce the overall pumping impact.

6. WATER RESOURCE ALTERNATIVES

To meet the projected future water demand in the Hidden Hills area as well as the Pahrump Valley in general, one or more of the following alternatives will have to be implemented: 1) the valley-fill aquifer will remain in a state of over drafted, i.e., groundwater will have to be removed from storage, 2) water will have to be imported to the valley from other basins, 3) severe conservation measures will have to be taken to reduce per capita water use, or 4) growth will have to be restricted through administrative means. If additional water supplies cannot be obtained, then overdraft of the valley-fill aquifer will continue and will accelerate as growth continues. While there is an apparent large volume of water stored in the upper valley-fill sediments, and this water is recoverable, there will likely be detrimental consequences as a result of continued overdraft of the basin. The consequences of overdraft include subsidence, higher well drilling and pumping costs, and degradation of water quality (Moreo, 1999).

Water imported to Pahrump from other basins in Nye County, Nevada, and Inyo County, California could be used to meet the future water demands of the community and to mitigate the past impacts of overdraft in the basin. Nye County has applications to appropriate groundwater in all of the basins in the County that have un-appropriated water resources. If permits to develop these sources are granted, then the portion of water that is not needed for future demands in the source basins or other parts of the County could be conveyed to Pahrump. The Nye County applications total a little more than 60,000 acre-feet. If that amount were to be permitted and available for development, then as much as 16,000 acre feet of the water would be needed in Amargosa Valley. The remaining 44,000 acre feet would be available for other purposes. The full 60,000 acre feet could be available if the perennial yield of the Amargosa Desert basin is raised or if the growth of agriculture and urbanization is less than that assumed in this plan.

The Southern Nevada Water Authority (SNWA) is actively seeking additional water resources within Clark County as part of their water resources planning initiative. The SNWA adopted a plan that calls for three water projects to be built over the next 10 years as a way to reduce the region's reliance on the Colorado River. The projects would tap groundwater in Clark, Lincoln and White Pine Counties and develop surface water rights that the authority owns on the Virgin and Muddy rivers. The projects would require the construction of pipelines that branch into northeastern and northwestern Clark County, bisect Lincoln County and stretch as far north as Ely. The SNWA board agreed to begin developing groundwater resources in the Three Lakes

Valley in northern Clark County, by 2008. The possibility of securing additional water rights through transfer for Pahrump Valley development would be difficult

The development of these water resources would require time and considerable expense first to acquire the water rights and then in the development of well fields and conveyance systems. In the event that no water rights are granted, or the amount granted is insufficient to justify an interbasin transfer of water, then alternate supplies would have to be identified, permitted, and developed. Water could be imported from the Colorado River system and conveyed to Pahrump Valley via pipeline or aqueduct. Issues that are associated with this approach include federal concurrence and funding for implementation. Conservation can reduce the demand for water. If the per capita water demand in Pahrump Valley can be reduced from 486 gallons per day to 350 gallons per day, then the projected demand for water at a full build out would drop from about 80,000 acre feet to about 60,000 acre feet, a 25 percent reduction. Conservation measures can include water reuse, smart landscaping, and watering, and low volume fixtures in residences. Water reuse in Pahrump Valley is already underway at Central Nevada Utilities where treated waste water is used for golf course irrigation. Smart landscaping and watering is best achieved through a program of public education. Low volume fixtures in residences can be required by building ordinances and/or regulations. One of the most effective conservation techniques, pricing, cannot be easily implemented in a community such as Pahrump where the numerous community water systems have rate structures regulated by the Public Service Commission.

If voluntary conservation cannot be successfully implemented and water cannot be imported from outside the basin, then limiting growth would be the only approach that could keep the demand for water in line with the yield of the basin. Such an approach may not be acceptable to stakeholders in both Nevada and California as it would unduly limit the future prosperity of both the communities and would represent a water management failure. From a practical point of view, it may be possible to place restrictions on future growth in the form of conservation requirements for developers and builders.

The best approach to matching water sources with future demand is probably a combination of these alternatives. If conservation can reduce the demand from 80,000 to 60,000 acre feet per year, restrictions aimed at reduced per capita water use are implemented, and 40,000 acre feet can be imported from other basins in southern Nye County, then withdrawals from the groundwater reservoir in Pahrump Valley could be limited to about 20,000 acre feet per year, slightly above the perennial yield of 19,000 acre feet per year, but below the maximum reported safe yield of 26,000 acre feet per year. This volume of pumping would probably be within the sustainable yield of the basin and, at a minimum, would lessen both the timing and severity of the adverse impacts of long-term overdraft of the basin. If water rights and funding for water importation can be obtained, then the overdraft of the basin can be limited in both duration and severity.

6.1 Feasibility of Alternatives

Water conservation is a proven method for achieving water savings and can be implemented through education, regulation, or pricing. The importation of water from other basins would be a costly and time-consuming process. If water rights are secured, design work, environmental documentation, and permitting will all have to be completed before construction can begin. Nye County is unlikely to obtain the financial resources to fund such a project, which could cost 100 million dollars or more for water from north of Highway 95 and as much as 500 million dollars or more to convey water from the Colorado River system. Regardless of the water source, financial assistance would be required to construct the facilities. Such assistance could either come from the federal government or from a private water development entity such as Vidler Water Company, who has offered to assist Nye County in the development of any water rights granted by the State Engineer.

Numerous constraints exist on water development. They include legal availability of water, water system ownership and domestic well issues, land and environmental restrictions, and costs all of which constrain the feasibility of the options that are available for Pahrump. It may be possible to drill deeper wells in the basin to help mitigate the adverse impacts of overdraft. However, any withdrawals from deeper zones would have to be done under existing water right permits as no new permits will be issued. In any target basins for the development of water supplies, the amount of water available for export will be limited by the legal availability of water in the basin of origin. The presence of more than 20 community water systems under different ownership also complicates the implementation of alternatives. If water were to be imported to the basin, it would not be practical to "hook up" each of these systems because of the reluctance of individual owners to bear the costs. Similarly, domestic well owners would be reluctant to abandon their wells so they could pay to join an existing utility. It would likely be necessary to inject the imported water into the valley-fill aquifer so that the community as a whole would receive the benefit of the water. The water could be injected into those areas with the greatest rates of water level decline and those areas with the greatest potential for subsidence. Any water importation project would be constrained by whatever conditions are imposed on the water right permits and by the many restrictions on the development of water supplies and the construction of a conveyance system. First, Nye County must go through the protest period and state its case to the Division of Water Resources who will then issue a ruling that may or may not grant Nye County water rights in each of the 14 basins where the County filed. Next, access to federal lands would have to be obtained in the form of rights-of-way across portions of the Nevada Test Site and BLM administered land over which a pipeline would run, and mitigation fees would have to be paid. Monitoring programs would likely have to be developed and implemented before construction could begin. Construction would probably require another decade. In total, it could take decades and more than \$ 1 billion to develop the infrastructure necessary to develop the groundwater resources on federal lands and convey that water to populated basins.

Interbasin transferr within California may be feasible. The issues would stem from the CEQA process as well as costs. Should the desire to develop the Hidden Hills property into a high

density development the most likely option for water may be basins to the south and west of Pahrump Valley.

DRAFT

REFERENCES

- Belcher, W. R., Seewkind, D.S., and Elliot, P.E., 2002. Probability Distributions of Hydraulic Conductivity for the Hydrogeologic Units of the Death Valley Regional Groundwater flow System, Nevada and California. U.S. Geological Survey Water-Resources Investigations Reports 02-4212. 2002.
- Bell, J.W., Utley, J.A., Buco T.S., 2005, Geology, Hydrology, Subsidence and earth Fissures Pahrump Valley, Nevada. 2005 Annual Meeting of the Association of Engineering Geologists Filed Trip Guide.
- Blakely, R.J., Langenheim, V.E., Ponce, D.A. and Dixon, G.L. 2000, Aeromagnetic Survey of the Amargosa Desert, Nevada and California: A Tool for Understanding Near-surface geology and Hydrology.
- Bedinger, M.S., Langer, W.H., and Reed, J.E. 1989a. Groundwater hydrology, *in* Bedinger, M.S., Sargent, K.A., and Langer, W.H., eds, Studies of geology and hydrology in the Basin and Range Province, South-western United States, for isolation of high-level radio-active waste-Characterization of the Death Valley region, Nevada and California: U.S Geological Survey Professional paper 1370-F.
- Bedinger, M.S., Langer, W.H., and Reed, J.E. 1989b. Hydraulic properties of rocks in the Basin and Range Province *in* Bedinger, M.S., Sargent, K.A., and Langer, W.H., eds, Studies of geology and hydrology in the Basin and Range Province, South-western United States, for isolation of high-level radio-active waste-Characterization of the Death Valley region, Nevada and California: U.S Geological Survey Professional paper 1370-A.
- Blakely, R.J., Jachens, R.C., Calzia, J.P., and Langenheim, V.E., 1999 Cenozoic basins of the Death Valley extended terrain as reflected in regional-scale gravity anomalies, *in* Wright L.A., and Troxel, B.W., eds, Cenozoic basins of the Death Valley region: Geological Society of America Special Paper 333, p. 1-16, scale 1:1,000,000.
- Blakley, R. J., Morin, R.L., McKee, E.H., Schmidt, K.M., Langenheim, V.E., and Dixon, G.L., 1998, Three-dimensional model of Paleozoic basement beneath Amargosa Desert and Pahrump Valley, California and Nevada: Implications for tectonic evolution and water resources: U.S. Geological Survey Open-File Report 98-496, 31 p.
- Buco T. S., 2004, Nye County Water Resources Plan; Technical report prepared for Nye County Department of Natural Resources and Federal Facilities, 115p.
- California Department of Water Resources (CDWR), California Groundwater Bulletin 118 Update 2003. South Lahontan Hydrologic Region Pahrump Valley Groundwater Basin. http://www.dpla2.water.ca.gov/publications/groundwater/bulletin118/basins/pdfs_desc/6-28.pdf Last updated 2-27-2005.
- California Department of Water Resources (CDWR), 2006, Groundwater Level Database.

<http://wdl.water.ca.gov/gw/>. Queried March, 2006.

- Chapmans, R.H., Healy, D.L., and Troxel, B.W., 1971. Bouger gravity map of California, Death Valley sheet: California Division of Mines and Geology map.
- D'Agnese, F.A., Faunt, C.C., Turner, A.K., and Hill, M.C., 1997, Hydrogeologic evaluation and numerical simulation of the Death Valley Regional groundwater flow system, Nevada and California: U.S. Geological Survey Water-Resources Investigations Report, 96-4300, 124p.
- dePolo, C.M. Ramelli, A.R. and Bell, J.W., 1999, Preliminary geologic map of the Pahrump quadrangle: Nevada Bureau of Mines and Geology Open-file Report OF99-14.
- Fenelon J.M., & Moreo M.T., 2002, Trend Analysis of Groundwater Levels and Spring Discharge in the Yucca Mountain Region, Nevada and California, Water Resources Investigations Report 02-4178, U.S. Geological Survey
- Geotechnical Consultants, Inc. 1966. Groundwater Investigation Southern Portion of Pahrump Valley County of Inyo, California for S.V.H. Investments. Private Consultants' Report. June 1, 1966.
- Harrill, J.R., 1986 Groundwater Storage Depletion in Pahrump Valley, Nevada-California, 1962-75: U.S. Geological Survey Water Supply Paper 2279, 53p.
- Hardcastle, J., 2001 Nevada County Population Estimates July 1, 1986, to July 1, 2000, The Nevada State Demographers Office, 13 p. Last accessed July 2003.
- Hevesi, J.A., Flint, A.L., and Flint L. E. 2002. Preliminary Estimates of Spatially Distributed Net Infiltration and Recharge for the Death Valley Region, Nevada-California: U.S. Geological Survey Water resources Investigations Report 02-4010.
- Healy, D.L., 1973. Bouger gravity map of California, Kingman sheet: California Division of Mines and Geology map.
- Healy, D.L., and Miller, C.H., 1965. Gravity survey of the Amargosa Desert area of Nevada and California: U.S. Geological Survey technical Letter NTS-99, 32 p.
- Hoffard, J.L., 1991, Quaternary tectonics and basin history of Pahrump and Stewart Valley, Nevada and California: University of Nevada Reno, M.S. thesis. 138 p. 5 plates.
- Kane, M.F., and Carlson, J.E., 1964. Bouger gravity anomaly map of Clark County, Nevada: U.S Geological Survey open-file report.
- Laczniak, R.J. Cole, J.C., Sawyer, D.A and Trudeau, D.A., 1996, Summary of hydrogeologic controls on groundwater flows at the Nevada Test Site, Nye County, Nevada: U.S. Geological Survey Water-resources Investigations Report 96-4109.

- Laczniak, R.J., Smith J. L, Elliot P.E, DeMeo G. A., Chatigny M A., and Roemer G.J. Groundwater Discharge Determined from Estimates of Evapotranspiration, Death Valley Regional Flow System, Nevada and California: United States Geological Survey and GeoTrans, Water resources Investigations Report 01-4195.
- Lundstrom, S.C., Mahan, S.A., Blakely, R.J., Paces, J.B., Young, O.D., and Dixon, G.L., 2000, Geologic map of the Mound Spring Quadrangle, Nye and Clark Counties, Nevada, and Inyo County, California: U.S. Geological Survey Miscellaneous Field Investigations Map, scale 1:24,000 with text, in press.
- Malberg, G.T., 1967 Hydrology of the Valley-Fill and Carbonate-Rock reservoirs, Pahrump Valley, Nevada-California, United States Geological Survey, Department of the Interior, Published as "Geological Survey Water-Supply Paper 1832.
- Maxey G.B., Robinson T.W., 1947, Groundwater in Las Vegas, Pahrump, and Indian Springs Valleys, Nevada, State of Nevada Office of the State Engineer Water Resources Bulletin No. 6
- Maxey, G.B., and Jameson, C.H., 1948 Geology and Water Resources of the Las Vegas, Pahrump, and Indian Springs Valleys, Clark and Nye Counties, Nevada: Nevada Department of Conservation and Natural Resources, Water Resources Bulletin 5, 128 p.
- Montgomery Engineers of Nevada, Water for Nevada, Special Planning report, Water Supply for the Future in Southern Nevada, Las Vegas, Nevada, January 1, 1971.
- Moreo, M.T., Halford, K.J. La Camera, R.J., Laczniak, R. J, 1999, Estimated Groundwater Withdrawals from the Death Valley Regional Flow System, Nevada and California 1913-98.
- Nye County Department of Natural Resources and Federal Facilities, Nye County Nuclear Waste Repository Project Office, 2001: US Department of Energy, Independent Scientific Investigations Program Final report, Fiscal Years 1996-2001, NWRPO -2001-04.
- Office Report on Water Well and Groundwater data in Pahrump, Mesquite, Ivanpah, Lanfair, Fenner, Chuckawalla and Jacumbe Valleys, State of California, Department of Public Works, Division of Water Resources, Los Angeles, California, January, 1956.
- Potter, C.J., Sweetkind, D.S., Dickerson, R.P., and Killgore, M.L., 2002. Hydrostructural Maps of the Death Valley Regional Flow System, Nevada and California. Us Department of the Interior, U.S. Geological Survey. 2002.
- Public Broadcasting Station, 2006, Featured Program Life in Death Valley, Little Fish, Big Splash. <http://www.pbs.org/wnet/nature/deathvalley/pupfish.html>

- Quade, J., Mifflin, M.D., Pratt, W.L., McCoy, W., and Burckle, L., 1995, Fossil Springs deposits in the southern Great Basin and their implications for changes in water table levels near Yucca Mountain, Nevada, during Quaternary time: Geological Society of America Bulletin, v.107. p. 213-230.
- Riggs, A.C. & Deacon J.E., 2002, Connectivity in Desert Aquatic Ecosystems: The Devils Hole Story: Conference Proceedings. Spring Fed Wetlands: Important Scientific and Cultural Resources of the Intermountain Region.
- Tiedeman C. R., et. al., 2003, Methods for using groundwater model predictions to guide hydrogeologic data collection with application to the Death Valley regional groundwater flow system; Water Resources Research, Vol. 39, No. 1
- United States Department of Agriculture National Resources Conservation Service, 2006, PRISM (Parameter-elevation Regressions on Independent Slopes Model) <http://www.wcc.nrcs.usda.gov/climate/>. 2006.
- USGS Nevada Water Science Center Water-Resources Data Groundwater Database. 2006, http://nevada.usgs.gov/ADR/cont_gw_list.cfm. Queried March, 2006.
- Utle, J.A., 2004, Using InSAR and GPS to Detect Ground Subsidence in Pahrump Valley, Southern Nevada/California: unpub M.S. thesis, University of Nevada, Reno 87 p.
- University of Washington Joint Institute for the Study of the Atmosphere and Ocean. 2006. <http://www.jisao.washington.edu/>. Queried March, 2006.
- Waddell, R.K. 1982. Two-dimensional, steady state model of groundwater flow, Nevada test Site and vicinity, Nevada-California: U.S. Geological Survey Water Resources Investigations Report 82-4085.
- Waring, G.A., 1921 Groundwater in Pahrump, Mesquite, and Ivanpah Valleys, Nevada and California: U.S. Geological Survey water Supply Paper 450-C, p. 51-86.
- Wunderground. Website. 2006. Pahrump Valley, Nevada. <http://www.weatherunderground.com/> Queried March, 2006.
- Winograd, I.J., and Thordarson, W., 1975, Hydrogeologic and hydrochemical framework, south-central Great Basin, Nevada-California, with special reference to the Nevada test site: U. S. Geological Survey Professional paper 712-C. 1975.
- Wright, L.A., 1988, Overview of the role of strike-slip and normal faulting in the Neogene history of the region northeast of Death Valley, California-Nevada, in Ellis, M.A., ed., Selected



APPENDIX C

CARDNO ENTRIX 2012 REPORT

Long-Term Aquifer Performance Test Report 2

Hidden Hills Solar Electric Generating System Site



October 2012
Project Number: 33153001

Prepared by
Cardno ENTRIX
201 N. Calle Cesar Chavez, Suite 203
Santa Barbara, CA 93103
1.805.962.7679
www.cardnoentrix.com

Prepared for
BrightSource Energy
1999 Harrison Street, Suite 2150
Oakland, California 94612

BRIGHTSOURCE ENERGY

HIDDEN HILLS SOLAR ELECTRIC GENERATING SYSTEM SITE,
CALVADA SPRINGS, CALIFORNIA

Long-Term Aquifer Performance Test 2 Report

OCTOBER 2012

Prepared by



ENTRIX, Inc.
201 North Calle Cesar Chavez, Suite 203
Santa Barbara, CA 93101
T 925.935.9920 • F 925.935.5368

Prepared for

BrightSource Energy

1999 Harrison Street, Suite 2150
Oakland, California 94612

Table of Contents

Executive Summary	ES-1
Introduction	1
1.1 Purpose and objectives	1
1.2 Site and Vicinity General Characteristics	1
Existing Well Evaluation	5
1.3 Objective	5
1.4 Personnel and Procedures	5
1.5 Site Safety	5
1.6 Well 3A Evaluation	5
1.7 Well 3A step Test	5
1.8 Summary	7
Well 3B Installation	8
1.9 Personnel and Procedures	8
1.10 Site Safety	8
1.11 Permitting	8
1.12 Utility Clearance	8
1.13 Dust Control	8
1.14 Well Installation Methods	9
1.15 Well Development and Testing	9
1.16 Summary	10
Regional Stratigraphic Analysis	11
1.17 Collection and Analysis Of Geophysical Data	11
1.18 Summary	13
Aquifer Pumping Test	15
1.19 Set Up	15
1.20 Personnel and Procedures	15
1.21 Site Safety Procedures	16
1.22 Dust Control	16
1.23 Water Level Measurements	16
1.23.1 Background Levels	16
1.23.2 Stump Spring Monitoring Well	16
1.24 Aquifer Pumping Test	16
1.25 Water Quality Samples	17

Analysis of APT-2 Data	19
1.26 APT Results Summary	19
1.27 APT Drawdown Analysis	23
1.28 Projection of Drawdown Over Project Duration	31
1.29 Summary	33
References	35

Appendices

Appendix A - Inyo County Department of Environmental Health Monitoring Well Permit
Appendix B - Well 3B Boring Logs
Appendix C – Well 3B Geophysical Logs
Appendix D – Gamma Logs from On-site Wells
Appendix E – Gamma Log from Stump Spring Well
Appendix F – Water Level Data Tables
Appendix G –Stump Spring Monitoring Well Water Level Data
Appendix H – Long Term Aquifer Performance Test-2 Plan

Figures

Figure 1-1	Map Showing Aquifer Performance Test Wells and Adjacent Monitoring Wells	2
Figure 1-2	Well 3 Area and Nearby Monitoring Wells	3
Figure 2-1	Well 3A Step Test Drawdown	7
Figure 3-1	Drawdown during Well 3B Step Test	10
Figure 4-1	Geologic Cross-Section from Orchard Well to Stump Spring	12
Figure 4-2	Geologic Cross-Section in Vicinity of Well 3	14
Figure 6-1	Schematic diagram of observed drawdowns in monitoring wells	20
Figure 6-2	Observed water levels in monitoring wells during APT 2	21
Figure 6-3	Observed water levels in monitoring wells, July 17, 2012 to end of APT-2	22
Figure 6-4	Drawdown measured in the Stump Spring Monitoring Well, March to September, 2012	23
Figure 6-5	Drawdown vs. time plot for Well 3, located 20 feet from Well 3B	25
Figure 6-6	Drawdown vs. time plot for Well 3A, located 37 feet from Well 3B	26
Figure 6-7	Drawdown vs. time plot for MW-3, located 178 feet from Well 3B	28
Figure 6-8	Drawdown vs. time plot for MW-4, located 69.5 feet from Well 3B	29
Figure 6-9	Drawdown vs. time plot for MW-5, located 13 feet from the Well 3	30
Figure 6-10	Drawdown vs. distance from Well 3B after 14 days of pumping at 45 gpm	32

Tables

Table 2-1	Summary of Step Test conducted at Well 3A	6
Table 3-1	Summary of Pumping Test conducted at Well 3B	9
Table 6-1	Summary of Transmissivity Values from Curve Fitting	31

Executive Summary

This report summarizes activities and results of the second comprehensive aquifer performance test (APT-2) conducted at the Hidden Hills Solar Electric Generating System (HHSEGS) site (Figure 1-1). The purpose of APT-2 is to provide an extended test pumping duration that adds to the data and results associated with the first APT (APT-1).

Following the completion of the APT-1, Cardno ENTRIX (CE) was informed of an existing well, Well 3A, near well #3 that was not evaluated during the APT-1 preparations. Preliminary investigation of Well 3A identified it as a potential candidate for the APT-2 pumping well but sand production observed during a short step drawdown test made it unlikely that the well would sustain the planned pumping rate without destroying the test pump. Subsequently, a new well, Well 3B, was installed near Wells 3 and 3A. APT-2 was then conducted by pumping well 3B at a constant rate of 45 gallons per minute (gpm) over the 14-day period from September 7 through September 21, 2012.

The APT-2 test provided reliable measurements of the aquifer properties at the project site. The duration of the test was long enough to measure the transmissivity, storage, leakance, and boundary conditions of the aquifer and achieve stabilized water levels in the aquifer. The APT-2 data are consistent with the information collected from APT-1 and further demonstrate that the aquifer can sustainably supply the water needed to support the project for the 25 years of operation as well as for the 3-year construction period pumping. Moreover, based upon these data and also consistent with the results of APT-1, off-site water level drawdowns are not expected to occur and therefore there won't be project-associated drawdown caused at either the nearby private domestic wells or at Stump Spring.

While it is not possible to predict future development in the Pahrump Valley, the historic water level data provided by Nye County indicates that water levels west of the State Line Fault system have been relatively stable over the last 20 years. Barring unforeseen changes in the pumping pattern in the valley, it is unlikely that regional pumping could substantially impact the aquifer at the project site or substantially change the prediction of this analysis.

Introduction

Cardno ENTRIX, on behalf of BrightSource Energy, has prepared this report summarizing the activities and results of the second comprehensive aquifer performance test (APT-2) that was conducted at the HHSEGS Project site over the 14-day period from September 7 through September 21, 2012 (Figure 1-1).

1.1 PURPOSE AND OBJECTIVES

The purpose of APT-2 is to develop additional data on aquifer properties which can better establish aquifer yield and potential drawdown effects associated with proposed project pumping at the site. The objectives of this APT are:

1. Determine aquifer hydraulic coefficients (i.e., transmissivity, storativity, and leakance).
2. Assess the drawdown impacts to nearby users based on actual measured drawdown at selected locations.
3. Assess the potential for drawdown impacts at Stump Spring.
4. Determine the potential presence of hydraulic barrier boundaries within the aquifer.
5. Assess the potential biological drawdown impacts from the project on groundwater dependent vegetation around the site.

The projected water demand for the proposed project is approximately 140 acre-feet per year (AFY) to be provided from three proposed wells to be constructed at appropriate locations across the site.

1.2 SITE AND VICINITY GENERAL CHARACTERISTICS

The HHSEGS site is located in the Pahrump Valley, near Calvada Springs, California, approximately 15 miles south of Pahrump, Nevada and 50 miles west of Las Vegas, Nevada. The site is separated from the Las Vegas Valley to the east by the Spring Mountains. The western boundary of the Pahrump Valley is formed by the Nopah and Kingston Ranges. The Nopah and Kingston Ranges extend to between 6,400 to 7,300 feet above mean sea level. The Spring Mountains of Nevada reach 11,900 feet above mean sea level and provide the principle source of recharge to the basin (Waring, 1920; DWR, 1964). The valley is relatively flat and up to approximately 15 miles wide (Flynn, et al, 2006). Elevations of the valley floor above mean sea level ranges from 2,457 feet at Stewart Lake (dry) to about 3,000 feet in the southwestern portion of the basin (DWR, 1975).

The Pahrump Valley is on the southwest margin of the Basin and Range Physiographic Province. The region has experienced multiple periods of deformation. The State Line Fault Zone is a zone of strike-slip faulting that strikes almost parallel to the border of California and Nevada in the center of the valley (Flynn, et al, 2006). The mountains bordering the Pahrump Valley are mostly composed of late Proterozoic and Paleozoic carbonate and siliciclastic rocks, which probably also underlie the valley. The subsurface bedrock of the Pahrump Valley is deformed and topographically complex. It is overlain by sedimentary deposits that are Oligocene and younger in age. These include Quaternary playa deposits and large alluvial fans on the northeast side of the valley (Flynn, et al, 2006).




Figure 1-1 Map Showing Aquifer Performance Test Wells and Adjacent Monitoring Wells




Figure 1-2 Well 3 Area and Nearby Monitoring Wells

The HHSEGS site is underlain by Quaternary sediments, which form the primary water-bearing units within the basin. Channel gravels become finer grained upward, becoming mudstone near the top of the sequence. The mudstones are overlain by silt and thin gravel beds. These deposits record a change from a fluvial and lacustrine condition during the most recent glacial cycle to the arid conditions found today (Flynn, et al, 2006). The maximum thickness of the alluvium is at least 800 feet (DWR, 1964).

Annual Precipitation ranges from about 4 to 6 inches. Surface runoff drains toward Stewart Lake to the west and towards Pahrump Lake to the north in Nevada (DWR, 1975).

Recharge to the basin is derived from the percolation of runoff through alluvial deposits at the base of the bordering mountains and from the infiltration of precipitation that falls on the valley floor. Groundwater in the alluvium moves towards either Stewart Lake or Pahrump Lake. Groundwater is confined near the margins of the dry lakes and along the base of the alluvial deposits originating from the Spring Mountains in the Nevada Portion of the basin. Groundwater discharge from the alluvial aquifer occurs mainly through pumpage and spring discharge, or through evapotranspiration (DWR, 1964).

The character of the groundwater in the basin varies from calcium-magnesium bicarbonate to magnesium-calcium bicarbonate. Total dissolved solid (TDS) concentrations range from about 150 milligrams per liter (mg/L) to 540 mg/L. Recent results from on site well sampling indicated TDS concentrations of 250 and 320 mg/L.

Existing Well Evaluation

1.3 OBJECTIVE

In an effort to conduct a longer duration APT that would provide additional aquifer characterization data, an evaluation was conducted to assess a previously unknown existing well near well #3 which was discovered following the completion of APT-1. Because this well is near well #3, it was named 'Well 3A'.

1.4 PERSONNEL AND PROCEDURES

All work was performed by a qualified Cardno ENTRIX field scientist working under the supervision of a California Professional Geologist. This person supervised the field activities and oversaw all phases of the work including managing subcontractors and report preparation. All field procedures (e.g., permitting, sampling protocol, chain-of-custody, preparation of a Health and Safety Plan, etc.) followed Inyo County and State of California guidelines at the time the work was performed. Biological monitors were also present during all phases of this activity.

1.5 SITE SAFETY

A site safety plan was developed for each phase of the field investigation. The document was reviewed and signed by all Cardno ENTRIX personnel and subcontractors performing work on the site. A copy was present on-site at all times and kept in an easily accessible location. Additionally, mandatory health and safety tailgate meetings were conducted daily and included all on-site personnel.

1.6 WELL 3A EVALUATION

An initial well evaluation was conducted at Well 3A in June and July of 2012. The depth to water was recorded at 130.68 feet below ground surface (ft bgs) and the bottom of the well was tagged at approximately 346 ft bgs. In addition to the above evaluations, video and gamma logging was conducted followed by a step-drawdown test to assess well production and efficiency.

1.7 WELL 3A STEP TEST

In order to fully assess the pumping capacity of Well 3A, Cardno ENTRIX conducted a step-drawdown pumping test on July 17, 2012. The step-drawdown test was conducted using a submersible pump set to approximately 315 ft bgs. The flow rate was controlled using the throttle on the pump control box and a valve installed on the discharge effluent line. Discharge from the step drawdown test was conveyed to a discharge point approximately 500 ft northwest of the well site.

The test was conducted with a series of increasing flow rates, each sustained for approximately one hour. The step-drawdown data is shown on Figure 2-1. A summary of the pumping rates, pumping levels and specific capacity are provided in the table below:

The depth to water was measured from the top of the casing (ft btoc) during the test with a manual water level meter. A totalizer with a flow meter was used to measure the rate of discharge and the total volume of water pumped from the well. During the test, the flow rates and totalizer readings were recorded at the same intervals as the water level measurements. If the pumping rate was not within 5 percent of the target flow rate, then the flow rate was adjusted until the desired rate was reached. During some pumping intervals, especially at the lower pumping rates, sand production from the well plugged the flow meter and readings were not available. To unplug the meter between rates the pump was shut down and the meter was flushed of sand and debris. These intervals are noted (Appendix F, Table F-3).

Table 2-1 Summary of Step Test conducted at Well 3A

Test Interval (minutes)	Measured Rate (gpm)	Pumping Level (ft btoc)	Drawdown (ft)	Specific Capacity (gpm/ft)
0	--	130.55	0	--
1-60	50	147.7	17.15	2.92
60-66	Pump off to clear totalizer			
66-128	90	204	73.45	1.22
128-136	Pump off to clear totalizer			
136-230	95	238.7	108.15	0.92
230-232	Pump off to clear totalizer			
232-301	100	245	114.45	0.87

The Well 3A data shown in Figure 2-1 indicate steady, increasing drawdown during the first two pumping rates. Water levels were beginning to stabilize at approximately 17.1 feet of drawdown during pumping at 50 gallons per minute (gpm) for one hour. When increased to 90 gpm, levels continued to drop reaching approximately 73.4 feet below the static water level after approximately 60 minutes of pumping. The pumping rate during the final two steps was unstable because of the interference caused by sand production and degradation of the pump performance. The third rate step began at approximately 135 gpm and had dropped to approximately 100 gpm after 20 minutes and 90 gpm from approximately 35 minutes into the test through the end of the step. The fourth rate step began at approximately 165 gpm, dropped to 138 gpm in 5 minutes and 93 gpm 30 minutes into the step.




Figure 2-1 Well 3A Step Test Drawdown

1.8 SUMMARY

The results of the step-drawdown test completed at Well 3A indicate that the aquifer penetrated by the well has sufficient capacity to be yield groundwater at rates of 150 gpm or more. However, because of the original well construction, and also the age and deterioration of the well casing, abundant entrainment of fine sand from the aquifer formation precluded the use of the well for APT-2. Well development was considered along with a range of retro-fit options, although the costs and uncertainty of success were sufficiently large that the installation of a new well nearby was selected instead.

This section discussing the well 3A investigation is provided to document the potential high yield of well 3A and is valuable information regarding the potential of some of the areas of the on-site aquifer to produce high flow rates from wells of 350 ft depth. Contrasting the yield of well 3A, as tested, with that of other on-site wells evaluated (such as well 3, well 3B and the Orchard well), also provides important information regarding the need to carefully select well sites and incorporate as much site lithologic information as possible in that selection process.

Well 3B Installation

A new well, known as Well 3B, was installed from August 13 to August 21, 2012 at the location shown in Figure 1-2. The location of Well 3B, near wells 3, 3A, MW-5 and MW-4, allowed for collection of an array of drawdown data from nearby monitoring locations that are valuable in documenting aquifer characteristics from the pumping test.

1.9 PERSONNEL AND PROCEDURES

All work was performed by a qualified Cardno ENTRIX field scientist working under the supervision of a California Professional Geologist. This person supervised the field activities and oversaw all phases of the work including managing subcontractors and report preparation. All field procedures (e.g., permitting, sampling protocol, chain-of-custody, preparation of a Health and Safety Plan, etc.) followed Inyo County and State of California guidelines at the time the work was performed. Biological monitors were also present during all phases of this activity.

1.10 SITE SAFETY

A site safety plan was developed for each phase of the field investigation. The document was reviewed and signed by all Cardno ENTRIX personnel and subcontractors performing work on the site. A copy was present on-site at all times and kept in an easily accessible location. Additionally, mandatory health and safety tailgate meetings were held daily with all on-site personnel.

1.11 PERMITTING

Prior to conducting the field activities, permits for well installation were obtained from the Inyo County Department of Environmental Health. A copy of the permit is provided in Appendix A. Additionally, correspondence with Lahontan Regional Board staff was conducted to obtain approval for the proposed APT-2 discharge as was approved during the APT-1 testing.

1.12 UTILITY CLEARANCE

Underground Services Alert was notified more than 48 hours prior to the start of subsurface activities to assist in identifying subsurface utilities present in the vicinity of the proposed well locations. There were no underground utilities identified in the vicinity of the work areas or well locations.

1.13 DUST CONTROL

During all well installation activities dust control was conducted using a water truck provided by Water Pros, a Las Vegas, Nevada-based company.

1.14 WELL INSTALLATION METHODS

Well 3B was installed to a depth of approximately 355 ft bgs by Cascade Drilling; a State of California licensed driller (C-57 License No. 938110) using mud-rotary drilling. A boring log for Well 3B is provided in Appendix B. The well was constructed with 8-inch diameter steel blank casing and 0.030-inch slotted steel screen. Groundwater was encountered at approximately 130 ft bgs and the screened interval was set from 255 to 355 ft bgs. The sand filter pack was built with #3 Monterey sand from 193 ft to 355 feet bgs.

The wells were sealed with hydrated bentonite from the top of the sand filter pack to approximately 183 feet bgs. The annular space above the bentonite seal was filled with Portland cement to the ground surface and each well was finished at the surface with a secure well monument that extended approximately 3.5 feet above the ground surface. Geophysical logging consisted of deploying an e-log (resistivity and SP) and a gamma log – the logs are provided in Appendix C.

1.15 WELL DEVELOPMENT AND TESTING

Well 3B was developed using a variety of techniques including, surging, bailing, jetting, swabbing and pumping. Once development was completed the test pump was set in the well and a step-drawdown test was conducted using a submersible pump set at 350 ft bgs. The flow rate was controlled using the throttle on the pump control box and a valve installed on the discharge effluent line.

The depth to water was measured from the top of the casing (ft btoc) during the test with a manual water level meter at increasing intervals. A totalizer with a flow meter was used to measure the rate of discharge and the total volume of water pumped from the well. Discharge from the step drawdown tests were conveyed through lay flat hose to a point approximately 1,000 ft northwest of the well site.

The step test was conducted with a series of increasing flow rates (25, 35 and 45 gpm), each sustained for approximately one hour. The step-drawdown data is shown on Figure 3-1. A summary of the pumping rates, pumping levels and specific capacity are provided in the table below:

Table 3-1 Summary of Pumping Test conducted at Well 3B

Test Interval (minutes)	Measured Rate (gpm)	Pumping Level (ft btoc)	Drawdown (ft)	Specific Capacity (gpm/ft)
0	--	133.2	0	--
1-60	25	185.8	52.6	0.5
60-120	35	223.1	89.9	0.4
120-322	45	304.0	170.8	0.15

The data shown in Figure 3-1 indicate steady, increasing drawdown during the first two pumping rates. Water levels in the well were beginning to stabilize at approximately 52.6 feet of drawdown while pumping at 25 gpm for one hour. When increased to 35 gpm levels continued to drop after approximately

60 minutes of pumping, reaching approximately 89.9 feet below the static water level. Pumping at 45 gpm dropped levels to approximately 170.7 ft below static levels. Overall, the data indicate that the Well 3B can sustain pumping at 45 gpm as needed for APT-2.




Figure 3-1 Drawdown during Well 3B Step Test

1.16 SUMMARY

The results of the step-drawdown test completed at Well 3B indicate that the well can sustain pumping at 45 gpm for a 14 day APT.

Regional Stratigraphic Analysis

A stratigraphic evaluation of the HHSEGS site was conducted to characterize location and extent of aquifer materials in support of the APT-2 analysis. Because of the limited geologic data available for the site, geophysical logging was conducted at a selection of the existing on-site and nearby wells, as described in this section.

Geophysical well logs can be used to determine the properties of the formation near a borehole. A variety of logging methods have been developed to measure different physical properties of the formation that can be used to determine the geologic properties of the formation. Most logging methods can only be run in uncased holes and therefore are not viable for the existing wells on site (which are all completed with steel casing). One of the standard geophysical methods is known as gamma logging. This technique measures the gamma ray radiation that naturally occurs from radioactive elements present in clay minerals of the formation. Strata with high gamma ray emissions generally contain clay and are relatively impermeable as aquifer material. Formations with low gamma ray emission generally have low clay content, and are typically sand and gravel units. In general, lower gamma log responses correspond with coarser deposits and therefore typically have greater permeability.

1.17 COLLECTION AND ANALYSIS OF GEOPHYSICAL DATA

Gamma logging was conducted at the following wells: Orchard Well, MW1, MW6, Well 3, and the Stump Spring monitoring well. These logs are attached as Appendix D. At Well 3B, both a gamma log and an electrical log were run. The gamma logs plotted on geologic cross-sections which are used to conduct stratigraphic correlations that illustrate key aquifer zones.

Figure 4-1 is a geologic cross-section from the Orchard Well, through the Well 3 area, to the Stump Spring monitoring well. The gamma logs show that the upper 100 to 130 feet on the project site generally consists of dense clay. The material between about 100 and 300 feet is a sand and gravel aquifer unit with a consistent 10 to 20 foot thick clay layer about 50 feet above the base of the aquifer. The log of Well 3 and the Orchard Well indicates that the formation below the aquifer is primarily fine-grained or clay-rich with occasional thin layers of silty sand. The log of the Stump Spring monitoring well indicates that the shallow clay layer is thicker in this area east of the site. Based on the elevation difference between the HH SEGS site and Stump Spring, and the assumed position of the faults under the spring mounds, it appears that the faults have a component of vertical motion that may juxtapose fine grained units against a portion of the aquifer.

REGIONAL STRATIGRAPHIC ANALYSIS



Figure 4-2 is a geologic cross section focused on the wells located in the vicinity of Well 3. The logs show the upper clay unit is about 130 feet thick in the area. The material from 130 to about 220 feet consists of fine grained sand, probably with some silt. The material between 220 and 320 feet consists of layers of more coarse permeable sand and gravel and finer silty sand, with a consistent clay layer between about 270 and 280 feet. The material below 320 feet is generally fine-grained or clay with a few thin, isolated silty sand layers. The gamma response of the aquifer in Well 3B is about 20 GAPI units higher than in Well 3 or Well 3A. This indicates that the formation at Well 3B probably is finer grained and contains more silt and clay and is probably not as permeable as the formation at Wells 3 or 3A.

1.18 SUMMARY

These geologic cross-sections provide important information on the geometry of the aquifer not previously available. The gamma logs indicate that the general stratigraphy is fairly continuous from the Orchard Well to the area near Well 3. The logs indicate that the base of the aquifer lies about 300 to 350 feet below the surface, and the deeper parts of Well 3 and the Orchard Well are composed of clay and silt-rich sediments and probably do not contribute significant volumes of water to the wells. Based on this information, production wells do not have to be more than about 350 feet deep to produce from the main aquifer units. Similarly, monitoring wells do not need to be more than 350 feet deep to fully-penetrate the aquifer. The gamma logs indicate that the upper portion of the aquifer is finer grained and the lower portion of the aquifer consists of stratified units of coarse sand and gravel, finer sand or silty sand, and a deep clay layer. The permeability of the aquifer also appears to vary laterally over relatively short distances. It also appears that the faults of the State Line Fault System may at least partially juxtapose fine grained units against the aquifer and are likely to create a partial hydraulic barrier boundary that would limit the spread of a cone of depression across the faults.




Figure 4-2 Geologic Cross-Section in Vicinity of Well 3

Aquifer Pumping Test

APT-2 was conducted at the HHSEGS site from September 7 to 21, 2012 employing the approach and methods described in the Long-Term Aquifer Performance Testing Plan (Cardno ENTRIX, 2012; Appendix H). The aquifer testing was conducted to determine aquifer properties such as transmissivity, storage and leakance and to compare with the results of an APT-1 conducted in February, 2012. The results of APT-1 are presented in the Long-Term Aquifer Performance Test Report, Hidden Hills Solar Electric Generating System Site report (Cardno ENTRIX, March, 2012). The primary objective of APT-1 was to demonstrate that the aquifer can provide a reliable supply for both project long-term operations and the initial construction period. A secondary objective of APT-1 was to determine if barrier boundaries such as faults are present within the aquifer. APT-1 was planned to pump a minimum of seven days but was terminated after four days due to vandalism of one of the pumping wells. APT-2 was conducted to confirm the aquifer properties measured by APT-1 and to demonstrate that water levels in the aquifer would stabilize within a few days of pumping.

The test consisted of pumping Well 3B at 45 gpm while monitoring water levels in an array of monitoring wells. Water level data were also collected manually at the Stump Spring monitoring well before, during and after APT-2.

1.19 SET UP

A submersible pump was installed in well 3B with the intake set at 350 ft bgs. The pump surface completion consisted of the gate valve, an in-line flow meter and totalizer, a sampling port, piping and hardware necessary to provide a leak proof-seal at the well head and along the discharge line to the point of discharge. The gate valve on the pump set up was used to help control the pumping rate, shut off flow and to stop gravity discharge.

The pumped groundwater was conveyed to a discharge area 1,000 feet northwest of the well. The location and offset distance of the discharge site was selected to: 1) avoid recirculation of water, 2) to avoid influencing the monitoring wells, 3) prevent offsite discharge of the produced water and 4) to protect sensitive plant and animal species. At the point of discharge (POD), a diffuser, plastic sheeting and straw wattles were used to dissipate the discharge flow to prevent erosion.

1.20 PERSONNEL AND PROCEDURES

All work was performed by a qualified Cardno ENTRIX field scientist working under the supervision of a California Professional Geologist. This person supervised the field activities and oversaw all phases of the work including managing subcontractors and report preparation. All field procedures (e.g., permitting, sampling protocol, chain-of-custody, preparation of a Health and Safety Plan, etc.) followed Inyo County and State of California guidelines at the time the work was performed. Biological monitors were also present during all phases of this activity.

1.21 SITE SAFETY PROCEDURES

A site safety plan was developed for each phase of the field investigation. The document was reviewed and signed by all Cardno ENTRIX personnel and subcontractors performing work on the site. A copy was present on-site at all times and kept in an easily accessible location. Additionally, mandatory health and safety tailgate meetings were held daily with all on-site personnel.

1.22 DUST CONTROL

During all well installation activities dust control was conducted using a water truck provided by Water Pros, a Las Vegas-based company.

1.23 WATER LEVEL MEASUREMENTS

Data logging pressure transducers (In-Situ Level Loggers) were installed in Well 3B, in monitoring wells (MW-1, MW-3, MW-4, MW-5 and MW-6), and in pre-existing on-site wells (Well 3, Well 3A and the Orchard Well). Additionally, manual measurements using an electronic water level tape were made at all wells during the test to verify and calibrate the transducer data. More than 72 hours of background data were collected before to the start of the test and the transducers were left in the wells for 3 days following the cessation of APT-2 to monitoring aquifer recovery. Water level data are provided in Appendix F.

1.23.1 Background Levels

Background water levels were measured using data logging pressure transducers in Well 3B, Well 3, Well 3A, MW-5, MW-4, MW-3, MW-6, MW-1 and the Orchard Well. Manual water level measurements were also made at existing on-site wells; MW-1, Well #2 and Well #4.

Background data collection was started on July 17, 2012 in wells MW-3, MW-4 and MW-5. Background data collection was started on August 22, 2012 at the pumping well and the remaining on-site wells. The manual measurements were made at various times during site visits. Overall background water levels were steady and level over the entire period of monitoring, except during well development and step test procedures.

1.23.2 Stump Spring Monitoring Well

A data logging pressure transducer was installed in the Stump Spring well by the BLM in Spring 2012 to measure long term background water levels. Manual water level data were collected from the Stump Spring well during and after APT-2 and is included in Appendix G.

1.24 AQUIFER PUMPING TEST

The APT was started at 8:00 am on September 7, 2012. Although Well 3B was pumped at a nominal rate of 45 gpm for the test. The gate valve was regularly adjusted as needed to keep the rate at 45 gpm. Water level and flow rate monitoring data are provided in Appendix F.

The discharge site was watched closely by the biological monitor throughout the test for signs of erosion, encroachment into sensitive plant and animal species habitat and for containment on-site. The discharge water spread quickly for a few hours at the beginning of the test. After the first day of the test the area of visible water at the surface did not appear to expand, though the soft wetted ground did noticeably expand a small amount each day. There was no erosion observed at the discharge points during the test.

1.25 WATER QUALITY SAMPLES

Water quality samples were collected from Well 3B, the Stump Spring monitoring well and MW-6 and sent to CalScience Laboratories, a State of California Certified Lab, for chemical analysis. Sample collection procedures and an analysis of the data will be presented when the results are provided by the analytical laboratory.

Analysis of APT-2 Data

1.26 APT RESULTS SUMMARY

The monitoring data collected during the course of APT-2 was used to determine the magnitude and lateral extent of drawdown as well as to calculate aquifer parameters and boundary conditions. Drawdown at the closest monitoring well, MW-5 (13 feet away from well 3B) was 4.6 feet at the end of the test, indicating that most of the drawdown in Well 3B was due to well loss associated with poor formation permeability. The drawdown in the farthest monitoring well within the radius of influence, MW-3 (184 feet away), was 2.1 feet at the end of the test. A map view of the drawdown in the wells near Well 3B is provided as Figure 6-1.

The water level changes observed in monitoring wells during the course of the test are illustrated in Figure 6-2. Figure 6-3 presents the change in water level for the pumping well and monitoring wells prior to the test, during the testing period, and during the recovery period. Water levels in all of the wells were essentially stable preceding APT-2. Water levels in Well 3, Well 3A, MW-3, MW-4, and MW-5 stabilized by the end of the APT.

No drawdown was observed in any other monitored wells more distant than MW-3 from the pumping well. Water levels were remarkably stable in MW-1 and the Orchard well, showing only minor short term fluctuations in water level of less than 0.1 feet for the period before, during and after the test. MW-1 experienced two short duration apparent rises in water level of about 0.2 feet during the pumping period. These events coincide with times that manual water level measurements were made in the well suggesting that the spikes are due to the manual water level probe disturbing the transducer setting and do not indicate an actual change in water level. Water levels in MW-6 showed a consistent linear decline of 0.2 feet from three days prior to the test and through the duration of the test. The pumping test did not change the slope of this linear trend, which demonstrates that the change in water level was from external factors and not from the pumping well. The water level data from these monitoring wells demonstrates that the cone of depression from the pumping well was limited to the area around the well and did not propagate as far as MW-6. Water levels in all wells affected by the pumping recovered to approximately their pre-pumping water levels within a day following the termination of the APT.

Water levels at the Stump Springs monitoring well (Figure 6-4) show short duration variations of up to a foot or more that are consistent with changes in water due to changes in atmospheric barometric pressure (barometric efficiency of the well). A longer term trend in water levels is present in addition to the short period oscillations. The water level rose approximately a foot from February through June and then followed a declining trend without significant change during and after the pumping test. The change in water level in this monitoring well is consistent to longer term monitoring data that indicates that water levels rise several feet in response to natural recharge events and slowly return to normal levels over periods of months to years. The rapid response in the well to natural recharge events is somewhat surprising given the gamma log data that suggests the well is completed in strata that contains an abundance of clay. The low hydraulic conductivity of clay generally retards vertical migration of water and suppresses the response of an aquifer to recharge. The rapid response of this well suggests that the shallow aquifer in this area is receiving focused recharge either from the surface or from other sources such as the fault system.

The Stump Springs monitoring well data demonstrates that the pumping test produced no drawdown in the well. It also demonstrates that water levels in this well respond much more quickly to recharge events and shows much greater variability than the monitoring wells on the HH SEGS site. This suggests that

the shallow aquifer in the area around the Stump Spring monitoring well is more connected to recharge sources and not well connected to the shallow aquifer as on the HH SEGS site. The cause for this difference is not conclusively known but is likely due to a partial hydraulic barrier and stratigraphic variations caused by the State Line Fault System and its influences on the depositional patterns of the aquifer. Water level sampling conducted by Nye County has demonstrated that the State Line Fault system appears to affect the response of water levels in wells in the area as discussed in the APT-1 report.




Figure 6-1 Schematic diagram of observed drawdowns in monitoring wells




Figure 6-2 Observed water levels in monitoring wells during APT 2




Figure 6-3 Observed water levels in monitoring wells, July 17, 2012 to end of APT-2





Figure 6-4 Drawdown measured in the Stump Spring Monitoring Well, March to September, 2012

1.27 APT DRAWDOWN ANALYSIS

The monitoring well drawdown data document that the cone of depression created around the pumping well during APT-2 did not extend far. The pumping test data from the wells that showed drawdown response to pumping were analyzed using AQTESOLV™ (Version Pro4), an industry standard aquifer analysis package. The drawdown data for each monitoring well was plotted against time and fitted to the appropriate 'type curve' to determine the transmissivity, storage, and boundary conditions of the aquifer at each monitoring well. All five monitoring wells in which drawdown was detected followed drawdown curves associated with 'leaky artesian' aquifer characteristics indicating that the aquifer sediments are bounded above and below by a semi-permeable confining unit that allows a slow release of recharge to the aquifer in response to pumping.


Figures 6-5 and 6-6 illustrate the best fitting curves for the drawdown vs. time plot for Well 3 and Well 3A, located 20 feet and 37 feet from the pumping well, respectively. Well 3 is completed with slotted casing from 157 to 773 feet below the surface, and is uncased (i.e., open hole) to a depth of greater than 975 feet. Well 3A is completed with slotted casing from the surface to 346 feet below the surface. These two wells fully penetrate the aquifer and are completed in the same units that Well 3B is pumping from. The data were fitted to various type curves and found to fit the Hantush (leaky artesian aquifer with storage in the confining unit) family of curves.

Water levels in both wells stabilized after about a week of pumping and did not change more than 0.2 feet over the second week of pumping. Projecting the type curves forward in time indicates that water levels will not increase with continued pumping unless the pumping rate is increased or some other external change, such as pumping from another source, is imposed on the aquifer. The test data demonstrates the aquifer reaches steady state after about one week of pumping at 45 gpm and that the aquifer can sustain this rate with no additional drawdown indefinitely. The results of the analysis are summarized in Table 6.1.



WELL TEST ANALYSIS					
Data Set: <u>C:\...\BSE Well 3 Hantush.aqt</u>			Time: <u>14:45:50</u>		
Date: <u>09/23/12</u>					
AQUIFER DATA					
Saturated Thickness: <u>250</u> ft			Anisotropy Ratio (Kz/Kr): <u>0.1</u>		
Aquitard Thickness (b'): <u>1</u> ft			Aquitard Thickness (b''): <u>1</u> ft		
WELL DATA					
Pumping Wells			Observation Wells		
Well Name	X (ft)	Y (ft)	Well Name	X (ft)	Y (ft)
Well 3B	0	0	Well 3	20	0
SOLUTION					
Aquifer Model: <u>Leaky</u>			Solution Method: <u>Hantush</u>		
T = <u>2637.8</u> gal/day/ft			S = <u>0.003992</u>		
r/B' = <u>0.1318</u>			β' = <u>0.1</u>		
r/B'' = <u>0.</u>			β'' = <u>0.</u>		

Figure 6-5 Drawdown vs. time plot for Well 3, located 20 feet from Well 3B



WELL TEST ANALYSIS					
Data Set: C:_BSE Well 3A Hantush.aqt			Time: 14:39:39		
Date: 09/23/12					
AQUIFER DATA					
Saturated Thickness: 250. ft			Anisotropy Ratio (Kz/Kr): 0.1		
Aquitard Thickness (b'): 1. ft			Aquitard Thickness (b''): 1. ft		
WELL DATA					
Pumping Wells			Observation Wells		
Well Name	X (ft)	Y (ft)	Well Name	X (ft)	Y (ft)
Well 3B	0	0	Well 3A	37	0
SOLUTION					
Aquifer Model: Leaky			Solution Method: Hantush		
T = 4273. gal/day/ft			S = 0.003045		
r/B' = 0.1072			B' = 0.1		
r/B'' = 0.			B'' = 0.		

Figure 6-6 Drawdown vs. time plot for Well 3A, located 37 feet from Well 3B.

Figures 6-7 to 6-9 present best fitting curves for the drawdown vs. time plot for MW-3, located 178 feet from the Well 3B, MW-4, located 69 feet from Well 3B, and MW-5, located 14 feet from Well 3B. All


three of these monitoring wells are 200 feet deep. The gamma logs indicate that these wells are completed in a finer grained portion of the aquifer and do not penetrate the more permeable deeper zones of the aquifer that Wells 3, 3A and 3B penetrate. Well 3B pumps from slotted casing 250 to 350 feet deep, 50 feet below the bottom of the monitoring wells. Well 3B is pumping from a deeper part of the aquifer that is generally more permeable than the upper zone.

We used the Neumann-Witherspoon leaky artesian solution to account for the vertical variation of the aquifer properties and the partial penetration effects of the monitoring well completions. The Neumann-Witherspoon solution estimates the hydraulic properties of an aquifer-aquitard system for monitoring wells completed in an aquitard above a pumped aquifer. Although it was originally derived for aquifers with low leakance (the so called slightly leaky aquifer) Neumann and Witherspoon showed that it can be used for aquitards with high leakance values (the so called very leaky aquifer) (Kruseman and deRidder 1990). Although the monitoring wells are not completed in the tightest portion of the aquitard, they are completed in a finer grained portion of the aquifer that is probably transitional in nature to the overlying dense clay aquitard. We used this method to account for the lower permeability of the upper portion of the aquifer and the partial penetration effects of the monitoring wells.

The transducer in MW-3 produced several short duration spikes in the data of several inches to about one foot after about 3 days of pumping. The transducer experienced a static shift of several inches after about 9 days of pumping. These events correlate to manual measurements made with an electric water level indicator in the well. None of the changes in transducer data were confirmed by changes in water level from the manual measurements. It appears that transducer was disturbed when the manual measurements were made, possibly by snagging the cable. The transducer position seems to have been permanently shifted after the event on the 9th day of pumping making the last part of the curve useless for curve fitting. We removed the data after 13,000 minutes of pumping (9.03 days) for the curve fitting process but left the short duration spikes in the data because they did not seem to result in a long term shift in the data and could easily be ignored when fitting the curves.


The monitoring wells behaved differently than the fully penetrating wells (Well 3 and Well 3A) due to the slower vertical drainage of the finer grained material in the upper portion of the aquifer, the partial penetration of the monitoring wells, and the vertical gradients created by pumping Well 3B. Water levels in MW-4 had nearly stabilized by the end of the test. The data from MW-3 and MW-5 indicates that water levels were still declining at a very small rate, but that the water levels were getting close to stabilizing. Projecting the type curves forward indicates that water levels in MW4 would not experience any additional drawdown with prolonged pumping and the water levels in MW3 and MW5 would experience additional drawdown of a few tenths of a foot at most. The results of the curve fitting using the Neumann-Witherspoon curves are summarized in Table 5-1. The results from the Neumann-Jacob curves fits from APT-1 using Well 3 as the pumping well are also listed on Table 5-1.

The average transmissivity for the aquifer based upon the results of APT-2 is about 4,800 gpd/ft. This is about 45% lower than the average value from APT-1 (8,700 gpd/ft). This difference is significant, but within the range of variability typically seen in multiple pumping tests from an aquifer. A large part of this difference is probably caused by the less permeable nature of the aquifer in the vicinity of Well 3B relative to Well 3 as demonstrated by the gamma logs and the wells' different specific capacities.



WELL TEST ANALYSIS					
Data Set: C:\...BSE MW3 Neumann-Witherspoon 9 days.aqt					
Date: 09/28/12			Time: 11:59:37		
AQUIFER DATA					
Saturated Thickness: 150. ft			Anisotropy Ratio (Kz/Kr): 0.1		
Aquitard Thickness (b'): 70. ft			Aquitard Thickness (b''): 700. ft		
WELL DATA					
Pumping Wells			Observation Wells		
Well Name	X (ft)	Y (ft)	Well Name	X (ft)	Y (ft)
Well 3B	0	0	□ MW3	178	0
SOLUTION					
Aquifer Model: Leaky			Solution Method: Neuman-Witherspoon		
T = 6888.3 gal/day/ft			S = 0.001914		
r/B = 0.1516			β = 1.0E-5		
T2 = 2.913E+4 gal/day/ft			S2 = 0.005111		

Figure 6-7 Drawdown vs. time plot for MW-3, located 178 feet from Well 3B



WELL TEST ANALYSIS

Data Set: C:\...BSE MW4 Neumann-Witherspoon.aqt

Date: 09/23/12Time: 15:58:15

AQUIFER DATA

Saturated Thickness: 150. ftAnisotropy Ratio (Kz/Kr): 0.1

Aquitard Thickness (b'): 70. ftAquitard Thickness (b''): 700. ft

WELL DATA

Pumping Wells			Observation Wells		
Well Name	X (ft)	Y (ft)	Well Name	X (ft)	Y (ft)
Well 3B	0	0	□ MW4	69.5	0

SOLUTION


Aquifer Model: LeakySolution Method: Neuman-Witherspoon

T = 5690.7 gal/day/ftS = 0.00267

r/B = 0.151β = 0.001

T2 = 1.077E+4 gal/day/ftS2 = 0.001

Figure 6-8 Drawdown vs. time plot for MW-4, located 69.5 feet from Well 3B



WELL TEST ANALYSIS

Data Set: C:\...\BSE MW5 Neumann-Witherspoon.agt
Date: 09/24/12Time: 08:56:10

AQUIFER DATA

Saturated Thickness: 150. ftAnisotropy Ratio (Kz/Kr): 0.1
Aquitard Thickness (b'): 70. ftAquitard Thickness (b''): 700. ft

WELL DATA

Pumping Wells			Observation Wells		
Well Name	X (ft)	Y (ft)	Well Name	X (ft)	Y (ft)
Well 3B	0	0	□ MW5	13	0

SOLUTION

Aquifer Model: LeakySolution Method: Neuman-Witherspoon
T = 4522.4 gal/day/ftS = 0.01411
r/B = 0.07568β = 0.001
T2 = 1.077E+4 gal/day/ftS2 = 0.001

Figure 6-9 Drawdown vs. time plot for MW-5, located 13 feet from the Well 3.

Well	Distance (ft)	T (gpd/ft)	S	r/B	APT-2 Solution	APT-1 T value	APT-1 Solution
Well 3	20	2,640	0.003	0.13	Hantush	NA	
Well 3A	37	4,273	0.003	0.11	Hantush	NA	
MW-3	69.5	6,888	0.002	0.08	Neumann-Witherspoon	11,750	Hantush-Jacob
MW-4	13	5,690	0.002	0.151	Neumann-Witherspoon	7,342	Hantush-Jacob
MW-5	178	4,522	0.014	0.07	Neumann-Witherspoon	6,984	Hantush-Jacob
Average		4,802	0.005	0.108		8,692	

NA=Not Applicable

Table 6-1 Summary of transmissivity values from curve fitting.

1.28 PROJECTION OF DRAWDOWN OVER PROJECT DURATION

The project is expected to have an operational life of 25 years. While it is not possible to pump wells for 25 years to directly observe the response of the aquifer, it is possible to project future drawdown in the aquifer from the pumping test data.

In a perfectly confined, homogeneous aquifer with no gradient (no regional flow), the cone of depression created by a pumping well would theoretically expand for as long as the well was pumped. In nature, no aquifers are perfectly confined and there is almost always some regional flow within the aquifer. In real world conditions, the cone of depression around a pumping well grows until it intercepts enough recharge or regional flow to replace the water being extracted, at which point the cone stabilizes and ceases to expand. This creates a new steady-state condition within the aquifer where recharge and discharge are balanced and the flow pattern does not change unless there is some other disturbance in the system.

APT-1 and APT-2 both demonstrated that the aquifer receives recharge from leakance from the fine grained units above and below the aquifer. APT-1 demonstrated that the Orchard Well reached steady state conditions after about one day of pumping. APT-2 demonstrated that the aquifer around Well 3B reached steady state after about one week of pumping.

Figure 6-10 is a distance drawdown plot for APT-2 after 14 days of pumping. The data points represent the drawdown measured in the three monitoring wells and in Wells 3 and 3A at the end of the pumping test. The data show some scatter due to the variations in aquifer properties, both laterally and vertically, and the differences in well construction. The blue line passes through Well 3 and Well 3A, the two fully penetrating monitoring wells. The blue line also passes through MW-4, the monitoring well that had reached steady state. MW-3 and MW-5 do not fall on this line. The red line passes through MW-3, MW-4, and MW-5. All three monitoring wells fit closely to the line but Well 3 and Well 3A do not. The discrepancy in the data fits indicates that aquifer properties for the shallow monitoring wells are different than for the fully penetrating monitoring wells. Looking at the red line as the most conservative indicator, the cone of depression from Well 3B is not expected to extend beyond about 1,000 feet. This means that pumping Well 3B at 45 gpm at steady state will not cause measureable drawdown in the aquifer beyond about 1,000 feet from the pumping well. This is largely consistent with the projections made from the APT-1 data that estimated a radius of influence of about 1,500 feet using projected water levels from non-

steady state data. This estimate is also confirmed by the field observations that did not measure any APT-related drawdown in MW-6 (approximately 1,500 feet away), nor at any of the other more distant wells being monitored during APT-2.




Figure 6-10 Drawdown vs. distance from Well 3B after 14 days of pumping at 45 gpm

1.29 SUMMARY

APT-2 was conducted for 14 days from September 7 to 21, 2012. Well 3B was installed for this purpose and was pumped at a nominal rate of 45 gpm while water levels were recorded in two fully penetrating monitoring wells (Well 3 and Well 3A) as well as three partially penetrating monitoring wells. Several additional wells and monitoring wells were monitored during the test but no drawdown was observed.

Analysis of the test data demonstrated that the measured aquifer properties were similar, though the transmissivity was lower than, the results from APT-1. The lower transmissivity values are probably a function of the finer grained aquifer material discovered in the vicinity of Well 3B.

APT-2 confirmed that the aquifer behaves as a leaky confined aquifer. The data from the fully penetrating observation wells indicates that the aquifer reached steady state conditions after about one week of pumping. The monitoring wells are completed in a finer grained portion of the aquifer. One of the three monitoring wells had reached steady state by the end of the test. The other two monitoring wells were within about 0.2 feet of steady state conditions.

The geometry of the aquifer was better defined by running gamma logs in several wells on site. The logging showed that the aquifer lies between approximately 130 and 350 feet below the surface, with the most permeable zones below about 220 feet. The production wells for the facility are expected to be approximately 350 deep and any monitoring wells will only need to be constructed to this depth to fully penetrate the aquifer. The lower portion of Well 3 is completed in predominantly fine grained deposits and contributed minimal amounts of water during APT-1.

Well 3A was evaluated and determined to be approximately 350 feet deep and can produce over 100 gpm. Heavy sand production related to the age and simple construction of the well prevented it from being used as a pumping well. Well 3B was drilled to 360 feet and was completed with slotted casing from 255 to 355 feet. The production of the well was limited by a combination of formation damage from the drilling process (which was partially restored by aggressive development efforts) and the presence of less permeable formation around Well 3B as compared to wells 3 or 3A. The well was able to produce 45 gpm for the duration of APT-2 but water levels in adjacent wells indicates that the majority of the drawdown in Well 3B was due in part to poor well efficiency and that a more efficient well could have produced several times as much water.

The data indicates that the aquifer can support two wells pumping 45 gpm each indefinitely with a cone of depression that will not propagate beyond about 1,000 feet away from each well. The data from APT-2 supports the conclusions reached by the APT-1 report.

- The aquifer on the project site can easily produce the water needed for the project.
- The cone of depression will not extend off site
- Pumping from the project wells will not cause additional drawdown in off-site wells.
- Pumping from the project wells will not affect Stump Spring.
- Retiring active water rights in the basin equal to the project pumping will mitigate the impacts of the project and render the project water-neutral for the basin water balance.

- The project will not affect groundwater dependent vegetation because there is no groundwater dependent vegetation within the projected cone of depression of the project wells.


References

- California Department of Water Resources (DWR), 1964. Ground Water Occurrence and Quality Lahontan Region. Bulletin No. 106-1.
- California Department of Water Resources (DWR), 1975. California's Ground Water. Bulletin No. 118.
- Cardno ENTRIX, 2011. Hidden Hills Project Interim Assessment Report, prepared for BrightSource Energy.
- Cardno ENTRIX, 2012, Long-Term Aquifer Performance Test Report: Hidden Hills Solar Electric Generating System Site, Prepared for BrightSource Energy. March, 2012.
- Flynn, K.S., Ludington, S., McLaurin, B.T., Castor, S.B., 2006. Chapter K. Mineral Resource Potential of The Stump Spring Area of Critical Environmental Concern, Clark County, Nevada. U.S. Geological Survey Scientific Investigations Report 2006-5197.
- Hantush, M. S., and R. G. Thomas, 1966. A method for analyzing a drawdown test in anisotropic aquifers, Water Resour. Res., 2(2), 281–285.
- Hunt, C.B., T.W. Robinson, W.A. Bowles, and A.L. Washburn, 1966. Hydrologic Basin Death Valley California. U.S. Geological Survey Professional Paper 494 – B.
- Kruseman, GP, and NA deRidder, 1989. Analysis and Evaluation of Pumping Test Data, ILRI publication 47, 377p.
- Malmberg, G.T., 1967. Hydrology of the valley-fill and carbonate-rock reservoirs, Pahrump Valley, Nevada--California: U.S. Geological Survey Water-Supply Paper 1832, 47 p.
- Waring, G. A., 1920. Ground Water in Pahrump, Mesquite, and Ivanpah Valleys Nevada and California. Water-Supply Paper 450-C.



Cardno
ENTRIX

Shaping the Future



Down to Earth.
Down to Business.™

Toll-free 800 368 7511

www.cardnoentrix.com
www.cardno.com


Australia • Belgium • Indonesia • Kenya • New Zealand • Papua New Guinea
United Arab Emirates • United Kingdom • United States • Operations in 60 countries



APPENDIX D USGS 2020 REPORT

Prepared in cooperation with the U.S. Department of Energy Office of Environmental Management, National Nuclear Security Administration, Nevada Site Office, under Interagency Agreement DE-EM0004969

Groundwater Characterization and Effects of Pumping in the Death Valley Regional Groundwater Flow System, Nevada and California, with Special Reference to Devils Hole



Professional Paper 1863

Cover: Map of study area showing Alkali Flat–Furnace Creek Ranch, Ash Meadows, Bullfrog Hills, Pahrump to Death Valley South, and Pahute Mesa–Oasis Valley groundwater basins; and Nevada National Security Site boundary and internal operations area, in the Death Valley regional flow system, Nevada and California.
Source: U.S. Geological Survey.

Groundwater Characterization and Effects of Pumping in the Death Valley Regional Groundwater Flow System, Nevada and California, with Special Reference to Devils Hole

By Keith J. Halford and Tracie R. Jackson

Prepared in cooperation with the U.S. Department of Energy Office of Environmental Management, National Nuclear Security Administration, Nevada Site Office, under Interagency Agreement DE-EM0004969

Professional Paper 1863

**U.S. Department of the Interior
U.S. Geological Survey**

U.S. Department of the Interior
DAVID BERNHARDT, Secretary

U.S. Geological Survey
James F. Reilly II, Director

U.S. Geological Survey, Reston, Virginia: 2020

For more information on the USGS—the Federal source for science about the Earth, its natural and living resources, natural hazards, and the environment—visit <https://www.usgs.gov> or call 1–888–ASK–USGS.

For an overview of USGS information products, including maps, imagery, and publications, visit <https://store.usgs.gov>.

Any use of trade, firm, or product names is for descriptive purposes only and does not imply endorsement by the U.S. Government.

Although this information product, for the most part, is in the public domain, it also may contain copyrighted materials as noted in the text. Permission to reproduce copyrighted items must be secured from the copyright owner.

Suggested citation:

Halford, K.J., and Jackson, T.R., 2020, Groundwater characterization and effects of pumping in the Death Valley regional groundwater flow system, Nevada and California, with special reference to Devils Hole: U.S. Geological Survey Professional Paper 1863, 178 p., <https://doi.org/10.3133/pp1863>.

Associated data for this publication:

Jackson, T.R., and Halford, K.J., 2020, MODFLOW-2005 model and supplementary data used to characterize groundwater flow and effects of pumping in the Death Valley regional groundwater flow system, Nevada and California, with special reference to Devils Hole: U.S. Geological Survey data release, <https://doi.org/10.5066/P9HIYVG2>.

ISSN 1044-9612 (print)
ISSN 2330-7102 (online)

Contents

Abstract.....	1
Introduction.....	2
Purpose and Scope	5
Description of Study Area	5
Previous Investigations.....	6
Regional Models—1982–97	6
Regional Investigations—1998–2004.....	6
Predevelopment Discharge Investigations	6
Hydraulic-Property and Water-Use Investigations.....	8
Hydrogeologic Framework.....	8
DFRVS.v1 Model.....	9
DVRFS.v2 Model.....	10
Approach.....	10
Geology.....	12
Interbasin Flow Between Groundwater Basins	17
Predevelopment Groundwater Flow.....	17
Discharge Areas	19
Ash Meadows.....	21
Furnace Creek Area	21
Previous Predevelopment Estimates And Conceptual Models	21
DV3 Conceptual Model—Three Hydrologically Distinct Periods.....	25
Discharge from Springs	25
Discharge from Phreatophytes on Alluvial Fan	26
Furnace Creek Wash—A Transmissive Feature	26
Mining-Tourism Period—A Steady-State Condition.....	28
Pahrump Valley	28
Lower Amargosa Area	30
Saratoga Spring Area	32
Recharge	34
Spatially Distributed Long-Term Rates	35
Precipitation-Runoff	35
Perched and Semi-Perched Groundwater	36
Temporal Variability	36
Hydraulic Conductivity.....	40
Field Estimates of Transmissivity.....	41
Transmissivity and Rock Type	44
Transmissivity and Thickness	44
Hydraulic Conductivity and Depth	46
Hydrogeologic Framework.....	49
Discretization	50
Water-Table Surface	50
Vertical Discretization.....	50
Faults	52

Contents—Continued

Hydrogeologic Units.....	52
Revisions from Underground Test Area Projects	54
Hydraulically Mandated Features.....	58
Groundwater Development.....	59
Data Compilation.....	59
Pumping and Return Flow	61
Areas Affected by Pumping	63
Central Amargosa Desert and Pahrump Valley	63
Central Amargosa Desert.....	64
Pahrump Valley	64
Jackass Flats	66
Isolated Areas of Groundwater Development	70
Ash Meadows and Devils Hole	70
Stresses Affecting Water Levels in Devils Hole	70
Devils Hole Water-Level Model.....	74
Integrated Estimation of Recharge and Hydraulic-Property Distributions with Numerical Models.....	76
Common Construction of Models.....	76
Distributing Hydraulic Properties And Recharge	76
Hydraulic Conductivity.....	78
Specific Yield and Specific Storage	82
Recharge	82
Stress-Response Models	84
Common Boundary Conditions	84
Predevelopment—DV3-SS Model	84
Lateral Flow Across Study Area Boundary	84
Water Table and Perched Groundwater Assumptions.....	84
Boundary Conditions	85
Simulation of Springs	85
Groundwater Development—DV3-AM-AFFCR and DV3-PDVS Models.....	87
Temporal Discretization	88
Boundary Conditions	88
Well <i>ER-6-1-2 main</i> Multiple-Well Aquifer Test—DV3-ER612 Model.....	89
Temporal Discretization	89
Boundary Conditions	91
Calibration.....	91
Measurement Observations	91
Predevelopment Observations—DV3-SS Model	94
Water-Level Altitudes in Wells	94
Water-Level Altitudes in Evapotranspiration Areas	94
Spring-Pool Altitudes	95
Water-Table Altitude Comparisons to Land Surface	95
Water-Level Differences Between Measurement Sites.....	95
Transmissivity Comparisons.....	95

Contents—Continued

Conceptual Preferences of Recharge, Predevelopment Discharge, and Groundwater-Basin-Boundary Flows	95
Groundwater-Development Observations—DV3-AM-AFFCR and DV3-PDVS Models	98
Water-Level Changes.....	98
Accounting for Temporal Variability in Recharge	99
Groundwater Capture from Springs and Evapotranspiration Areas	99
Well <i>ER-6-1-2 main</i> Multiple-Well Aquifer Test—DV3-ER612 Model	102
Regularization Observations	102
Goodness of Fit.....	103
Predevelopment Observations	103
Groundwater-Development Observations	106
Well <i>ER-6-1-2 main</i> Multiple-Well Aquifer Test	112
Ash Meadows And Devils Hole.....	120
Hydrologic Features	124
Water Table Beneath Rainier Mesa	124
Boundary Between AFFCR and PMOV Groundwater Basins.....	124
Megachannel	127
Gravity Fault.....	129
Well <i>AD-4</i> Corridor.....	129
Furnace Creek Wash.....	129
Water Table Beneath Black Mountains and Greenwater Range	132
Continuous Aquifer of Carbonate Rocks and Basin Fill in PDVS Groundwater Basin	133
Simulated Predevelopment Groundwater Flow.....	133
Recharge and Discharge Areas	133
Flow from Ash Meadows Groundwater Basin to the Furnace Creek Area	137
Basin-Fill Flow Conceptualization	137
Flow Potential Through Well <i>AD-4</i> Corridor	140
Flow Potential Through Basin Fill in the Central Amargosa Desert	141
Basin-Fill, Carbonate-Rock, and Volcanic-Rock Hydraulic Connections.....	141
Geochemically Differentiated Sources of Furnace Creek Area Discharge	141
Major Ions.....	141
Stable Isotopes	144
Deep-Carbonate Flow Conceptualization	145
Furnace Creek Fault Zone	145
Hydrochemical Evidence.....	146
Contradictory Results from Drilling and Numerical Simulation	146
Basin-Fill Flow Path More Probable.....	147
Predevelopment Water Budgets.....	147
Pahute Mesa—Oasis Valley Groundwater Basin	147
Ash Meadows Groundwater Basin	147
Alkali Flat—Furnace Creek Ranch Groundwater Basin.....	150
Pahrump to Death Valley South Groundwater Basin.....	150

Contents—Continued

Rainier Mesa Groundwater Sub-Basin	150
Effects of Groundwater Development	150
Extent of Water-Level Declines	151
Sources of Pumped Water	151
Reductions in Natural Discharges	151
Ash Meadows and Devils Hole	154
Potential Effects of Future Groundwater Development	158
Groundwater-Basin Boundary Uncertainty	160
Evaluation of Advective Flow from Corrective Action Units	160
Model Limitations	163
Summary	165
Acknowledgments	168
References Cited	168

Figures

1. Map of study area showing groundwater basins and hydrographic areas in the Death Valley regional flow system, Nevada and California	3
2. Map showing areal extent of previous regional groundwater models and the regional model [Death Valley version 3 (DV3)] used in this study, Nevada and California	7
3. Graph showing minimum, maximum, geometric mean, and 95-percent confidence interval of log-hydraulic conductivities in 9 hydrogeologic units in the Death Valley Regional Flow System version 2 model framework using 377 hydraulic-conductivity estimates, Nevada and California	9
4. Hydrograph showing measured and simulated water-level changes in Devils Hole from the Death Valley Regional Flow System versions 1 and 2 (DVRFS.v1 and DVRFS.v2) models, Nevada and California, 1930–2018	11
5. Map showing major geologic structures, in the study area, Nevada and California	16
6. Map showing groundwater basins and major discharge areas in the study area, Nevada and California	18
7. Map showing springs and evapotranspiration areas in the Ash Meadows discharge area and vicinity, Nevada	22
8. Conceptual model showing groundwater flow to springs and phreatophyte areas in the Ash Meadows discharge area, Nevada	23
9. Map showing discharge locations and the historical water-collection system in the Furnace Creek area, California	24
10. Hydrographs showing groundwater-level fluctuations in the Furnace Creek area from collection galleries in Furnace Creek Wash and water-supply wells, California, 2008–12	27
11. Map showing discharge areas in Pahrump and Stewart Valleys, Nevada and California	29
12. Map showing discharge areas in the Lower Amargosa discharge area and extent of Pleistocene Lake Tecopa, Nevada and California	31

Figures—Continued

13.	Graph showing groundwater discharge to river and estimated evapotranspiration in the Amargosa River downstream of Borehole Spring, California, on February 27, 2014, and cumulative annual evapotranspiration.....	32
14.	Map showing upgradient source and discharge areas for the Saratoga Spring area, California.....	33
15.	Graphs showing relation between precipitation rate and conceptual recharge rate from infiltration and runoff to the study area, and cumulative recharge resulting from this relation, in the study area, Nevada and California	36
16.	Map showing conceptual recharge distribution, in the study area, Nevada and California	37
17.	Graphs showing winter precipitation (October–March) and excess winter precipitation (recharge) using 125-percent threshold, and hypothetical water-level change under predevelopment (steady-state) conditions, in the study area, Nevada and California, 1900–2016	39
18.	Hydrographs showing measured water levels and water-level models for wells <i>U-19bk</i> and <i>USFWS DR-1</i> , in the study area, Nevada and California, 1910–2018	40
19.	Map showing transmissivity estimates from single-well aquifer tests and specific capacity, in the study area, Nevada and California.....	42
20.	Graph showing volume of water pumped or displaced from single-well aquifer tests (pumping and slug tests) and specific capacity, in the study area, Nevada and California	44
21.	Graphs showing minimum, maximum, median, and 95-percent confidence interval of log-transmissivities in four rock-type categories from 271 field estimates of transmissivity, in the study area, Nevada and California.....	46
22.	Graphs showing relation between transmissivity and thickness of carbonate rocks, volcanic rocks, basin fill, and low-permeability rocks, in the study area, Nevada and California	47
23.	Graph showing relation between specific capacity and thickness of basin fill classified as permeable in the Amargosa Desert, Nevada	48
24.	Graphs showing average, depth-dependent hydraulic conductivity in volcanic and carbonate rocks, in the study area, Nevada and California	49
25.	Map showing differences in the water-table surface between the Death Valley version 3 (DV3) and Death Valley Regional Flow System version 2 (DVRFS.v2) hydrogeologic framework, and areas where the DVRFS.v2 hydrogeologic framework was modified, in the study area, Nevada and California.....	51
26.	Example cross sections through intermediate grid of Death Valley Regional Flow System version 2 (DVRFS.v2) (Belcher and others, 2017; top cross section), and Death Valley version 3 (DV3; bottom cross section) hydrogeologic framework models, Nevada and California	55
27.	Map showing extents of hydrogeologic framework models for Frenchman Flat, Yucca Flat–Climax Mine, Rainier Mesa–Shoshone Mountain, and Pahute Mesa corrective action units; extent of Frenchman Flat basin in Death Valley Regional Flow System version 2 model (DVRFS.v2) hydrogeologic framework; and areas where carbonate rocks at water table in DVRFS.v2 were revised to volcanic rocks, basin fill, or low-permeability rocks in Death Valley version 3 model (DV3) hydrogeologic framework based on lithologic well data, Nevada and California.....	56

Figures—Continued

28.	Maps showing hydrogeologic units in Death Valley Regional Flow System version 2 model (DVRFS.v2), Death Valley version 3 model (DV3), and Fenelon and others (2012), at the water table beneath Yucca Flat, Nevada	57
29.	Map showing pumping wells, areas affected by groundwater development, and hydraulic barriers, in the study area, Nevada and California	60
30.	Graphs showing total annual groundwater withdrawals by water-use type, return flow, and predevelopment discharge by groundwater basin, in the study area, Nevada and California, 1910–2010, with withdrawal estimates from 2010 projected through 2018	62
31.	Graph showing net groundwater withdrawals and return flow, in the study area, Nevada and California, 1910–2018	64
32.	Map showing observation wells affected by groundwater development and hydraulic barriers, in the study area, Nevada and California	65
33.	Hydrographs showing water-level changes in well <i>AD-5</i> in the central Amargosa Desert and well <i>ESB1</i> in Pahrump Valley, Nevada, 1910–2018	66
34.	Graph showing net pumpage in the Alkali Flat-Furnace Creek Ranch groundwater basin, and hydrographs showing measured water levels in wells <i>BGMW-8</i> , <i>NC-EWDP-Washburn-1X(deep)</i> , <i>DVJ-02</i> , and <i>Travertine Point 1</i> , in the central Amargosa Desert, Nevada and California, 1910–2018	67
35.	Graph showing net pumpage in the Pahrump to Death Valley South groundwater basin, and hydrographs showing measured water levels in wells <i>BLM Stewart Valley Well</i> , <i>Last Chance Well</i> , <i>Jeep Trail</i> , <i>021N010E04L01S</i> , and <i>Hwy 127 MM21-1</i> , around Pahrump Valley, Nevada and California, 1910–2018	68
36.	Graph showing annual pumping from Jackass Flats , and hydrographs showing measured water levels in wells <i>JF-2</i> , <i>J-13 WW</i> , and <i>JF-3</i> , in Jackass Flats, Nevada, 1950–2018	69
37.	Map showing hydrogeologic units at the water table, wells, <i>Devils Hole</i> , springs, pumping wells, and injection well [<i>Devils Hole Well (AM-5)</i>] in the Ash Meadows discharge area and surrounding areas, Nevada	71
38.	Graph showing monthly pumping from northern wells, southern wells, and <i>Spring Meadows 6</i> well and injection into <i>Devils Hole Well (AM-5)</i> by Cappaert Enterprises in the Ash Meadows discharge area, Nevada, 1968–82	72
39.	Graph showing monthly pumping and injection from the Ash Meadows discharge area, and hydrographs showing measured water levels in wells <i>Devils Hole Well (AM-5)</i> , <i>Point of Rocks North (AM-6)</i> , and <i>Spring Meadows 7db2</i> , during groundwater development by Cappaert Enterprises, Nevada, 1965–2000	73
40.	Graphs showing estimated natural water-level fluctuations, long-term natural trend of recharge and steady discharge, measured water levels, water-level model that includes all natural and pumping stresses, and pumping effects without natural fluctuations in <i>Devils Hole</i> , Nevada, 1900–2018	75
41.	Map showing boundary of Death Valley version 3 (DV3) model and areas of finer discretization, in the study area, Nevada and California	77
42.	Diagram showing process for distributing hydraulic conductivities from pilot points to U.S. Geological Survey finite-difference model (MODFLOW) layers through hydrogeologic units in a hydrogeologic framework	79
43.	Map showing conceptual transmissivity distribution in shallow carbonate rocks and hydraulic-conductivity pilot points for the shallow carbonate rocks, in the study area, Nevada and California	80

Figures—Continued

44. Map showing extents of all hydrogeologic units and hydraulic-conductivity pilot points at the water table, in the study area, Nevada and California.....	81
45. Map showing estimated recharge distribution and recharge pilot points, from the Death Valley version 3 steady-state model (DV3-SS), in the study area, Nevada and California	83
46. Map showing locations and types of boundary conditions and measurement observations used in the Death Valley version 3 steady-state model (DV3-SS), in the study area, Nevada and California.....	86
47. Map showing observation wells monitored during well <i>ER-6-1-2 main</i> multiple-well aquifer test, in the study area, Nevada and California.....	90
48. Conceptual diagram showing the model-run process of the Death Valley version 3 model (DV3), which is an integrated stress-response model, in the study area, Nevada and California	92
49. Map showing lateral and vertical water-level difference observations used in the Death Valley version 3 steady-state model (DV3-SS), in the study area, Nevada and California	96
50. Map showing transmissivity observations from aquifer tests and specific capacities, in the study area, Nevada and California.....	97
51. Hydrograph showing “raw” water-level measurements, measured water levels, which are annual averages of measured water-level data during an annual stress period, and simulated water levels in well <i>ESB1</i> , Nevada, 1910–2020	100
52. Hydrographs showing “raw” water-level measurements, measured (average) water-level changes, and simulated water-level changes in terms of depth to water level and water-level change, at well <i>Travertine Point 1</i> , California, 1950–2018.....	100
53. Map showing estimated transmissivity distribution from integrated Death Valley version 3 model, extent of megachannel, and wells with measured water levels noticeably affected by natural fluctuations from recharge, Nevada National Security Site and vicinity, Nevada	101
54. Graph showing comparison of measured and simulated water-level altitudes from the calibrated Death Valley Regional Flow System version 2 model (DVRFS.v2) and Death Valley version 3 steady-state model (DV3-SS), in the study area, Nevada and California	104
55. Map showing steady-state water-level altitude residuals in the Death Valley version 3 steady-state model (DV3-SS), in the study area, Nevada and California	105
56. Graph showing comparison of simulated and measured transmissivities from the Death Valley Regional Flow System version 2 model (DVRFS.v2) and Death Valley version 3 steady-state model (DV3-SS), in the study area, Nevada and California	107
57. Map showing maximum simulated drawdown and selected observation sites with hydrographs shown in this report, in the study area, Nevada and California, 2018	108
58. Hydrographs showing “raw” water-level measurements and simulated and measured (average) water-level declines in wells <i>AD-5</i> , <i>TG Well</i> , and <i>Inyo-BLM1</i> , in the central Amargosa Desert, Nevada and California, 1950–2018.....	109
59. Hydrographs showing “raw” water-level measurements and simulated and measured (average) water-level declines in wells <i>AD-1</i> , <i>NC-EWDP-Washburn-1X (deep)</i> , <i>DVJ-02</i> , and <i>WRPMW-4</i> that result from pumping in the central Amargosa Desert, Nevada and California, 1950–2018	110

Figures—Continued

60.	Hydrographs showing “raw” water-level measurements and simulated and measured (average) water levels in wells <i>GSA</i> , <i>SD2</i> , and <i>JAW</i> , in Pahrump Valley, Nevada, 1910–2020	111
61.	Hydrographs showing “raw” water-level measurements and simulated and measured (average) water-level changes in wells <i>BLM Stewart Valley Well</i> , <i>Last Chance Well</i> , <i>Jeep Trail</i> , <i>021N010E04L01S</i> , <i>022N007E13L01S</i> , and <i>Hwy 127 MM21-1</i> that result from pumping in Pahrump Valley, in the study area, Nevada and California, 1910–2020	113
62.	Hydrographs showing comparison of simulated and measured discharges from <i>Bennetts</i> and <i>Manse</i> Springs, Pahrump Valley, Nevada, 1910–2018	114
63.	Hydrographs showing “Raw” water-level measurements and simulated and measured (average) water-level changes in well <i>WW-4</i> in CP basin, and <i>USAF Well 3</i> in Indian Springs, Nevada, 1950–2018.....	115
64.	Map showing estimated specific-yield distribution and pilot points from integrated Death Valley version 3 model, in the study area, Nevada and California	116
65.	Map showing estimated storage-coefficient distribution, which is specific storage times thickness of model layers 2–6, and pilot points from integrated Death Valley version 3 model, in the study area, Nevada and California	117
66.	Hydrographs showing periods when well <i>ER-6-1-2 main</i> pumped; simulated drawdowns from Death Valley version 3 model simulating Jackson and Halford, 2020 pumping during the <i>ER-6-1-2 main</i> multiple-well aquifer test (DV3-ER612); and measured drawdowns, which were estimated from water-level models (Jackson and Halford, 2019), in wells <i>ER-3-1-2 (shallow)</i> , and <i>ER-7-1</i> , Nevada, 2004–05	118
67.	Hydrographs showing periods when well <i>ER-6-1-2 main</i> pumped; simulated drawdowns from Death Valley version 3 model simulating Jackson and Halford, 2020 pumping during the <i>ER-6-1-2 main</i> multiple-well aquifer test (DV3-ER612); and measured drawdowns, which were estimated from water-level models (Jackson and Halford, 2019), in wells <i>UE-1h</i> , and <i>Tracer Well 3</i> , Nevada, 2004–05.....	118
68.	Map showing estimated transmissivity distribution from integrated Death Valley version 3 model (DV3), extent of megachannel, and observation sites during well <i>ER-6-1-2 main</i> multiple-well aquifer test, in the study area, California and Nevada.....	119
69.	Graphs showing measured, and DV3-SS- and DVRFS.v2-simulated pool altitudes and spring discharges, and total measured and simulated spring discharges, in the Ash Meadows discharge area, Nevada	121
70.	Hydrographs showing “raw” water-level measurements, measured (average) water-level changes, and simulated water-level changes in the megachannel, including wells <i>Tracer Well 3</i> , <i>North Crystal Well</i> , and <i>Spring Meadows 12</i> , and <i>Devils Hole</i> , Nevada, 1950–2018.....	122
71.	Graph showing monthly pumping by Cappaert Enterprises; injection into <i>Devils Hole Well (AM-5)</i> ; total simulated capture in the Ash Meadows discharge area from DV3-AM-AFFCR model; and hydrographs showing measured and simulated (DV3-AM-AFFCR model) discharges from <i>Jack Rabbit</i> , <i>Point of Rocks</i> , and <i>Big Springs</i> , Nevada, 1968–82	123
72.	Map showing estimated transmissivity distribution from integrated Death Valley version 3 model and traces of water-level profiles through major hydrologic features, in the study area, Nevada and California	126

Figures—Continued

73.	Measured water-level profile and simulated water-level profiles from Death Valley Regional Flow System version 2 model (DVRFS.v2) and Death Valley version 3 steady-state model (DV3-SS), and transmissivity profile from the DV3-SS model, through Rainier Mesa, Nevada.....	127
74.	Measured and simulated water-level profiles, and transmissivity profiles from the Death Valley version 3 steady-state model (DV3-SS), through boundary between Pahute Mesa–Oasis Valley and Alkali Flat–Furnace Creek Ranch groundwater basins, Nevada.....	128
75.	Measured and simulated water-level profiles, and transmissivity profiles from the Death Valley version 3 steady-state model (DV3-SS), through megachannel from Yucca Flat to the Ash Meadows discharge area, Nevada and California	130
76.	Measured and simulated water-level profiles, and transmissivity profiles from the Death Valley version 3 steady-state model (DV3-SS), through the well <i>AD-4</i> corridor, Nevada and California	131
77.	Measured and simulated water-level profiles, and transmissivity profile from the Death Valley version 3 steady-state model (DV3-SS), through the Furnace Creek area, California	132
78.	Measured and simulated water-level profiles, and transmissivity profile from the Death Valley version 3 steady-state model (DV3-SS), through the Black Mountains and Greenwater Range, California	134
79.	Measured and simulated water-level profiles, and transmissivity profile from the Death Valley version 3 steady-state model (DV3-SS), from the Spring Mountains to the Amargosa River, Nevada and California.....	135
80.	Map showing groundwater-flow paths to selected discharge areas and contributing recharge areas for discharge areas in Oasis Valley, Ash Meadows, Furnace Creek, Lower Amargosa, and Pahrump and Stewart Valleys, Nevada and California	136
81.	Cross section along a simulated groundwater-flow path from the Spring Mountains to the Amargosa River, Nevada and California	138
82.	Map showing basin-fill and deep-carbonate flow-path conceptualizations from the Ash Meadows groundwater basin to discharge areas in Furnace Creek, Nevada and California	139
83.	Cross section along a simulated groundwater-flow path from the Ash Meadows groundwater basin to the Furnace Creek area through the well <i>AD-4</i> corridor, Nevada and California	140
84.	Map showing water-chemistry sites in the Alkali Flat–Furnace Creek Ranch and Ash Meadows groundwater basins, Nevada and California	142
85.	Piper diagram showing major ion water chemistry for sites in the Alkali Flat–Furnace Creek Ranch and Ash Meadows groundwater basins, Nevada and California	143
86.	Graph showing stable isotopes for sites in the Alkali Flat–Furnace Creek Ranch and Ash Meadows groundwater basins, Nevada and California.....	145
87.	Maps showing flow-weighted paths from Furnace Creek discharge area to contributing recharge areas in the Death Valley Regional Flow System version 2 model (DVRFS.v2) and Death Valley version 3 steady-state model (DV3-SS), in the study area, Nevada and California.....	148

Figures—Continued

88.	Map showing predevelopment water budgets within and between geographic areas in the study area from the Death Valley version 3 steady-state model (DV3-SS), Nevada and California	149
89.	Graphs showing total annual groundwater withdrawals by groundwater-storage depletion, return flow, and capture of discharge from springs and evapotranspiration areas by groundwater basins Alkali Flat–Furnace Creek Ranch and Ash Meadows, Pahute Mesa–Oasis Valley, and Pahrump to Death Valley South, in the study area, 1910–2018, with withdrawal estimates from 2010 projected to 2018.....	152
90.	Hydrographs showing measured and simulated discharges from <i>Travertine</i> and <i>Texas</i> Springs in the Furnace Creek area, California, 1950–2018	155
91.	Map showing pumping centers analyzed for affecting water levels in <i>Devils Hole</i> , Nevada and California	156
92.	Graphs showing annual net pumpage by pumping center and water-level changes in Devils Hole by pumping center, as simulated with the Death Valley version 3 stress-response model simulating groundwater development in the Ash Meadows, Alkali Flat–Furnace Creek Ranch, and Pahute Mesa–Oasis Valley groundwater basins, Nevada and California, 1950–2018	157
93.	Graphs showing groundwater withdrawals and injections; and measured water levels, and simulated water levels with and without injections, in <i>Devils Hole Well (AM-5)</i> , Nevada, 1960–2000.....	159
94.	Hydrograph showing measured water levels without long-term natural fluctuations from recharge, and simulated water levels from DV3-AM-AFFCR and DV3-PRED models, in <i>Devils Hole</i> , Nevada, 1950–2100.....	159
95.	Map showing simulated 165-year advective-flow paths from 296 underground nuclear tests detonated near or below the water table, in the study area, Nevada National Security Site, Nevada	162

Tables

1. Predevelopment discharge estimates from previous and current investigations for Alkali Flat–Furnace Creek Ranch, Ash Meadows, and Pahute Mesa–Oasis Valley groundwater basins, Nevada and California, 1982–2018	8
2. Groundwater models developed for Death Valley version 3 model (DV3) project	12
3. Major lithology and occurrence descriptions of hydrogeologic units in the study area, as defined in the Death Valley Regional Flow System version 2 hydrogeologic framework, Nevada and California	13
4. Predevelopment discharge by discharge area for previous and current regional flow analyses of the study area, Nevada and California	20
5. Predevelopment and post-development discharge estimates for all sites in the Furnace Creek area, California, prior to 1880 to 2018	26
6. Relation between simple-rock types and previously defined hydrogeologic units in the Death Valley Regional Flow System version 2 model (DVRFS.v2) hydrogeologic framework, Nevada and California	45
7. Hydrogeologic units in the Death Valley version 3 model (DV3) hydrogeologic framework that were defined by rock type, depth, and previously defined hydrogeologic units from the Death Valley Regional Flow System version 2 model (DVRFS.v2) project, Nevada and California	53
8. Fraction of return flow and velocity through unsaturated zone, in the study area, Nevada and California	63
9. Springs explicitly simulated in Death Valley version 3 steady-state model (DV3-SS), estimated predevelopment spring discharge, and the minimum measured discharge from springs during groundwater development, in the study area, Nevada and California	87
10. Summary of observations and Death Valley version 3 model (DV3) fit to simulated comparisons, in the study area, Nevada and California	93
11. Expected and simulated groundwater-flow rate observations, in the study area, Nevada and California	98
12. Summary of major hydrologic features simulated in the integrated Death Valley version 3 model (DV3), for the study area, Nevada and California	125
13. Simulated discharges by discharge area for predevelopment (DV3-SS model), 2018 (DV3-AM-AFFCR or DV3-PDVS model), and projected future conditions in 2100 (DV3-PRED model), in the study area, Nevada and California	153
14. Pumping centers; net pumpage volumes, 1969–2018; and effect of pumping centers on water levels in <i>Devils Hole</i> , in the study area, Nevada and California	155

Conversion Factors

U.S. customary units to International System of Units

Multiply	By	To obtain
Length		
inch (in.)	25.4	millimeter (mm)
foot (ft)	0.3048	meter (m)
mile (mi)	1.609	kilometer (km)
Area		
square foot (ft ²)	0.09290	square meter (m ²)
square mile (mi ²)	2.590	square kilometer (km ²)
acre	4,047	square meter (m ²)
Volume		
gallon (gal)	3.785	Liter (L)
acre-foot (acre-ft)	1,233	cubic meter (m ³)
cubic mile (mi ³)	4.168	cubic kilometer (km ³)
Flow rate		
acre-foot per year (acre-ft/yr)	1,233	cubic meter per year (m ³ /yr)
cubic foot per second (ft ³ /s)	0.02832	cubic meter per day (m ³ /d)
gallon per minute (gal/min)	0.06309	liter per second (L/s)
Velocity		
foot per day (ft/d)	0.3048	meter per day (m/d)
foot per year (ft/yr)	0.3048	meter per year (m/yr)
Radioactivity		
picocurie per liter (pCi/L)	0.037	becquerel per liter (Bq/L)
Specific capacity		
gallon per minute per foot ([gal/min]/ft)	0.2070	liter per second per meter ([L/s]/m)
Hydraulic gradient		
foot per foot (ft/ft)	1	meter per meter (m/m)
foot per mile (ft/mi)	0.1894	meter per kilometer (m/km)
Transmissivity		
foot squared per day (ft ² /d)	0.09290	meter squared per day (m ² /d)

International System of Units to U.S. customary units

Multiply	By	To obtain
Length		
meter (m)	3.281	foot (ft)
Flow rate		
cubic meter per day (m ³ /d)	264.2	gallon per day (gal/d)
kilogram per second (kg/s)	2.205	pound per second (lb/s)
Chemical constituent concentration		
mg/L	0.0001335	ounce per U.S. gallon (oz/gal)
Density		
gram per cubic centimeter (g/cm ³)	62.4220	pound per cubic foot (lb/ft ³)

Temperature in degrees Fahrenheit (°F) may be converted to degrees Celsius as follows:

$$(^{\circ}\text{C})\ ^{\circ}\text{C} = (^{\circ}\text{F} - 32) / 1.8.$$

Datums

Vertical coordinate information is referenced to the National Geodetic Vertical Datum of 1929 (NGVD29).

Horizontal coordinate information is referenced to the North American Datum of 1983 (NAD 83).

Altitude, as used in this report, refers to distance above NGVD29.

Supplemental Information

Concentrations of chemical constituents in water are given in milligrams per liter (mg/L).

Activities for radioactive constituents in water are given in picocuries per liter (pCi/L).

Transmissivity: The standard unit for transmissivity is cubic foot per day per square foot times foot of aquifer thickness [(ft³/d)/ft²]ft. In this report, the mathematically reduced form, foot squared per day (ft²/d), is used for convenience.

Abbreviations

2D-FD	two-dimensional finite difference
2D-FE	two-dimensional finite element
AFFCR	Alkali Flat–Furnace Creek Ranch
CAU	corrective action unit
DEM	digital elevation model
DVSS1	Death Valley steady-state version 1 model
DVSS2	Death Valley steady-state version 2 model
DVRFS	Death Valley regional flow system
DVRFS.v1	Death Valley Regional Flow System version 1 model
DVRFS.v2	Death Valley Regional Flow System version 2 model
DV3	Death Valley version 3 model
DV3-AM-AFFCR	Death Valley version 3 stress-response model simulating groundwater development in the Ash Meadows, Alkali Flat–Furnace Creek Ranch, and Pahute Mesa–Oasis Valley groundwater basins
DV3-ER612	Death Valley version 3 stress-response model simulating pumping during the well <i>ER-6-1-2 main</i> multiple-well aquifer test
DV3-PDVS	Death Valley version 3 stress-response model simulating groundwater development in the Pahrump to Death Valley South groundwater basin
DV3-PRED	Death Valley version 3 predictive model
DV3-SS	Death Valley version 3 stress-response model simulating steady-state (predevelopment) conditions

Abbreviations—Continued

ET	evapotranspiration
ET _{GW}	groundwater discharge by evapotranspiration
HUF	Hydrogeologic-Unit Flow package of MODFLOW
IT	IT Corporation
MODFLOW	USGS modular, finite-difference, groundwater-flow model
MWAT	multiple-well aquifer test
NNSS	Nevada National Security Site
PDVS	Pahrump to Death Valley South
PEST	Parameter ESTimation code
PRISM	Precipitation-elevation Regressions on Independent Slopes Model
PMOV	Pahute Mesa–Oasis Valley
RMS	root-mean-square
r ²	coefficient of determination
SDWA	Safe Drinking Water Act
UGTA	Underground Test Area
USGS	U.S. Geological Survey
VSU	volcanic-sedimentary unit

Groundwater Characterization and Effects of Pumping in the Death Valley Regional Groundwater Flow System, Nevada and California, with Special Reference to Devils Hole

By Keith J. Halford and Tracie R. Jackson

Abstract

Groundwater flow and development were characterized in four groundwater basins of the Death Valley regional flow system in Nevada and California with calibrated, groundwater-flow models. Natural groundwater discharges in the Furnace Creek, Lower Amargosa, and Saratoga Spring areas were defined and distributed consistently with a revised hydrogeologic framework. This simplified hydrogeologic framework was limited to four hydraulically unique, hydrogeologic units: (1) basin fill; (2) carbonate rocks; (3) volcanic rocks; and (4) low-permeability granitic and siliciclastic rocks. Hydrogeologic units and division of carbonate and volcanic rocks between shallow and deep were supported by results from 271 aquifer tests and specific-capacity estimates. Greater than 90 percent of field-estimated transmissivity occurred within 1,600 feet (ft) of the water table. Pumping in the study area from 1960 to 2010 averaged 46,000 acre-feet per year (acre-ft/yr), which is 80 percent of the predevelopment discharge. The central Amargosa Desert and Pahrump Valley were the two primary pumping centers and measurably affected water levels across 900 square miles in 2018.

Water levels in *Devils Hole* were a special focus because endangered Devils Hole pupfish (*Cyprinodon diabolis*) are affected by water-level declines. Pumping 42,100 acre-ft by Cappaert Enterprises, formerly Spring Meadows, Inc., caused a 2.3 ft water-level decline in *Devils Hole*, which temporarily reduced habitat of Devils Hole pupfish by 85 percent in 1972. If no pumping occurred, water levels in *Devils Hole* would have risen naturally about 1 ft between 1973 and 2018 from temporal variations in recharge. The 2.6-ft range of measured

water-level changes in *Devils Hole* was simulated with a root-mean-square error of 0.2 ft during the 70-year period of record. Simulated water-level declines from pumping totaled 1.4 ft in 2018, with 25 and 34 percent attributed to pumping by Cappaert Enterprises and the central Amargosa Desert, respectively. Water levels in *Devils Hole* will decline at rates of 0.1–0.2 ft per decade if pumping from Ash Meadows groundwater basin and the central Amargosa Desert continue at current rates. Effects of future natural water-level fluctuations remain unknown.

Ash Meadows and Alkali Flat–Furnace Creek Ranch groundwater basins are hydraulically connected near well AD-4, about 5 miles south of the town of Amargosa Valley, Nevada. About 40 percent of the discharge from the Furnace Creek area is recharged in the Ash Meadows groundwater basin. Basin fill in the central Amargosa Desert hydraulically connects carbonate rocks east of well AD-4 with saturated carbonate rocks in the Funeral Range. About 7 percent of the 960,000 acre-ft pumped from Ash Meadows and Alkali Flat–Furnace Creek Ranch groundwater basins prior to 2019 was captured discharge from springs and phreatophytes. Greater than 40 percent of the 2,080,000 acre-ft pumped from Pahrump Valley between 1910 and 2019 was capture that primarily discharged from *Bennetts and Manse* Springs.

Simulated advective-flow distances and velocities from underground nuclear tests are within the range of advective transport calculations from tritium data and previous radionuclide transport investigations. Boundary conditions and flow rates from the regional model in this study are plausible for local-scale flow and radionuclide transport models. Simulated 165-year groundwater-flow paths do not extend into pumping areas and effects of regional pumping on advective transport are negligible.

Introduction

Potential radionuclide transport, effects of groundwater pumping, and groundwater-basin boundary uncertainty are of interest in the Death Valley regional flow system, which includes four groundwater basins in Nevada and California: (1) Pahute Mesa–Oasis Valley (PMOV); (2) Alkali Flat–Furnace Creek Ranch (AFFCR); (3) Ash Meadows; and (4) Pahrump to Death Valley South (PDVS). These groundwater basins compose the 6,720,000-acre study area (fig. 1). Radionuclides were introduced into the groundwater system by underground nuclear testing beneath the Nevada National Security Site (NNSS). Groundwater has been pumped primarily for irrigation in Pahrump Valley and the central Amargosa Desert (Moreo and Justet, 2008), where groundwater withdrawals have considerably lowered water levels more than 10 mi from each pumping center. Pumping for irrigation in the Ash Meadows discharge area during the 1970s directly affected water levels in *Devils Hole*¹, the exclusive habitat of the Devils Hole pupfish, *Cyprinodon diabolis* (Dudley and Larson, 1976). [Discharge in this report refers to predevelopment (natural) groundwater discharge from springs and evapotranspiration areas, whereas pumping discharge is referred to as either groundwater development or pumping]. Observed water-level changes in *Devils Hole* have raised awareness about potential effects of groundwater pumping on other federally protected groundwater-dependent ecosystems in the regional flow system. Addressing groundwater-basin boundary uncertainty is of interest for estimating potential radionuclide transport from Pahute Mesa (Fenelon and others, 2016) and for determining hydraulic connections between pumping centers and groundwater-dependent ecosystems across groundwater-basin boundaries. These problems require regional analysis because considerable flow occurs between some groundwater basins (Winograd and Thordarson, 1975).

Investigation and long-term monitoring of radionuclides from 828 underground nuclear tests beneath the NNSS from 1951 to 1992 (U.S. Department of Energy, 2015) are the focus of the U.S. Department of Energy Underground Test Area activity (U.S. Department of Energy, 2010). An objective of the long-term activity is to assess potential transport downgradient of detonations. Radionuclide movement from Frenchman Flat, Yucca Flat–Climax Mine, Rainier Mesa–Shoshone Mountain, and western and central Pahute Mesa corrective action units (CAUs) has been investigated since the 1990s. Western and central Pahute Mesa CAUs will be referred to as the Pahute Mesa CAU in this report. Regional

analysis of groundwater flow remains necessary for hydrologic context around CAUs and to estimate advective movement beyond CAUs. Boundary conditions and flow rates from regional groundwater models also are used to support local-scale CAU models of groundwater flow and radionuclide transport (Navarro-Intera, LLC, 2013). Because regional groundwater models implicitly estimate advective transport, showing advective movement along groundwater-flow paths is a relevant way to evaluate the reasonableness of using simulated flow rates from a regional model in local-scale models.

Substantial groundwater pumping for irrigation occurred after 1945 with the introduction of high-capacity, turbine pumps (Harrill, 1986; Moreo and others, 2003). Successful artesian wells were drilled initially in Pahrump Valley and the central Amargosa Desert beginning in 1913 and 1916, respectively, but total irrigated acreage was less than 700 acres and annual pumping totaled 4,000 acre-ft prior to 1945 (Moreo and Justet, 2008). Total irrigated acreage increased more than tenfold to almost 10,000 acres and annual pumping from Pahrump Valley and the central Amargosa Desert exceeded 46,000 acre-ft in 1965 (Moreo and others, 2003). Annual pumping remains substantial, with 17,200 and 17,600 acre-ft pumped from Pahrump Valley and the central Amargosa Desert, respectively, in 2010. More than 80 percent of pumpage in the central Amargosa Desert supplied irrigation, whereas irrigation accounted for less than one-quarter of pumpage in Pahrump Valley during 2010 (Elliott and Moreo, 2018).

Groundwater development in the Ash Meadows discharge area and near *Devils Hole* during the late 1960s conflicted with preservation of an endangered species, the Devils Hole pupfish. Ash Meadows discharge area was developed considerably between 1967 and 1970 by a ranching corporation, Spring Meadows, Inc. (Dudley and Larson, 1976). Government and private conservationists forecasted extinction of the Devils Hole pupfish in response to expected water-level declines from pumping by Spring Meadows, Inc., which became Cappaert Enterprises after 1972 (Dudley and Larson, 1976; Williams and others, 1996). These concerns established a Desert Pupfish Task Force in 1969 that recommended identifying causes of water-level declines in *Devils Hole*. A scientific investigation by the U.S. Geological Survey (USGS) correlated pumping from eleven wells in the Ash Meadows discharge area with water-level declines in *Devils Hole* (Dudley and Larson, 1976). The established correlation was sufficient for the U.S. Supreme Court, in the 1976 court case *Cappaert v. United States* (426 U.S. 128 [1976]), to limit pumping of groundwater so that a minimum pool elevation is maintained in *Devils Hole* (Williams and others, 1996).

¹ Groundwater sites, including wells and springs, are italicized and hyperlinked to their respective data stored in the U.S. Geological Survey National Water Information System database.




Figure 1. Study area showing groundwater basins and hydrographic areas in the Death Valley regional flow system, Nevada and California.

Effects of pumping from areas distant from the Ash Meadows discharge area and *Devils Hole* were considered by State and Federal agencies after 1976 (Williams and others, 1996). This was because aquatic and riparian ecosystems in a desert environment depend on discharges from an aquifer that can encompass areas considerably larger than the local topographic basin. For example, recharge to a dozen topographic basins (shown as hydrographic areas in [fig. 1](#)) within the Ash Meadows groundwater basin covers 2,840,000 acres and supplies the 18,000 acre-ft/yr of discharge in the Ash Meadows discharge area (Winograd and Thordarson, 1975; Lacznia and others, 1999). Hydraulic connections exist between many topographic basins, where groundwater moves beneath topographic (surface-water) divides. These hydraulic connections increase the potential for pumping in a local topographic basin to affect discharges in other topographic basins.

Hydraulic connections have been recognized between two major pumping centers, the central Amargosa Desert and Pahrump Valley, and three federally protected groundwater-dependent ecosystems in the study area. The central Amargosa Desert is connected hydraulically to the Furnace Creek area in Death Valley National Park (Winograd and Thordarson, 1975, p. C112), and to the Ash Meadows National Wildlife Refuge (Claassen, 1985, p. F19; Fenelon and others, 2016, p. 6), which is near *Devils Hole*—a detached unit of Death Valley National Park. The Ash Meadows National Wildlife Refuge and *Devils Hole* are part of the Ash Meadows discharge area. Pahrump Valley is hydraulically connected to a 26-mi perennial reach of the Amargosa River between Shoshone, California, and Dumont Dunes (Malmberg, 1967; Harrill, 1986), which has been designated as a National Wild and Scenic River (Interagency Wild and Scenic Rivers Coordinating Council, 2018). Hydraulic properties that define degrees of connection and susceptibility to pumping effects have not been quantified plausibly, despite recognition of these hydraulic connections more than 40 years ago.

The location of one or more boundaries between the PMOV, AFFCR, Ash Meadows, and PDVS groundwater basins is uncertain. Some of these boundaries are defined by water-level altitudes in wells, where water-level declines from nearby pumping can affect the location of the boundary and degrees of connection between pumping centers and natural discharge areas. The southeastern boundary of the PMOV groundwater basin between Rainier Mesa and Bare Mountain is uncertain based on water-level data ([fig. 1](#); Fenelon and others, 2016), and the boundary is susceptible to movement by nearby pumping. Addressing boundary uncertainty for the PMOV groundwater basin will determine whether radionuclides migrating downgradient from Pahute Mesa will move only downgradient toward Oasis Valley or, if the boundary is affected by pumping, radionuclides potentially will migrate southward into the Amargosa Desert.

Characterization of predevelopment flow, advective movement, pumping effects, hydraulic connections, and basin-boundary uncertainty are best investigated with groundwater

models of the study area because complex geometries, heterogeneous hydraulic properties, and groundwater discharges from springs and evapotranspiration areas can be simulated consistently. These study objectives are addressable with a steady-state model of predevelopment conditions and transient models of pumping in the groundwater basins. A steady-state model can be used to estimate predevelopment water levels, groundwater-flow paths, recharge, spring discharges, and groundwater evapotranspiration within each groundwater basin. A steady-state model also can be used to consistently estimate water budgets between groundwater basins. Timing and magnitude of groundwater capture from springs and evapotranspiration areas by pumping, in addition to water-level changes from pumping, can be estimated consistently within each groundwater basin and between groundwater basins with a transient model. Steady-state and transient models should be developed simultaneously because they share common hydraulic properties and related boundary conditions in discharge areas.

Development of plausible groundwater models requires conceptualizations of predevelopment discharge and recharge that are consistent with geologic and hydrologic evidence. Groundwater conceptualizations have evolved as new data have been collected. Predevelopment discharge estimates should be evaluated for consistency with conceptualizations of groundwater movement through discharge areas based on the relation of discharge estimates to hydrogeologic data, water levels, transmissivity estimates, and locations of known discharge. Conceptual models of recharge, transmissivity, specific-yield, and specific-storage distributions should be developed that are consistent with data and observations. For example, recharge should be greater in permeable mountain ranges than on valley floors because available precipitation is greater in mountain ranges. Hydrogeologic framework models should be evaluated to determine whether hydrogeologic units have unique hydraulic variability and if major hydrologic features are incorporated. Testing of the hydrogeologic framework requires comparison of hydrogeologic units to transmissivity estimates from aquifer tests and specific-capacity estimates.

Plausible results from groundwater models depend on model calibration to data and conceptual frameworks. Definitive measurements such as water levels, water-level changes, predevelopment discharges, and spring capture must be replicated at a minimum. Simulated transmissivities must compare favorably with aquifer-test results, even if supporting volumes of aquifer investigated by pumping are defined subjectively, because replicating observed heterogeneity depends greatly on transmissivity estimates (Halford, 2016). Distributions of recharge, transmissivity, specific yield, and specific storage in numerical models also must agree with conceptual models of these hydraulic properties. Critical hydraulic features and responses must be replicated, such as water-level gradients in Yucca Flat and water-level changes in *Devils Hole*.

Purpose and Scope

The purposes of this report are to:

1. Characterize predevelopment groundwater flow;
2. Evaluate effects of historical (1913–2018) groundwater development on water levels and spring discharges;
3. Estimate potential future (2019–2100) effects of groundwater development on water levels and spring discharges;
4. Evaluate advective flow from selected underground nuclear tests to determine if boundary conditions and flow rates from the regional model in this study are reasonable for local-scale flow and transport models; and
5. Address groundwater-basin boundary uncertainty in the study area, which comprises the Ash Meadows, AFFCR, PMOV, and PDVS groundwater basins.

Predevelopment groundwater flow, effects of groundwater development, advective movement from nuclear tests, and basin-boundary uncertainty were investigated with three-dimensional, groundwater models. Recharge, hydraulic-conductivity, specific-yield, and specific-storage distributions were estimated by simultaneously calibrating a steady-state model of the study area to predevelopment conditions and transient models of groundwater development to water-level changes from pumping during 1913–2018. Hydraulic-conductivity and specific-yield estimates were constrained from specific-capacity tests, aquifer-test results, and analysis of multiple-year water-level declines in the central Amargosa Desert, Ash Meadows discharge area, Beatty, Bullfrog Hills area, Emigrant Valley, Indian Springs, NNSS, Pahrump Valley, and Yucca Mountain. A total of four groundwater models, which are discussed in more detail in section, “Approach,” contributed information to calibrated distributions of hydraulic conductivity, specific yield, and specific storage. Potential future effects of groundwater development on water levels and spring discharges were simulated with a predictive groundwater model that used the calibrated distributions of hydraulic conductivity, specific yield, and specific storage. This predictive model simulated capture of discharge from springs and evapotranspiration areas by pumping, where total capture was limited to predevelopment discharge rates. All pertinent data, analyses, the hydrogeologic framework, and the calibrated and predictive groundwater models are published in a separate data release (Jackson and Halford, 2020).

Conceptual models of predevelopment and groundwater development were required to accomplish the five purposes of this study. Characterization of predevelopment groundwater flow required conceptual models for recharge, discharge, and hydraulic-conductivity distributions within hydrogeologic

units. Conceptual models integrated water-level data, transmissivity estimates, geologic data, water availability in recharge areas, and locations and estimates of predevelopment discharge. A hydrogeologic framework was used to distribute hydraulic properties within hydrogeologic units during simulation of predevelopment and groundwater development.

Conceptual and numerical models that were developed in this study were compared to results from previous investigations. Many comparisons were to results from the Death Valley Regional Flow System version 2 (DVRFS.v2) model because this study supersedes the DVRFS.v2 project.

Description of Study Area

The study area comprises the PMOV (940,000 acres), AFFCR (1,480,000 acres), Ash Meadows (2,840,000 acres), and PDVS (1,460,000 acres) groundwater basins (Fenelon and others, 2016). The four groundwater basins are in Clark, Lincoln, and Nye Counties, southern Nevada, and Inyo and San Bernardino Counties, southern California (fig. 1). In-place recharge (Fenelon and others, 2016) principally occurs in Pahute Mesa; Spring Mountains; Timber Mountain; and Belted, Groom, Pahrnagat, and Sheep Ranges. Land-surface altitudes exceed 6,000 ft in these highland areas, which are in the northern and eastern quadrants of the study area. Natural discharge occurs primarily in the Ash Meadows discharge area, Lower Amargosa area, Death Valley, Oasis Valley, and Pahrump Valley, which are in the southern and western quadrants of the study area. Altitudes range from –282 ft in Death Valley to 11,916 ft in the Spring Mountains.

The study area mostly is isolated from surrounding groundwater basins by low-permeability boundaries and groundwater divides (Fenelon and others, 2016). About 290 mi of the 460 mi perimeter of the study area coincides with low-permeability rocks. About 80 mi of boundary through carbonate rocks in the Spring Mountains and Sheep Range are classified as low permeability because of the occurrence of high-altitude springs. Greater than 80 mi of low-permeability boundary coincides with the floor of Death Valley. Potentially permeable rocks are mapped north of Kawich, Emigrant, and Tikaboo Valleys (Heilweil and Brooks, 2011), but flow across these boundaries is expected to be limited. Flows of less than 1,000 acre-ft/yr into Kawich Valley have been estimated (Blankennagel and Weir, 1973; Fenelon and others, 2016). Penoyer Valley north of Emigrant and Tikaboo Valleys has been interpreted as a closed basin (Harrill and others, 1988). Potential flow between Tikaboo and Pahrnagat Valleys is least certain, with previous estimates ranging from 5,000 acre-ft/yr into the study area (Winograd and Thordarson, 1975) to 800 acre-ft/yr out of the study area (Belcher and Sweetkind, 2010, appendix 2).

The climate of the study area is arid to semi-arid, characteristic of a high desert region. The climate is characterized by hot summers and mild winters, large fluctuations in daily and annual temperatures, and low precipitation and humidity. Average summertime maximum temperatures at Furnace Creek are 120 °F (National Climatic Data Center, 2017), and average wintertime minimum temperatures on Mount Charleston are about 20 °F (National Climatic Data Center, 2017). Average annual precipitation in the study area ranges from about 2 in. in Death Valley to about 24 in. on Mount Charleston (National Climatic Data Center, 2017). Precipitation occurs primarily in late autumn through early spring and in mid-summer. Precipitation falls primarily as rain, and during the winter months at high altitudes, as snow. Most streams in the study area are ephemeral and flow only for brief periods after infrequent intense rainfall or during and shortly after spring snowmelt.

Previous Investigations

Regional groundwater models were first developed in the 1980s to estimate potential transport of radionuclides from proposed radioactive waste disposal beneath Yucca Mountain (Waddell, 1982; Rice, 1984). These models were areally extensive because, at the time, known discharge areas and assumed recharge areas were separated by more than 50 mi (Winograd and Thordarson, 1975) and boundaries between groundwater basins were uncertain. In numerical models by Waddell (1982) and Rice (1984), simulated groundwater flow from Yucca Mountain discharged primarily to Franklin Lake (Alkali Flat in Czarnecki and Waddell, 1984) because available discharge estimates totaled 10,000 acre-ft/yr (Walker and Eakin, 1963). Revised Franklin Lake discharge estimates from field measurements and satellite imagery were about 1,000 acre-ft/yr (Laczniaik and others, 2001). This altered the conceptual model of Franklin Lake from being the primary discharge area downgradient of Yucca Mountain to a mostly irrelevant discharge area (Fenelon and others, 2016).

Subsequent regional groundwater models were developed to estimate potential transport of radionuclides from Yucca Mountain (D'Agnese and others, 1997) and underground nuclear tests (IT Corporation, 1997). Areal extents of these subsequent models increased relative to Waddell (1982) so that uncertainty of boundaries between groundwater basins could be investigated (fig. 2). Simulated groundwater-flow paths and velocities from these revised models remained uncertain mostly because uncertainties in discharge estimates remained.

Regional Models—1982–97

The four regional models (Waddell, 1982; Rice, 1984; D'Agnese and others, 1997; IT Corporation, 1997) were calibrated to markedly different estimates of predevelopment discharge. Differences in model extents (fig. 2) prohibit

comparison of discharge estimates from some discharge areas between models, such as discharges in the PDVS groundwater basin (fig. 1). Comparisons are possible for predevelopment discharges from Ash Meadows, AFFCR, and PMOV groundwater basins. Total predevelopment discharges from these three groundwater basins for the four regional models ranged from 34,400 to 82,000 acre-ft/yr (table 1). Some differences can be attributed to likely double counting of spring discharge and groundwater evapotranspiration. Groundwater pumping also was simulated erroneously in steady-state models where depletion of storage is a substantial part of the water budget (Rice, 1984; D'Agnese and others, 1997). Legitimate differences resulted from uncertainties in discharge estimates that required better measurements to reduce uncertainties (Waddell, 1982; IT Corporation, 1997).

Regional Investigations—1998–2004

A series of investigations were initiated by the USGS to address inadequacies of the existing regional models and develop another regional model, Death Valley Regional Flow System version 1 model (DVRFS.v1; Belcher, 2004; Belcher and Sweetkind, 2010). These investigations resulted in about three dozen publications from 1998 to 2004 that mapped geologic features, measured hydrologic components, and developed hydrologic models. Geologic cross sections were interpreted from mapped exposures, borehole data, and geophysical mapping of aeromagnetic, gravity, and seismic anomalies (Sweetkind and others, 2001). Hydrologic components such as predevelopment discharge, pumping, water levels, and aquifer-test results were defined better with additional measurements and scrutiny of existing measurements. Hydrologic models were developed to estimate recharge and simulate groundwater flow.

Predevelopment Discharge Investigations

Multiple investigations measured natural discharges to support the DVRFS.v1 model. Discharges from the Ash Meadows discharge area and Oasis Valley were defined well from 18, multiyear, micrometeorological measurement sites where groundwater discharge by evapotranspiration (ET_{GW}) was estimated (Laczniaik and others, 1999; Reiner and others, 2002). Discharges from Chicago Valley, California Valley, Franklin Well area, Franklin Lake, Shoshone-to-Tecopa area, and Stewart Valley were refined with ET_{GW} rates extrapolated from Oasis Valley and Ash Meadows discharge areas (Laczniaik and others, 2001). Discharges from Death Valley were estimated similarly with a site-specific investigation that measured ET_{GW} rates with four micrometeorological measurement sites (DeMeo and others, 2003). Discharge from 100,000 acres of playa in Death Valley remained uncertain because annual playa ET_{GW} rates less than 0.3 ft were within the measurement error of the Bowen-ratio approach (Jackson and others, 2018).




Figure 2. Areal extent of previous regional groundwater models and the regional model [Death Valley version 3 (DV3)] used in this study, Nevada and California.

Table 1. Predevelopment discharge estimates from previous and current investigations for Alkali Flat–Furnace Creek Ranch, Ash Meadows, and Pahute Mesa–Oasis Valley groundwater basins, Nevada and California, 1982–2018.

[**Model:** 2D-FD, two-dimensional finite difference; 2D-FE, two-dimensional finite element; DVSS1, Death Valley steady-state version 1 model; IT, IT Corporation; DVSS2, Death Valley steady-state version 2 model; DVRFS.v1, Death Valley Regional Flow System version 1 model; DVRFS.v2, Death Valley Regional Flow System version 2 model; DV3, Death Valley version 3 model. **AFFCR:** Alkali Flat–Furnace Creek Ranch. **PMOV:** Pahute Mesa–Oasis Valley]

Year	Model	Citation	Groundwater discharge (acre-feet per year)			
			AFFCR	Ash Meadows	PMOV	Total
1982	2D-FE	Waddell, 1982	15,600	16,800	2,000	34,400
1984	2D-FD	Rice, 1984	20,000	50,000	4,000	74,000
1997	DVSS1	D’Agnese and others, 1997	40,800	36,900	4,300	82,000
1997	IT	IT Corporation, 1997	23,000	31,200	6,500	60,700
2002	DVSS2	D’Agnese and others, 2002	14,000	18,900	5,700	38,600
2004	DVRFS.v1	Belcher, 2004	8,500	18,500	6,000	33,000
2010	DVRFS.v1	Belcher and Sweetkind, 2010	8,500	18,500	6,000	33,000
2017	DVRFS.v2	Belcher and others, 2017	8,500	18,500	6,000	33,000
2018	DV3	This report	7,500	19,000	6,000	32,500

Changes in predevelopment discharge estimates substantially affected simulated transport results. For example, Franklin Lake was interpreted as the primary discharge area from the AFFCR groundwater basin with an initial estimate of 10,000 acre-ft/yr (Walker and Eakin, 1963), which was double the estimated discharge from the Furnace Creek area (Waddell, 1982; Czarnecki and Stannard, 1997). Revised discharge estimates from Franklin Lake totaled 1,000 acre-ft/yr, where 25 percent discharged from the playa (Lacznia and others, 2001). ET_{GW} rates of 0.17 ft/yr for playas likely were overestimated and better approximated as near 0 ft/yr (Jackson and others, 2018). Discharge from Franklin Lake is best interpreted as less than 700 acre-ft/yr because most of the discharge is local recharge derived from flooding events on the Amargosa River, not regional discharge. Reduced discharge estimates changed Franklin Lake from being interpreted as a primary receptor to an improbable terminus for potential transport from Yucca Mountain.

Hydraulic-Property and Water-Use Investigations

Aquifer-test results were compiled, and groundwater use was inventoried to improve regional datasets in support of the DVRFS.v1 model. A total of 377 transmissivity estimates from aquifer tests in southern Nevada and California were compiled (Belcher and others, 2001, appendix A). Transmissivity estimates were normalized to hydraulic conductivities by assuming that contributing thicknesses equaled screen lengths so that hydraulic conductivities could be classed by hydrogeologic units. Estimated pumping for the DVRFS.v1 model was an interpretive effort because minimal reporting existed prior to 1950 and permitted water rights are not correlated directly with wells (Moreo and others, 2003). Annual pumping volumes and uncertainty were estimated for 9,300 wells in the extent of the DVRFS.v1 model.

Hydrogeologic Framework

A hydrogeologic framework model also was developed that was intended to improve the DVRFS.v1 groundwater model. The volume within the hydrogeologic framework was differentiated into hydrogeologic units on the basis of similar geologic and hydraulic properties (Winograd and Thordarson, 1975; Lacznia and others, 1996; Faunt, Sweetkind, and Belcher, 2010; Fenelon and others, 2010). Hydrogeologic units were assumed to represent volumes of fairly uniform hydraulic properties in structurally similar zones (Faunt, Blainey, and others, 2010, p. 280). Hydraulic properties were distributed throughout the DVRFS.v1 model by assigning a single value to each zone in a hydrogeologic unit (Faunt, Blainey, and others, 2010).

An unexpected result from another supporting investigation (Belcher and others, 2002) of the DVRFS.v1 model was that hydraulic conductivities were predicted and constrained poorly by hydrogeologic units in the DVRFS.v1 hydrogeologic framework. Probability distributions of hydraulic conductivity, which were estimated from aquifer-test results, were computed for 18 of 27 hydrogeologic units in the DVRFS.v1 hydrogeologic framework. Hydraulic conductivities were highly heterogeneous rather than uniform for all analyzed hydrogeologic units. Hydraulic conductivities in each hydrogeologic unit ranged from three to seven orders of magnitude (fig. 3). The geometric mean hydraulic conductivity of the alluvial confining unit exceeded the geometric mean hydraulic conductivity of the alluvial aquifer, which contradicts conceptual models of aquifers and confining units (Belcher and others, 2002, table 1). Highly heterogeneous hydraulic conductivities contradict assumptions that hydrogeologic units in DVRFS.v1 approximate uniform hydraulic conductivities (Faunt, Blainey, and others, 2010, p. 280).




Figure 3. Minimum, maximum, geometric mean, and 95-percent confidence interval of log-hydraulic conductivities in 9 hydrogeologic units in the Death Valley Regional Flow System version 2 model framework using 377 hydraulic-conductivity estimates, Nevada and California.

DFRVS.v1 Model

The DVRFS.v1 model was developed to supply boundary conditions to CAU models that simulated radionuclide transport beneath the NNSS, and to simulate water-level changes in critical areas from pumping. These development goals were reported as appropriate uses of the DVRFS.v1 model: “*The model can provide boundary conditions for the development of local-scale models, such as those being developed by the Department of Energy...*” (Belcher, 2004, p. 348; Belcher and Sweetkind, 2010, p. 340) and “[*t*he model can be used for examining the effects of continued or increased pumpage on the regional ground-water flow system to effectively manage ground-water resources within conflicting land-use management policies.” (Belcher, 2004, p. 349; Belcher and Sweetkind, 2010, p. 341.)

Boundary conditions from the DVRFS.v1 model that were applied to a local-scale CAU model of the carbonate aquifer beneath Yucca Flat were not adequate for their stated purpose. The DVRFS.v1 model simulated a groundwater-flow rate of 14,000 acre-ft/yr into northern Yucca Flat through

low-permeability shale, quartzite, granite, marble, and siltstone (Belcher and Sweetkind, 2010). Applying 14,000 acre-ft/yr as the northern boundary condition for the Yucca Flat CAU model resulted in rapid groundwater velocities, large extents of simulated tritium plumes that were not supported by tritium data, and model-estimated hydraulic properties that exceeded aquifer-test results (Navarro-Intera, LLC, 2013). The 14,000 acre-ft/yr of northern flow is erroneously large because predevelopment flow through Yucca Flat ranges from 350 and 1,000 acre-ft/yr (Winograd and Thordarson, 1975; Harrill and others, 1988; Fenelon and others, 2016), and estimated flow through low-permeability rocks in northern Yucca Flat is less than 40 acre-ft/yr (Winograd and Thordarson, 1975, p. C93).

Groundwater resources within 25 mi of *Devils Hole* have been managed with an empirical rule (Nevada State Engineer, 2008b), instead of using the DVRFS.v1 model. The State Engineer administers water resources in Nevada and designated Amargosa Desert hydrographic area 230 in 1979. Nevada State Engineer Order No. 724 manages pumping to maintain a minimum pool elevation in *Devils Hole*. The

empirical rule was developed in response to proposed changes in points of diversion, where the protestant was the National Park Service (Nevada State Engineer, 2008a). The National Park Service also cooperatively developed and funded the DVRFS.v1 model (Belcher, 2004, p. 7) because conflicting land uses were anticipated (Belcher, 2004, p. 349). The protestant estimated effects of proposed changes in pumping on water levels in *Devils Hole* with a Theis analysis (Nevada State Engineer, 2008b), despite having cooperatively developed and funded the DVRFS.v1 model.

DVRFS.v2 Model

A revised regional model, DVRFS.v2, was developed to update the DVRFS.v1 model with new data and interpretations (Belcher and others, 2017). Two primary purposes of the DVRFS.v2 model were stated: “... (1) *inform definition of boundary conditions for the Underground Test Area (UGTA) Corrective Action Units (CAUs) on the NNSS*, (2) *evaluate the effects of changes in groundwater-system fluxes, regardless of whether the changes are natural or human-induced...*” (Belcher and others, 2017, p. 3). Revisions to the DVRFS.v1 model included altering the hydrogeologic framework, estimating annual variations in recharge, extending the simulated period 5 years to 2003, comparing transmissivities and water-budget terms in the objective function, and distributing hydraulic properties with pilot points in some basin-fill units. Despite revisions, the DVRFS.v2 model is inadequate for its reported purposes.

Simulated flow through Yucca Flat remained unrealistic even though flow into northern Yucca Flat was reduced from 14,000 to 1,400 acre-ft/yr between the DVRFS.v1 and DVRFS.v2 models, respectively (Navarro-Intera, LLC, 2013, table 5-7). The DVRFS.v2 model simulated 7,700 acre-ft/yr (300 kg/s) across the southern edge of the Yucca Flat–Climax Mine CAU model of carbonate rocks (Navarro-Intera, LLC, 2013, table 5-7). Regional water-balance analyses limited flow from southern Yucca Flat to about 1,000 acre-ft/yr (Winograd and Thordarson, 1975; Fenelon and others, 2016). Groundwater-flow estimates from hydraulic gradients and aquifer-test results ranged from 240 to 970 acre-ft/yr (Navarro, 2016a) between wells ER-7-1 and ER-6-1-2 main, where these estimates represent groundwater flow from approximately two-thirds of the Yucca Flat hydrographic area. UGTA investigators concluded: “*This limit on flux through the high-transmissivity eastern corridor suggests that several models documented in N-I (2013a) [Navarro-Intera, LLC, 2013]—including the base case and many Null Space Monte Carlo (NSMC) results with northern boundary fluxes greater than 50 kg/s [1,300 acre-ft/yr]—are unrealistic.*” (Navarro, 2016a, p. 24.)

The DVRFS.v2 model poorly explains effects of natural changes and pumping on water levels in *Devils Hole* and spring discharges in the Ash Meadows discharge area, which precludes analyzing effects of either stress with the DVRFS.v2 model. Measured water levels in carbonate rocks naturally fluctuate from 0.5 to 3 ft in wells and in *Devils Hole*, where these natural changes correlate with fluctuations in cumulative

departure from mean precipitation (Fenelon and Moreo, 2002, p. 51). The DVRFS.v2 model simulated less than 0.02 ft of natural water-level changes in *Devils Hole* (fig. 4). Simulated and measured water-level changes notably differ in *Devils Hole*, where maximum water-level declines from pumping, or drawdown, in the DVRFS.v2 model were simulated about 30 years after maximum measured drawdown occurred (fig. 4). Measured spring discharges of 1,400 acre-ft/month (10,700 gal/min) decreased 34 percent during August 1971 in response to pumping of about 1,000 acre-ft/month in the Ash Meadows discharge area (Dudley and Larson, 1976, p.22). Simulated capture in the DVRFS.v2 model from all springs and evapotranspiration areas totaled less than 1 percent of the predevelopment discharge, in response to pumping in the Ash Meadows discharge area.

The stated goals of informing boundary conditions and estimating the effects of groundwater pumping were not achieved in the DVRFS.v1 and DVRFS.v2 projects because geologic differences were emphasized in the hydrogeologic frameworks and groundwater models. Results from the DVRFS.v1 and DVRFS.v2 projects indicate the need for hydrology to inform the hydrogeologic framework by empirically testing hydrogeologic units with results from aquifer tests. Achieving the stated goals requires a new approach that emphasizes hydrologic results.

Approach

The study area, purpose, and approach of this project differ from the DVRFS.v1 and DVRFS.v2 studies. The study area of this project is about 6,720,000 acres, which is less than one-third the areal extent of the approximately 24,710,000-acre DVRFS.v2 model (fig. 2). Because the study area does not encompass the entire Death Valley regional flow system (Harrill and others, 1988), the general descriptor for this project has been simplified to Death Valley version 3 (DV3).

The DV3 study area encompasses the AFFCR, Ash Meadows, PMOV, and PDVS groundwater basins to address the study objectives. Potential radionuclide transport from historical underground nuclear tests at the NNSS occurs in the AFFCR, Ash Meadows, and PMOV groundwater basins. Groundwater development occurs in all four groundwater basins; however, extensive development occurs in the AFFCR, Ash Meadows, and PDVS groundwater basins. The outer boundaries of groundwater basins in the DV3 study area mostly are separated from surrounding groundwater basins outside the study area by no-flow boundaries (Fenelon and others, 2016). However, within the DV3 study area, groundwater-basin boundary uncertainty needs to be addressed for the boundaries between the four groundwater basins. Groundwater-basin boundary uncertainty affects estimation of potential radionuclide transport from underground tests, and degrees of hydraulic connection between pumping centers and areas of interest, such as *Devils Hole*, across groundwater divides.




Figure 4. Measured and simulated water-level changes in Devils Hole from the Death Valley Regional Flow System versions 1 and 2 (DVRFS.v1 and DVRFS.v2) models, Nevada and California, 1930–2018.

Predevelopment conditions, historical groundwater development, and potential pumping effects from future development were simulated with multiple, stress-response groundwater models that honor hydraulic constraints. Stress-response models are groundwater models that simulate an identifiable stress within the aquifer system. Average recharge is the stress during steady-state, predevelopment conditions and is better defined than time-varying recharge. Pumping for groundwater development is the stress in transient models and is highly identifiable relative to other hydraulic stresses. The primary assumption of the stress-response approach is that differentiating natural (recharge) and anthropogenic (pumping) stresses introduces less errors than compensating errors in a single model that attempts to simultaneously simulate all stresses.

Developing a set of stress-response models simplifies estimation of hydraulic properties because structural errors are easier to discern and remove where responses to steady-state and transient stresses are separated. A set of stress-response models also better addresses multiple questions than a single groundwater model because boundary conditions are tailored to the effects of each stress. For example, models simulating both predevelopment flow (steady-state) and groundwater development (transient) should inform a calibrated transmissivity distribution. Spring discharge is best specified as a constant value for calibration to predevelopment conditions but must decrease in response to pumping as groundwater development is simulated (Halford and Plume, 2011). Spring discharge can be simulated advantageously as a specified discharge in a steady-state model and as a head-dependent discharge in a groundwater-development model. Both models have common hydraulic properties and are calibrated simultaneously so that all observations inform an estimated transmissivity distribution (Garcia and others, 2017).

Predictive utility of the DV3 model depends on plausibility of calibrated recharge, transmissivity, specific-yield, and specific-storage distributions. Plausibility increases as simulated results better match as many relevant observations and concepts as possible. Predevelopment flow was simulated and compared to water-level altitudes, discharges, and transmissivity estimates from aquifer tests. Groundwater development in AFFCR, Ash Meadows, PMOV, and PDVS groundwater basins was simulated as changes from predevelopment and compared to measured changes in water levels and spring discharges. Pumping from well *ER-6-1-2 main* during a large-scale, multiple-well aquifer test (MWAT) in Yucca Flat also was simulated, where simulated drawdowns were compared to drawdown estimates in observation wells located 0–33 mi from the pumped well. Four stress-response models simulated predevelopment conditions, groundwater development in the PDVS groundwater basin, groundwater development in the PMOV, AFFCR, and Ash Meadows groundwater basins, and the large-scale MWAT (table 2). All models shared common recharge, transmissivity, specific-yield, and specific-storage distributions, as needed, and were calibrated simultaneously.

Advective flow from nuclear tests and effects of groundwater pumping were estimated with separate models that were appropriate for addressing each question. Advective flow from selected nuclear tests was estimated with the DV3-SS model because flow paths from these tests do not extend into pumping areas (table 2). Potential effects of historical (1913–2018) and future (2019–2100) groundwater pumping were simulated directly as change from predevelopment conditions (Leake and others, 2010) with another model, DV3-PRED. This model is discretized temporally to annual pumping changes in all groundwater basins from 1913 to 2100. Directly simulating potential effects of pumping with a separate predictive model has been effective elsewhere in Nevada (Halford and Plume, 2011).

Table 2. Groundwater models developed for Death Valley version 3 model (DV3) project.

Groundwater model	Description	Purpose
DV3-SS	Steady-state model of predevelopment flow	Calibration and transport estimates
DV3-AM-AFFCR	Transient superposition model of groundwater development in the Alkali Flat–Furnace Creek Ranch, Ash Meadows, and Pahute Mesa–Oasis Valley groundwater basins	Calibration
DV3-ER612	Well <i>ER-6-1-2</i> main aquifer test, 2004	Calibration
DV3-PDVS	Transient superposition model of groundwater development in the Pahrump to Death Valley South groundwater basin	Calibration
DV3-PRED	Capture-limited model for predicting pumping effects	Predict pumping effects

Geology

Geologic units were formed by magmatic activity, volcanism, and depositional processes in the study area. These rocks subsequently have been uplifted, thrust, offset, and deformed. Depositional, magmatic, volcanic, and tectonic processes have juxtaposed geologic units into a complex three-dimensional framework that affects groundwater flow. The geologic history is divided into six periods of deposition and tectonic deformation:

1. Precambrian and Paleozoic marine and non-marine deposition;
2. Late Paleozoic to Early Cenozoic folding, thrusting, and strike-slip faulting;
3. Mesozoic intrusion;
4. Cenozoic volcanism;
5. Cenozoic normal and strike-slip faulting; and
6. Cenozoic basin-fill deposition (table 3).

Precambrian and Paleozoic marine and orogenic processes resulted in two major sedimentation sequences of siliciclastic and carbonate rocks (Winograd and Thordarson, 1975; Lacznia and others, 1996; Slate and others, 2000; Sweetkind and others, 2010). The continental margin of the southwestern United States intersected the study area from the Neoproterozoic to Devonian (Sweetkind and others, 2010). Marine sedimentary rocks, primarily siltstones, were deposited from Neoproterozoic to Lower Cambrian (table 3), where deposits thicken westward in the study area. The siliciclastic rocks are overlain by thick sequences of Middle Cambrian to Devonian carbonate rocks. From the Late Devonian to Mississippian, siliciclastic rocks—predominantly shales and argillites—interrupted marine carbonate deposition in the eastern part of the study area. Siliciclastic sediments were derived from uplifted areas north of the study area (Sweetkind and others, 2010). Marine carbonate deposition continued from the Late Mississippian to Permian (table 3).

Precambrian and Paleozoic rocks were subjected to compressional tectonic forces from the Late Paleozoic to Early Cenozoic. Siliciclastic and carbonate rocks were offset by regional thrust faulting (fig. 5), which emplaced Neoproterozoic to Lower Cambrian siliciclastic rocks over younger Paleozoic rocks (Sweetkind and others, 2010). Many mountain ranges have exposed thrust faults, including the Belted, Eleana, Specter, Resting Spring, and Nopah Ranges, as well as Bare Mountain and the Spring and Funeral Mountains (fig. 5; Sweetkind and others, 2010). Thrust faulting displaced rocks laterally more than 10 mi away (Winograd and Thordarson, 1975). Siliciclastic and carbonate rocks also were subjected to folding and strike-slip faulting (Lacznia and others, 1996). Compressional tectonics have formed broad anticlines and synclines in the Precambrian and Paleozoic sequence within the Ash Meadows groundwater basin. Mesozoic rocks mostly are absent because of uplift and erosion of Precambrian and Paleozoic rocks (Sweetkind and others, 2010). Therefore, Mesozoic rocks are minor and occur as localized granitic intrusions.

Volcanic and associated sedimentary rocks formed during the Cenozoic (table 3). From the Oligocene to Miocene, thick sequences of volcanic rocks were deposited by caldera-forming eruptions in the southwestern Nevada volcanic field, located in the northwestern part of the study area (Byers and others, 1976; Christiansen and others, 1977; Sawyer and others, 1994; Lacznia and others, 1996; Prothro and Drellack, 1997). Volcanic centers within the southwestern Nevada volcanic field caldera complex (fig. 5) erupted rhyolitic-to-dacitic lava flows, variably welded ash-flow tuffs, ash-fall tuffs, and volcaniclastic rocks (Winograd and Thordarson, 1975; Lacznia and others, 1996; Sweetkind and others, 2010). From the Miocene to Pliocene, localized rhyolitic and basaltic lava flows erupted from the central Death Valley volcanic field in Greenwater Valley (Sweetkind and others, 2010). During the Holocene, localized basaltic lava flows erupted from five cinder cones in the Crater Flat volcanic field (Wells and others, 1990).

Table 3. Major lithology and occurrence descriptions of hydrogeologic units in the study area, as defined in the Death Valley Regional Flow System version 2 hydrogeologic framework, Nevada and California.

[**Abbreviations:** AM, Ash Meadows groundwater basin; AFFCR, Alkali Flat-Furnace Creek Ranch groundwater basin; CDVVF, Central Death Valley volcanic field; PDVS, Pahrump to Death Valley South groundwater basin; PMOV, Pahute Mesa-Oasis Valley groundwater basin; SAMM, Southern AMargosa Model; SWNVF, southwestern Nevada volcanic field. Table summarizes information obtained from Noble and others (1964, 1984); Blankennagel and Weir (1973); Winograd and Thordarson (1975); Byers and others (1976); Christiansen and others (1977); Simonds (1989); Sawyer and others (1994); Lacznia and others (1996); Prothro and Drellack (1997); Slate and others (2000); Sweetkind and others (2010); Taylor and Sweetkind (2014)]

Era	Period	Abbreviation	Hydrogeologic unit	Major lithology	Occurrence
Cenozoic	Tertiary - Quaternary	Cenozoic basin-fill and volcanic sediments (unconsolidated)			
		YAA	Younger alluvial aquifer	Coarse-grained alluvium and colluvium with minor debris-flow and eolian sediments. Proximal to distal fan alluvial deposits grade from gravels and sands to silts and clays, whereas fluvial deposits consist of gravel and sand. Debris flows are poorly sorted coarse- and fine-grained deposits. Eolian deposits are well-sorted dunal sands or sand sheets.	Saturated basin fill beneath ephemeral channels, such as Amargosa River and Fortymile Wash, and beneath depositional basins, such as Oasis, Death, and Pahrump Valleys, Amargosa Desert, and Crater, Yucca, and Frenchman Flats [AFFCR, AM, PDVS, PMOV].
		OAA	Older alluvial aquifer		
		YACU	Younger alluvial confining unit	Fine-grained playa and lacustrine deposits. Deposits consist of alternating sequences of fine sand, silt, and clay. Playa sediments are imbued with salt and capped by a salt crust.	Saturated basin-axis and playa deposits beneath valley floors, such as Death and Pahrump Valleys, Amargosa Desert, and Yucca and Frenchman Flats [AFFCR, AM, PDVS, PMOV].
		OACU	Older alluvial confining unit		
		LA	Limestone aquifer	Lacustrine and spring deposits of limestone and travertine.	Localized saturated units in Amargosa Desert [AFFCR].
		LFU	Lava-flow unit	Localized rhyolitic and basaltic lava flows, cinder cones, and nonwelded tuff. Rocks erupted from CDVVF.	Unit typically located above water table, except for localized lava flows in Amargosa Desert and Crater Flat [AFFCR].
	Tertiary	YVU	Younger volcanic-rock unit	Localized volcanic tuffs.	Unit typically located above water table, except for localized tuffs in Desert Range [AM].
		SmAA	Coarse-grained units from SAMM	Coarse-grained (gravel and sand) basin-fill deposits, basaltic lava flows, and limestones mapped in SAMM.	Saturated basin fill beneath Amargosa Desert, Crater and Jackass Flats, and the Ash Meadows discharge area [AFFCR, AM].
		SmCU	Fine-grained units from SAMM	Fine-grained (silt and clay) basin-fill deposits mapped in SAMM.	Saturated basin fill beneath Amargosa Desert, Crater and Jackass Flats, and the Ash Meadows discharge area [AFFCR, AM].

Table 3. Major lithology and occurrence descriptions of hydrogeologic units in the study area, as defined in the Death Valley Regional Flow System Version 2 hydrogeologic framework, Nevada and California.—Continued

Era	Period	Abbreviation	Hydrogeologic unit	Major lithology	Occurrence
Cenozoic	Tertiary	Cenozoic volcanic rocks of the southwestern Nevada volcanic field			
		TMVA	Thirsty Canyon-Timber Mountain volcanic-rock aquifer	Variably welded ash-flow tuffs, ash-fall tuffs, rhyolite and trachyte lavas and domes, and intracaldera landslide breccia with minor nonwelded tuff.	Volcanics erupted from Timber Mountain caldera complex and Black Mountain caldera. Unit saturated beneath Pahute Mesa, Oasis Valley, Yucca Mountain, and Jackass, Yucca, and Frenchman Flats [AFFCR, AM, PMOV].
		PVA	Paintbrush volcanic-rock aquifer	Rhyolitic lavas, variably welded ash-flow tuffs, nonwelded ash-fall tuff, bedded tuff, and fluvially reworked tuff. Nonwelded tuffs have argillic, hematitic, silicic, or zeolitic alteration.	Volcanics erupted from the Claim Canyon caldera. Unit saturated beneath Pahute Mesa, Yucca Mountain, and Jackass, Yucca, and Frenchman Flats [AFFCR, AM, PMOV].
		CHVU	Calico Hills volcanic-rock unit	Variably welded ash-flow tuffs, nonwelded zeolitically altered ash-fall and bedded tuffs, rhyolitic lavas, and volcanoclastic deposits.	Volcanics erupted from the Silent Canyon caldera complex. Unit saturated beneath Pahute Mesa, Yucca Mountain, and Jackass and Yucca Flats [AFFCR, AM, PMOV].
		WVU	Wahmonie volcanic-rock unit	Biotite-rich nonwelded tuff, andesitic-to-dacitic lavas, tuffaceous sandstone, and tuff breccia.	Volcanics erupted from stratovolcanoes in the Wahmonie volcanic center near Skull Mountain. Unit saturated beneath Jackass and Yucca Flats [AFFCR, AM].
		CFPPA	Crater Flat–Prow Pass aquifer	Rhyolitic-to-andesitic lava flows and variably welded ash-flow tuffs. Partly welded to nonwelded tuffs are commonly zeolitized.	Location of source for erupted volcanics unknown. Unit saturated beneath Rainier Mesa, Yucca Mountain, and Yucca Flat [AFFCR, AM, PMOV].
		CFBCU	Crater Flat–Bullfrog confining unit	Nonwelded and variably welded ash-flow and ash-fall tuffs. Nonwelded tuff commonly zeolitized.	Volcanics erupted from the Silent Canyon caldera complex. Unit saturated beneath Pahute Mesa and Yucca Mountain [AFFCR, PMOV].
		CFTA	Crater Flat–Tram aquifer	Nonwelded to variably welded ash-flow tuffs. Mostly partially welded to nonwelded tuffs with localized areas of dense welding.	Volcanics possibly erupted from an unnamed caldera beneath northern Crater Flat. Unit saturated beneath Yucca Mountain [AFFCR].
		BRU	Belted Range unit	Rhyolitic lavas and densely welded ash-flow tuffs with minor nonwelded (commonly zeolitized) tuff.	Volcanics erupted from Silent Canyon caldera complex. Unit saturated beneath Pahute Mesa and Yucca Flat [AM, PMOV].
		OVU	Older volcanic-rock unit	Undifferentiated older volcanic rocks of the SWNVF, including lavas, variably welded ash-flow tuffs, zeolitically altered nonwelded tuffs, reworked tuff, and volcanoclastic rocks.	Volcanic rocks erupted from volcanic centers either in or north of the SWNVF. Unit saturated beneath Pahute and Rainier Mesas, Yucca Mountain, and Yucca and Frenchman Flats [AFFCR, AM, PMOV].
		Cenozoic volcanic and sedimentary deposits (consolidated)			
		VSU upper	Upper volcanic-sedimentary rock unit	Undifferentiated volcanic and sedimentary rocks, including welded and nonwelded tuffs, rhyolitic-to-basaltic lava flows, alluvium, colluvium, and eolian, fluvial, and lacustrine deposits. Rocks not associated with previously defined volcanic and sedimentary units.	VSU upper and VSU lower contain rocks that overlie and underlie volcanic rocks of the SWNVF, respectively. Outside the SWNVF boundary, the division between VSU upper and VSU lower is arbitrary. Saturated unit is regionally extensive throughout study area [AFFCR, AM, PDVS, PMOV].
		VSU lower	Lower volcanic-sedimentary rock unit		

Table 3. Major lithology and occurrence descriptions of hydrogeologic units in the study area, as defined in the Death Valley Regional Flow System Version 2 hydrogeologic framework, Nevada and California.—Continued

Era Period	Abbreviation	Hydrogeologic unit	Major lithology	Occurrence
Pre-Cenozoic rocks				
Mesozoic - Cenozoic	ICU	Intrusive-rock confining unit	Mesozoic granite, granodiorite, quartz monzonite, and tonalite in stocks, dikes, and sills. Cenozoic (Oligocene and Miocene) granite, gabbro, and diorite plutons associated with extension and caldera-related volcanism.	Localized stocks in Greenwater, Groom, Kawich, and Kingston Ranges, Black Mountains, and north of Rainier Mesa and Yucca Flat [AFFCR, AM, PMOV, PDVS].
Mesozoic - Triassic	SCU	Sedimentary-rock confining unit	Interbedded sedimentary rocks, including gypsum, limestone, calcareous shale, shale, siltstone, sandstone, and conglomerate.	Localized unit beneath the Spring Mountains and Pahrump Valley [PDVS].
Paleozoic	UCA	Upper carbonate-rock aquifer	Limestone, dolomite, and calcareous shale.	Localized saturated unit above UCCU in western Yucca Flat [AM].
	UCCU	Upper clastic-rock confining unit	Quartzite, argillite, conglomerate, sandstone, siltstone, and shale with minor limestone. Carbonate and siliciclastic rocks were derived from debris flows and turbidites, where sediments grade from coarse to fine from ridges to the valley floor.	Localized unit saturated beneath northern Jackass Flats and western and northern Yucca Flat [AFFCR, AM].
	LCA_T1	Lower carbonate-rock aquifer (thrust)	Massive dolomite and limestone with minor quartzite, chert, shale and calcareous siltstone. LCA includes Mississippian and Pennsylvanian carbonate rocks, where these rocks are not separated by UCCU.	Saturated unit occurs beneath the Spring Mountains, Sheep Range, Specter Range, Skull Mountain, and central Yucca Flat [AFFCR, AM, PDVS].
	LCA	Lower carbonate-rock aquifer	Massive dolomite and limestone with minor quartzite, chert, shale and calcareous siltstone. LCA includes Mississippian and Pennsylvanian carbonate rocks, where these rocks are not separated by UCCU.	Saturated unit is regionally extensive throughout AM groundwater basin, occurs beneath Amargosa Desert, Pahrump, Chicago, and California Valleys, and Spring and Funeral Mountains [AFFCR, AM, PDVS].
	LCCU_T1	Lower clastic-rock confining unit (thrust)	Quartzite, sandstone, siltstone, shale, minor limestone and dolomite, and their metamorphic equivalents. Unit includes the Pahrump Group and Noonday Dolomite.	Saturated unit occurs beneath the Spring Mountains, Sheep Range, Specter Range, Funeral Mountains, and Rainier Mesa [AFFCR, AM, PDVS].
Neoproterozoic era to Cambrian period	LCCU	Lower clastic-rock confining unit	Quartzite, sandstone, siltstone, shale, minor limestone and dolomite, and their metamorphic equivalents. Unit includes the Pahrump Group and Noonday Dolomite.	Saturated unit occurs throughout study area [AFFCR, AM, PDVS, PMOV].
Precambrian eon	XCU	Crystalline-rock confining unit	Metamorphosed sedimentary rocks, granite, gneiss, and quartzfeldspathic schist.	Saturated unit occurs beneath Funeral and Black Mountains [AFFCR, PDVS].




Figure 5. Major geologic structures, in the study area, Nevada and California.

Large-scale normal faulting occurred during and after the period of Cenozoic volcanism (Winograd and Thordarson, 1975; Laczniaik and others, 1996; Prothro and Drellack, 1997; Sweetkind and others, 2010). From the Mid-Tertiary to Quaternary, normal faults (fig. 5) formed the Basin and Range topography of the Great Basin province. Normal faults are the most common structural feature in the study area and displacement along normal faults continues today (Winograd and Thordarson, 1975). Normal faults typically have displaced the Precambrian through Cenozoic section by less than 500 ft; however, in some cases, normal faults have displaced rocks more than 1,000 ft (Winograd and Thordarson, 1975). Sedimentary rocks associated with volcanism occur throughout the study area, and consist of tuffaceous sandstone and siltstone, lacustrine tuff, and claystone.

Cenozoic unconsolidated basin fill occurs throughout the study area in intermontane basins (Sweetkind and others, 2010; Taylor and Sweetkind, 2014). Coarse-grained basin fill typically consists of alluvial and colluvial deposits with minor fluvial, debris-flow, and eolian deposits. Fine-grained basin fill consists of playa and lacustrine sediments. Limestone and spring deposits also are present locally.

Interbasin Flow Between Groundwater Basins

Interbasin flow is the movement of groundwater across groundwater-basin boundaries. Groundwater-basin boundaries were delineated by Fenelon and others (2016) to minimize interbasin flow between groundwater basins. Therefore, interbasin flow is limited to four small areas in the study area. Expected flows between groundwater basins were derived from Darcy estimates through well-defined features, such as basin fill bounded by low-permeability rocks south of Beatty and near Eagle Mountain (fig. 6).

Groundwater moves from the Ash Meadows groundwater basin to the AFFCR groundwater basin through a 2–5-mi-wide corridor around well AD-4 (fig. 6). Permeable basin fill contacts permeable carbonate rock along the Gravity fault (fig. 5) in the well AD-4 corridor. This is atypical along the Gravity fault because, south of the well AD-4 corridor, low-permeability basin fill in the AFFCR groundwater basin has been juxtaposed against carbonate rocks in the Ash Meadows groundwater basin. Groundwater upwells from underlying carbonate rocks to overlying basin fill in the well AD-4 corridor, and flows through permeable basin fill in the Amargosa Desert. Groundwater flows between groundwater basins and does not discharge at land surface because shallow basin fill is sufficiently permeable in the well AD-4 corridor (fig. 6).

Expected predevelopment flow from the Ash Meadows to the AFFCR groundwater basin through the well AD-4 corridor ranges from 2,000 (Fenelon and others, 2016) to 4,000 acre-ft/yr, where the expected flow rate likely is closer to 2,000 acre-ft/yr. Expected flow rates were computed from

Darcy's Law assuming a hydraulic gradient of 0.01 ft/ft, a transmissivity of 2,000 ft²/d from specific-capacity tests, and a corridor width of 2–5 mi.

Groundwater moves from the PMOV groundwater basin to the AFFCR groundwater basin through basin fill of limited saturated thickness south of Beatty (fig. 6). Basin fill underlies the Amargosa River channel and is bounded by low-permeability rocks from Bullfrog Hills and Bare Mountain. Reiner and others (2002) estimated about 100 acre-ft/yr of groundwater flow from the PMOV to the AFFCR groundwater basins (fig. 6). The Amargosa River is perennial in Beatty and about 300 acre-ft/yr of streamflow flows past *USGS streamgage 10251217* (Amargosa River at Beatty, Nevada). Part of this streamflow infiltrates basin fill in the Amargosa River channel and recharges the AFFCR groundwater basin (Stonestrom and others, 2007).

Saturated basin fill beneath the Amargosa River near Eagle Mountain connects the AFFCR and PDVS groundwater basins (fig. 6). Basin fill has limited thickness, is less than 1-mi wide, and Eagle Mountain is an isolated block of carbonate rocks (Sweetkind and others, 2001). Less than 300 acre-ft/yr of predevelopment flow is estimated to move beneath the Amargosa River, assuming a hydraulic gradient of 29 ft/mi between wells *Eagle Mtn North* and *Hwy 127 MM21-1*, a width of 1 mi, and an average transmissivity of 1,000 ft²/d.

Saturated basin fill between Stewart Valley and the Ash Meadows discharge area connects the PDVS and Ash Meadows groundwater basins (fig. 6). Basin fill is less than 1 mi wide and bounded by low-permeability rocks (Sweetkind and others, 2001). Less than 200 acre-ft/yr of predevelopment flow is estimated to move from the PDVS groundwater basin, assuming a hydraulic gradient of 14 ft/mi between wells *BLM Stewart Valley Well* and *GS-1 Well (AD-12)*, a width of 1 mi, and an average transmissivity of 1,000 ft²/d.

Predevelopment Groundwater Flow

Groundwater flow prior to development can be characterized by distributions and rates of groundwater recharge and discharge, and by the hydraulic conductivities of saturated rocks in the study area. Recharge adds water to the groundwater system and locally elevates water levels. Water levels locally are depressed where groundwater discharges from the system. Recharge and discharge areas are controlled by topography, where more recharge occurs in highland areas, compared to valley floors, and moves downgradient to discharge areas. Topography and hydraulic conductivities of geologic units control the rate and distribution of recharge and discharge. Hydraulic conductivity and recharge control water-level altitudes, flow rates, and flow directions in the saturated rocks between recharge and discharge areas. Recharge, discharge, and hydraulic conductivities are distributed spatially throughout the flow system and their distributions characterize the four principal groundwater basins in the study area (Fenelon and others, 2016).




Figure 6. Groundwater basins and major discharge areas in the study area, Nevada and California.

Discharge Areas

Discharges define groundwater budgets for undeveloped groundwater basins because (1) discharge is approximately equal to recharge prior to development; and (2) recharge is more difficult to quantify than discharge because recharge cannot be measured directly (Bredehoeft, 2007). Imbalances between discharge and recharge estimates in the Great Basin typically are attributed to interbasin flow (Maxey and Eakin, 1951).

Spatial distribution of discharge is controlled by topography, hydraulic conductivity (transmissivity), and geologic features. Discharge typically occurs either at a break in slope of the topography or by strong contrasts in hydraulic conductivity between geologic units. *Bennetts* and *Manse* Springs in Pahrump Valley were formed by the break in slope between the Spring Mountains and valley floor, whereas springs in the Ash Meadows discharge area (fig. 6) were formed by a normal fault known as the Gravity fault (fig. 5). Discharge from Ash Meadows springs occurs from transmissive carbonate rocks because clayey basin fill downgradient of the Gravity fault limits flow. Locations and magnitudes of discrete discharges also are controlled by estimated transmissivity distributions. For example, assuming two springs discharge from the same aquifer, the part of the aquifer contributing 6 ft³/s to one spring must be considerably more transmissive than another part of the aquifer contributing 0.006 ft³/s to another spring. In the study area, each regional discharge area is characterized individually because estimated hydraulic-property distributions affect local variations in discharge rates within each discharge area.

Discharge typically occurs in topographically low areas where groundwater is at or near land surface by three processes: (1) spring flow and seepage; (2) transpiration by local phreatophytic vegetation; and (3) evaporation from soil and open water. Each of these processes can be measured directly or estimated. As groundwater emerges from springs, it forms ponds or flows into free-flowing drainages or local reservoirs. Some of this water infiltrates downward into soils and possibly into an underlying aquifer, but most of the water ultimately is consumed by phreatophytic vegetation or is evaporated. The combined processes of evaporation and transpiration are referred to as evapotranspiration (ET), where only groundwater evapotranspiration is considered in this study. Major discharge areas in the study area occur in topographic lows of each groundwater basin (fig. 6).

The amount and rate of groundwater lost to the atmosphere by ET from discharge areas varies with vegetation type and density, soil characteristics, depth to water, and climate (Laczniaik and others, 1999, 2001; Reiner and others, 2002; DeMeo and others, 2003; Moreo and others, 2007; Allander and others, 2009). ET rates generally increase as vegetation health, vegetation density, and soil moisture increase. Previous studies in Nevada have applied various remote-sensing techniques using satellite imagery

in combination with field mapping and ET measurements to identify and group areas of similar vegetation and soil conditions within discharge areas (Smith and others, 2007; Allander and others, 2009; Garcia and others, 2014; Berger and others, 2016). Vegetation and soil groupings are referred to as ET units because they represent areas with similar ET rates. Typical ET units include areas of no vegetation (such as open water, dry playa, and moist bare soil) and areas with vegetation dominated by phreatophytic shrubs, grasses, rushes, and reeds.

Regional discharge is estimated by mapping ET units, estimating the total ET from all units, and subtracting non-groundwater contributions such as local precipitation and infiltrated floodwaters. Local precipitation and infiltrated floodwaters are assumed to evaporate locally, or supply plant needs when available (Laczniaik and others, 1999). Total discharge can be approximated well by estimating ET rates at discrete locations and delineating ET areas, as was done in the Ash Meadows discharge area (Laczniaik and others, 1999). Total discharge in Ash Meadows and Oasis Valley is defined well because groundwater discharge by ET (ET_{GW}) from different types of vegetative cover was estimated from 18 multiyear, micrometeorological measurement sites (Laczniaik and others, 1999; Reiner and others, 2002).

Predevelopment discharge has been estimated for each discharge area in the study area (table 4). Estimates consisted of existing values within each discharge area (Maxey and Jameson, 1948; Malmberg, 1967; Laczniaik and others, 1999, 2001, 2006; Reiner and others, 2002; DeMeo and others, 2003; and Fenelon and others, 2016). Estimates from the Ash Meadows discharge area (Laczniaik and others, 1999), Indian Springs (Maxey and Jameson, 1948), and Oasis Valley (Reiner and others, 2002) are accurate because of detailed, site-specific, field studies (fig. 6). Discharges from Chicago Valley, California Valley, Franklin Well area, and Shoshone-to-Tecopa areas are less certain because ET_{GW} rates were extrapolated from ET measurements in Oasis Valley and Ash Meadows discharge areas (Laczniaik and others, 2001). Discharges from Death Valley playa, Franklin Lake, Furnace Creek area, Pahrump Valley, and Saratoga Spring area were revised in this study because ET rates from playas have been previously overestimated, ET areas have been classified incorrectly, or discharges have been excluded inadvertently (Belcher, 2004; Belcher and Sweetkind, 2010; Belcher and others, 2017).

Discharges primarily differed between DVRFS.v2 and DV3 projects in areas with playas (table 4). Revised discharges were reduced markedly from previous estimates because plausible ET_{GW} rates from playas approach 0 ft/yr (Jackson and others, 2018). Previously estimated ET_{GW} rates on playas in the study area ranged from 0.13 to 0.15 ft/yr (DeMeo and others, 2003). These ET_{GW} rates were interpreted as annual averages, but better represent the detection limit on ET_{GW} rates, given limitations of the Bowen-ratio method (Garcia and others, 2014).

Table 4. Predevelopment discharge by discharge area for previous and current regional flow analyses of the study area, Nevada and California.

[**Groundwater basin:** AFFCR, Alkali Flat–Furnace Creek Ranch; PDVS, Pahrump to Death Valley South; PMOV, Pahute Mesa–Oasis Valley. **DVRFS.v2:** Death Valley Regional Flow System version 2 model (previous regional flow analysis). **DV3,** Death Valley version 3 model (current regional flow analysis)]

Groundwater basin	Discharge area	Annual discharge (acre-feet)	
		DVRFS.v2	DV3
AFFCR	Furnace Creek area ^{1,2}	5,700	6,100
	Franklin Well area	340	340
	Franklin Lake ¹	1,000	0–700
	Death Valley playa ^{3,1}	1,400	0–100
Ash Meadows	Ash Meadows with Amargosa Flat	17,900	18,100
	Indian Springs	660	700
PMOV	Oasis Valley	6,000	6,200
PDVS	Pahrump and Stewart Valleys ⁴	10,600	13,300
	Chicago Valley	430	430
	Shoshone area	2,100	2,100
	Tecopa/California Valley area	6,200	6,300
	Saratoga Spring area ⁵	2,460	0–400
	Death Valley playa ^{3,1}	6,800	0–100
TOTAL		61,600	53,600–54,900

¹ Discharges differ because playas were assigned different groundwater-evapotranspiration rates.

² Discharges differ because diversions from Furnace Creek wash were not included in DVRFS.v2 project.

³ Comparison limited to playa area in DV3 study area.

⁴ Discharges differ because total discharge from Pahrump Valley in DVRFS.v2 project was limited to predevelopment discharges from Bennetts and Manse Springs.

⁵ Discharges differ because DVRFS.v2 project used groundwater-evapotranspiration areas and rates that were classified incorrectly in DeMeo and others (2003) and did not subtract the 720 acre-feet per year (acre-ft/yr) (1 cubic foot per second) of return flow from the Amargosa River downstream of Dumont Dunes streamgage. The DV3 discharge estimate is a net discharge estimated from a water balance done for the Saratoga Spring topographic basin in this study. Predevelopment discharge ranges between 800 and 1,200 acre-ft/yr, where subtraction of the 720 acre-ft/yr of return flow results in a net discharge of less than 400 acre-ft/yr in this study.

Hydraulic-property estimates and predictions of groundwater discharges from springs depend greatly on specified locations and rates of discharges. Previous studies were designed to estimate the total predevelopment discharge from discharge areas, but not specifically to identify each discrete discharge location within a discharge area (Laczniak and others, 1999, 2001, 2006; Reiner and others, 2002; DeMeo and others, 2003). Most groundwater either discharges discretely from springs or evapotranspires in ET units that are downgradient of the springs. Discharge rates differ markedly between springs and ET areas. For example, *Crystal Pool* in the Ash Meadows discharge area discharges 6.4 ft³/s (4,600 acre-ft/yr) from a 5-ft-diameter spring pool (0.0018 acres), which equates to a discharge rate of more than 2,500,000 ft/yr. This discharge rate is much more intense than ET rates of 0.9–8.2 ft/yr from the 3,000 acres of ET units downgradient of *Crystal Pool* (Laczniak and others, 1999).

“Double counting” of discharge occurs when discharges from spring orifices feed downgradient spring runs, wetlands, and moist soils that support phreatophytic vegetation. Predevelopment discharge in a discharge area is double counted if spring discharge and ET are summed and the ET areas are fed by the springs. Spring orifices and ultimate ET locations can differ by more than 3 mi. To prevent double counting of discharge, differences in locations and rates of discharge were reconciled by delineating the ET area fed by each spring and attributing cumulative ET_{GW} in excess of the spring discharge to the ET area. ET areas fed by springs were delineated by summing ET_{GW} rates from ET units downgradient of the springs until cumulative ET_{GW} equaled measured spring discharges. Differences in locations and rates from diversions, ET areas, and springs were reconciled in Ash Meadows, Furnace Creek, Pahrump Valley, Lower Amargosa, and Saratoga Spring discharge areas (fig. 6).

Ash Meadows

Ash Meadows discharge area includes Amargosa Flat, more than 30 springs and seeps at Ash Meadows, and ET areas that extend downgradient from Ash Meadows springs to Carson Slough (fig. 7). Predevelopment discharge from the Ash Meadows discharge area totals 18,100 acre-ft/yr (Laczniaik and others, 1999). Most of the discharge occurs from 19 springs in Ash Meadows, which discharge a total of 16,150 acre-ft/yr (Dudley and Larson, 1976; Laczniaik and others, 1999). Discharge by ET_{GW} from ET units within Amargosa Flat accounts for 1,700 acre-ft/yr of the total discharge, whereas estimated discharge from ET units downgradient of Ash Meadows springs is about 250 acre-ft/yr (Laczniaik and others, 1999).

Discharge from the Ash Meadows discharge area would be twice the predevelopment estimate of 18,100 acre-ft/yr if double counting of discharge is not reconciled. Total discharge from springs in Ash Meadows (16,150 acre-ft/yr) is similar to the 16,400 acre-ft/yr of ET_{GW} (Laczniaik and others, 1999) estimated from about 10,000 acres of ET units downgradient of the springs (fig. 7). Spring discharges and estimated ET_{GW} from ET units are functionally equivalent within the uncertainty of the measurements (Laczniaik and others, 1999). Attributing virtually all discharge to springs rather than to large areas of seeps implies that all discharge in the Ash Meadows discharge area occurs through less than 1 acre of spring pools.

Some water that evapotranspires from ET units downgradient of Ash Meadows springs is sourced from diffuse seepage rather than runoff from spring discharge. Water seeps diffusely from the underlying carbonate rocks to the water table through overlying clay-rich, basin fill. Diffuse seepage of 0.02 ft/yr was estimated from local hydraulic gradients of 0.2 ft/ft and a hydraulic conductivity of 0.0003 ft/d. Diffuse seepage discharges as ET_{GW} from the water table in the Ash Meadows discharge area and totals about 250 acre-ft/yr.

Springs in Ash Meadows discharge groundwater from underlying carbonate rocks that minimally interact with overlying basin fill prior to entering spring pools (fig. 8). Flows are controlled by heads decreasing between carbonate rocks and spring pools. Water levels in spring pools generally are higher than the water table around spring pools, as evidenced by the lack of vegetation far from spring pools and runs. Vegetation typically occurs in the Ash Meadows discharge area where the water table is within 10 ft of land surface (Laczniaik and others, 1999). Absence of vegetation far from spring pools and runs suggests that the water table is more than 10 ft below land surface, and thus, lower than the pools. Minimal spring discharge returns to the water table from spring runs because clay predominates in the basin fill. A delta-shaped area of phreatophytes downgradient of *Crystal Pool* is an exception where return flow occurs (fig. 7).

Furnace Creek Area

About 90 percent of predevelopment discharge from the AFFCR groundwater basin (fig. 6) exits in the Furnace Creek area (table 4), which extends from the alluvial fan of Furnace Creek Wash in the southwest to *Nevares* Springs in the northeast (fig. 9). Prior to development in the Furnace Creek area, groundwater either discharged from springs upgradient of Furnace Creek Wash or moved as subsurface flow through Furnace Creek Wash and discharged by ET_{GW} from phreatophytes on the alluvial fan (fig. 9). Groundwater development began with the alteration of springs and installation of collection galleries that act as French drains in Furnace Creek Wash. Furnace Creek Wash has three collection galleries: (1) a sump; (2) buried tile; and (3) the Furnace Creek Inn tunnel (fig. 9), which collect and divert groundwater in the wash principally for irrigation at The Oasis at Death Valley, formerly known as Furnace Creek Ranch. Discharge from *Travertine* and *Texas* Springs also is collected and diverted for water supply in the Furnace Creek area.

Predevelopment discharge from the Furnace Creek area totals 8.5 ft³/s (6,200 acre-ft/yr). *Nevares*, *Travertine*, *Texas*, and undeveloped springs discharge 2.8 ft³/s (2,000 acre-ft/yr) and ungaged ET_{GW} near *Travertine* Springs discharges about 0.1 ft³/s (70 acre-ft/yr). A total of 2.0 ft³/s (1,400 acre-ft/yr) of subsurface flow in Furnace Creek Wash is diverted by three collection galleries, whereas the remaining subsurface flow passes through the wash and discharges as ET_{GW} on the alluvial fan (fig. 9).

Predevelopment discharge from the Furnace Creek area was estimated by reevaluating previous water-budget estimates and conceptual models. Rates and locations of predevelopment discharge differed primarily because of conceptual models that either included or excluded collection galleries in Furnace Creek Wash. The conceptual model used in this study is based on the evaluation of data during three hydrologically distinct periods: (1) predevelopment; (2) mining-tourism; and (3) restoration.

Previous Predevelopment Estimates And Conceptual Models

Previously published water budgets of the Furnace Creek area synoptically totaled discharge during two periods: 1956–63 (Pistrang and Kunkel, 1964; Hunt and others, 1966) and 1990–2000 (Belcher and Sweetkind, 2010). Estimates of total discharge from the Furnace Creek area ranged from 5.6 ft³/s (4,100 acre-ft/yr; Hunt and others, 1966) to 7.9 ft³/s (5,700 acre-ft/yr; Belcher and Sweetkind, 2010). Estimates of total discharge from the Furnace Creek area differed because conceptual models differed. Miller (1977) is not included because reported discharges were limited to *Travertine* and *Texas* Springs.




Figure 7. Springs and evapotranspiration areas in the Ash Meadows discharge area and vicinity, Nevada.




Diagram not to scale, vertical dimension greatly exaggerated.

EXPLANATION



Basin fill—Gravel, sand and mud; silt and clay west of gravity fault



Carbonate rock



Spring-flow zone—Upward flow zone developed along and contemporary with growth faults



Fault—Arrow indicates direction of relative fault movement. Solid where fault forms barrier to lateral flow from carbonate rock. Dashed where fault forms conduit for upward flow in basin fill



Water table



Potentiometric surface in carbonate rock



Area of evapotranspiration—Height of vegetation indicates relative quantity of transpiration. Length of arrow indicates relative quantity of evaporation



General direction of groundwater flow—Size of arrow indicates relative magnitude of groundwater flow

Figure 8. Groundwater flow to springs and phreatophyte areas in the Ash Meadows discharge area, Nevada. Figure modified from Lacznia and others (1999).




Figure 9. Discharge locations and the historical water-collection system in the Furnace Creek area, California.

Predevelopment-discharge estimates from the Furnace Creek area during 1956–63 (Pistrang and Kunkel, 1964; Hunt and others, 1966) were similar (table 5) and assumed that all discharge occurred in Furnace Creek Wash upgradient of Furnace Creek Inn tunnel (fig. 9). Water collected by a sump, buried tile, and the Furnace Creek Inn tunnel for irrigation at Furnace Creek Ranch (fig. 9) were included as part of the predevelopment discharge because collected groundwater would have passed through the wash prior to development. Discharge by ET_{GW} on the alluvial fan was not included because this discharge was assumed to be reinfiltated spring discharge and return flow from irrigation at Furnace Creek Ranch, which was sourced from diverted groundwater in Furnace Creek Wash (Hunt and others, 1966, p. B37). Discharge from *Nevares* Springs during 1956–63 differed by 0.1 ft³/s (70 acre-ft/yr; table 5) because small springs downgradient of *Nevares* Springs were interpreted as reinfiltated spring discharge and not included by Pistrang and Kunkel (1964, p. Y19), whereas all discharges were totaled by Hunt and others (1966, p. B35). The low permeability of the underlying mudstones, classified as volcanic-sedimentary rocks in figure 9, downgradient of carbonate rocks supports the interpretation of Pistrang and Kunkel (1964).

Predevelopment conditions were approximated during the 1990–2000 period (Belcher and Sweetkind, 2010) by summing discharges from *Travertine*, *Texas*, and *Nevares* Springs, and ET_{GW} areas on the alluvial fan (table 5). Average discharges from *Travertine* and *Texas* Springs were estimated from measurements during the periods 1956–72 and 1989–96, respectively (Belcher and Sweetkind, 2010, table C-2). Discharge from *Nevares* Springs was the sum of average discharge from the main spring area during the period 1956–57 and discharges from other nearby springs. Belcher and Sweetkind (2010) did not include discharge from the collection galleries in Furnace Creek Wash because predevelopment conditions were being simulated (Belcher and Sweetkind, 2010). The conceptual model used by Belcher and Sweetkind (2010) assumes that 4.7 ft³/s (3,400 acre-ft/yr) bypasses *Travertine* and *Texas* Springs, moves downgradient, and enters the head of the alluvial fan.

Differences in conceptual models of the natural system understandably arise because all discharges were measured 60 or more years after the Furnace Creek area was developed and total predevelopment discharges differed little in previous investigations. *Travertine* and *Texas* Springs were diverted to collection galleries in Furnace Creek Wash between 1880, when mining commenced, and 1920 when tourism was introduced (Greene and Latschar, 1981). A single discharge measurement was reported for *Texas* Springs and the sump during 1941, but frequent, repeatable measurements of discharge from springs and collection galleries in the Furnace Creek area were not reported until 1956 (Pistrang and Kunkel, 1964). ET_{GW} areas on the alluvial fan were not estimated systematically until more than 100 years after the Furnace Creek area was developed (DeMeo and others, 2003).

DV3 Conceptual Model—Three Hydrologically Distinct Periods

Predevelopment, mining-tourism, and restoration are three hydrologically distinct periods in the Furnace Creek area that occurred prior to 1880, and during 1880–2008 and 2009–18, respectively. Groundwater flow prior to development was inferred to total 8.6 ft³/s (6,200 acre-ft/yr)—where *Nevares*, *Travertine*, *Texas*, and undeveloped springs discharged 2.9 ft³/s (2,100 acre-ft/yr), and the remaining 5.6 ft³/s (4,100 acre-ft/yr) flowed through Furnace Creek Wash to the alluvial fan (table 5). Development during the mining-tourism period diverted a total of 4.1 ft³/s (3,000 acre-ft/yr) from springs and collection galleries in Furnace Creek Wash. Diversions from *Travertine* and *Texas* Springs redirected 2.1 ft³/s (1,500 acre-ft/yr) from flowing down washes and across the alluvial fan. Collection galleries in Furnace Creek Wash diverted 2.0 ft³/s (1,400 acre-ft/yr) of subsurface flow that would have entered the alluvial fan; therefore, discharge from the alluvial fan was reduced from 5.6 to 3.6 ft³/s (table 5). Most of the diverted water was applied at Furnace Creek Ranch for irrigation of date palms and a golf course, and to support tourism. Flow through the Furnace Creek area was altered during the restoration period by (1) restoring 1.7 ft³/s (1,200 acre-ft/yr) to spring runs downgradient of *Travertine* and *Texas* Springs; (2) pumping 0.4 ft³/s (300 acre-ft/yr) from water-supply wells FCWSPW-01, FCWSPW-02, and FCWSPW-03 north of *Travertine* Springs; and (3) collecting non-potable groundwater from collection galleries in Furnace Creek Wash (fig. 9).

Changing discharge from any location affects all other discharges in the Furnace Creek area, as shown by pumping. Supply wells FCWSPW-01, FCWSPW-02, and FCWSPW-03 began pumping in March 2009 and averaged 0.4 ft³/s (300 acre-ft/yr) during 3 years of pumping (fig. 10). Combined discharge from *Travertine* and *Texas* Springs decreased by 0.3 ft³/s (200 acre-ft/yr) during the first 2 years of pumping before a local equilibrium was established (Jackson and Halford, 2020). The additional 0.1 ft³/s (100 acre-ft/yr) of pumped water that did not come from spring capture was supplied from storage in the basin fill.

Discharge from Springs

Discharges from *Travertine*, *Texas*, and undeveloped springs are assumed to minimally infiltrate Furnace Creek Wash and the alluvial fan, and do not contribute to discharge by ET_{GW} from phreatophytes on the alluvial fan. This was true during the mining-tourism period because all spring discharges were collected and applied to Furnace Creek Ranch. During the restoration period, this assumption is supported by discharge from *Travertine* Springs flowing across the alluvial fan. A sufficient fraction of the 1.3 ft³/s (940 acre-ft/yr) from the restored *Travertine* Springs flows across the alluvial fan to form ponds and wetlands on the floor of Death Valley (Richard Friese, National Park Service, oral commun., 2015).

Table 5. Predevelopment and post-development discharge estimates for all sites in the Furnace Creek area, California, prior to 1880 to 2018.

["—"] indicates that the site existed and was measured, but measurements were not included based on the conceptual model. No data indicates that the site existed but was not measured during the period of study. **Abbreviations:** acre-ft/yr, acre-feet per year; ft³/s, cubic feet per second; N/A, not applicable]

Measurement site	Discharge (cubic feet per second)						Sub Area
	1956–63	1956–63	1990–2000	Prior to 1880	1880–2008	2009–18	
	Pistrang and Kunkel (1964)	Hunt and others (1966)	Belcher and Sweetkind (2010)	This study	This study	This study	
	Pre-development	Pre-development	Pre-development	Pre-development	Mining-tourism	Restoration	
Travertine Springs	1.9	1.9	1.9	1.9	1.7	1.3	Furnace Creek Wash
Texas Springs	0.5	0.5	0.5	¹ 0.3	0.4	0.4	
Undeveloped springs	0.1	0.1	—	0.1	0.1	0.1	
Ungaged ET near Travertine Springs	0.5	—	—	0.1	0.1	0.1	
Sump	1.3	1.3	—	—	1.3	1.3	
Buried tile	0.4	0.4	—	—	0.4	0.4	
Furnace Creek Inn tunnel	0.3	0.5	—	—	0.3	0.3	
Trench – destroyed in 1959	—	0.2	—	—	—	—	
Phreatophytes on alluvial fan	No data	No data	4.7	5.6	3.6	3.6	Alluvial fan
Nevares Springs	0.6	0.7	0.8	0.6	0.6	0.6	Carbonate rocks
Pumping	N/A	N/A	N/A	N/A	N/A	0.4	
Total discharge —ft ³ /s	5.6	5.6	7.9	8.6	8.5	8.5	
—acre-ft/yr	4,100	4,100	5,700	6,200	6,200	6,200	

¹ Discharge measured in 1926 prior to construction of tunnel at Texas Spring.

Discharge from Phreatophytes on Alluvial Fan

ET_{GW} on the alluvial fan downgradient of Furnace Creek Ranch is sustained in part by return flow. Irrigation and water features at Furnace Creek Ranch are supplied by diversions from *Travertine Springs*, *Texas Springs*, and collection galleries in Furnace Creek Wash that total 4.1 ft³/s (3,000 acre-ft/yr). Some of the diverted water becomes return flow and infiltrates the alluvial fan to the west-northwest of Furnace Creek Ranch (fig. 9). All discharge from phreatophytes to the west-northwest of Furnace Creek Ranch totals about 1 ft³/s (720 acre-ft/yr).

In this study, predevelopment discharge from phreatophytes on the alluvial fan totaled 5.6 ft³/s (4,100 acre-ft/yr; table 5), which accounts for return flow and other factors. DeMeo and others (2003) reported a discharge of 4.7 ft³/s (3,400 acre-ft/yr) from the alluvial fan, which was used in the DVRFS.v2 project (Belcher and Sweetkind, 2010; table 5). The 4.7 ft³/s (3,400 acre-ft/yr) was revised by adding the 2.0 ft³/s (1,400 acre-ft/yr) of diverted water from collection galleries in Furnace Creek Wash, and then subtracting discharge from the Death Valley playa (0.1 ft³/s; 70 acre-ft/yr) and return flow (1 ft³/s; 720 acre-ft/yr).

A predevelopment-discharge estimate of 5.6 ft³/s (4,100 acre-ft/yr) from the alluvial fan assumes that all discharge from phreatophytes to the west-northwest of Furnace Creek Ranch (1 ft³/s; 720 acre-ft/yr) is entirely attributed to return flow. More likely only a fraction of the water diverted for Furnace Creek Ranch becomes return flow. About 1 ft³/s

of discharge from the alluvial fan occurs downgradient of Furnace Creek Ranch. Therefore, subsurface flow through Furnace Creek Wash during predevelopment could range from 5.6 to 6.6 ft³/s (4,100 to 4,800 acre-ft/yr), and subsurface flow through Furnace Creek Wash during the mining-tourism period could range from 3.6 to 4.6 ft³/s (2,600 to 3,300 acre-ft/yr).

Furnace Creek Wash—A Transmissive Feature

Permeable sediments in Furnace Creek Wash connect basin-fill deposits upgradient of *Travertine Springs* to the alluvial fan on the floor of Death Valley (fig. 9). Furnace Creek Wash consists of coarse-grained sediments as evidenced by lithologic well logs from wells *LFCW-01* and *UFCW-02*, which are open to gravels and sands in Furnace Creek Wash. Rocks surrounding Furnace Creek Wash are predominantly low-permeability mudstones, as evidenced by a low hydraulic conductivity of 0.0001 ft/d in well *TxCmpMW-1* (Jackson and Halford, 2020). Low-permeability mudstones surrounding Furnace Creek Wash and the radial shape of the alluvial fan indicate that most, if not all, groundwater enters the alluvial fan from the mouth of Furnace Creek Wash. The conceptual model depends greatly on 5.6 ft³/s (4,100 acre-ft/yr) passing through Furnace Creek Wash as subsurface flow, which requires an average transmissivity of 40,000 ft²/d. This assumes a channel width of 300 ft and hydraulic gradient of 0.04 ft/ft.




Figure 10. Groundwater-level fluctuations in the Furnace Creek area from collection galleries in Furnace Creek Wash and water-supply wells, California, 2008–12.

Conveying 5.6 ft³/s (4,100 acre-ft/yr) requires that Furnace Creek Wash between *Travertine* Springs and the Furnace Creek Inn tunnel be very transmissive. Annual fluctuations of 8 ft in well *LFCW-01* are consistent with Furnace Creek Wash being very transmissive (fig. 10). This is because seasonal water-level changes are attenuated minimally between the well and the sump and tile collectors that are 0.3-mi upgradient. Seasonal fluctuations were observed upgradient of the sump and tile collectors in well *UFCW-02* prior to pumping of the supply wells (fig. 10). Seasonal fluctuations were attenuated in wells *WRPMW-3* and *WRPMW-6* by less transmissive coarse-grained sediments upgradient of *Travertine* Springs.

Mining-Tourism Period—A Steady-State Condition

Discharge estimates during the mining-tourism period (1880–2008; table 5) best represent steady-state conditions for this investigation. Total predevelopment discharge from phreatophytes on the alluvial fan is uncertain because no information is available regarding the density of phreatophytes prior to development. Collection galleries in Furnace Creek Wash behave as French drains that divert a steady source of groundwater moving through the wash, resulting in little change in groundwater storage but the capture of discharge from phreatophytes on the alluvial fan. Phreatophyte density and ET_{GW} rates decreased with time in response to capture, but steady-state conditions likely were established by the end of the 128-year mining-tourism period.

Use of the predevelopment (prior to 1880) period for steady-state model calibration also is infeasible because of limited data. The mining-tourism period has concurrent measurements of discharges and water levels, unlike the predevelopment period. Earliest groundwater levels were measured during 1958 (Pistrang and Kunkel, 1964) or about 80 years after the hydrology of the Furnace Creek area was modified for mining (Greene and Latschar, 1981). Most wells in the Furnace Creek area were drilled after 2000. Discharges from *Nebares*, *Travertine*, *Texas*, and undeveloped springs and ET_{GW} on the alluvial fan were measured or estimated concurrently and totaled 6.4 ft³/s (4,600 acre-ft/yr). Water diverted by collection galleries in Furnace Creek Wash was measured during 1956 and 1963 (Pistrang and Kunkel, 1964). Total diversions of 2.0 ft³/s (1,400 acre-ft/yr) were assumed to be unchanged between 1960 and 2018.

Pahrump Valley

The Pahrump Valley discharge area includes *Bennetts*, *Manse*, and *Stump* Springs, and ET_{GW} areas in Pahrump and Stewart Valleys (fig. 11). Predevelopment discharge from the Pahrump Valley discharge area totaled 13,300 acre-ft/yr.

Bennetts and *Manse* Springs discharged 9,800 acre-ft/yr (13.5 ft³/s) prior to development in 1910 and accounted for more than 70 percent of predevelopment discharge. Most discharge from *Bennetts* and *Manse* Springs reinfilted the shallow basin fill and was consumed by downgradient phreatophytes in central Pahrump Valley (Malmberg, 1967). Phreatophytes in northern Pahrump, southern Pahrump, and Stewart Valleys were sustained directly from shallow groundwater, not spring runs (Harrill, 1986). Discharge from these areas, which were not dependent on *Bennetts* and *Manse* Springs, totaled 3,500 acre-ft/yr (fig. 11).

Predevelopment discharges from Pahrump and Stewart Valleys for this investigation were revised by evaluating groundwater budgets from previous investigations. Quantities and distributions of discharge from Harrill (1986) were accepted as reported, with a few exceptions. Discharges from *Bennetts* and *Manse* Springs totaled 9,800 acre-ft/yr (13.5 ft³/s), but issued from spring orifices rather than being distributed downgradient across phreatophyte areas as was simulated by Harrill (1986). Remote sensing estimates of discharge from Stewart Valley, which totaled 1,000 acre-ft/yr (Lacznia and others, 2001), replaced estimates from Harrill (1986). Revised discharge estimates for *Stump* Spring (Jackson and Halford, 2020) and inclusion of phreatophytes 1–8 mi south of *Manse* Spring (Malmberg, 1967), which were inadvertently excluded by Harrill (1986) (fig. 11), added 300 acre-ft/yr to previous estimates by Harrill (1986). Mapped discharge areas (and predevelopment-discharge rates) from the previous investigations that are used in this project are shown in figure 11.

Discharge prior to development in Pahrump Valley was underestimated by Malmberg (1967). Evapotranspired discharge and extent of phreatophytes downgradient of *Bennetts* and *Manse* Springs in 1961 were assumed by Malmberg (1967) to be similar to predevelopment conditions. ET_{GW} from these phreatophytes totaled 7,000 acre-ft/yr (9.7 ft³/s) in 1961 and originated as return flow from irrigation and *Manse* Spring (Malmberg, 1967, p. 28–29). The assumption of similar ET_{GW} rates and phreatophyte extents prior to development and during 1961 is inconsistent with intensive groundwater development in Pahrump Valley. Between 1916 and 1961, pumping increased from 4,300 to 28,500 acre-ft/yr and spring discharges decreased from 9,800 to 1,500 acre-ft/yr (2.1 ft³/s; Malmberg, 1967, p. 31). ET_{GW} by phreatophytes from shallow groundwater in northern Pahrump, southern Pahrump, and Stewart Valleys totaled 3,300 acre-ft/yr (Malmberg, 1967, p. 29) and has differed little in subsequent estimates (Harrill, 1986; Lacznia and others, 2001) because these phreatophyte areas are farther from pumping than phreatophytes downgradient of *Bennetts* and *Manse* Springs.




Figure 11. Discharge areas in Pahrump and Stewart Valleys, Nevada and California.

Predevelopment discharge of 9,800 acre-ft/yr (13.5 ft³/s) from *Bennetts* and *Manse* Springs is accurate (Harrill, 1986). This discharge combined reported discharges of 7.5 and 6 ft³/s from *Bennetts* and *Manse* Springs, respectively, during 1875 and 1877 (Maxey and Jameson, 1948, p. 10). These measurements were corroborated by measured discharges during 1916 from springs and flowing wells that were drilled between 1910 and 1916 (Waring, 1921). Discharge from *Bennetts* and *Manse* Springs totaled 5,800 acre-ft/yr (8.0 ft³/s), whereas discharge from 8 of 13 flowing wells totaled 2,600 acre-ft/yr (3.6 ft³/s) during 1916 (Waring, 1921, p. 64). Discharge from springs and flowing wells exceeded 8,400 acre-ft/yr (11.6 ft³/s) and would equal measured predevelopment discharge from *Bennetts* and *Manse* Springs if flow from each of the five unmeasured wells equaled average discharge of the eight measured wells.

Predevelopment discharges from Pahrump Valley in the DVRFS.v2 project differed from those reported by Malmberg (1967) and Harrill (1986) and totaled 10,600 acre-ft/yr (table 4). Predevelopment discharge from *Bennetts* and *Manse* Springs totaled 9,600 acre-ft/yr (Belcher and Sweetkind, 2010; 32,400 m³/d in table C-2). The 200 acre-ft/yr (0.3 ft³/s) difference between Belcher and Sweetkind (2010) and Harrill (1986) likely resulted from rounding as discharge units were converted from cubic feet per second to cubic meters per day. All discharge from Pahrump Valley was simulated diffusely as ET_{GW} from phreatophyte areas with the DVRFS.v2 model, including *Bennetts* and *Manse* Springs.

Lower Amargosa Area

Lower Amargosa discharge area includes springs and ET areas between Shoshone, California, and Dumont Dunes, and in Chicago and California Valleys (fig. 12). The discharge area is divided into three subareas: (1) Chicago Valley; (2) Shoshone area; and (3) Tecopa/California Valley area. The Shoshone area spans the Amargosa River from the Shoshone Spring complex to north of Borehole Spring and extends east to include Chappo Spring. The Tecopa/California Valley area spans the Amargosa River from Borehole Spring to Dumont Dunes and extends east to include springs and ET areas in California Valley, China Ranch Wash, and at the southern part of the Resting Spring Range.

Predevelopment discharge from the Lower Amargosa discharge area totaled 8,830 acre-ft/yr. Discharge from Twelvemile Spring and ET_{GW} areas within Chicago Valley accounted for 430 acre-ft/yr of the total discharge. Predevelopment discharge from the Shoshone area and Tecopa/California Valley area totaled 2,100 and 6,300 acre-ft/yr, respectively.

Predevelopment discharge from the Lower Amargosa discharge area was estimated with remote sensing and extrapolated ET_{GW} rates (Laczniak and others, 2001). Reported

predevelopment discharges have differed by less than 100 acre-ft/yr between previous investigations (Laczniak and others, 2001, p. 36; Belcher and Sweetkind, 2010, p. 103). These minor differences can be attributed to rounding and not simulating small discharges in model cells on the periphery of the Lower Amargosa discharge area (Faunt, Blainey, and others, 2010, p. 269).

Shoshone and Tecopa/California Valley areas are the functional terminus of discharge within the PDVS groundwater basin (fig. 1) because the Greenwater Range and Ibex Hills west of the Amargosa River and Sperry Hills south of Tecopa are mostly impermeable (fig. 12). Low-permeability quartzite and Miocene sedimentary, volcanic, and intrusive rocks are present beneath the water table from the Amargosa River to the ridges of the Greenwater Range and Ibex Hills (Sweetkind and others, 2001, plate 3). Sperry Hills consist of low-permeability siliciclastic and Miocene rocks (Sweetkind and others, 2001, plate 3). Miocene rocks are correlated with mudstones of the Furnace Creek area that have a hydraulic conductivity of 0.0001 ft/d in well *TxCmpMW-1* (fig. 9). All these geologic units have expected transmissivities of less than 10 ft²/d.

The extent of the ancestral Lake Tecopa also is consistent with the area west of the Amargosa River and south of Tecopa being relatively impermeable. Lake Tecopa occupied Tecopa Valley, reached a maximum depth of 500 ft, and was drained 186,000 years ago after the Amargosa River breached the Sperry Hills (Morrison, 1999). Downgradient features such as Dublin Hills and Sperry Hills cannot be transmissive and sustain a 500-ft-deep lake.

The terminus of regionally transmissive units south of Tecopa was delineated using synoptic discharge measurements at temporary streamgage sites (seepage run) in the Amargosa River on February 27, 2014 (Belcher and others, 2019). When storm-runoff gains are minimal, streamflow gains between synoptic measurements identify reaches where groundwater flow into the river exceeds evaporative losses. These conditions existed because ET_{GW} is less in winter and the last runoff event in the Amargosa River at Tecopa, California (*USGS streamgage 10251300*) occurred 60 days prior to the seepage run.

Flow in the Amargosa River increased by 3.5 ft³/s (2,500 acre-ft/yr) between Borehole Spring (*USGS streamgage 10251290*) and site AR11 (*USGS streamgage 354903116130401*), a 5.5-mi reach (fig. 13). Increases from areas 3–5.5 mi downstream of Borehole Spring came from springs discharging from conglomerates, sandstones, and localized megabreccia (China Ranch beds) at the contact with underlying siliciclastic rocks on the east side of the Amargosa River canyon (Belcher and others, 2019). This contact occurs from 50 to 100 ft above the channel of the Amargosa River.




Figure 12. Discharge areas in the Lower Amargosa discharge area and extent of Pleistocene Lake Tecopa, Nevada and California.




Figure 13. Groundwater discharge to river and estimated evapotranspiration in the Amargosa River downstream of Borehole Spring, California, on February 27, 2014, and cumulative annual evapotranspiration.

Site AR11 (*USGS streamgage 354903116130401*) marked the terminus of the groundwater system because streamflow decreased downstream of site AR11 (fig. 13), indicating no additional groundwater gains. Flow in the Amargosa River decreased by about 1 ft³/s (720 acre-ft/yr) between sites AR11 (*USGS streamgage 354903116130401*) and AR31 (*USGS streamgage 354159116144901*) near Dumont Dunes (fig. 12). Observed conditions were consistent with relatively large evaporative losses during late February and negligible groundwater/surface-water interaction.

Not all groundwater flow into the Amargosa River downstream of Borehole Spring was measured because substantial ET_{GW} occurred during the seepage run (fig. 13). Maximum daily temperatures in Shoshone range from 60 to 81°F during late February (National Climatic Data Center, 2017). ET_{GW} rates during late February average 60 percent of annual average ET_{GW} rates (Lacznia and others, 1999, 2001). Estimated ET_{GW} along the Amargosa River on February 27, 2014, was computed by multiplying average winter ET_{GW} rates by the acreage of ET units for each ET unit, and summing total ET_{GW} between streamflow measurement sites. Similarly, annual average discharge along the Amargosa River was computed using annual average ET_{GW} rates. ET_{GW} totaled 3,000 acre-ft/yr (4.2 ft³/s) during the seepage run because ET_{GW} rates during late February averaged 1.16 ft/yr across 2,600 acres of ET units.

Annual average discharge and total discharge agree in magnitude and distribution on February 27, 2014 during the seepage run (fig. 13). Total discharge from the Amargosa River downstream of Borehole Spring averages 4,900 acre-ft/yr or

6.8 ft³/s (Lacznia and others, 2001). Discharge (streamflow) in the Amargosa River and ET_{GW} during late February totaled 7.0 ft³/s (5,100 acre-ft/yr) at site AR11 (*USGS streamgage 354903116130401*). Combined discharge and ET_{GW} varied little between sites AR11 and AR31 (fig. 13). These results partially validate estimates from Lacznia and others (2001) and are consistent with site AR11 being the terminus of the groundwater system.

ET_{GW} areas sourced from upgradient springs were not simulated in this investigation to prohibit double counting of discharge. ET_{GW} areas in the Amargosa River canyon downstream of site AR11 had discharges totaling 1,100 acre-ft/yr (1.5 ft³/s), which were attributed to springs discharging from the China Ranch beds upstream of site AR11 (fig. 12). Discharges in ET_{GW} areas downgradient of springs in China Ranch Wash similarly was totaled and attributed to upgradient springs. Discharges from West Willow and East Willow Springs totaled 300 and 200 acre-ft/yr (0.4 and 0.3 ft³/s), respectively.

Saratoga Spring Area

Groundwater in the Saratoga Spring area is supplied by a small topographic basin that mostly is isolated within the PDVS groundwater basin (fig. 14). Recharge to the Saratoga Spring area is derived from infiltration of streamflow from the Amargosa River, local recharge, and subsurface bedrock leakage to basin fill. Discharge from the Saratoga Spring area occurs from one spring and about 1,450 acres of phreatophytic vegetation.




Figure 14. Upgradient source and discharge areas for the Saratoga Spring area, California.

Saratoga Spring topographic basin principally is recharged by infiltration from the Amargosa River downstream of the Dumont Dunes streamgage (fig. 14). In the period of record (1999–2001) at Dumont Dunes streamgage (USGS 10251375), base flow in the Amargosa River averaged 720 acre-ft/yr (1.0 ft³/s). This base flow is assumed to infiltrate basin-fill deposits in the river channel, assuming minimal evaporative losses, prior to entering Saratoga Spring topographic basin as subsurface flow.

Recharge to Saratoga Spring topographic basin also occurs from flood events. During flood events, part of the streamflow that enters Saratoga Spring topographic basin infiltrates the Amargosa River channel (fig. 14). Average streamflow during flood events is needed to estimate flood-event recharge to Saratoga Spring topographic basin. Dumont Dunes streamgage (USGS 10251375) has an insufficient period of record (2 years) to estimate average streamflow during flood events. The nearest streamgage with long-term streamflow measurements occurs at Tecopa, California (USGS streamgage 10251300), where streamflow during flood events averaged 1,100 acre-ft/yr (1.5 ft³/s) from 1961 to 2017. This average was computed from daily streamflows that exceed base flow but are less than 100,000 acre-ft/yr (138 ft³/s). Infrequent, extreme flood events with streamflows of more than 100,000 acre-ft/yr likely do not infiltrate the Amargosa River channel. Instead, this runoff flows downstream of Saratoga Springs topographic basin and floods the Death Valley floor with large volumes of water during extreme events (DeMeo and others, 2003). Recharge to Saratoga Spring topographic basin during flood events would average about 220 acre-ft/yr (0.3 ft³/s) if infiltration rates, computed as a percentage of streamflow, in the Amargosa River channel are similar to measured infiltration in Fortymile Wash (Savard, 1998).

Additional sources of water to the Saratoga Spring area are local recharge and subsurface bedrock leakage to basin fill. The Saratoga Spring topographic basin is 220,000 acres in size. The annual precipitation volume totals 23,000 acre-ft for precipitation rates that exceed 0.4 ft/yr from the 1981–2010 Precipitation-elevation Regressions on Independent slopes Model (PRISM) precipitation distribution (PRISM Climate Group, 2012). A local Maxey-Eakin relation estimates recharge as 0.9 percent of annual precipitation volume in excess of 0.4 ft/yr (Fenelon and others, 2016) or 200 acre-ft. Subsurface bedrock leakage from surrounding low-permeability rocks to basin fill is less than 50 acre-ft/yr assuming a transmissivity of less than 5 ft²/d, a width of 10 mi, and a gradient of 100 ft/mi.

Previous predevelopment discharge estimates from Saratoga Spring have differed by an order of magnitude, but primarily resulted from different areas being labeled Saratoga Spring. Saratoga Spring initially was identified as an area of 23 acres that discharges 200 acre-ft/yr (Kunkel and Robinson, 1966) and is discussed as Saratoga Pools in this report (fig. 14). Saratoga Spring also has been identified as a much larger area consisting of Saratoga Pools and mapped ET units

(Faunt, Blainey, and others, 2010, p. 269, table F-4). Reported discharge from the larger Saratoga Spring area totaled 2,460 acre-ft/yr (Faunt, Blainey, and others, 2010), which was estimated with remote sensing and extrapolated ET_{GW} rates (DeMeo, and others, 2003). This estimate was biased high and likely occurred because ET_{GW} rates were extrapolated from areas with denser vegetation than in the Saratoga Spring area.

Discharge from Saratoga Pools totaled 150 acre-ft/yr in this investigation. Kunkel and Robinson (1966) overestimated discharge (200 acre-ft/yr) from Saratoga Pools by applying an ET_{GW} rate of 13 ft/yr to reeds, whereas rates of 8 ft/yr are more likely (Laczniaik and others, 1999). DeMeo and others (2003) underestimated discharge (50 acre-ft/yr) from Saratoga Pools because about 13 acres of open water and reeds were not mapped. Discharge from Saratoga Pools was corrected in this investigation by assigning an ET_{GW} rate of 8 ft/yr to the unmapped 13 acres, which increased total discharge from Saratoga Pools from 50 to 150 acre-ft/yr.

Predevelopment discharge from the Saratoga Spring area totaled 800–1,200 acre-ft/yr from a local water budget, and net discharge was less than 400 acre-ft/yr (table 4). Discharge from Saratoga Spring topographic basin was estimated by summing estimated inputs (recharge) and assuming that discharge equaled recharge. Minimum discharge was supported mostly by 720 acre-ft/yr of base flow infiltrating the Amargosa River channel downstream of Dumont Dunes, California (USGS streamgage 10251375). Estimated recharge from flood events (220 acre-ft/yr), local recharge (200 acre-ft/yr), and subsurface bedrock leakage (50 acre-ft/yr) is uncertain, but minor compared to base-flow infiltration. Because the 720 acre-ft/yr of base-flow infiltration is derived from springs and seeps along the Amargosa River between Shoshone and Tecopa, including base-flow infiltration in the Saratoga Spring water budget would result in double-counting of groundwater between Lower Amargosa and Saratoga Spring discharge areas. Subtracting base-flow infiltration results in a net discharge of less than 400 acre-ft/yr for the Saratoga Spring area.

Recharge

Recharge is spatially and temporally variable in the study area. Spatially varying recharge is dependent on unsaturated zone depth, hydraulic conductivities of unsaturated and saturated rocks, and the distribution of precipitation, where higher altitudes receive more precipitation. Time-varying, or episodic, recharge is precipitation-derived and occurs during brief intermittent periods that cause distinct water-level rises in well hydrographs. Conceptual models of spatial and temporal recharge in the study area are discussed in the following sections.

Spatially Distributed Long-Term Rates

A recharge distribution was estimated for the study area based on a conceptual model of water availability and permeability of rocks in recharge areas. Rates of infiltration below the root zone were assumed related to precipitation rates and increased as precipitation rates increased. Recharge rates were assumed equal to infiltration rates below the root zone, except where runoff occurs from surface-water flow or subsurface flow. Precipitation-runoff (surface-water flow) occurs when snowmelt runoff or high-intensity rainfall flows downgradient from low-permeability rocks in highland areas and infiltrates adjacent, permeable, alluvial-fan deposits or basin fill in ephemeral channels. Subsurface flow occurs when discontinuous low-permeability rocks form perched intervals above the regional water table. Subsurface flow is assumed to move laterally within the perched system until sufficiently permeable, saturated rocks of the regional system are encountered that can be recharged by the infiltrated water.

The conceptual model of total annual recharge to the study area is a modified Maxey-Eakin (Maxey and Eakin, 1951) approach that honors the annual predevelopment discharge, which ranges from 53,600 to 54,900 acre-ft/yr (table 4). Distributed recharge is conceptualized as a piecewise linear function of total annual precipitation, as defined by the 1981–2010 PRISM precipitation distribution (PRISM Climate Group, 2012). A three-stage relation is assumed to exist between precipitation and total potential recharge. Potential recharge includes in-place infiltration, precipitation-runoff, and runoff by subsurface flow. The assumed relation exists for a precipitation rate of 0.3–2.5 ft/yr, which is the range of annual precipitation estimates in the study area (fig. 15). The water available for recharge was estimated from precipitation, where stages are demarcated by inflection points at annual precipitation rates of 1.0 and 1.5 ft/yr (fig. 15A). Proportions of recharge increase from 0 to 0.9, 0.9 to 4.6, and 4.6 to 41 percent of annual precipitation in the ranges 0.3–1.0, 1.0–1.5, and 1.5–2.5 ft/yr of precipitation. Relations between total conceptual recharge and precipitation in excess of 1.0 and 1.5 ft/yr were adjusted for each groundwater basin so that the cumulative volume of annual recharge equaled net discharge from each groundwater basin and the study area as a whole.

The three-stage relation approximates conceptual differences in water availability even if the inflection points of 1.0 and 1.5 ft/yr for changes in slope are arbitrary. Infiltration of runoff from summer storms is the primary mechanism for generating recharge at low elevations, where precipitation rates are less than 1 ft/yr. Summer storms occur infrequently and much of the water is lost to ET, resulting in a low ratio of precipitation converted to recharge. About 20 percent (12,000 acre-ft/yr) of the total recharge in the study area occurs in areas with precipitation rates of less than 1 ft/yr (fig. 15B). At higher altitudes where precipitation rates are more than 1 ft/yr, winter snowpack generates most of the recharge and a higher ratio of the precipitation is converted to recharge. Efficiencies increase where precipitation rates are more than 1.5 ft/yr

because ET losses decrease as altitude increases. All water that infiltrates below the root zone is assumed to migrate to the water table in the absence of low-permeability bedrock at the water table.

Except for surface-water channels, recharge is assumed not to occur on valley floors (French and others, 1996), which were defined as areas with land-surface slopes less than 1.5 percent. The valley floors have clay-rich soils, low precipitation rates, and warm air temperatures, which promote retention of soil water and ET.

Recharge volumes are limited where hydraulic conductivity of bedrock is less than infiltration rates. Recharge rates cannot exceed hydraulic conductivity of saturated rocks, which results in excess infiltration being displaced laterally downgradient (Fenelon and others, 2008) in Cactus, Kawich, Belted, Groom, Eleana, and Greenwater Ranges and areas of the Spring Mountains (fig. 16).

Precipitation-Runoff

Infiltration is limited where low-permeability rocks occur at land surface and precipitation-runoff flows laterally downgradient until more permeable rocks are encountered. Recharge rates of 0.004 ft/yr (0.00001 ft/d) were assumed for low-permeability bedrock and excess infiltration was displaced downgradient to where more permeable rocks could accept the water. The excess infiltration available for recharge from precipitation-runoff was halved and then applied to permeable rocks because additional evaporative losses occur in alluvial channels.

Focused recharge occurs beneath channels of the Amargosa River and Fortymile Wash during infrequent flood events (fig. 16). Annual volumes of infiltration have been estimated for reaches of the Amargosa River from Beatty to the central Amargosa Desert, from Eagle Mountain to Shoshone, and from Dumont Dunes to the Saratoga Spring area. Infiltration to the Amargosa River from Beatty to the central Amargosa Desert ranges from 80 to 100 acre-ft/yr² (Stonestrom and others, 2007). Infiltration to the Amargosa River from Eagle Mountain to Shoshone is less than 700 acre-ft/yr (Osterkamp and others, 1994). Infiltration to the Amargosa River from Dumont Dunes to the Saratoga Spring area totals 920 acre-ft/yr, where about 720 acre-ft/yr is reinfiltreated groundwater that originally discharged into the Amargosa River upstream of Dumont Dunes, California (USGS streamgage 10251375). Infiltration estimates to Fortymile Wash plausibly are about 900 acre-ft/yr (Osterkamp and others, 1994) and have ranged from 90 to 6,550 acre-ft/yr (Czarnecki and Waddell, 1984; French and others, 1996; Savard, 1998).

² Infiltration rates were miscalculated in Stonestrom and others (2007) because recharge-rate fractions of 12 and 15 percent were multiplied by the 4-year (1998–2001) total of streamflow from table 3 of that report, rather than by the annual average streamflow.




Figure 15. Relation between precipitation rate and (A) conceptual recharge rate from infiltration and runoff to the study area, and (B) cumulative recharge resulting from this relation, in the study area, Nevada and California.

Perched and Semi-Perched Groundwater

Infiltrated water moves laterally in the subsurface where more permeable rocks permit infiltration near land surface and less permeable rocks at depth limit recharge, resulting in perched or semi-perched conditions. Perched groundwater is a localized, unconfined, saturated volume of groundwater that is separated from the underlying regional groundwater system by an unsaturated zone of discontinuous low-permeability rocks. Semi-perched groundwater is similar to perched groundwater, except that the discontinuous low-permeability rocks are saturated. Perched (and semi-perched) intervals impede infiltration because vertical hydraulic conductivities of underlying low-permeability rocks are less than local infiltration rates, which impounds water and laterally diverts flow. Subsurface flow moves downgradient atop discontinuous low-permeability rocks until permeable saturated rocks of the regional groundwater system are encountered. Perched and semi-perched intervals conceptually redistribute recharge, with less recharge beneath and more at the peripheries of the perched and semi-perched intervals. Recharge rates of 0.004 ft/yr (0.00001 ft/d) were assumed for low-permeability bedrock and excess infiltration from subsurface flow was displaced downgradient to where more permeable rocks could accept the water.

In this investigation, the water table encompasses the uppermost occurrence of saturation, which includes perched and semi-perched intervals. Inclusion of perched and semi-perched intervals affects conceptual models of recharge and is a practical necessity to simulate advective flow from the locations of nuclear tests beneath Rainier Mesa (U.S. Department of Energy, 2018). Advective movement from Rainier Mesa cannot be addressed if the locations of nuclear tests are not in the groundwater model of the study area.

Temporal Variability

Predevelopment conditions are analyzed as steady state in this investigation, which assumes recharge and natural discharge differ negligibly. This steady-state assumption is true if time-varying recharge is averaged over centuries. A long-term average is used because multi-decade water-level rises in wells have resulted from short-term imbalances between recharge and discharge (Fenelon and Moreo, 2002; Elliott and Fenelon, 2010; Fenelon and others, 2012; Jackson and Fenelon, 2018). Short-term (decadal) water-level changes generally can be ignored because spatial gradients are affected minimally, and water-level changes from natural stresses are small relative to pumping effects. Water-level changes in *Devils Hole* and wells throughout the Ash Meadows discharge area were the exception because natural changes were similar in magnitude to pumping effects. These natural changes were simulated and differentiated analytically from pumping effects with water-level models (Halford and others, 2012). Natural water-level changes were not simulated numerically because hydraulic-property estimates would have been degraded.

A water-level model simulates measured water levels in a well by summing analytically solved water-level changes from recharge, natural discharge, and pumping. This technique has been used effectively by Jackson and Fenelon (2018) to determine stresses affecting water-level trends and can be used to subtract time-varying recharge from the water-level trend in a well. The water-level modeling approach requires a conceptual model of recharge to explain rising water-level trends based on recharge patterns in the study area.

A conceptual model of time-varying recharge and natural discharge was used to explain the behavior of water-level trends in the study area prior to development. Water levels fluctuate naturally in response to short-term (hourly to seasonal) hydrologic stresses; therefore, a sufficiently long timescale is required to achieve steady-state conditions. As a rule of thumb, small groundwater basins have short steady-state timescales, whereas large groundwater basins, such as those within the study area, have long steady-state timescales. Jackson and Fenelon (2018) assumed that steady-state conditions occur on a century timescale in the study area based on available water-level data. The conceptual model requires a long-term (century-scale) precipitation record to represent recharge patterns in the study area, and this precipitation record is used to construct a hypothetical water-level record to explain steady-state water-level trends.




Figure 16. Conceptual recharge distribution, in the study area, Nevada and California.

The conceptual model postulates that long-term water-level fluctuations in predevelopment groundwater systems indicate changes in storage that result from differences between recharge entering the system and discharge leaving the system. In the Great Basin and the study area, more specifically, most natural discharge occurs at springs, seeps, and phreatophyte areas distant from the recharge areas. This regional discharge is nearly constant from year to year because the regional gradient that controls changes in discharge is insensitive to local water-level fluctuations of less than 50 ft in recharge areas relative to greater than 1,000-ft-head differences along flow paths between recharge areas and distant discharge areas. Unlike discharge, recharge varies temporally, and is the primary cause of annual-to-decadal, water-level fluctuations in the aquifer, as measured in wells.

Recharge principally occurs during winter months between October and March, in years with greater-than-average precipitation. This is because minimal ET occurs during the winter, which allows infiltrating precipitation to exceed the storage capacity of the root zone and infiltrate below the root zone (Smith and others, 2017). More recharge also occurs during winter months because surface runoff is less in areas where snow falls, and the slow melting of snowpack allows more time for infiltration compared to relatively brief rainfall events. Stable-isotope analyses of precipitation and shallow groundwater at Rainier Mesa (Russell and others, 1987; Hershey and others, 2008) and the Spring Mountains (Winograd and others, 1998) have indicated that most recharge is derived from winter precipitation. During a winter with less-than-average to slightly above-average precipitation, infiltrating precipitation mostly or entirely contributes to the soil-moisture reservoir depleted by ET during the previous summer. In these years, little to no water infiltrates beyond the root zone. Following winters with greater-than-average precipitation (wet winters), snowmelt infiltrates the root zone, wetting the soil sufficiently to exceed its field capacity and allows percolation downward to recharge the groundwater system (Smith and others, 2017).

A simple conceptual model of steady discharge and episodic recharge explains expected water-level trends prior to groundwater development (Jackson and Fenelon, 2018). Discharges are conceptualized as steady because water-level gradients and regional discharges are relatively invariant between decades. Episodic recharge events are approximated with precipitation during winter months that exceeds a threshold. Estimated recharge events from the precipitation-threshold model were correlated with infiltration below the root zone. Winter precipitation greater than a defined threshold infiltrates below the root zone, passes through the unsaturated zone, and ultimately becomes recharge at the water table in the conceptual model (Smith and others, 2017).

A precipitation index of monthly precipitation for south-central Nevada (Western Regional Climate Center, 2016) was used to examine century-scale precipitation trends and resultant recharge trends. Although the precipitation index does not represent the true magnitude of precipitation in the study area, the relative patterns of wet and dry years in south-central Nevada are similar. Recharge is defined as winter precipitation in excess of a threshold that approximates the volume of the root zone. This simple water balance assumes that all moisture evaporates from the root zone prior to October of each year. In the example for south-central Nevada, excess winter precipitation (recharge) during wet winters is defined as 125 percent of the long-term average (1900–2016), where long-term average precipitation is 4.8 in. (fig. 17A). A threshold of 125 percent (6 in.) resulted in the occurrence of wet winters about 20 percent of the time from 1900 to 2016 (fig. 17B). Notably, wet conditions after 1968 generated nearly 70 percent of the recharge for the 117-year period. The 125-percent threshold used is arbitrary. Thresholds of 100 or 150 percent of the long-term average produce similar long-term recharge patterns.

Jackson and Fenelon (2018) derived a hypothetical long-term water-level record to explain expected steady-state water-level trends in the study area. The hypothetical water-level record is the sum of two components: water-level change resulting from recharge and water-level change resulting from aquifer discharge. The water-level change from recharge was calculated as the sum of excess winter precipitation using a 125-percent threshold divided by an effective porosity of 10 percent. Selection of a larger or smaller effective porosity would result in a smaller or larger magnitude of water-level change, respectively. However, the hypothetical water-level trend would remain unchanged. Cumulative water-level increase from recharge equals about 30 ft over 117 years. Cumulative aquifer discharge was assumed equal in magnitude to cumulative recharge during the 117-year period; therefore, water-levels declined 0.26 ft/yr from discharge. Hypothetical water levels declined prior to 1970 because aquifer discharge exceeded recharge during persistent dry conditions. Hypothetical water levels rose from 1970 to 2016 because recharge exceeded discharge in response to frequent wet winters (fig. 17).

In areas distant from groundwater development, the longest consistent water-level records (1990s to 2018) show that water levels have been rising in the study area and throughout southern Nevada (Fenelon and Moreo, 2002; Elliott and Fenelon, 2010; Fenelon and others, 2012; Jackson and Fenelon, 2018). For example, rising water-level trends are observed in well *U-19bk*, open to volcanic rocks in Pahute Mesa, and well *USFWS DR-1*, open to carbonate rocks near the Sheep Range (figs. 16 and 18).




Figure 17. Winter precipitation (October–March) and excess winter precipitation (recharge) using 125-percent threshold (A), and hypothetical water-level change under predevelopment (steady-state) conditions (B), in the study area, Nevada and California, 1900–2016. Threshold of 125 percent of long-term average is an arbitrary threshold used to designate a “wet winter.” Hypothetical water-level change under predevelopment conditions is the sum of cumulative recharge from 1900 to 2016 and constant discharge. Precipitation data from south-central Nevada precipitation index (Western Regional Climate Center, 2016). DV3, Death Valley version 3. Figure modified from Jackson and Fenelon (2018).




Figure 18. Measured water levels and water-level models for wells *U-19bk* and *USFWS DR-1*, in the study area, Nevada and California, 1910–2018.

Water-level models show that rising trends in wells *U-19bk* and *USFWS DR-1* can be attributed to precipitation-derived recharge from a series of wet winters (Jackson and Fenelon, 2018). Water-level models simulated rising trends by fitting an analytical model of recharge and discharge to measured water levels. Recharge was simulated using winter precipitation (October–March) in excess of 6 in. from the south-central Nevada precipitation index (fig. 17AA). Discharge was assumed to be constant and was simulated as a linear decline. The fit of the water-level models to the measured data in wells *U-19bk* and *USFWS DR-1* compare favorably (fig. 18), indicating that rising trends can be explained by recharge and discharge. The poor fit in both models prior to 1996 is attributed to less accurate (± 1 ft) water-level measurements (Elliott and Fenelon, 2010).

Water levels in most, if not all, wells would have rising trends if groundwater development never occurred in the study area. Water levels in wells within pumping areas have declining trends because the magnitude of water-level decline from pumping has exceeded water-level rises from recharge.

Hydraulic Conductivity

Spatial variations in hydraulic conductivities of saturated rocks control water-level gradients and flow rates between recharge and discharge areas. Spatially distributed hydraulic conductivities must be estimated throughout the study area to simulate groundwater flow. The hydraulic-conductivity distribution encompasses the lateral and vertical extent of saturated rocks in the aquifer system.

Hydraulic conductivities are estimated indirectly from pumping aquifer tests. Each aquifer test is a controlled field experiment (Stallman, 1971) because water is pumped at a known rate and resulting water-level declines, or drawdowns, can be interpreted with an analytical or numerical model. Transmissivity estimates are the most prevalent and reliable aquifer-test result. Hydraulic conductivity equals transmissivity divided by aquifer thickness or well screen length. Aquifer thickness is assumed to be equal to well screen length in areas where transmissivity is less than 1,000 ft²/d or small volumes of water are pumped (less than 100,000 gal), whereas the aquifer thickness is used for saturated rocks where transmissivity exceeds 1,000 ft²/d or large volumes of water are pumped (more than 100,000 gal, such as pumping at 100 gal/min for 1 day) (Halford and others, 2006). Aquifer thickness frequently is unknown at a field site, which is a source of uncertainty; however, aquifer thickness is defined in a hydrogeologic framework model, which is based on geologic data and interpretations. Relating the product of groundwater-model-estimated hydraulic conductivities and assigned hydrogeologic framework model thicknesses to field-estimated transmissivities reduces this uncertainty.

Transmissivity estimates from aquifer tests can be extrapolated throughout the study area by correlating hydraulic conductivity with mappable hydrogeologic units. These hydrogeologic units theoretically have unique hydraulic variability or transport properties compared to other units (Mirus and others, 2016). Unique hydraulic variability within a hydrogeologic unit is defined as a hydrogeologic unit having a hydraulic-conductivity probability distribution that does not sufficiently overlap with the hydraulic-conductivity probability distributions of other hydrogeologic units.

More hydrogeologic units have been defined than can be supported hydrologically in previous studies (fig. 3). This was suggested by disagreement between estimated geometric mean hydraulic conductivities and their conceptual ranking, where geometric means indicate that some confining units are more permeable than aquifers (fig. 3). Furthermore, probability distributions of hydraulic conductivity significantly overlap between multiple hydrogeologic units, indicating non-uniqueness in hydraulic variability. Relations between geologic units, hydraulic conductivity, and transmissivity are examined so that resulting hydrogeologic units have unique hydraulic variability in this investigation.

Reducing the number of hydrogeologic units is practical for the stated purpose of this investigation. Numerous hydrogeologic units originally were defined within complex hydrostratigraphic frameworks to allow for comprehensive evaluation of uncertainty in radionuclide transport predictions. However, these framework models have more hydrogeologic units than are needed to calibrate groundwater models. More hydrogeologic units hinder the calibration process because of incomplete data and computational burden.

Field Estimates of Transmissivity

Transmissivity can be estimated from single-well or multiple-well aquifer tests and from specific capacities. Single-well aquifer tests include pumping tests and slug tests. Multiple-well aquifer tests involve pumping one well and measuring water levels within the pumped well and nearby observation wells. Specific capacity is the pumping rate divided by drawdown at an unspecified time.

In this report, the terms “borehole” and “well” have specific definitions. A borehole refers to the mapped (X,Y) location where a hole was drilled, and the borehole may have more than one well. A well is a single, temporary or permanent, screened (or open) completion in a borehole. Many wells in the study area have multiple reported transmissivity estimates because multiple aquifer tests occurred, or an aquifer test was analyzed by multiple investigators (Frus and Halford, 2018).

A single, representative transmissivity is estimated for each well in this investigation. Multiple-well aquifer test results are limited to a transmissivity that is attributed to the pumping well. In individual boreholes beneath Pahute Mesa, transmissivities were estimated from pumping aquifer tests, where the entire borehole was pumped, and from slug tests of 200-ft intervals of the open hole that were isolated with packers (Blankennagel and Weir, 1973). Transmissivities from only pumping aquifer tests were compared, where a pumping aquifer test and multiple slug tests occurred within a borehole. This was appropriate for characterization of geologic units and calibration of a regional groundwater model. Wells, construction, aquifer-test results, sources, and representative transmissivity estimates used in this study are summarized in Jackson and Halford (2020).

Transmissivities have been estimated from aquifer tests at 113 wells within the study area (fig. 19), where nearly all aquifer tests supported NNSS activities. Exploratory boreholes were drilled and tested in the 1960s primarily to identify low-permeability rocks suitable for the testing of nuclear devices underground (Blankennagel and Weir, 1973). Radionuclides potentially could migrate from underground nuclear tests and hydrologic studies began investigating potential migration within a few years of the first underground nuclear test in 1957 (Winograd and Thordarson, 1975, p. C1). Regional aquifers and confining units from Yucca Flat to the Ash Meadows discharge area were characterized with drilling and aquifer testing that included 10 wells completed in carbonate rocks (Winograd and Thordarson, 1975, p. C20). Aquifers and confining units in the nearby Yucca Mountain area also were characterized with drilling and aquifer testing for a proposed nuclear waste repository to store high-level radioactive waste and spent nuclear fuel (Craig and Robison, 1984). Additional wells have been drilled and tested for water supplies that supported NNSS operations. After nuclear testing ceased in 1992, most aquifer tests have supported subsurface characterization to better estimate potential migration of radionuclides for the U.S. Department of Energy UGTA activity.




Figure 19. Transmissivity estimates from single-well aquifer tests and specific capacity, in the study area, Nevada and California.

Transmissivity estimates characterize a volume of aquifer rather than a point. The volume of aquifer sampled generally is proportional to the volume of water pumped or displaced. For example, 2,400,000 gal were pumped from well *ER-20-7* (fig. 19) and drawdowns were detected as far away as 2 mi from the pumping well. Likewise, 7,000,000 gal were pumped from well *ER-EC-14 main lower zone* (fig. 19) and drawdowns were detected more than 4 mi from the pumping well. In a simplistic example, if it was assumed that the 4-mi drawdown distance in the latter aquifer test represented the radius of a spherical capture volume, then the transmissivity estimated from this test would characterize a 268-mi³ volume of aquifer. Of the 113 aquifer tests, 83 were pumping aquifer tests, where a median volume of 700,000 gal was pumped during each test (fig. 20).

Transmissivities from low-permeability units were estimated primarily with slug tests because only limited volumes of water could be removed. Transmissivities of 0.00002–1 ft²/d were estimated exclusively with slug tests. The median volume displaced from slug testing was about 400 gal (fig. 20), which is large relative to typical slug-test volumes of less than 1 gal. Relatively large displacement volumes resulted from initial displacements exceeding 1,000 ft (Frus and Halford, 2018) or evacuation of wells with diameters greater than 50 in. during slug tests. Recovery periods for many slug tests exceeded 1 year, with the longest period exceeding 20 years in well *U-15k Test Hole* (fig. 19). Investigated radial distances of slug tests remained considerably less than the influence of pumping aquifer tests (Frus and Halford, 2018). A transmissivity estimated from tidal-forcing of water levels in well *Inyo-BLM 1* (fig. 19; Cutillo and Bredehoeft, 2011) was classified as a slug test because less than 1 gal of water was displaced.

Transmissivity estimates from pumping aquifer tests in siliciclastic rocks and zeolitized tuffs likely represent permeable inclusions in otherwise low-permeability rocks. Biased results were suggested by transmissivity estimates decreasing during later analysis periods and locally inconsistent water levels. For example, well *ER-5-4-2* (fig. 19) is open to zeolitized tuff 4,850–7,000 ft below Frenchman Flat and 2,200,000 gal were pumped during a 10-day test. Transmissivities of 200 and 60 ft²/d were estimated during periods 0–1 and 2–6 days after pumping started, respectively, with Cooper-Jacob (1946) analyses. Transmissivities of 13 and 6 ft²/d were estimated during periods 0.3–4 and 4–15 years after pumping stopped, respectively, with Cooper-Jacob recovery analyses. The water-level altitude in well *ER-5-4-2* exceeds 2,480 ft, which is 70 and 90 ft higher than water-level altitudes in overlying basin fill and adjacent carbonate

rocks, respectively. The water-level altitude in well *ER-5-4-2* unlikely represents predevelopment conditions within the last 500 years and is best explained as incomplete drainage from past pluvial conditions. Sustaining 70- to 90-ft head differences during a 10,000-yr period of drainage requires an average hydraulic conductivity of less than 0.00001 ft/d, or 300 times less than the smallest estimate from the aquifer test, when converted to a hydraulic conductivity (0.003 ft/d).

Transmissivities also were estimated empirically from 158 specific-capacity estimates using a local power-law relation for Pahute Mesa (Frus and Halford, 2018). Transmissivity (foot squared per day) equaled 380 times specific capacity (gallons per minute per foot) and was developed with results from 39 Pahute Mesa pumping aquifer tests. Greater than 80 percent of 39 transmissivities estimated with the Pahute-Mesa relation were within a factor of five from aquifer-test results. The Pahute-Mesa relation *functionally* differs little from other empirical relations developed in California and northern Nevada (Thomasson and others, 1960; Yager and others, 2012). Greater than 70 percent of the 158 specific-capacity estimates sampled large volumes of aquifer because more than 100,000 gal were pumped (fig. 20).

Transmissivities outside the NNSS were estimated predominantly from specific capacities using well logs (Nevada Division of Water Resources, 2018). Reported pumping rates (gallons per minute) and water-level declines (feet) were used to minimize spurious specific-capacity estimates from domestic wells. For example, specific-capacity estimates were reported for 4,442 of 12,226 well logs in Pahrump Valley, where 3,582 wells had a reported pumping rate of 20 gal/min with a drawdown of 4 ft. To eliminate questionable specific-capacity estimates, wells with pumping rates less than 30 gal/min or water-level declines less than 10 ft were not used in this study, which reduced the number of specific-capacity estimates from 4,442 to about 300. The number of useful specific capacities declined from about 300 to 129, after each of the remaining well logs were read. Most of the specific capacities were rejected because bailed volumes were reported as pumping rates, such as the removal of 5 gal of water being reported as a pumping rate of 5 gal/min. The 129 specific-capacity estimates primarily were from irrigation wells in the central Amargosa Desert and Pahrump Valley (fig. 19). The 129 specific-capacity estimates were computed from pumping rates that averaged 700 gal/min, with a maximum of 3,500 gal/min. Specific capacities ranged from 0.01 to 400 gal/min/ft and transmissivities from specific capacities ranged from 4 to 160,000 ft²/d.




Figure 20. Volume of water pumped or displaced from single-well aquifer tests (pumping and slug tests) and specific capacity, in the study area, Nevada and California.

Transmissivity and Rock Type

Relations between transmissivity and rock type were investigated using four broad categories that group previously defined hydrogeologic units from DVRFS.v2 (table 6). Previous investigations (fig. 3) and limited data for some hydrogeologic units suggest that only four broad categories of rock type can be related to transmissivity: (1) carbonate rocks; (2) volcanic rocks; (3) basin fill; and (4) low-permeability rocks. Carbonate rocks were not further subdivided because few wells penetrate the localized, upper carbonate aquifer. Volcanic rocks were not subdivided because distributions of log-hydraulic conductivity were similar in younger volcanic and Tertiary volcanic units (fig. 3). Probability distributions overlapped considerably where the Tertiary volcanic unit was differentiated into eight hydrogeologic units (Belcher and others, 2002; p. 12). Log-hydraulic conductivity distributions of alluvial aquifer and alluvial confining unit differed little (fig. 3); therefore, units were grouped into a single category of basin fill. Low-permeability rocks consist of granitic rocks, siliciclastic rocks, and older volcanic rocks, which form the basement of the study area. Low-permeability rocks were not further subdivided because there were only a small number of transmissivity estimates.

Log-transmissivity distributions for carbonate rocks, volcanic rocks, basin fill, and low-permeability rocks do not sufficiently overlap, indicating hydraulic uniqueness (fig. 21). Median transmissivities of carbonate rocks, volcanic

rocks, and basin fill are all near 1,000 ft²/d but variability differs markedly. Transmissivity of basin fill was the most predictable, with a 95-percent confidence interval that ranged from 40 to 20,000 ft²/d. Transmissivity of volcanic rocks was the least predictable, with a 95-percent confidence interval that ranged from 0.006 to 60,000 ft²/d. Rock type most reliably establishes a maximum transmissivity that likely would be present at a site (fig. 21). Transmissivity estimates were analyzed, in preference to hydraulic conductivity, because contributing aquifer thickness generally was unknown.

Transmissivity and Thickness

Thickness and transmissivity are not correlated regardless of definition of thickness or rock type (fig. 22). Thickness alternatively was defined by length of open interval or thickness of rock type penetrated by the well. Thicknesses of rock types were the summation of hydrogeologic unit thicknesses for each rock type from the DVRFS.v2 hydrogeologic framework (Belcher and others, 2017). Observed rock types in 25 of 271 wells were misclassified in the hydrogeologic framework. Misclassification errors occurred too infrequently to explain the lack of correlation. Spatial variability in transmissivity can be attributed almost exclusively to variability in hydraulic conductivity. This suggests that refining thicknesses of hydrogeologic units further will minimally benefit future hydrologic investigations.


Table 6. Relation between simple-rock types and previously defined hydrogeologic units in the Death Valley Regional Flow System version 2 model (DVRFS.v2) hydrogeologic framework, Nevada and California.

[Source: Belcher and others (2017)]

Rock type	DVRFS.v2 abbreviation	DVRFS.v2 hydrogeologic unit
Carbonate rocks	UCA	Upper carbonate-rock aquifer
	LCA T1	Lower carbonate-rock aquifer (thrust)
	LCA	Lower carbonate-rock aquifer
Volcanic rocks	LFU	Lava-flow unit
	YVU	Younger volcanic-rock unit
	TMVA	Thirsty Canyon-Timber Mountain volcanic-rock aquifer
	PVA	Paintbrush volcanic-rock aquifer
	CHVU	Calico Hills volcanic-rock unit
	WVU	Wahmonie volcanic-rock unit
	CFPPA	Crater Flat-Prow Pass aquifer
	CFBCU	Crater Flat-Bullfrog confining unit
	CFTA	Crater Flat-Tram aquifer
	BRU	Belted Range unit
Basin fill	YAA	Younger alluvial aquifer
	YACU	Younger alluvial confining unit
	OAA	Older alluvial aquifer
	OACU	Older alluvial confining unit
	LA	Limestone aquifer
	VSU upper	Upper volcanic-sedimentary rock unit
Low-permeability rocks	OVU	Older volcanic-rock unit
	VSU lower	Lower volcanic-sedimentary rock unit
	ICU	Intrusive-rock confining unit
	SCU	Sedimentary-rock confining unit
	UCCU	Upper clastic-rock confining unit
	LCCU T1	Lower clastic-rock confining unit (thrust)
	LCCU	Lower clastic-rock confining unit
	XCU	Crystalline-rock confining unit

Basin fill in the Amargosa Desert was differentiated previously for the stated reason of “...*improved understanding of the hydrogeologic system.*” (Taylor and Sweetkind, 2014, p. 1.) Grain size, sorting, and texture were inferred from 210 drillers’ logs to define 28 unique lithologic classes. These refined lithologic classes replaced previously defined basin-fill hydrogeologic units in the DVRFS.v2 model and were assigned relative permeabilities of low, moderately low, or high (Belcher and others, 2017, p. 13). High-permeability classes were composed of gravel, sand, or freshwater limestone, which presumably would be correlated with high specific capacities or transmissivities. Specific capacities were reported on 50 of the drillers’ logs and used to test the hydrologic utility of finely differentiating basin fill.

Finely differentiated basin fills poorly predicted specific capacities in the Amargosa Desert, regardless of how permeable classes were assigned (fig. 23). High permeability from Belcher and others (2017, p. 13) defined a test group. A second test group combined all classes dominated by gravel or sand. Effective thicknesses of each of the 24 lithologic classes were estimated independently in a third test group, where the effective thickness was the coarse-grained fraction of the saturated thickness. Coefficient of determination (r^2) was less than 0.01 regardless of whether thicknesses were compared to specific capacities or log-specific capacities. Independently estimating an effective thickness for each of 24 classes improved r^2 to 0.39, but the results were nonsensical. This was because specific capacity increased as effective thickness of permeable sediments decreased (fig. 23).



Note: Number of transmissivity estimates for each rock type is shown in parentheses.

Figure 21. Minimum, maximum, median, and 95-percent confidence interval of log-transmissivities in four rock-type categories from 271 field estimates of transmissivity, in the study area, Nevada and California.

Hydraulic Conductivity and Depth

Hydraulic conductivity is distributed heterogeneously with depth in carbonate and volcanic rocks, where few permeable intervals contribute most of the transmissivity in a well. Few flowing intervals have been detected with flow logs in carbonate rocks beneath Yucca Flat in wells *ER-6-1-2 main* (Garcia and others, 2010), *ER-6-2* (Stoller-Navarro Joint Venture, 2005a), and *UE-10j* (2232-2297 ft) (IT Corporation, 1995) (fig. 19). About 10 percent of the combined 3,200 ft of saturated thickness from the three wells contributed greater than 80 percent of flow. Depth-dependent variations in volcanic rocks beneath Pahute Mesa are well defined in 17 boreholes, where these boreholes have an average depth of 6,200 ft below land surface (Blankennagel and Weir, 1973). For each of these boreholes, interval transmissivities were estimated from packer testing 200-ft intervals and total transmissivities were defined by pumping aquifer tests. Most of the permeability occurred in about 2 percent of 74,800 ft of saturated borehole that was tested (Frus and Halford, 2018). Hydraulic variations are consistent with complex bedded and fractured rocks, which have been observed in boreholes and

outcrops in the study area (Sweetkind and others, 2010, p. 71). These observable hydraulic and structural heterogeneities cannot be represented adequately by simulating groundwater flow through thick, homogeneous, hydrogeologic units.

Greater than 90 percent of estimated hydraulic conductivity in carbonate and volcanic rocks occurs within 1,600 ft (500 m) of the water table (fig. 24). To estimate hydraulic conductivity with depth, transmissivities from pumping aquifer tests were binned into 330-ft (100-m) saturated intervals of the wells for consistency in comparing carbonate and volcanic rocks. For example, consider a well open to 2,000 ft of carbonate rocks with a transmissivity of 1,000 ft²/d. The 2,000 ft saturated open interval would be binned into six 330-ft saturated intervals, where each interval would have a hydraulic conductivity of about 0.5 ft/d. Transmissivity was distributed uniformly across open intervals in carbonate rocks because depth-dependent contributions were unknown in 23 of 26 wells. However, depth-dependent contributions have been estimated in volcanic rocks (Frus and Halford, 2018) and distributed accordingly. Interval-averaged hydraulic conductivity was the average transmissivity in each interval divided by interval thickness (fig. 24).




Figure 22. Relation between transmissivity and thickness of carbonate rocks, volcanic rocks, basin fill, and low-permeability rocks, in the study area, Nevada and California.




Figure 23. Relation between specific capacity and thickness of basin fill classified as permeable in the Amargosa Desert, Nevada.

Hydraulic conductivity does not decrease smoothly as a function of depth below land surface as conceptualized in depth-decay models. These models assume that permeability decreases with depth as geostatic and hydrostatic load increases, which decreases widths of pore spaces and fracture apertures. Hydraulic conductivity previously has been correlated weakly with depth below land surface, where average hydraulic conductivity decreased by an order of magnitude with a 2,300-ft decrease in depth below land surface (Stoller-Navarro Joint Venture, 2004a, p. 5-30). The weak correlation had no predictive value because individual hydraulic-conductivity estimates ranged from 0.02 to 100,000 ft/d within 2,300 ft of land surface (Stoller-Navarro Joint Venture, 2004a, p. 5-28). Unpredictable hydraulic-conductivity variations at depth differences of less than 2,000 ft below the water table and less than 5,000 ft below land surface are consistent with previous observations in carbonate rocks (Winograd and Thordarson, 1975, p. C20) and volcanic

rocks (Blankennagel and Weir, 1973). Previous groundwater models in the study area (Belcher, 2004; Stoller-Navarro Joint Venture, 2009; Navarro-Intera, LLC, 2013; Belcher and others, 2017) have simulated vertical variations in hydraulic conductivity with depth-decay models despite available data.

Carbonate and volcanic rocks can be divided into shallow and deep rocks as an alternative to a depth-decay model. The division between shallow and deep rocks at 1,600 ft (500 m) below the water table is supported by depth-dependent hydraulic-conductivity data (fig. 24). Transmissive shallow rocks transmit most of the groundwater between recharge and discharge areas, whereas deep rocks have low-permeability and transmit a small component of the flow. The shallow-deep concept does not negate part of the groundwater budget because all flow from the active part of the groundwater system is included. The shallow-deep concept has been used previously within the study area (Fenelon and others, 2008, 2010, 2012).




Figure 24. Average, depth-dependent hydraulic conductivity in volcanic and carbonate rocks, in the study area, Nevada and California.

The limited number of deep carbonate wells does not negate the concept of low-permeability carbonate rocks more than 1,600 ft below the water table. Six wells were completed in carbonate rocks at depths greater than 1,600 feet below the water table. Transmissivities in deep carbonate rocks ranged from 2 to 2,200 ft²/d and averaged 10 times less than transmissivities in shallow carbonate rocks. Wells *ER-5-3-2*, *Inyo-BLM 1*, and *UE-25p1 (JF-2a)* (fig. 19) were drilled to test the concept of transmissive carbonate rocks at depth. However, the carbonate rocks encountered by these wells were not very transmissive, with transmissivities of 100–900 ft²/d. Wells *ER-5-4-2*, *ER-8-1 (recompleted)*, and *Inyo-BLM 2* (fig. 19) targeted, but never penetrated, transmissive carbonate rocks, and encountered low-permeability volcanic and granitic rocks. Although a rigorous evaluation of deep carbonate rocks is not possible, failed attempts to find transmissive intervals in deep carbonate rocks support the shallow-deep concept. The shallow-deep concept is supported by the substantial decrease in hydraulic conductivity with depth in 17 Pahute Mesa boreholes, where 16 of the 17 boreholes were completed in volcanic rocks at depths greater than 1,600 ft below the water table (fig. 24).

Hydrogeologic Framework

The hydrogeologic framework of the DV3 project is a simplification of the hydrogeologic framework from the DVRFS.v2 project (Belcher and others, 2017). The DVRFS.v2 hydrogeologic framework integrates a regional hydrogeologic framework with CAU-scale frameworks for Frenchman Flat (Bechtel Nevada, 2005a), Yucca Flat–Climax Mine (Bechtel Nevada, 2006; Fenelon and others, 2012), Rainier Mesa–Shoshone Mountain (National Security Technologies, LLC, 2007; Fenelon and others, 2008), and Pahute Mesa (Bechtel Nevada, 2002; Garcia and others, 2017). The DV3 hydrogeologic framework simplifies the DVRFS.v2 hydrogeologic framework (Belcher and others, 2017) by grouping hydraulically similar hydrogeologic units and limiting vertical discretization.

Unlike the DVRFS.v2 hydrogeologic framework, the DV3 hydrogeologic framework included hydrologically mandated features and incorporated revisions to frameworks for Frenchman Flat, Yucca Flat–Climax Mine, and Rainier Mesa–Shoshone Mountain CAUs. An example of including a hydrologically mandated feature is explicitly mapping Furnace Creek Wash in the DV3 hydrogeologic framework. The DVRFS.v2 framework, polygons for modifying hydrogeologic unit extents by DV3 model layer, and the DV3 framework are available in Jackson and Halford (2020).

Discretization

The DV3 hydrogeologic framework grid is consistent with the numerical grid used in the groundwater models created for the DV3 project. The hydrogeologic framework for the DV3 project extends from the water table to 3,280 ft (1,000 m) below the National Geodetic Vertical Datum of 1929 (NGVD 29), which encompasses all rocks with considerable permeability. This volume was discretized laterally into 268 rows of 221 columns of variably spaced, rectangular cells that ranged from 820 ft (250 m) to 4,920 ft (1,500 m) on a side. The volume was discretized vertically with deformed layers, where each cell was assigned a unique hydrogeologic unit. Hydraulically similar rock types with depth and computed vertical hydraulic gradients indicated that known gradients and hydrologic conditions can be simulated sufficiently with five layers.

Water-Table Surface

The DV3 hydrogeologic framework was developed to distribute hydraulic properties within the saturated rocks in the groundwater-flow models. The top of the hydrogeologic framework is the water table. In this report, the water table encompasses the uppermost occurrence of saturation, which includes perched intervals. The water-table surface was estimated from potentiometric maps and water levels in low-permeability ranges (IT Corporation, 1997; Fenelon and others, 2008, 2010, 2016).

The top of the saturated flow system in the DVRFS. v2 project was defined differently than in the DV3 project (fig. 25). An undefined “idealized” potentiometric surface was the top of the saturated flow system in the DVRFS.v2 project (Belcher and others, 2017, p. 17) that excluded higher altitudes of saturation in low-permeability ranges. Compared to the DVRFS.v2 project, the top of saturation of the DV3 framework is 1,000 to 3,200 ft higher (fig. 25). Using the uppermost occurrence of saturation as the top surface of the DV3 hydrogeologic framework allowed for the simulation of major groundwater divides in the groundwater models. Unlike the DVRFS.v2 project, groundwater divides can be represented in the DV3 project in Bare Mountain, Eleana Ridge, north of Climax Mine, Skull Mountain, Sheep Range, Greenwater Range, and Black Mountains (fig. 25). Inclusion of perched groundwater also allowed for the simulation of advective flow from nuclear test locations in Rainier Mesa and Shoshone Mountain, which were detonated within the perched system (fig. 25).

Vertical Discretization

Vertical discretization of the DV3 hydrogeologic framework was the same as the groundwater-flow model. This differed from the DVRFS.v2 hydrogeologic framework, which was discretized independently of the groundwater-flow model grid. Hydrogeologic units were distributed in the DVRFS.v2 framework by specifying tops and thicknesses. This permitted multiple hydrogeologic units to be present in each model cell. Hydraulic conductivities distributed with the DVRFS.v2 hydrogeologic framework were translated to the groundwater model grid with the Hydrogeologic-Unit Flow (HUF) package of MODFLOW—a USGS modular hydrologic model software (Anderman and Hill, 2000). In each groundwater model cell, hydraulic conductivities from multiple hydrogeologic units were reduced to an equivalent hydraulic conductivity by assuming parallel flow in the horizontal direction and series flow in the vertical direction between hydrogeologic units.

The strength of the HUF package is the ability to use a hydrogeologic framework that has a different spatial discretization from the groundwater model. However, this strength is also a weakness because using different spatial grids introduces (sometimes unwarranted) complexity and can easily cause errors if not implemented correctly. When multiple hydrogeologic units occupy a MODFLOW model cell, the estimated effective hydraulic conductivity does not provide information on the hydrogeologic units that are behaving as aquifers or confining units. Parallel and series flow assumptions for computing equivalent hydraulic conductivities fail where dips of hydrogeologic-unit contacts and MODFLOW model layers depart more than a few degrees. This can transpose conceptual flow barriers and conduits in the groundwater model. Specifying tops and thicknesses of hydrogeologic units in the HUF package also can erroneously allow multiple hydrogeologic units to occupy identical volumes of aquifer, which is physically impossible and not checked by the HUF package.

The DV3 hydrogeologic framework was developed by first mapping hydrogeologic units from the DVRFS.v2 framework (Belcher and others, 2017) to an intermediate grid. The intermediate grid was discretized vertically into uniform 164-ft-thick (50-m-thick) layers. This assured that the volumes of the individual units would sum correctly to the total volume of the framework. The thickest hydrogeologic unit in each 164-ft-thick cell was assigned to the cell. Hydrogeologic unit assignment was altered minimally because less than 3 percent of the 164-ft-thick cells were intersected by more than one of the original hydrogeologic units from the DVRFS.v2 framework.




Figure 25. Differences in the water-table surface between the Death Valley version 3 (DV3) and Death Valley Regional Flow System version 2 (DVRFS.v2) hydrogeologic framework, and areas where the DVRFS.v2 hydrogeologic framework was modified, in the study area, Nevada and California. See figure 26 for cross section A–A'.

Faults

Faults and caldera margins have been conceptualized as forming barriers or conduits to groundwater flow. Few geologic structures have sufficient hydraulic information to determine their behavior as a barrier or conduit. For example, lithologic data and aquifer-test results indicate that the Gravity fault (fig. 5) forms a hydraulic barrier (Dudley and Larson, 1976). The Gravity fault causes groundwater to move from underlying carbonate rocks into overlying basin fill and discharge at land surface from spring pools in the Ash Meadows discharge area (Laczniak and others, 1999). The northern part of the Timber Mountain caldera complex (fig. 5) is a transmissive feature, with transmissivities exceeding 100,000 ft²/d (Garcia and others, 2017). The southern part of the Claim Canyon caldera (fig. 5) likely forms a hydraulic barrier, as indicated by the steepening of lateral hydraulic gradients between Timber Mountain and Yucca Mountain (IT Corporation, 1999; Fenelon and others, 2010, plate 3; Navarro-Intera, LLC, 2013). Attributing these hydraulic properties to caldera margins or adjacent rocks remains ambiguous.

Many faults are not hydraulically distinct from adjacent host rocks and have no direct hydraulic significance. Yucca fault (fig. 5) has been conceptualized as a conduit to groundwater flow in a local-scale CAU model of the carbonate aquifer beneath Yucca Flat (Navarro-Intera, LLC, 2013). However, drawdown analyses from multiple-well aquifer tests in wells *ER-6-1-2 main* (fig. 25; Jackson and Halford, 2019) and *ER-4-1 m1* (fig. 25; Jackson, 2017) showed that pumping signals propagated across Yucca fault. The calibrated Yucca Flat CAU model of the carbonate aquifer also interpreted Yucca fault as an inconsequential hydraulic feature (Navarro-Intera, LLC, 2013). In another example, the West Greeley fault in Pahute Mesa has been conceptualized as a conduit for groundwater flow and radionuclide transport (Stoller-Navarro Joint Venture, 2009). This interpretation was tested during analysis of a multiple-well aquifer test in well *U-20 WW (cased)* (fig. 25), and results showed that estimated hydraulic conductivities of the fault were similar to those of the surrounding volcanic rocks, indicating that West Greeley fault is neither a conduit nor barrier to flow (Garcia and others, 2011).

Faults were implemented explicitly by the offset of juxtaposed hydrogeologic units in the DV3 framework. Juxtaposition of a low-permeability hydrogeologic unit against a permeable unit causes a fault to function as a hydraulic barrier. Juxtaposition of permeable units along a fault allows for the movement of groundwater flow across the fault. Behavior of a fault as a barrier or conduit to groundwater flow

was determined during calibration of the DV3 model by fitting simulated results to predevelopment water levels, water-level declines from pumping, and aquifer-test results.

Hydrogeologic Units

The DV3 framework was divided into ten hydrogeologic units (table 7) based on rock type, depth, and previously defined hydrogeologic units from the DVRFS.v2 project (table 6). Hydrogeologic units were consolidated initially for this study into four rock types (fig. 21). Two of the rock types contain thick sequences of carbonate and volcanic rocks, which were divided in the DV3 framework into shallow and deep intervals at 1,600 ft (500 m) below the water table based on analysis of hydraulic conductivity with depth (fig. 24). The *shallow-deep* concept (see section, “[Hydraulic Conductivity and Depth](#)”) was used as an alternative to a depth-decay model. Shallow carbonate rocks were further subdivided by separating Pennsylvanian (UCA, upper carbonate-rock aquifer) and fault-thrusted [*LCA_T1*, lower carbonate-rock aquifer (thrusted)] carbonate rocks, which have low permeabilities, from other carbonate rocks in the shallow interval so that expected transmissivity contrasts could be simulated (table 7). Deep volcanic rocks are relatively impermeable and were included in the low-permeability rock type (table 7). For example, transmissivity was 30 ft²/d around well *UE-20f (4456-13686 ft)* in deep volcanic rocks, or an average hydraulic conductivity of 0.003 ft/d (fig. 19).

Basin fill was differentiated into shallow and deep intervals to accommodate known hydrologic variability in the central Amargosa Desert and Pahrump Valley (table 7). Pronounced seasonal water-level fluctuations from seasonal irrigation pumping in the central Amargosa Desert suggest that less permeable sediments overlie the pumped interval. For example, water levels fluctuate seasonally and distinctly in wells *AD-3a* and *AD-9* in response to seasonal irrigation, which requires a confining unit that is laterally extensive at distances greater than 1 mi from pumped wells. Refined lithologic classes for basin fill in the Amargosa Desert (Taylor and Sweetkind, 2014) were not considered when defining the extent of the less permeable sediments because hydraulic properties were predicted poorly (fig. 23). Instead, basin-fill sediments were defined based on lithologic well logs, locations of flowing wells, and water-level trends in wells. Continuity of fine-grained sediments that confine deeper, coarse-grained basin fill in Pahrump Valley was indicated by historically flowing wells near *Bennetts Spring* and 4 mi south-southwest of *Manse Spring* (Waring, 1921). Wells such as *H & H*, which was capped and had a water level of 57 ft above land surface in 1948, extended the area of confinement at least 4 mi north of *Bennetts Spring* (Harrill, 1986).

Table 7. Hydrogeologic units in the Death Valley version 3 model (DV3) hydrogeologic framework that were defined by rock type, depth, and previously defined hydrogeologic units from the Death Valley Regional Flow System version 2 model (DVRFS.v2) project, Nevada and California.

[Source: Belcher and others (2017). **Description:** AFFCR, Alkali Flat–Furnace Creek Ranch; AM, Ash Meadows; PDVS, Pahrump to Death Valley South; PMOV, Pahute Mesa–Oasis Valley. **DVRFS.v2 hydrogeologic unit:** BRU, Belted Range unit; CFBCU, Crater Flat–Bullfrog confining unit; CFPPA, Crater Flat–Prow Pass aquifer; CFTA, Crater Flat–Tram aquifer; CHVU, Calico Hills volcanic-rock unit; ICU, Intrusive-rock confining unit; LA, Limestone aquifer; LCA, Lower carbonate-rock aquifer; LCA_T1, Lower carbonate-rock aquifer (thrusted); LCCU, Lower clastic-rock confining unit; LCCU_T1, Lower clastic-rock confining unit (thrusted); LFU, Lava-flow unit; OAA, Older alluvial aquifer; OACU, Older alluvial confining unit; OVU, Older volcanic-rock unit; PVA, Paintbrush volcanic-rock aquifer; SCU, Sedimentary-rock confining unit; TMVA, Thirsty Canyon-Timber Mountain volcanic-rock aquifer; UCA, Upper carbonate-rock aquifer; UCCU, Upper clastic-rock confining unit; VSU upper, Upper volcanic-sedimentary rock unit; VSU lower, Lower volcanic-sedimentary rock unit; WVU, Wahmonie volcanic-rock unit; XCU, Crystalline-rock confining unit; YAA, Younger alluvial aquifer; YACU, Younger alluvial confining unit; YVU, Younger volcanic-rock unit]

Rock type	DV3 hydrogeologic unit	Description	DVRFS.v2 hydrogeologic unit
Carbonate rocks	Shallow, low-permeability carbonate rocks	Occur primarily beneath Rainier Mesa, western Yucca Flat, Specter Range, and Sheep Range.	UCA, LCA_T1
	Shallow carbonate rocks	Regionally extensive in the AM basin. Spans from Pahrump Valley to the Amargosa River in the PDVS basin and occurs in the southern Funeral Mountains in the AFFCR basin.	LCA_T1, LCA
	Deep carbonate rocks	Regionally extensive in the AM basin. Spans from Pahrump Valley to the Amargosa River in the PDVS basin. Occurs beneath Shoshone Mountain, Yucca Mountain, Jackass Flats, Amargosa Desert, and the Funeral Mountains in the AFFCR basin.	LCA_T1, LCA
Volcanic rocks	Shallow volcanic rocks	Extends north-south from Pahute Mesa and Black Mountain to Yucca Mountain and Jackass Flats, and extends west-east from Oasis Valley to Rainier Mesa in the PMOV and AFFCR basins. Forms localized units beneath Yucca Flat, Frenchman Flat, and Emigrant Valley in the AM basin.	LFU, YVU, TMVA, PVA, CHVU, WVU, CFPPA, CFBCU, CFTA, BRU
Basin fill	Shallow basin fill	Upper 200 ft of saturated basin fill beneath valleys, including the Amargosa Desert, Death Valley, Pahrump Valley, Oasis Valley, Emigrant Valley, Yucca Flat, and Frenchman Flat.	YAA, YACU, OAA, OACU, LA, VSU upper
	Confining unit in Pahrump Valley	Saturated basin fill between 200 and 400 ft below the water table in Pahrump Valley. Basin fill divided into three units, where this is the intermediate unit, which was used to provide hydraulic separation between shallow (unconfined) basin fill and deep (confined) basin fill.	YAA, YACU, OAA, OACU, LA, VSU upper
	Deep basin fill	Remainder of saturated basin fill beneath valleys, including the Amargosa Desert, Death Valley, Pahrump Valley, Oasis Valley, Emigrant Valley, Yucca Flat, and Frenchman Flat.	YAA, YACU, OAA, OACU, LA, VSU upper
Volcanic-sedimentary rocks	Volcanic-sedimentary rocks	Shallow volcanic-sedimentary rocks. Rocks are saturated in northern PMOV basin from the Cactus Range to Kawich Valley. These rocks form the low-permeability “tuff pile” beneath Rainier Mesa, Yucca Flat, and Frenchman Flat, and extend beneath Emigrant Valley in the AM basin. Rocks extend from Amargosa Desert to Greenwater Range in AFFCR basin, and occur beneath Pahrump Valley and Sperry Hills in PDVS basin.	OVU, VSU upper
Low-permeability rocks	Deep volcanic rocks	Deep volcanic rocks and volcanic-sedimentary rocks. Regionally extensive throughout PMOV basin. Occur beneath Yucca Mountain, Amargosa Desert, Death Valley, and Eagle Mountain in AFFCR basin. Saturated rocks are localized beneath Emigrant Valley in the AM basin, and localized beneath Pahrump Valley and Sperry Hills in the PDVS basin.	TMVA, PVA, CHVU, WVU, CFPPA, CFBCU, CFTA, BRU, OVU, VSU lower
	Granitic and siliciclastic rocks	Clastic sediments (and their metamorphosed equivalents), and granite, granodiorite, quartz monzonite, and tonalite in stocks, dikes, sills, and plutons. Rocks extend from the Resting Spring Range and California Valley to Death Valley in the PDVS basin, and between Pahrump Valley and the Ash Meadows discharge area. Rocks occur beneath the Greenwater Range, Black Mountains, and northern Funeral Mountains in the AFFCR basin. Rocks are saturated to the west, north, and east of Yucca Flat in the Eleana Range, Climax Stock, and Halfpint Range, respectively.	ICU, SCU, UCCU, LCCU_T1, LCCU, XCU

Deep basin fill mostly was differentiated from shallow basin fill in the DVRFS.v2 framework and classified as lower volcanic-sedimentary rock unit (VSU lower; [table 3](#)). These deep, volcanic-sedimentary rocks are clay-rich and cemented, and are otherwise impermeable (Sweetkind and others, 2010). For example, well *Inyo-BLM 2* is open to deep, volcanic-sedimentary rocks that have a hydraulic conductivity of 3×10^{-6} ft/d ([fig. 19](#)). Greater cementation, occurrence of evaporites, and other less-permeable basin fill have been observed at depths greater than 1,600 ft below the water table elsewhere in the Great Basin (Halford and Plume, 2011). The VSU lower was classified as part of the low-permeability rock type in the DV3 framework ([table 7](#)).

Shallow volcanic-sedimentary rocks were retained as a unique hydrogeologic unit in the DV3 framework because hydraulic isolation was needed between overlying and underlying aquifers and because rocks in some basins and ranges were undifferentiated. Volcanic-sedimentary rocks consist of tuffs; lavas; alluvium; colluvium; and eolian, fluvial, and lacustrine deposits (Sweetkind and others, 2010). Volcanic-sedimentary rocks function as confining units that hydraulically isolate basin fill from underlying carbonate rocks in CP basin ([fig. 25](#)), Frenchman Flat, and Yucca Flat. Basin fill in Gold Flat and Kawich Valley and consolidated rocks in the surrounding mountain ranges mostly were undifferentiated because these rocks were grouped into volcanic-sedimentary unit. Expected differences between transmissivity of basin fill and mountain ranges were addressed when hydraulic conductivities were distributed in groundwater models during calibration.

The intermediate hydrogeologic framework grid, which consisted of uniform 164-ft-thick (50-m-thick) layers, was reduced to 5 layers for the DV3 hydrogeologic framework. Hydrogeologic units from DV3 were substituted for previously defined hydrogeologic units from DVRFS.v2 ([table 7](#)). Layer contacts were assigned nominally at depths of 164, 328, 820, and 1,640 ft (50, 100, 250, and 500 m) below the water table. An exception occurred if lithologic well data provided sufficient control to align the contacts between layers at the contacts between hydrogeologic units ([fig. 26](#)). Sufficient hydrologic control was limited to an area in the NNSS that was bounded by Yucca Mountain, Rainier Mesa, and Yucca Flat ([fig. 25](#)). Layer contacts were nominal depths below the water table outside the limited area, which was sufficient to preserve contacts between hydrogeologic units because units typically thinned or thickened by less than 330 ft (100 m). The thickest hydrogeologic unit was assigned where multiple hydrogeologic units intersected a cell. This primarily occurred in the deepest layer because average thicknesses exceeded 4,000 ft.

Revisions from Underground Test Area Projects

Hydrogeologic frameworks for Frenchman Flat, Yucca Flat–Climax Mine, Rainier Mesa–Shoshone Mountain, and Pahute Mesa CAUs ([fig. 27](#)) were created and revised to

support the UGTA project. Hydrogeologic frameworks for CAUs were developed after the DVRFS.v1 hydrogeologic framework was developed (Belcher, 2004; Belcher and Sweetkind, 2010). Hydrogeologic units beneath Frenchman Flat (Bechtel Nevada, 2005a), Yucca Flat (Bechtel Nevada, 2006; Fenelon and others, 2012), and Rainier Mesa–Shoshone Mountain (National Security Technologies, LLC, 2007; Fenelon and others, 2008) were revised in the DV3 framework. Revisions were warranted because details were missing in the DVRFS.v2 framework, such as aquifers that are known to be isolated where volcanic tuffs intervened between underlying carbonate rocks and overlying basin fill or volcanic rocks.

Revisions to hydrogeologic frameworks for CAUs were informed by additional data collection through the drilling of wells. Geologic and hydrologic uncertainties were reduced as a result of the UGTA project; 34 new boreholes were drilled and 119 new wells were completed during 2000–16, with most boreholes having multiple completions referred to as wells. Features such as Frenchman Flat basin were revised extensively because data from wells superseded surface mapping and geophysical inferences (Bechtel Nevada, 2005a). Well *ER-5-3-2* ([fig. 27](#)) drilled through 4,000 ft of saturated basin fill before encountering carbonate rocks (Bechtel Nevada, 2005b), in contrast to the DVRFS.v2 framework, which interprets the basin fill contact with carbonate rocks as occurring above the water table. The edge of Frenchman Flat basin, where saturated basin fill occurs, was moved 3 mi north because of additional well control ([fig. 27](#)). Carbonate rocks were expected 6,000 ft below land surface in well *ER-5-4-2* but were not encountered after drilling 7,000 ft below land surface (Bechtel Nevada, 2005c). Data from wells quintupled the volume of saturated basin fill in Frenchman Flat basin from the DVRFS.v2 framework to the DV3 framework.

Revisions to the DV3 framework were hydraulically important in northern Yucca Flat, and for local basin-fill aquifers and adjacent volcanic-sedimentary rocks in the eastern NNSS. Quartzite Ridge and Climax Mine, upgradient of wells *WW-2* (3422 ft) and *ER-8-1* (recompleted), are mapped as low-permeability rocks (DV3 framework) rather than as carbonate rocks (DVRFS.v2 framework), which is consistent with surface geology, well logs, and elevated water levels ([fig. 28](#); Winograd and Thordarson, 1975; Fenelon and others, 2012). Better mapping extents and thicknesses of basin fill and volcanic rocks in Yucca Flat improved representation of local aquifers ([fig. 28](#)). Local basin-fill aquifers in Yucca Flat supplied pumping wells *WW-A* and *WW-3* with 2,700 and 620 acre-ft, respectively, from 1952–1988 ([fig. 28](#); Elliott and Moreo, 2011). Revising these local basin-fill aquifers improved simulation of water-level declines in pumping wells *WW-A* and *WW-3* because these basin-fill aquifers were absent in the DVRFS.v2 framework ([fig. 28](#)) and incorrectly simulating pumping from volcanic rocks of limited extent imposes an artificial hydraulic barrier, resulting in larger simulated water-level declines in wells *WW-A* and *WW-3* than otherwise occurs based on water-level data.




Figure 26. Example cross sections through intermediate grid of Death Valley Regional Flow System version 2 (DVRFS.v2) (Belcher and others, 2017; top cross section), and Death Valley version 3 (DV3; bottom cross section) hydrogeologic framework models, Nevada and California. Trace of cross section A–A' is shown in figure 25.




Figure 27. Extents of hydrogeologic framework models for Frenchman Flat, Yucca Flat–Climax Mine, Rainier Mesa–Shoshone Mountain, and Pahute Mesa corrective action units; extent of Frenchman Flat basin in Death Valley Regional Flow System version 2 model (DVRFS.v2) hydrogeologic framework; and areas where carbonate rocks at water table in DVRFS.v2 were revised to volcanic rocks, basin fill, or low-permeability rocks in Death Valley version 3 model (DV3) hydrogeologic framework based on lithologic well data, Nevada and California.




Figure 28. Hydrogeologic units in Death Valley Regional Flow System version 2 model (DVRFS.v2; top left map), Death Valley version 3 model (DV3; top right map), and Fenelon and others (2012) (bottom map), at the water table beneath Yucca Flat, Nevada.

Extents of permeable rocks in CP basin and surrounding low-permeability rocks (fig. 27) were revised for similar reasons because CP basin is isolated hydraulically (Fenelon and others, 2010, p. 21). Water levels in well WW-4, in CP basin (fig. 27), declined more than 10 ft in response to pumping 7,300 acre-ft of water from wells WW-4 and WW-4A during 1981–2017. The transmissivity of basin fill at well WW-4A is 27,000 ft²/d, indicating that water levels in well WW-4 would have declined less than 1 ft if CP basin were not isolated.

Hydrogeologic frameworks for the Pahute Mesa CAU were not incorporated in the DV3 framework because Pahute Mesa consists primarily of thick sequences of volcanic rocks (Fenelon and others, 2016). Uniqueness of hydraulic variability between hydrogeologic units from the original and a revised framework for Pahute Mesa CAU (Bechtel Nevada, 2002; Garcia and others, 2017) was tested by simultaneously interpreting 8–16 interfering MWATs. Hydraulic-conductivity estimates varied more within hydrogeologic units than between hydrogeologic units (Belcher and others, 2002; Mirus and others, 2016; Garcia and others, 2017). Another interpretation using a single MWAT at well ER-20-11 (fig. 27) reached a similar conclusion: “*The hydraulic conductivities of the aquifers, confining units, and composite units show considerable overlap in their estimated values with no discernible trend among the different rock types,*” (Navarro, 2016a, p. 5-35).

Hydraulically Mandated Features

In the DV3 framework, discharge areas were connected to upgradient aquifers by changing shallow hydrogeologic units in the Furnace Creek area, Lower Amargosa area, and Saratoga Spring area. Potential localized hydraulic barriers were introduced in the Ash Meadows discharge area based on hydraulic data and attenuated responses to local pumping. Revisions to the DV3 framework, from the DVRFS.v2 framework, were warranted based on geologic evidence and hydrologic data.

A localized hydraulic barrier was introduced into shallow carbonate rocks in the Ash Meadows discharge area north of *Fairbanks Spring* (fig. 7) because a steep horizontal hydraulic gradient exists. Water-level altitudes declined from 2,361 ft in well GF-2B deep (AM-11) to 2,250 ft at *Fairbanks Spring* over a distance of 3,500 ft, a gradient of 160 ft/mi. Hydraulic gradients north of well GF-2B deep (AM-11) are less than 2 ft/mi and transmissivities exceed 100,000 ft²/d. This high hydraulic gradient can be explained by a low-permeability feature, such as a fault, north of *Fairbanks Spring* that offsets thin permeable horizons in shallow carbonate rocks (Dudley and Larson, 1976, p. 49). Groundwater would need to flow through shallow carbonate rocks south of the low-permeability feature to discharge from *Fairbanks Spring*. The location and orientation of the low-permeability feature were interpreted from a fault map of the Ash Meadows discharge area (Dudley and Larson, 1976).

Another potential localized hydraulic barrier is suggested by attenuated responses to injection in *Devils Hole Well* (AM-5), which is 900 ft east of *Devils Hole* (fig. 7). About 1,700 acre-ft of water was injected in *Devils Hole Well* (AM-5) from July 1973 to August 1977 at rates of 400 gal/min, with the intent of mitigating water-level declines in *Devils Hole* (Larson, 1974a, 1974b, 1975; Carson, 1979). A detectable rise of 1 ft would be expected in *Devils Hole* if transmissivity and specific yield reasonably averaged 50,000 ft²/d and 0.02, respectively, around *Devils Hole Well* (AM-5). No discernable response was observed in *Devils Hole* (Dudley and Larson, 1976), which suggests a low-permeability feature exists in the shallow carbonate rocks between *Devils Hole Well* (AM-5) and *Devils Hole*. A fault was postulated and introduced in the shallow carbonate rocks (fig. 7) along previously mapped lineaments and faults (Dudley and Larson, 1976, p. 49).

Furnace Creek Wash was revised in the DV3 framework for consistency with the conceptualization of discharge from the Furnace Creek area (fig. 9). Furnace Creek Wash consists of basin-fill deposits based on well logs but was mapped as undifferentiated volcanic-sedimentary rocks in the DVRFS.v2 framework. These undifferentiated volcanic-sedimentary rocks were changed to basin fill in the DV3 framework so that groundwater flow could be simulated through Furnace Creek Wash between upgradient *Travertine Springs* and downgradient alluvial fan on the Death Valley floor (fig. 9).

Low-permeability rocks formed an unwarranted hydraulic barrier in the Lower Amargosa area. The DVRFS.v2 framework mapped low-permeability rocks at the water table between the Nopah Range and Amargosa River, which impeded the movement of groundwater downgradient of Chicago Valley to discharge areas near Tecopa (fig. 12). Low-permeability rocks between the Nopah Range and Amargosa River were remapped, based on geologic interpretations, as carbonate rocks and basin fill, which was needed to allow westward flow to be simulated to Resting Spring and Tecopa (fig. 12). Basin fill added near Tecopa primarily represents saturated China Ranch beds in the area bounded by Resting Spring, Tecopa, and West Willow Spring.

Spatial distribution of discharge in the Lower Amargosa area differs between the DVRFS.v2 project and this investigation because low-permeability rocks were remapped in the DV3 framework. Discharges were simulated in the DVRFS.v2 project (Faunt, Sweetkind, and Belcher, 2010) at locations where ET units were mapped by Lacznia and others (2001). However, more than 30 percent of the ET units occurred from rocks mapped as impermeable in the DVRFS.v2 hydrogeologic framework. Mapped ET in these instances should overlie basin fill in the Amargosa River downstream of Tecopa and China Ranch Wash (fig. 12). Errors occurred in the DVRFS.v2 hydrogeologic framework because basin-fill deposits in these channels have limited extents and are bounded by impermeable rocks. Shallow geology of the Tecopa/California Valley area was changed in this investigation so that discharges from ET units are simulated from basin-fill deposits (fig. 12).

The Amargosa River channel was revised in the DV3 framework for consistency with the conceptualization of flow in the Saratoga Spring area. The Amargosa River channel between Dumont Dunes and the Saratoga Spring area (fig. 14) consists of basin fill; however, the DVRFS.v2 framework mapped the channel as low-permeability rocks. Incorrectly mapped low-permeability rocks at the water table were remapped as basin fill between Dumont Dunes and the Saratoga Spring area. Basin fill is required upgradient of Saratoga Pools for the simulation of flood infiltration and base flow downstream of the Amargosa River at Dumont Dunes, California (*USGS streamgage 10251375*).

Groundwater Development

Groundwater development entails pumping wells and nonpumping flowing wells, which affect groundwater flow as water is withdrawn from the aquifer system. When a pump is first turned on, water is supplied from storage. Eventually, if pumping continues for sufficient time, some of the pumped water will be supplied by natural discharge. Sources of water to wells were summarized originally by Theis (1940, p. 10) as follows: “All water discharged by wells is balanced by a loss of water somewhere. This loss is always to some extent and in many cases largely from storage in the aquifer. Some groundwater is always mined,” and “After sufficient time has elapsed...further discharge by wells will be made up in part by a diminution in the natural discharge.” Decreased discharge to springs, wetlands, and phreatophytes as a result of pumping is termed capture (Konikow and Leake, 2014).

Water-level declines and capture that result from groundwater development are affected by the rate and volume pumped, distance to pumping centers, distance to discharge areas, and aquifer hydraulic properties. In pumped wells, water levels decline proportionally with increasing pumping rates. Pumping centers where large volumes of water are withdrawn have greater magnitudes and extents of water-level declines compared to pumping centers where small volumes are withdrawn. Pumping centers distant from discharge areas have greater magnitudes and extents of water-level declines compared to pumping centers within discharge areas. Water-level declines and capture also are affected by hydraulic properties of the rocks. The ratio of transmissivity to storativity (specific yield plus specific storage times thickness), known as hydraulic diffusivity, controls the magnitude and lateral extent of water-level declines from groundwater development. Water-level declines propagate farther and faster from pumping centers as hydraulic diffusivities increase.

Groundwater development in the study area principally has removed water from storage because pumping has been relatively distant from discharge areas (fig. 29). Large groundwater withdrawals primarily have occurred in the central Amargosa Desert and Pahrump Valley, but discharge

areas greater than 10 mi from these pumping centers have not been affected measurably. For example, local pumping wells in the Ash Meadows discharge area affected spring discharges within 5 mi during 1968–80 (Dudley and Larson, 1976), but effects of distant pumping from the central Amargosa Desert were not discernable. About one-half of the discharge in Ash Meadows is from *Crystal Pool*, *Fairbanks Spring*, and *Big Spring*, which averaged 12.7 ft³/s (9,200 acre-ft/yr) prior to 1969 (Dudley and Larson, 1976). Combined discharge from these springs averaged 12.6 ft³/s (9,100 acre-ft/yr) from 2008–2017 (U.S. Geological Survey, 2018a), which is no change relative to measurement standard deviations of 0.1–0.4 ft³/s (100–300 acre-ft/yr).

Predicted effects of groundwater development depend on estimated pumping rates, water-level changes, and capture (Bredehoeft, 2002). Uncertainty in these quantities propagates into estimated distributions of transmissivity and storativity. Estimates of pumping prior to 1950 are uncertain because most groundwater was withdrawn from nonpumped flowing wells where data are sparse. Long-term (>50 years) water-level data are limited in the central Amargosa Desert and Pahrump Valley despite long pumping histories. For example, groundwater development has occurred in Pahrump Valley from 1913 to present (2018); however, only five wells in Pahrump Valley have long-term (1950–2018) water-level measurements and no wells provide information about water-level declines from 1913–1950. Based on comparison of historical and current spring discharges, 15–20 percent of predevelopment discharge has been captured in response to more than 100 years of groundwater development in the study area.

Data Compilation

Groundwater-withdrawal data and return-flow estimates used in this report are provided in a supplemental data release (Jackson and Halford, 2020). Groundwater-withdrawal data from 1913 to 2010 were compiled from Elliott and Moreo (2018), which is an updated database that supersedes previous databases (Moreo and others, 2003; Moreo and Justet, 2008). In this report, more-recent groundwater withdrawals were estimated by projecting 2010 pumping rates through 2018.

Groundwater-withdrawal data used in this report incorporate minor revisions to Elliott and Moreo (2018). For example, in the Elliott and Moreo (2018) database, pumping for dewatering the Barrick-Bullfrog mine incorrectly was attributed to wells 3 and 4 mi south of the Barrick-Bullfrog pit. This pumpage was assigned to temporary dewatering wells within 1,000 ft of the north edge of the Barrick-Bullfrog pit in this study. Injection in *Devils Hole Well (AM-5)* of about 1,700 acre-ft from July 1973 to August 1977 (Larson, 1974a, 1974b, 1975; Carson, 1979) was not inventoried in Elliott and Moreo (2018) and was added for this study.




Figure 29. Pumping wells, areas affected by groundwater development, and hydraulic barriers, in the study area, Nevada and California. DV3, Death Valley version 3.

Pumping and Return Flow

Pumping in the study area has been inventoried and estimated by water-use type because water-use type is correlated strongly with measurement uncertainty (Moreo and others, 2003). This is because pumping is estimated differently for irrigation, domestic, and metered water-use groups. Irrigation pumping was estimated by multiplying irrigated acreage by annual crop application rates that averaged 7 ft/yr (Moreo and Justet, 2008). Domestic pumping was estimated by multiplying the number of wells by an annual pumping volume of 0.7 acre-ft for each well (Moreo and others, 2003). Pumping estimates for domestic and irrigation water uses have an uncertainty of about 20 percent (Moreo and Justet, 2008). Metered pumping includes commercial, industrial, mining, and public-supply wells, and is known within 10 percent. Most metered pumping is for public supply, which includes NNSS and Department of Defense supply wells (Moreo and others, 2003).

Total groundwater withdrawals from irrigation, domestic, and metered water use were compared to predevelopment discharge estimates for each groundwater basin (fig. 30). AFFCR and Ash Meadows groundwater basins were combined because pumping from either basin can affect predevelopment discharges in *both basins* (see section, “[Groundwater-Basin Boundary Uncertainty](#)”). Annual groundwater withdrawals exceeded predevelopment discharge in the PDVS groundwater basin from 1952–2002 (fig. 30). As of 2018, groundwater withdrawals have never exceeded predevelopment discharges in the AFFCR, Ash Meadows, or PMOV groundwater basins (fig. 30).

Groundwater withdrawals primarily have occurred in the AFFCR and PDVS groundwater basins where, historically, withdrawals principally supplied irrigation (fig. 30). Groundwater withdrawals in the AFFCR groundwater basin have increased from 1950 to present (2018) where, on average, withdrawals for irrigation account for about 90 percent of total withdrawals. Maximum groundwater withdrawals in the PDVS groundwater basin occurred between 1960 and 2000, when withdrawals for irrigation averaged 30,100 acre-ft/yr and total withdrawals averaged 32,600 acre-ft/yr.

Substantial pumping from domestic wells was limited to Pahrump Valley in the PDVS groundwater basin (fig. 30). Pumping from domestic wells in the PDVS groundwater basin was minor prior to 1970 and totaled 8,100 acre-ft/yr during

2010. Domestic pumping in Pahrump Valley accounted for 95 percent of all pumping from domestic wells in the study area during 2010.

Most metered pumping in the study area was for public supply, with episodic periods when mining usage was prevalent. About 60 percent of metered pumping in the study area supported activities at the NNSS between 1960 and 1980 (Moreo and Justet, 2008). Pumping for NNSS activities occurred in the AFFCR, Ash Meadows, and PMOV groundwater basins (fig. 30). Pumping at the NNSS declined after 1990 and averaged 800 acre-ft/yr from 2000–2010 (Elliott and Moreo, 2011). Pumping for mine dewatering south of Bullfrog Hills and in Crater Flat averaged 1,800 acre-ft/yr from 1984–2004 (Elliott and Moreo, 2018), where this pumping occurred in the AFFCR and PMOV groundwater basins. Ninety percent of metered pumping in the AFFCR and Ash Meadows groundwater basins during 2010 was for commercial and public supply (fig. 30). Public supply accounted for greater than 90 percent of metered pumping in the PDVS groundwater basin between 1980 and 2010 (Moreo and Justet, 2008).

A fraction of pumped groundwater infiltrates below the root zone and recharges the saturated groundwater system as return flow (Harrill, 1986). Return flow is computed as a fraction of total groundwater withdrawals, where fractions differed between metered, domestic, and irrigation water use (table 8). Of the three water-use components, return flows from irrigation wells were the smallest decimal fraction (0.17) of annual pumping volumes (Stonestrom and others, 2007). However, return flows from irrigation wells accounted for 60 percent of total return-flow volumes in the study area from 1913–2010 (fig. 30). Return flows from metered wells averaged one-half of annual pumping volumes (Harrill, 1986). Moreo and Justet (2008) estimated an annual pumping volume of 0.7 acre-ft per domestic well, whereas the revised estimate of annual net consumptive use is 0.5 acre-ft/yr (Geter, 2015, p. 2). Return flow for each domestic well was 0.2 acre-ft/yr, which was computed from the product of 0.7 acre-ft/yr and 0.29 (table 8). A domestic well return-flow rate of 0.2 acre-ft/yr is the difference between the revised net consumptive-use (0.5 acre-ft/yr) and the previously published pumping estimate (0.7 acre-ft/yr). Annual return-flow volumes from domestic wells exceeded 2,000 acre-ft after 2005 in the study area. Return flow for mining was reported as injection to wells or infiltration in basins (Moreo and Justet, 2008).




Figure 30. Total annual groundwater withdrawals by water-use type, return flow, and predevelopment discharge by groundwater basin, in the study area, Nevada and California, 1910–2010, with withdrawal estimates from 2010 projected through 2018. Irrigation water use is differentiated between Alkali Flat–Furnace Creek Ranch and Ash Meadows groundwater basins, whereas metered and domestic use are combined totals.

Table 8. Fraction of return flow and velocity through unsaturated zone, in the study area, Nevada and California.

[Water-use group: Metered includes commercial, industrial, mining, and public-supply wells]

Water-use group	Return flow fraction	Pore velocity (feet per year)	Reference
Metered	0.50	20	Harrill (1986)
Domestic	0.29	30	Geter (2015), Naranjo and others (2013)
Irrigation	0.17	5	Stonestrom and others (2007)

Recharge to the saturated groundwater system is delayed as return flow passes through the unsaturated zone between the root zone and water table. Annual delay time between application of return flow and recharge was estimated at each well. Annual delay time was the depth to water table divided by pore velocity, which varied by water-use group (table 8) because return flow occurred over different areas. For example, assuming 130 acres are irrigated with an application rate of 7 ft/yr, the return-flow volume applied to the irrigated acreage is about 1 ft/yr and the return-flow rate, assuming a porosity of 0.2, is 5 ft/yr. Pumped water from domestic wells primarily returned through leach fields in septic systems, which restricted application areas and increased pore velocities, compared to irrigation wells (Naranjo and others, 2013). Return-flow volume per domestic well is 0.2 acre-ft/yr (0.7 acre-ft/yr $\times$ 0.29 fraction). Dividing the return-flow volume by a leach-field area of about 0.034 acres (1,500 ft²) (Naranjo and others, 2013) and a porosity of 0.2, the return-flow rate is 30 ft/yr. Average pumping for commercial and public supply from 1913–2010 was 47 acre-ft/yr (Elliott and Moreo, 2018) and, assuming a 5-acre reclamation area, the return-flow rate is about 20 ft/yr. Delays between application of return flow and recharge generally were less than 10 years because depths to water table were less than 70 ft for about 90 percent of pumped wells (fig. 30). Delays greater than 10 years affect about 10 percent of wells where depths to the water table range from 200 to 2,060 ft.

Groundwater pumped, consumed, and lost to the saturated system is the net pumpage, which is the difference between groundwater pumping and return flow (fig. 31). Net pumpage in the study area averaged 39,100 acre-ft/yr from 1960 to 2000, or 83 percent of total groundwater withdrawals. Net pumpage averaged 71 percent of total groundwater withdrawals during 2010 because irrigation pumping decreased as a fraction of all groundwater withdrawals.

Return flow mitigates the effects of pumping on capture from discharge areas. In the absence of return flow, total groundwater withdrawals would have exceeded total predevelopment discharge in the study area during 6 years between 1960 and 2000 (fig. 31). Instead, return flow has resulted in an average net pumpage of 39,100 acre-ft/yr between 1960 and 2000, which is 73 percent of the predevelopment discharge.

Net pumpage (pumping and return flow) causes localized effects on water-level declines and capture from discharge areas. Pumped intervals in wells and recharge from return flow can differ vertically by 50–500 ft and laterally by as much as 0.6 mi (Moreo and others, 2003). These spatial differences can affect local groundwater levels and capture by reducing the rate of water-level decline from pumping or the rate of capture from discharge areas. These effects are unimportant at distances greater than 1–2 mi from areas of pumping and return flow (fig. 29).

Areas Affected by Pumping

Areas affected by pumping were delineated with a minimum water-level decline of 0.1 ft per decade (fig. 29). Delineated areas were compared to the density of pumping well locations and volumes pumped (fig. 29). Delineated areas also were compared to locations of observation wells with observed water-level declines in pumping centers and geologic controls, such as low-permeability rocks that function as hydraulic barriers (fig. 29). Declining water-level trends in wells within the delineated areas are caused by pumping. Net pumpage, rather than total groundwater withdrawals, better explains water-level declines in wells because net pumpage better indicates the actual stresses affecting water levels. Therefore, water-level trends from pumping are discussed in terms of net pumpage in this section.

Central Amargosa Desert and Pahrump Valley

The central Amargosa Desert and Pahrump Valley are the two principal pumping centers in the study area (fig. 32) and had maximum measured water-level declines of 50 and 80 ft, respectively (fig. 33). Water levels declined continuously in well AD-5 in the central Amargosa Desert (fig. 32), where pumping generally has increased from 1950 to 2010 (fig. 33). Water levels in well ESB1 in Pahrump Valley (fig. 32) declined 80 ft by 1980 and recovered 60 ft by 2010 (fig. 33), to about 20 ft below predevelopment water levels. The water-level trend in Pahrump Valley is a response to net pumping that peaked at 40,000 acre-ft/yr in 1968 and decreased to about 12,000 acre-ft/yr in 2010.




Figure 31. Net groundwater withdrawals and return flow, in the study area, Nevada and California, 1910–2018.

Pumping from the central Amargosa Desert and Pahrump Valley affected areas of 300 and 600 mi², respectively (fig. 32). Extents of pumping effects were delineated using decadal rates of water-level declines in wells. Decadal rates of water-level declines in wells are successively smaller as distance from the pumping center increases. Areas within each delineated pumping center (fig. 32) had rates of decline of greater than 0.1 ft per decade, whereas groundwater levels either had rising trends (fig. 18) or no trend (neither upward or downward) in areas affected minimally or not at all by pumping.

Central Amargosa Desert

Pumping in the central Amargosa Desert has propagated north toward Jackass Flats and Bare Mountain and south toward Death Valley Junction (fig. 32), as determined from water-level declines in wells. Small water-level declines in well BGMW-8 (fig. 34B) are not observable 1 mi west in well BGMW-6 (fig. 32). Likewise, water-level declines evident in well NC-EWDP-Washburn-1X (deep) (fig. 34C) do not extend 2 mi north to well NC-EWDP-22PA (shallow) (fig. 32), where water levels have risen 0.8 ft. Water-level declines in well DVJ-02 (fig. 34D) are expected to be limited farther south because of the occurrence of low-permeability rocks (fig. 32).

The maximum westward extent of pumping from the central Amargosa Desert is uncertain. Pumping has propagated into the Funeral Mountains because substantial drawdowns of 3 ft per decade were observed in well *Travertine Point 1* (fig. 34). Distal pumping effects, if any, from the central

Amargosa Desert would be masked in Furnace Creek area wells by water-level declines from local pumping. Water levels have been declining in well *WRPMW-5*, about 10 mi northwest of well *Travertine Point 1* (fig. 32), at 1.2 ft per decade since 2008. These water levels are affected by local pumping for Furnace Creek water supply, where pumped wells are less than 1 mi south of well *WRPMW-5*.

Pahrump Valley

Pumping from Pahrump, Nevada, has propagated to the northern and southern extent of Pahrump Valley, into Stewart and Chicago Valleys, and north of Shoshone, California (fig. 32). Water levels declined at rates of 2.2 and 3.1 ft per decade in *Last Chance Well* and *BLM Stewart Valley Well*, respectively (fig. 35B–C), which are 5 mi northwest of pumping wells (fig. 29). Pumping effects did not propagate north of these wells because of the occurrence of low-permeability rocks (Winograd and Thordarson, 1975, p. C91–C92; fig. 32). Groundwater levels in wells *Jeep Trail* and *021N010E04L01S*, 10 mi south and southeast of pumping wells (fig. 29), declined at rates of 9 ft per decade between 1960 and 1980, which coincides with the period of largest groundwater withdrawals from Pahrump Valley (fig. 35D–E). Water levels were recovering in *Jeep Trail* well after 2004 from reduced pumping in Pahrump Valley (fig. 35D). Water levels in well *Hwy 127 MM21-1*, about 16 mi west of Pahrump Valley pumping wells and 6 mi north of Shoshone (fig. 32), declined at a rate of 0.5 ft per decade (fig. 35E).




Figure 32. Observation wells affected by groundwater development and hydraulic barriers, in the study area, Nevada and California.




Figure 33. Water-level changes in (A) well AD-5 in the central Amargosa Desert and (B) well ESB1 in Pahrump Valley, Nevada, 1910–2018. DV3, Death Valley version 3.

Low-permeability rocks west of the Amargosa River limited pumping effects from Pahrump Valley from extending west of well Hwy 127 MM21-1 (fig. 32).

Discharges from *Bennetts* and *Manse* Springs (fig. 32) were captured by pumping in Pahrump Valley. All 5,400 acre-ft/yr (7.5 ft³/s) of discharge from *Bennetts* Spring was captured by 1959 (Harrill, 1986). *Bennetts* Spring has remained dry through 2018. Predevelopment discharge from *Manse* Spring was 4,400 acre-ft/yr (6 ft³/s) and declined gradually after development. All discharge from *Manse* Spring was captured by 1977 (Harrill, 1986). Discharge from *Manse* Spring resumed by the late 1990s (Buqo, 2004). Pumping declines and rising water levels restored *Manse* Spring, and discharge averaged 1,500 acre-ft/yr (2.1 ft³/s) in 2011.

Jackass Flats

Pumping in Jackass Flats, about 15 mi north of the central Amargosa Desert (fig. 32), has affected groundwater levels but natural water-level rises from recharge mask pumping effects (fig. 36). During 1957–2018, total withdrawals from wells *J-12 WW* and *J-13 WW* were 2,250 and 4,050 acre-ft, respectively, and these wells supplied about 90 percent of the 7,000 acre-ft that was pumped from Jackass Flats (fig. 36). Water levels in wells *JF-2*, *J-13 WW*, and *JF-3* rose 1.5 ft in unison from 1997 to 2015 (fig. 36), which is consistent with water-level rises from recharge throughout the study area (Fenelon and Moreo, 2002; Elliott and Fenelon, 2010; Fenelon and others, 2012; Jackson and Fenelon, 2018). Measured water-level rises were not recoveries from reduced pumping because recovery rates would differ between wells.




Figure 34. Net pumpage in the Alkali Flat-Furnace Creek Ranch groundwater basin (A), and hydrographs showing measured water levels in wells *BGMW-8* (B), *NC-EWDP-Washburn-1X(deep)* (C), *DVJ-02* (D), and *Travertine Point 1* (E), in the central Amargosa Desert, Nevada and California, 1910–2018.




Figure 35. Net pumpage in the Pahrump to Death Valley South groundwater basin (A), and hydrographs showing measured water levels in wells *BLM Stewart Valley Well* (B), *Last Chance Well* (C), *Jeep Trail* (D), *021N010E04L01S* (E), and *Hwy 127 MM21-1* (F), around Pahrump Valley, Nevada and California, 1910–2018.




Figure 36. Annual pumping from Jackass Flats (A), and hydrographs showing measured water levels in wells JF-2 (B), J-13 WW (C), and JF-3 (D), in Jackass Flats, Nevada, 1950–2018.

Differences in recovery rates would be exaggerated further by heterogeneous transmissivities as occurs beneath Jackass Flats, where aquifer-test results yield transmissivity estimates that ranged from 2,400 to 200,000 ft²/d (U.S. Geological Survey, 2018b).

Isolated Areas of Groundwater Development

Isolated areas of groundwater development occur in Indian Springs, Frenchman Flat, Buckboard Mesa, CP basin, south of Bullfrog Hills, Beatty, Emigrant Valley, and the Furnace Creek area (fig. 32). Water-level declines in these areas were observed primarily in the pumped wells and at distances less than 6 mi from a pumping well. Indian Springs is the earliest isolated area, developed in 1942, and pumping averaged 600 acre-ft/yr from 1942 to 2010. Groundwater development began in Frenchman Flat, Buckboard Mesa, and CP basin in 1951, 1963, and 1981, respectively, as water supplies for the NNSS. Pumping averaged 470, 120, and 210 acre-ft/yr from Frenchman Flat, Buckboard Mesa, and CP basin, respectively, from the start of development to 2010. Pumping rates averaged 1,600 acre-ft/yr south of Bullfrog Hills between 1990 and 2000 as the Barrick Bullfrog mine (fig. 32) was dewatered. Pumping averaged 2,600 acre-ft/yr during 1963–2010 from six Beatty Water and Sanitation District wells, which supply water for the town of Beatty. Pumping averaged 3,900 acre-ft/yr from four water-supply wells in Emigrant Valley from 1955–2010. Groundwater in the Furnace Creek area was developed during 2009 for public supply, where pumping averaged 330 acre-ft/yr from 2009 to 2014.

Ash Meadows and Devils Hole

Effects of historic pumping from the Ash Meadows discharge area were noteworthy because pumping wells were within 5 mi of *Devils Hole* (fig. 37). Groundwater was pumped from 1969 to 1982 by Cappaert Enterprises, which was Spring Meadows, Inc. prior to 1972 (Dudley and Larson, 1976). In this report, Spring Meadows, Inc. and Cappaert Enterprises pumping is jointly referred to as Cappaert Enterprises pumping. A total of 42,100 acre-ft were pumped over 14 years (Westenburg, 1993), which is less than 7 percent of the 630,000 acre-ft pumped between 1950 and 2010 from AFFCR and Ash Meadows groundwater basins (figs. 30 and 32). Water-level declines from pumping by Cappaert Enterprises immediately affected water levels in *Devils Hole* and recovery from this local pumping has persisted for two decades (Williams and others, 1996). Groundwater levels declined 2.3 ft in *Devils Hole* (fig. 4). This would seem like a minor change relative to declines of more than 50 ft in other pumping centers (fig. 33) except that, prior to pumping in

1969, less than 2.5 ft of water covered the shelf where *Devils Hole* pupfish feed and reproduce (Dudley and Larson, 1976). Water covered only 15 percent of the shelf when water levels were lowest in *Devils Hole* during June of 1972 (Dudley and Larson, 1976).

Water levels in *Devils Hole* were affected by nine nearby pumping wells and one injection well (fig. 37). Pumping from individual wells uniquely affected *Devils Hole* depending on locations and pumping rates, which were measured frequently from 1969 to 1982. Electric-power consumption was measured to estimate pumping volumes. Pumped volumes and electric-power consumption were correlated for each well, where multipliers ranged from 0.0023 to 0.0041 acre-ft/kilowatt-hour (Westenburg, 1993). Pumping rates principally were estimates of pumped volumes divided by elapsed times between site visits. Electric-power consumption was measured during site visits more than 10 times per month from March to July of 1971, but most measurements between 1969 and 1982 were monthly (fig. 38). More than 90 percent of the pumpage was from southern wells within 1 mi of *Point of Rocks Spring* (fig. 37). Monthly pumping rates from all pumping wells ranged from 400 gal/min (0.8 ft³/s) in the winter to 7,500 gal/min (16.8 ft³/s) in the summer (fig. 38).

Groundwater levels and spring discharges were monitored intensively in the Ash Meadows discharge area in response to declining water levels in *Devils Hole* during the 1970s (Dudley and Larson, 1976). Water levels in *Devils Hole* have been measured regularly from an established reference point since 1962 but little else was monitored until 1970. Water levels in *Devils Hole* declined about 0.1 ft during 1968 and at a rate of 0.7 ft/yr during 1969, 1970, and 1971 (fig. 4). Monitoring of water levels in wells and discharges from a few springs began in 1970; however, intensive monitoring of most springs and wells in the Ash Meadows discharge area occurred during 1971 and 1972 (Dudley and Larson, 1976). Water levels in wells Spring Meadows 7db2 and *Point of Rocks North* (AM-6), near *Point of Rocks Spring* (fig. 37), had maximum declines of 20 and 50 ft, respectively, during the summer from 1970 to 1977 (fig. 39). Water levels in pumping wells near *Point of Rocks Spring* also likely had similar trends to pumping well *Point of Rocks North* (AM-6). Persistent recovery was observed in most wells between 1978 and 2000.

Stresses Affecting Water Levels in Devils Hole

Pumping by Cappaert Enterprises was the principal stress that affected water levels in *Devils Hole*, but not the only stress. Local injection, regional pumping, and natural water-level fluctuations measurably changed water levels in *Devils Hole* during the 1970s. Regional pumping and natural water-level fluctuations were dominant effects after 1990. All stresses must be considered to correctly explain measured water-level changes in *Devils Hole*.




Figure 37. Hydrogeologic units at the water table, wells, *Devils Hole*, springs, pumping wells, and injection well [*Devils Hole Well (AM-5)*] in the Ash Meadows discharge area and surrounding areas, Nevada. DV3, Death Valley version 3.




Figure 38. Monthly pumping from northern wells, southern wells, and *Spring Meadows 6* well and injection into *Devils Hole Well (AM-5)* by Cappaert Enterprises in the Ash Meadows discharge area, Nevada, 1968–82.

Water was injected into *Devils Hole Well (AM-5)* to mitigate declines in *Devils Hole* from pumping by Cappaert Enterprises during the peak irrigation season (fig. 38). *Devils Hole Well (AM-5)* is 900 ft east of *Devils Hole* (fig. 37). Injection began in June 1973 and continued seasonally through 1977 (fig. 38). The source of injected water was spring discharge diverted from *King Pool Spring* that would not have readily returned to the groundwater system otherwise. A single injection rate of 400 gal/min was reported during summer 1973 (Larson, 1974a), which caused water levels to rise 20 ft in *Devils Hole Well (AM-5)* (fig. 39). Water levels rose between 30 and 40 ft during injection periods from 1974 to 1977 (fig. 39). The increase in water-level rises from 20 ft to between 30 and 40 ft were attributed to “... *partial plugging of the perforations in the well by algae, air entrainment, or physical change in the well*” (Larson, 1975).

Water levels in *Devils Hole* fluctuate naturally in response to Earth tides, barometric-pressure changes, earthquakes, and

episodic recharge. Water levels fluctuate less than 0.4 ft in response to short-term tidal and barometric stresses, where Earth tides are the dominant stress (Dudley and Larson, 1976, p. 11). The range of short-term Earth tidal fluctuations can be observed with less than a month of continuous water-level measurements. Seismic waves from nuclear detonations and earthquakes have perturbed water levels in *Devils Hole*, but effects typically dissipate in less than a few hours (Dudley and Larson, 1976). Coseismic water-level responses to crustal deformation can persist for years, but ultimately dissipate (Cutillo and Ge, 2006). Landers/Little Skull Mountain and Hector Mine earthquakes initially displaced water levels in *Devils Hole* by 0.4 and 0.1 ft, respectively (Cutillo and Ge, 2006). Episodic recharge caused long-term water-level fluctuations in *Devils Hole*. Cycles of long-term fluctuations exceed 120 years, where multiple-decade periods of declining or rising water levels are the result of dry or wet periods (fig. 17).




Figure 39. Monthly pumping and injection from the Ash Meadows discharge area (A), and hydrographs showing measured water levels in wells *Devils Hole Well (AM-5)* (B), *Point of Rocks North (AM-6)* (C), and *Spring Meadows 7db2* (D), during groundwater development by Cappaert Enterprises, Nevada, 1965–2000.

Devils Hole Water-Level Model

Water levels in *Devils Hole* were simulated with a water-level model in this study (Jackson and Halford, 2020) so that natural water-level fluctuations could be estimated and differentiated from pumping effects (fig. 40). Water-level changes in *Devils Hole* from natural fluctuations must be explained in addition to changes from pumping. This is because the U.S. Supreme Court (*Cappaert v. United States*) mandated a minimum pool elevation of 2.7 ft below the reference point, whether or not water-level changes are due solely to pumping (Williams and others, 1996). Time-varying natural fluctuations were estimated with the water-level model and subtracted from water-level measurements in *Devils Hole* to obtain a *Devils Hole* hydrograph affected by pumping only for calibration of numerical groundwater models. Groundwater models were used to differentiate effects from different pumping centers on water levels in *Devils Hole*. Long-term natural fluctuations were removed because groundwater models in this study do not simulate time-varying recharge or earthquakes.

Natural fluctuations simulated include Earth tides, earthquakes, episodic recharge, and steady discharge. Landers/Little Skull Mountain and Hector Mine earthquakes were simulated because displacement and dissipation affected water levels for multiple years (Cuttillo and Ge, 2006). Recharge was simulated using winter precipitation (October–March) in excess of 6 in. from the south–central Nevada precipitation index (fig. 17) and natural discharge from springs and phreatophytes was assumed steady. In this report, long-term natural fluctuations refer to water-level fluctuations in response to time-varying recharge and steady discharge.

The assumption of steady natural discharge is violated near *Devils Hole*, but does not affect water-level model results. Spring discharge was not steady during pumping by Cappaert Enterprises (Dudley and Larson, 1976). Spring capture and pumping by Cappaert Enterprises were correlated highly for monthly pumping estimates. Net effects of pumping by Cappaert Enterprises and spring capture were estimated in the analytical model of water levels in *Devils Hole*.

Effects from injection into *Devils Hole Well (AM-5)*, local pumping, and regional pumping were approximated with Theis transforms (Halford and others, 2012). Combined pumping effects were estimated and cannot be attributed to individual pumping wells or pumping centers because of correlation between Theis transforms.

Pumping from the AFFCR groundwater basin and NNSS wells in carbonate rocks (figs. 29 and 39) was a regional stress that affected water levels in *Devils Hole*. Effects of pumping

more than 600,000 acre-ft from the AFFCR groundwater basin are attenuated in the Ash Meadows groundwater basin because a relatively small corridor near well AD-4 (fig. 32) connects the two basins (Claassen, 1985 p. F19; Fenelon and others, 2016, p. 6). Pumping from NNSS wells *Army 1 WW*, *ER-6-1-2 main*, *WW-2 (3422 ft)*, *WW-C (1373-1701 ft)*, *WW-C (recompleted)*, and *WW-C-1* (fig. 32) totaled 18,000 acre-ft and likely affected water levels in *Devils Hole*. This is because these NNSS wells pump water from carbonate rocks near a confined transmissive feature, the megachannel (fig. 32; Winograd and Pearson, 1976). Pumping from Indian Springs also likely affected water levels in *Devils Hole*, but effects of pumping from NNSS and Indian Springs cannot be differentiated with an analytical water-level model (Bedinger and Harrill, 2006).

Episodic recharge had to exceed steady discharge to explain annually averaged water levels rising 0.43 ft in *Devils Hole* from 2005–2015 (fig. 40). Water levels in *Devils Hole* declined between 1990 and 2005 as regional pumping from AFFCR and Ash Meadows groundwater basins increased (fig. 30). Nevada Division of Water Resources inventories of pumpage from the Amargosa Desert hydrographic area show less than 2 percent change during 2006–10 and 2011–15. Because regional pumping changed little from 2005–2015, water levels in *Devils Hole* would have stabilized or declined after 2005 in the absence of episodic recharge events. Recharge exceeding steady discharge after 2005 is consistent with ubiquitous rising water levels throughout the study area (Fenelon and Moreo, 2002; Elliott and Fenelon, 2010; Fenelon and others, 2012; Jackson and Fenelon, 2018).

Estimated long-term natural fluctuations suggest that water levels in *Devils Hole* would have risen about 1 ft from 1973–2018 in the absence of pumping and injection (fig. 40). Water-level rise estimates are interpretative because pumping-recovery effects and recharge are correlated. Rises from recharge of as much as 2.7 ft from 1973–2018 were estimated with alternative water-level models of *Devils Hole*. Estimated rises greater than 1 ft were rejected because comparable water-level rises in distant wells bounded estimates in *Devils Hole*. Proximity to discharge locations subdues water-level fluctuations and *Devils Hole* is within 1–5 mi of all major springs in the Ash Meadows groundwater basin (fig. 37). Estimated rises between 1973 and 2018 in wells *U-19bk* and *USFWS DR-1* were 2 and 5 ft, respectively (fig. 18). These wells are 20 and 50 mi from their respective discharge areas (fig. 16) and are not affected by pumping. Natural water-level fluctuations from recharge in *Devils Hole* should be less than in wells far removed from discharge areas such as wells *U-19bk* and *USFWS DR-1*.




Figure 40. Estimated natural water-level fluctuations (includes short-term and long-term natural stresses), long-term natural trend of recharge and steady discharge, measured water levels, water-level model that includes all natural and pumping stresses, and pumping effects without natural fluctuations in *Devils Hole*, Nevada, 1900–2018.

Integrated Estimation of Recharge and Hydraulic-Property Distributions with Numerical Models

Recharge and hydraulic-property distributions were estimated by simultaneously calibrating four, three-dimensional, numerical groundwater models of the study area. When the four models are coupled, the integrated model is referred to as the DV3 model. Multiple models with identical spatial extents were constructed to simulate and differentiate the effects of predevelopment flow; changes from groundwater development (two models); and changes from a large-scale, multiple-well aquifer test (MWAT; [table 2](#)). Interpretation of measured stress-response pairs with separate models introduced fewer errors than simulation of all responses with a single generalized model. This was because boundary conditions could be better constrained to known stresses and corresponding simulated responses could be compared to appropriate observations. For example, discharge from *Big Spring* averaged 2.4 ft³/s prior to development, with a pool altitude of 2,240 ft. Multiple models allowed simulation of *Big Spring* as a specified discharge of 2.4 ft³/s prior to development and as a head-dependent boundary during groundwater development. This prevented misfits between simulated and measured pool altitudes from affecting simulated capture during groundwater development.

Groundwater-flow equations were solved using the USGS finite-difference model, MODFLOW (Harbaugh, 2005). The four coupled (stress-response) groundwater models were calibrated simultaneously using the Parameter ESTimation code (PEST; Doherty, 2010a). Archives of the integrated DV3 model containing executables, PEST calibration files, stress-response models, and utilities for drawing maps are available in Jackson and Halford (2020).

Common Construction of Models

All groundwater models that were developed for the DV3 project shared a common domain, gridding, hydrogeologic framework, and hydraulic properties. Model domains extended laterally to the edges of the study area ([fig. 41](#)). Each model was divided areally into 268 rows of 221 columns of variably spaced, rectangular cells that ranged from 820 ft (250 m) to 4,920 ft (1,500 m) on a side. Furnace Creek area, Devils Hole area, Rainier Mesa, and Yucca Flat were areas of finer discretization ([fig. 41](#)). The model grid is oriented north-south in Universal Transverse Mercator (UTM), zone 11, North American Datum of 1983 (NAD 83) projection, and the X and Y coordinates of the northwest corner are 494,000 and 4,175,500 m, respectively.

All groundwater model grids were divided into six layers and coincided with the grid of the hydrogeologic framework, which extended vertically from the water table to 3,300 ft (1,000 m) below the National Geodetic Vertical Datum of 1929 (NGVD29) ([fig. 26](#)). Layer 1 of the groundwater models was 1-ft thick to better simulate groundwater/surface-water interaction and drainage at the water table. Groundwater model layers 2–6 coincided with hydrogeologic framework layers 1–5. Hydrogeologic units in groundwater model layers 1 and 2 were identical. Tops of layers 3–6 nominally occurred at depths of 164, 330, 800, and 1,600 ft (50, 100, 250, and 500 m) below the water table or followed contacts between hydrogeologic units where well control was sufficient ([fig. 26](#)). The bottom of layer 6 extended to 3,300 ft (1,000 m) below NGVD29.

Saturated thicknesses of all model layers were specified and did not change in response to simulated pumping. Therefore, the simulated water table does not deform or move through layers. This approach was adopted because models with specified thicknesses converge and execute quickly compared to models that simulate transmissivity as a function of head (Sheets and others, 2015). The central Amargosa Desert and Pahrump Valley were the only areas where this approach could be questioned, with maximum declines of 50 and 100 ft, respectively ([fig. 33](#)). Maximum change in saturated thickness was less than 30 percent of model cell thicknesses, which affects simulated drawdowns less than 20 percent (Sheets and others, 2015).

Distributing Hydraulic Properties And Recharge

Heterogeneous hydraulic-property (and recharge) distributions were estimated with PEST using pilot points. Hydraulic-property values of hydraulic conductivity, specific yield, and specific storage were estimated at pilot points (RamaRao and others, 1995), where the locations of pilot points were user-specified. In this study, more pilot points occurred in areas where more data are available to constrain hydraulic-property estimates. Estimated hydraulic-property values at user-specified locations were translated into continuous hydraulic-property fields by interpolation with kriging using variograms (Doherty, 2010b).

Isotropic, exponential variograms defined spatial variability of log-hydraulic properties, where spatial correlation was specified with user-defined ranges (distances). Spatial correlation is assumed non-existent where distances between the interpolated location (cell center) and known value (pilot point) exceed the range. A hydraulic-property value at a cell functionally was an inverse-distance weighted average of the eight nearest pilot-point values if all distances between cell center and pilot points were less than the range. A hydraulic-property value at a cell is a simple average if distances between a cell center and the eight nearest pilot points all exceed the range.




Figure 41. Boundary of Death Valley version 3 (DV3) model and areas of finer discretization, in the study area, Nevada and California.

Interpolated hydraulic properties varied laterally but were uniform with depth in multiple-layer hydrogeologic units. For example, consider the distribution of hydraulic-conductivity values within a hypothetical framework consisting of basin fill, volcanic rocks, and carbonate rocks (fig. 42). The thickness of carbonate rocks varies with depth but is collapsed into a two-dimensional array of the laterally mapped extent (fig. 42). In this study, each hydrogeologic unit is a unique zone in MODFLOW and the pilot points were grouped by zone. This means that only pilot points within the hydrogeologic unit (zone) were used in the interpolation of hydraulic-property values at model cells within the hydrogeologic unit. The hypothetical carbonate rocks (fig. 42) have three pilot points that only are used in the lateral interpolation of hydraulic conductivities within the carbonate rocks. The estimated hydraulic-conductivity values at each lateral (X,Y) location in the carbonate rocks are assigned to all model layers where the carbonate rocks occur. Therefore, hydraulic properties are estimated at pilot points, interpolated laterally within each hydrogeologic unit, and then assigned the same value for all layers where the hydrogeologic unit occurs. Map extents of hydrogeologic units and pilot points for each hydrogeologic unit are provided as spatial coverages in Jackson and Halford (2020).

Hydraulic properties are assumed to be laterally and vertically isotropic because of practical limitations. Outcrops clearly indicate that bedding occurs at every conceivable dip and orientation (Sweetkind and others, 2010). Flow logs (Garcia and others, 2010) and packer tests (Frus and Halford, 2018) show extreme anisotropy or heterogeneity across intervals of less than 200 ft. None of these details are indicated in the hydrogeologic units, which are featureless groups of rocks. Heterogeneity is simulated entirely by contrasts in hydraulic properties within and between hydrogeologic units. Lateral contrasts were simulated by adding pilot points to hydrogeologic units, where greater pilot-point density allows for increased heterogeneity. Vertical contrasts were simulated exclusively by differences in hydraulic properties between hydrogeologic units as occurred beneath Rainier Mesa (fig. 26). Basin fill in Amargosa Desert and Pahrump Valley was differentiated with depth by subdividing basin fill into three units (table 7) to simulate water table (unconfined) and confined conditions. Heterogeneity and anisotropy are correlated, where large degrees of anisotropy can be simulated with large contrasts in hydraulic properties.

Hydraulic Conductivity

Hydraulic conductivities and layer thicknesses define simulated transmissivities and were assigned with the Layer-Property Flow package in MODFLOW (Harbaugh, 2005). Heterogeneous hydraulic-conductivity distributions were estimated for each hydrogeologic unit. Hydraulic conductivities are estimable at pilot points in areas where data exist because the parameters are sensitive to and informed by the data. However, in areas where no data exist, hydraulic-conductivity estimates were constrained by conceptual

transmissivity distributions. A conceptual transmissivity distribution was estimated for each hydrogeologic unit from aquifer-test results. Hydraulic conductivities for a hydrogeologic unit initially were conceptual transmissivities divided by model thicknesses of a hydrogeologic unit. For example, broad areas of uniform transmissivity were postulated for shallow carbonate rocks to provide initial hydraulic conductivities for this hydrogeologic unit (fig. 43).

Hydraulic conductivities were distributed with pilot points so that observed spatial variability could be simulated in hydrogeologic units (fig. 21). Isotropic, exponential variograms were used to define spatial variability of log-hydraulic conductivities with ranges of 1.5–9 mi. Ranges of variograms were less than 3 mi in areas of high pilot-point densities (fig. 44) so that interpolated hydraulic conductivities could vary more. Distributed hydraulic conductivities in hydrogeologic units were mapped to the hydrogeologic framework and parsed to a two-dimensional array for each model layer (fig. 42). All groundwater models used the same arrays of hydraulic conductivity.

Hydraulic conductivities were specified with 2,476 pilot points and pilot-point density increased in areas where water-level measurements, spring discharges, and transmissivity estimates were more prevalent (fig. 44). Pahute Mesa, Rainier Mesa, Yucca Flat, central Amargosa Desert, Ash Meadows discharge area, Furnace Creek area, and northern Pahrump Valley were areas with high data densities (figs. 19 and 29).

Pilot-point occurrence differed between model layers. Pilot-point occurrence at the water table adequately shows variations in pilot-point density, even though only 45 percent of pilot points occur at the water table (fig. 44). Additional pilot points in deeper hydrogeologic units are not shown in figure 44. For example, shallow carbonate rocks are overlain by basin fill, volcanic rocks, and volcanic-sedimentary rocks in Yucca Flat and the Ash Meadows discharge area (figs. 43 and 44). Compared to other hydrogeologic units, more hydraulic data exist for these shallow carbonate rocks, which supports adding more pilot points because more data are available to inform hydraulic-conductivity estimates during model calibration. Hydraulic data include measured water levels in more than 100 wells, discharges and pool altitudes from 19 springs, water-level changes and spring captures from pumping by Cappaert Enterprises, and drawdowns from the well *ER-6-1-2 main* MWAT.

Hydraulic conductivities were specified at pilot points where knowledge of the mapped lithology constrained hydraulic-conductivity estimates despite an absence of hydraulic data. For example, the floor of Death Valley is classified as basin fill in the hydrogeologic framework (fig. 44). The upper 1,000 ft of sediments consist of alternating layers of salt and clay in boreholes north and south of the Furnace Creek area (Hunt and others, 1966, p. B42). Hydraulic conductivities of salt and clay are variable, but generally do not exceed 0.0001 ft/d (Jackson and others, 2018). Representative hydraulic conductivities were assigned, not estimated, during model calibration.




Figure 42. Process for distributing hydraulic conductivities from pilot points to U.S. Geological Survey finite-difference model (MODFLOW) layers through hydrogeologic units in a hydrogeologic framework.




Figure 43. Conceptual transmissivity distribution in shallow carbonate rocks and hydraulic-conductivity pilot points for the shallow carbonate rocks, in the study area, Nevada and California.




Figure 44. Extents of all hydrogeologic units and hydraulic-conductivity pilot points at the water table, in the study area, Nevada and California.

Specific Yield And Specific Storage

Storativity distributions were estimated for hydrogeologic units by categorizing these units in the DV3 hydrogeologic framework as either basin fill or consolidated rocks. The basin fill categorization includes basin fill and volcanic-sedimentary rocks, whereas consolidated rocks consist of carbonate, volcanic, and low-permeability rocks (table 7). A simplified framework of basin fill and consolidated rocks was used because storativities are less variable than hydraulic conductivities. Storativity is specific yield plus specific storage times thickness. Specific yields typically range from 0.05 to 0.25 in basin fill and from 0.01 to 0.05 in consolidated rocks. Specific-storage values typically range from 1×10^{-6} to 5×10^{-6} 1/ft, regardless of hydrogeologic unit. Specific-yield and specific-storage values only were estimated (with PEST) in areas where saturated rocks were affected by pumping (fig. 29). In areas where aquifers were unaffected by pumping, specific yields of 0.1 and 0.02 were assigned to basin fill and consolidated rocks, respectively, and a specific-storage value of 2×10^{-6} 1/ft was assigned.

Storativities were estimated (or assigned) using either specific yield or specific storage in MODFLOW layers. Storativities in layer 1 were interchangeable with specific yields because layer 1 is 1-ft thick and specific storage is at least three orders of magnitude smaller than specific yield. Specific storages were used in layers 2–6 and reported as storage coefficients, which is specific storage times thickness. Specific storages estimated (in pumping areas) and assigned (in nonpumping areas) were uniform with depth and independent of hydrogeologic units because specific storages range from 1×10^{-6} to 5×10^{-6} 1/ft for all hydrogeologic units. For example, the estimated specific storage at an (X,Y) location is assigned to model layers 2–6 and the storage coefficient is computed by multiplying the specific storage by the total thickness of layers 2–6. Therefore, the specific-storage distribution has lateral (X,Y) heterogeneity where estimated, but is uniform with depth at each spatial (X,Y) location.

Specific-storage values estimated with PEST ranged from 2×10^{-9} to 1×10^{-5} 1/ft, which are beyond expected values of 1×10^{-6} and 5×10^{-6} 1/ft. Extreme underestimation of specific storages likely compensated for overestimating contributing thicknesses of consolidated rocks. For example, if a 10-ft-thick unit with a specific storage of 2×10^{-6} 1/ft was simulated

incorrectly with a 1,000-ft-thick layer, then the correct storage coefficient would be simulated if a specific storage of 2×10^{-8} 1/ft is estimated. Correction of hydrogeologic unit thicknesses was beyond the scope of this study.

Specific yields and specific storages were estimated with 420 pilot points so that spatial variability could be simulated in hydrogeologic units. Interpolated specific yields varied laterally within basin fill and consolidated rocks in model layer 1. Interpolated specific storages varied laterally in model layers 2–6 but were uniform with depth. Isotropic, exponential variograms defined spatial variability of log-specific yields and log-specific storages with a range of 12 mi. Distributed specific yields and specific storages were mapped to the hydrogeologic framework and parsed to two-dimensional arrays for each MODFLOW model layer as was done with hydraulic conductivities (fig. 42). All transient (pumping) groundwater models used the same array of specific yield and arrays of specific storages.

Recharge

Recharge was distributed throughout the steady-state model simulating predevelopment flow with a total of 521 pilot points (fig. 45). Recharge rates were estimated at pilot points with PEST, then interpolated from pilot points to model cells with kriging, similar to the interpolation method used for distributing hydraulic properties (Doherty, 2010b). Spatial variability of recharge was defined with an isotropic, exponential variogram, where nugget and range were 0 and 30,000 ft, respectively.

Recharge zones (fig. 16) were used for estimating heterogeneous recharge-rate distributions (fig. 45), similar to the hydrogeologic unit zones used for estimating heterogeneous hydraulic-property distributions. Recharge zones were delineated for runoff areas downgradient of low-permeability rocks, channels of the Amargosa River and Fortymile Wash, and other geographic areas (fig. 16). Recharge zones informed the objective function at sufficiently large scales that relative water availability was well defined between zones. For example, annual recharge volumes from the Spring Mountains greatly exceed annual recharge volumes from the Funeral Mountains. Annual recharge volumes to these zones are well defined relative to cell-by-cell estimates in the conceptual recharge distribution (fig. 16).




Figure 45. Estimated recharge distribution and recharge pilot points, from the Death Valley version 3 steady-state model (DV3-SS), in the study area, Nevada and California.

Stress-Response Models

Predevelopment conditions; the well *ER-6-1-2 main* MWAT; groundwater development in Ash Meadows, AFFCR, and PMOV groundwater basins; and groundwater development in the PDVS groundwater basin were simulated with four separate, but coupled, stress-response models (table 2). The DV3-SS (steady-state) model simulated predevelopment conditions and informed estimates of recharge rates and hydraulic conductivities. The DV3-ER612 model simulated drawdowns from pumping during the well *ER-6-1-2 main* MWAT, and informed estimates of hydraulic properties between northern Yucca Flat and the Ash Meadows discharge area. The DV3-AM-AFFCR model simulated changes from groundwater development from 1950–2018 in the Ash Meadows, AFFCR, and PMOV groundwater basins. The DV3-PDVS model simulated changes from groundwater development from 1913–2018 in the PDVS groundwater basin. Transient DV3-ER612, DV3-AM-AFFCR, and DV3-PDVS models informed estimates of hydraulic conductivity, specific yield, and specific storage in areas where pumping measurably changed groundwater levels or spring discharges.

Common Boundary Conditions

The outer edges of the study area (fig. 41) and the bottom of layer 6 at 3,300 ft (1,000 m) below NGVD29 are no-flow boundaries in all groundwater models. Internal boundaries between groundwater basins were not simulated explicitly as no-flow boundaries. Instead, hydrogeologic units formed hydraulic barriers or conduits to groundwater flow based on estimated hydraulic properties. Hydraulic-property estimates were informed by water-level altitudes, lateral and vertical water-level differences, recharge, predevelopment discharges, water-level changes from pumping, captures of spring discharges, captures of discharge from ET areas, transmissivity estimates from aquifer-test results and specific capacity, and hydraulic inferences from lithologic data, such as siliciclastic and granitic rocks functioning as hydraulic barriers.

The top surface of each groundwater model was the water table. The DV3-SS model simulated recharge to the top surface of layer 1 across the entire model domain. The transient DV3-ER612, DV3-AM-AFFCR, and DV3-PDVS models are superposition models, where the top of layer 1 is the predevelopment water table (Halford and Plume, 2011). Transient superposition models have initial heads of 0 ft, which are conceptualized as no change or drawdown from predevelopment conditions. Simulated water-level changes are relative to predevelopment heads.

Predevelopment—DV3-SS Model

Steady-state flow during predevelopment conditions was simulated so that recharge and transmissivities (through hydraulic conductivities) could be estimated. Annual recharge volumes were defined primarily by predevelopment

discharges. Elevated water levels in areas of limited recharge identified low-permeability rocks. Transmissivities of areas between *Devils Hole* and *Army 1 WW* (fig. 32) were defined primarily by discharges from springs in the Ash Meadows discharge area. Volume and water chemistry of discharges from the Furnace Creek area defined transmissivities upgradient in the central Amargosa Desert (Winograd and Thordarson, 1975, p. C112). Transmissivities of areas between the Nopah Range and Amargosa River were defined by discharges from the Lower Amargosa area. Transmissivities between Oasis Valley and Pahute Mesa were defined by discharges from Oasis Valley and aquifer-test results. Transmissivities in Yucca Mountain, Jackass Flats, Yucca Flat, Frenchman Flat, Indian Springs, Emigrant Valley, the central Amargosa Desert, and Pahrump Valley were informed by aquifer-test results and specific capacities (fig. 19); however, the transient groundwater models further refined transmissivities in these areas.

Lateral Flow Across Study Area Boundary

The study area primarily is isolated from surrounding groundwater basins by low-permeability rocks and groundwater divides (Fenelon and others, 2016), as discussed in the section, “[Description of Study Area](#).” The outer boundaries of the study area are simulated as no-flow boundaries. Groundwater flow across the northern and eastern boundaries between Gold Flat and Pahranaagat Valley has been suggested previously (Winograd and Thordarson, 1975; Heilweil and Brooks, 2011; Fenelon and others, 2016), but flow across these boundaries is expected to be limited.

Potential groundwater flow across the lateral study-area boundary was not precluded by no-flow boundaries because potential lateral flow was accommodated in simulated recharge estimates. For model cells along the periphery of the model domain, adding recharge to tops of model cells or specifying flow at any depth would similarly affect simulated water levels. Differentiating recharge and lateral flow along the study-area boundary was not possible because little data exist. Less than a dozen wells are available within 10 mi of the northern and eastern boundaries of the study area. Estimated recharge along the periphery of the study area should be interpreted as undifferentiated recharge and lateral flow.

Water Table and Perched Groundwater Assumptions

The top surface of all groundwater models is the water table, which encompasses the uppermost occurrence of saturation and includes perched and semi-perched intervals. Inclusion of perched groundwater in the DV3-SS model allows for the simulation of groundwater-flow paths from nuclear test locations in Rainier Mesa and Shoshone Mountain, which were detonated within the perched system. Perched and semi-perched groundwater also was included in Bare Mountain, Eleana Ridge, north of Climax Mine, Skull Mountain, Sheep Range, Greenwater Range, and Black Mountains (fig. 25).

Errors introduced by simulating the unsaturated zone beneath perched intervals with a saturated groundwater model are assumed to be negligible at the regional scale. Infiltration is vertical through the unsaturated zone from overlying perched intervals into the underlying saturated flow system. When the unsaturated zone beneath a perched zone is simulated as saturated, minor amounts of vertical flow are simulated erroneously as lateral flow. For example, in Rainier Mesa, open intervals in wells *ER-12-3 piezometer* and *ER-12-3 main* are at average depths of 1,700 and 4,000 ft below land surface, respectively, with about 1,000 ft of unsaturated zone between the two open intervals. The vertical gradient averages 0.8 ft/ft, whereas lateral gradients range from 0.08 ft/ft in volcanic tuffs at the perched water table to 0.008 ft/ft in the saturated carbonate rocks at the regional water table (U.S. Department of Energy, 2018). By simulating the 1,000-ft unsaturated zone as part of the saturated flow system, less than 100 ft of lateral movement would be simulated in the unsaturated zone assuming a vertical gradient of 0.8 ft/ft and a maximum lateral gradient of 0.08 ft/ft. Erroneously simulating less than 100 ft of lateral movement in the unsaturated zone is not materially different than the conceptually correct 0 ft. Perched intervals and underlying saturated rocks coalesce into a single, thick saturated zone within 1 mi of outcrops beneath Rainier Mesa (U.S. Department of Energy, 2018), which suggests perched intervals are areally limited in the study area.

Boundary Conditions

More than 96 percent of the predevelopment discharge was specified in the DV3-SS model (fig. 46) using the well package in MODFLOW (Harbaugh, 2005). Specified discharges from springs totaled 30,300 acre-ft/yr as measured (table 9), where 18 of 27 springs were in the Ash Meadows discharge area (fig. 46). Diversions from Furnace Creek Wash also were included in the spring category (table 9). The remaining 23,400 acre-ft/yr of specified discharge was evapotranspired discharge in the Ash Meadows discharge area, Oasis Valley, Furnace Creek area, Franklin Well area, Stewart Valley, Pahrump Valley, Lower Amargosa area, and Saratoga Spring area, which were simulated as specified discharges from layer 1 (fig. 46). Evapotranspired discharge in each model cell was computed by mapping all ET unit areas in each cell and multiplying the ET areas by their respective discharge rates. Unlike the Ash Meadows discharge area, spring discharges and ET_{GW} from downgradient phreatophytes were not differentiated in Oasis Valley and the Lower Amargosa area because springs and their downgradient ET units typically

occurred within a cell. Therefore, total discharge from each model cell in Oasis Valley and the Lower Amargosa area is the sum of all discharge from springs and ET areas within each cell. Discharge from ET areas was specified from the southern two-thirds of the alluvial fan south of Furnace Creek Ranch where diverted water was not applied (figs. 9 and 46). Infiltration from the Amargosa River downstream of Dumont Dunes, California (*USGS streamgage 10251375*) (fig. 14) averaged 720 acre-ft/yr (1.0 ft³/s) and was specified with the well package in MODFLOW (Harbaugh, 2005) (fig. 46).

Discharges from high-altitude springs in recharge areas were not simulated in the DV3-SS model (fig. 46) because the springs are perched. Discharge from perched springs is not part of the regional groundwater system because infiltrated precipitation enters and exits from the perched groundwater system. Spring-pool altitudes from perched springs were used as measurement observations to constrain the top of the simulated water table, which is the uppermost occurrence of saturation and includes perched intervals.

Remaining discharges in ET areas not simulated as specified discharges were simulated as specified heads (fig. 46) because discharge estimates were uncertain and reference water levels were needed. Discharges from Franklin Lake and Death Valley playa were uncertain relative to water-table altitudes and hydraulic conductivities in these areas (table 4). Discharge by ET_{GW} from the northern third of the alluvial fan downgradient of Furnace Creek Ranch (fig. 9) was simulated with specified heads (fig. 46) because amounts of return flow in discharge estimates were unknown. Discharge near site AR11 (*USGS streamgage 354903116130401*) on the Amargosa River (fig. 12) was simulated with a specified head (fig. 46) for numerical stability and is the functional terminus of the PDVS groundwater system. The DV3-SS model converged slowly prior to introducing a specified-head cell near site AR11 because small differences between specified recharge and discharge were not reconciled easily. A flow observation near site AR11 assured that simulated discharge matched the measured discharge of 1,100 acre-ft/yr.

Simulation of Springs

Conduits between spring pools and the most transmissive layer beneath springs were inferred and not simulated, except in the Ash Meadows discharge area. Spring discharge was specified directly from the most transmissive layer in Indian Springs, Pahrump Valley, and the Furnace Creek area (table 9). The most transmissive layer coincides with the hydrogeologic unit that is the source of spring water, which typically is carbonate rock.




Figure 46. Locations and types of boundary conditions and measurement observations used in the Death Valley version 3 steady-state model (DV3-SS), in the study area, Nevada and California.

Table 9. Springs explicitly simulated in Death Valley version 3 steady-state model (DV3-SS), estimated predevelopment spring discharge, and the minimum measured discharge from springs during groundwater development, in the study area, Nevada and California.

[Discharge estimates compiled in Jackson and Halford (2020). **Minimum measured discharge during groundwater development:** Minimum discharge that is less than one-half of predevelopment spring discharge is highlighted in **bold**. "—" indicates that minimum measured discharge is unknown.

Abbreviations: acre-ft/yr, acre-feet per year; ft³/s, cubic feet per second; NGVD29, National Geodetic Vertical Datum of 1929]

Discharge area	Spring name	Site identifier	Model layer	Pool altitude (feet above NGVD29)	Predevelopment discharge, acre-ft/yr (ft ³ /s)	Minimum measured discharge during groundwater development, acre-ft/yr (ft ³ /s)
Indian Springs	<i>Indian Springs</i>	363354115400601	2	3,183	700 (0.96)	—
Pahrump Valley	<i>Manse Spring</i>	360919115541501	5	2,776	4,350 (6.00)	0 (0.00)
	<i>Bennetts Spring</i>	361222115585801	5	2,680	5,430 (7.50)	0 (0.00)
Ash Meadows	<i>Five Springs Area</i>	362723116184101	1	2,345	310 (0.43)	0 (0.00)
	<i>Purgatory Spring Well</i>	362822116193801	1	2,336	80 (0.11)	10 (0.02)
	<i>School Spring</i>	362532116181501	1	2,323	10 (0.01)	—
	<i>Point of Rocks Spring</i>	362405116161300	1	2,320	620 (0.85)	330 (0.46)
	<i>Collins Spring</i>	362450116174001	1	2,320	20 (0.02)	10 (0.01)
	<i>King Pool Spring</i>	362407116162401	1	2,314	1,960 (2.70)	1,920 (2.65)
	<i>Longstreet Spring</i>	362751116192701	1	2,310	1,090 (1.50)	830 (1.14)
	<i>North Scruggs Spring</i>	362601116182800	1	2,305	100 (0.14)	70 (0.10)
	<i>South Scruggs Spring</i>	362554116184101	1	2,300	30 (0.04)	—
	<i>Jack Rabbit Spring</i>	362324116163900	1	2,280	1,010 (1.40)	0 (0.00)
	<i>Rogers Spring</i>	362835116192101	1	2,275	940 (1.30)	690 (0.95)
	<i>Soda (Bell) Spring</i>	362848116195901	1	2,254	130 (0.18)	0 (0.00)
	<i>Fairbanks Spring (AM-1a)</i>	362924116203001	1	2,250	2,750 (3.80)	1,860 (2.57)
	<i>Big Spring (AM-8)</i>	362230116162001	1	2,247	1,590 (2.20)	1,160 (1.60)
	<i>2 Davis Spring</i>	362401116181102	1	2,245	10 (0.01)	—
	<i>1 Davis Spring</i>	362401116181101	1	2,243	640 (0.88)	—
	<i>Cold Spring</i>	362740116204201	1	2,235	120 (0.16)	110 (0.15)
	<i>Crystal Pool (AM-5a)</i>	362502116192301	1	2,203	4,750 (6.55)	2,630 (3.63)
Furnace Creek	<i>Nebares Springs</i>	363045116491601	2	946	430 (0.60)	—
	<i>Travertine Springs</i>	362630116494701	2	415	1,380 (1.90)	—
	<i>Texas Springs</i>	362728116501101	2	397	360 (0.50)	—
	Furnace Creek Wash sump	362627116494901	2	320	940 (1.30)	—
	Furnace Creek Wash buried tile	362632116501201	2	265	290 (0.40)	—
	Furnace Creek Inn tunnel	362709116505201	2	73	220 (0.30)	—

Spring discharges from the Ash Meadows discharge area were specified from layer 1. Vertical conduits were simulated explicitly between spring pools in layer 1 and underlying carbonate rocks as high-hydraulic conductivity paths through basin fill. These conduits were isolated from surrounding basin fill by minimizing cell-by-cell conductances between the conduits and adjacent basin fill with horizontal-flow barriers (Hsieh and Freckleton, 1993). The approach for simulating Ash Meadows springs is consistent with the Lacznia and others (1999) conceptual model (fig. 8). The conceptual model shows that these springs discharge groundwater from underlying carbonate rocks through permeable conduits that minimally interact with overlying basin fill prior to entering spring pools (fig. 8). The conduits may be permeable travertine deposits or lenses of gravels and sands within clay-rich basin fill. The precise geometry of the conduits within basin fill is unknown because these conduits have not been differentiated

in hydrogeologic frameworks and previous studies provide little guidance on their occurrence and extent. Therefore, a simplistic approach was used by simulating conduits as vertical, high-hydraulic conductivity paths from carbonate rocks to spring pools.

Groundwater Development—DV3-AM-AFFCR and DV3-PDVS Models

Groundwater development was simulated so that transmissivities, specific yields, and specific storages could be estimated in areas where water levels and spring discharges have been affected by pumping (fig. 29). The central Amargosa Desert, Ash Meadows discharge area, and Pahrump Valley are the principal areas affected by groundwater development. Groundwater development also was simulated in Yucca Mountain and on the NNSS, including Pahute Mesa,

Buckboard Mesa, Yucca Flat, Frenchman Flat, CP basin, and Jackass Flats. Isolated areas of groundwater development were simulated to refine hydraulic-property estimates around Indian Springs, Emigrant Valley, south of Bullfrog Hills, Beatty, and the Furnace Creek area (fig. 29). Water-level fluctuations from time-varying (episodic) recharge were not simulated because estimating episodic recharge would detract from estimating transmissivities and specific yields.

Groundwater development was simulated with two models because the PDVS groundwater basin is hydraulically isolated from the Ash Meadows, AFFCR, and PMOV groundwater basins. Separate models better accommodated differences in pumping histories and reduced computational time. Pumping from the PDVS groundwater basin began in 1913, whereas irrigation pumping from the central Amargosa Desert began in the 1950s (fig. 30). Groundwater development in the central Amargosa Desert, Ash Meadows discharge area, Yucca Mountain, the NNSS, and isolated areas was simulated with the DV3-AM-AFFCR model. Groundwater development in Pahrump Valley was simulated with the DV3-PDVS model.

Temporal Discretization

Temporal discretization of pumping in the DV3-AM-AFFCR and DV3-PDVS models differed because the temporal resolution of groundwater-level and spring-discharge measurements differed between groundwater-development areas. Groundwater levels and spring discharges were measured infrequently in Pahrump Valley during the first 40 years of pumping and regularly during limited periods after 1960. Groundwater levels were measured seasonally and consistently in the central Amargosa Desert since pumping began during the 1950s (fig. 30). Groundwater levels and spring discharges were measured frequently in the Ash Meadows discharge area during the period when groundwater was pumped by Cappaert Enterprises (fig. 39).

Seasonal and monthly pumping were simulated in the DV3-AM-AFFCR model so that measured water-level changes and spring captures could be matched in the central Amargosa Desert and the Ash Meadows discharge area. Seasonal pumping was approximated by assuming all irrigation pumping occurred between mid-March and mid-September. Monthly pumping was simulated from 1969 to 1977, when discharges were measured from the nine pumping wells and one injection well in the Ash Meadows discharge area near *Devils Hole* (fig. 38). Pumping from all other water uses and return flows were unchanged during each year. This included pumping from Indian Springs, Emigrant Valley, Yucca Mountain, the NNSS, south of Bullfrog Hills, Beatty, and the Furnace Creek area (fig. 29).

Annual pumping was simulated in the DV3-PDVS model because pumping, water-level changes, and spring captures are relatively uncertain. Pumping estimates are less certain in Pahrump Valley, compared to the central Amargosa Desert, because about 30 percent of the water in Pahrump Valley was pumped prior to crops being inventoried annually. Water levels in *Jeep Trail* and *Hwy 127 MM21-1* wells are typical, with limited measurements prior to 2000 (fig. 35). Simulating seasonal pumping for irrigation is not beneficial to calibration without commensurate water-level measurements.

Boundary Conditions

DV3-AM-AFFCR and DV3-PDVS models simulated changes from predevelopment conditions and directly simulated drawdowns and spring captures. Initial heads were all zero, which represented no drawdown relative to predevelopment conditions. Discharges from springs and ET areas that had been simulated as specified discharges in the DV3-SS model were simulated as capture-limited boundaries (Halford and Plume, 2011; p. 35) in the DV3-AM-AFFCR and DV3-PDVS models (fig. 46).

A capture-limited boundary limits the total capture of discharge from springs and ET areas to their predevelopment-discharge estimates. MODFLOW does not have a boundary-condition package that simulates limited capture. Therefore, two MODFLOW packages were combined in each model cell where discharge occurs that simulates limited capture. One package simulates the injection of water into the model cell, whereas the other package simulates the removal of water from the model cell. The water injected during each stress period is the predevelopment discharge. The water removed is controlled by a head-dependent boundary package, such as the drain package (Harbaugh, 2005). In the drain package, the elevation is equal to the extinction depth and the conductance is equal to the predevelopment discharge divided by the extinction depth. The extinction depth is the depth below the predevelopment water level at which the spring will go dry or ET ceases (phreatophytes die). When these packages are coupled and the simulated water level at the drain is equal to the initial head of zero, indicating the spring is unaffected by pumping, then the water injected is equal to the water removed and no capture occurs. As the simulated water level declines at the drain, the water injected remains the same, but the water removed (discharging from spring) decreases, causing capture, which is computed as injection minus water removed. Once the simulated water level at the drain is at or below the extinction depth, no water is removed from the drain and all injected water is captured, which equals the predevelopment discharge.

Capture-limited boundaries were simulated with a combination of the river and drain packages in MODFLOW (Harbaugh, 2005). Water was injected with the river package, instead of the well package, so that only pumping was simulated and tracked with the well package and the river package only simulated and tracked the injection component of capture when using ZONEBUDGET (Harbaugh, 1990). Predevelopment discharges were injected with the river package, where riverbed conductance is the predevelopment discharge divided by the difference between the river stage and river bottom. The river-stage parameter was set equal to 1 ft above the river-bottom altitude so that the riverbed conductance equaled the predevelopment discharge. River stages and bottom altitudes were sufficiently high above the top of the model so that the river cells always behaved as losing river cells, which allowed simulated river leakage to be a constant injection rate. Drain elevations equaled extinction depths and conductances equaled predevelopment-discharge rates divided by extinction depths. Differences between injected and drained water simulated limited groundwater capture, meaning that simulated captures cannot exceed measured discharges.

Extinction depths were estimated in Pahrump Valley and the Ash Meadows discharge area because spring discharges had been captured (table 9). Springs such as *Bennetts* and *Manse* Springs in Pahrump Valley and *Jack Rabbit Spring*, *Five Springs Area*, and *Soda (Bell) Spring* in the Ash Meadows discharge area had to be simulated as capture-limited because all springs ceased flowing in response to nearby pumping. Extinction depths were estimable in these springs and a dozen others because declines in discharge had been measured (table 9). A uniform extinction depth of 5 ft was assumed for all other discharges by springs and ET areas.

Discharges from ET areas that had been simulated as specified heads in the DV3-SS model (fig. 46) were simulated as specified heads of 0 ft in the DV3-AM-AFFCR and DV3-PDVS models. These specified heads simulated unconstrained no-drawdown boundaries in Franklin Lake, Death Valley playa, and near site AR11 (*USGS streamgage 354903116130401*) on the Amargosa River (fig. 46). These specified heads were not converted to capture-limited boundaries because capture never exceeded 80 acre-ft/yr relative to simulated predevelopment discharges of 1,840 acre-ft/yr from specified heads in the DV3-SS model.

Well *ER-6-1-2 main* Multiple-Well Aquifer Test—DV3-ER612 Model

A large-scale, multiple-well aquifer test (MWAT) was simulated with the DV3-ER612 model to better constrain transmissivity, specific yields, and specific storages in the shallow carbonate aquifer. A separate stress-response model,

DV3-ER612, was used to simulate the well *ER-6-1-2 main* MWAT, instead of using either the DV3-AM-AFFCR or DV3-PDVS models, because finer temporal discretization is required to adequately simulate drawdown responses to pumping. Well *ER-6-1-2 main* was pumped and drawdowns were estimated in 13 observation wells that were 0–33 mi from the pumping well. Drawdowns were detected in observation wells, open to carbonate rocks, as far away as 33 mi from the pumping well (Jackson and Halford, 2019). Detected drawdowns are within an irregular 5 × 50-mi corridor of carbonate rocks between northern Yucca Flat and the Ash Meadows discharge area (fig. 47).

Drawdowns from pumping in well *ER-6-1-2 main* were estimated from measured water-level data in 13 observation wells (Jackson and Halford, 2019). Drawdowns were not equivalent to measured water levels because natural water-level fluctuations, such as barometric pressure and Earth tides, masked water-level changes from well *ER-6-1-2 main* pumping. Water levels were measured continuously in pumping well *ER-6-1-2 main* and eight observation wells: (1) *ER-3-1-2 (shallow)*; (2) *ER-6-1 main (lower zone)*; (3) *ER-6-1 main (upper zone)*; (4) *ER-6-1-1*; (5) *ER-6-1-2 piezometer*; (6) *ER-7-1*; (7) *UE-1h*; and (8) *Tracer Well 3* (fig. 47). Drawdowns in these wells were differentiated from natural fluctuations and effects of other pumping wells with water-level models (Halford and others, 2012). Water levels were measured periodically with tape downs in five additional wells: (1) *Army 1 WW*; (2) *U-3cn 5*; (3) *UE-7nS*; (4) *UE-10j (2232-2297 ft)*; and (5) *WW-2 (3422 ft)* (fig. 47). All drawdown analyses are reported in Jackson and Halford (2019).

Temporal Discretization

Well *ER-6-1-2 main* pumped 75 million gal (230 acre-ft) from February 5 to July 23, 2004, during a MWAT and tracer test in southern Yucca Flat (Stoller-Navarro Joint Venture, 2005a). Well development, step-drawdown tests, and a preliminary 9-day constant-rate test occurred during February 5–21, 2004. The 90-day constant-rate test occurred during April 24–July 23, 2004, when well *ER-6-1-2 main* pumped 64 million gal at 524 gal/min (Stoller-Navarro Joint Venture, 2005a). Pumping was deliberately ceased during July 8–12, 2004, which introduced a calibration point for tracer transport analyses (Stoller-Navarro Joint Venture, 2005a).

Stress periods in the DV3-ER612 model matched the periods of well development, step-drawdown testing, constant-rate pumping, and the 4-day shut-off because these pumping changes clearly were observed in drawdowns (Jackson and Halford, 2019). Seasonal or annual stress periods used in the DV3-AM-AFFCR and DV3-PDVS models, respectively, would not have been adequate to simulate these responses.




Figure 47. Observation wells monitored during well ER-6-1-2 main multiple-well aquifer test, in the study area, Nevada and California.

Boundary Conditions

Pumping in well *ER-6-1-2 main* was simulated using the well package in MODFLOW (Harbaugh, 2005). Groundwater discharge from springs and ET areas (fig. 46) were simulated in the DV3-ER612 model as capture-limited boundaries, using the same method described for use in the DV3-AM-AFFCR and DV3-PDVS models.

Calibration

Hydraulic-conductivity, specific-yield, specific-storage, and recharge distributions, and spring-extinction depths in the Ash Meadows discharge area were estimated by minimizing a weighted composite, sum-of-squares objective function. Hydraulic-property and recharge distributions were defined with 3,415 pilot points, where about 60 percent of the parameters were adjusted with PEST (Doherty, 2010a). Differences between measured observations and simulated responses formally defined the goodness-of-fit or improvement of calibration. This formal definition also was informed by qualitative assessment of estimated hydraulic-property distributions and biases in residuals.

Stress responses were simulated with the integrated DV3 model, which was called by PEST (fig. 48). The DV3 model initially translated estimated hydraulic conductivities, specific yields, specific storages, and recharge rates at pilot points into two-dimensional MODFLOW arrays. Stress-response models were executed sequentially, where each model used the same hydraulic-property arrays stored in a common directory (fig. 48). Simulated responses from all four stress-response models were compared to measured observations. Results from all models simultaneously informed PEST, and parameter changes were estimated iteratively until the objective function had been minimized, resulting in calibration of the DV3 model. The objective function was informed by measurement and regularization observations.

The objective function defines misfit between measured data and simulated equivalents so that parameters can be changed to minimize this misfit. Data used to inform parameters are measurement observations. Adjustable parameters include hydraulic conductivities, specific yields, specific storages, recharge rates, and spring-extinction depths. Parameters are estimable at pilot points in areas where simulated results are sensitive to parameter changes and data exist to judge goodness of fit. However, parameter estimation is not effective at pilot points where no data are available.

Regularization informs the objective function of conceptual models for parameters relatively insensitive to measurement observations. Tikhonov regularization provides information in the form of either preferred values

of parameters or preferred relations between parameters (Doherty, 2010a). These preferred values or relations are regularization observations, which are added as prior information to the PEST control file (Doherty, 2010a). A hypothetical example of a preferred condition is the assumption of a homogeneous transmissivity of 1,000 ft²/d in a hydrogeologic unit. For each hydraulic-conductivity pilot point in the hydrogeologic unit, the regularization observation would be the transmissivity (1,000 ft²/d) divided by the hydrogeologic unit thickness. During calibration with PEST, measurement and regularization objective functions are minimized simultaneously by allowing measurement observations to inform parameters where data exist and regularization observations (preferred conditions) to inform parameters where measured observations are deficient.

Measurement Observations

Measured observations characterized predevelopment flow and pumping effects. Water-level altitudes, water-level differences between wells, transmissivities, and discharge rates characterized predevelopment flow (table 10). Measured water-level altitudes included groundwater levels in wells, spring-pool altitudes, water levels in ET areas, and water-table altitude comparisons to land surface. Water-level differences between wells, including water-level differences between wells and spring pools in the Ash Meadows discharge area, constrained vertical and lateral hydraulic gradients. Simulated transmissivities were compared to transmissivities estimated from aquifer tests and specific capacities. Predevelopment discharges primarily informed the objective function of conceptual preferences, such as flows across groundwater-basin boundaries, because most measured discharges were specified in the DV3-SS model. Water-level changes and spring captures characterized pumping effects. Water-level changes principally were responses to groundwater development, but also included drawdown from the well *ER-6-1-2 main* MWAT. Spring captures primarily were responses to pumping from Cappaert Enterprises in the Ash Meadows discharge area.

Groundwater levels, spring-pool altitudes, and transmissivities were measured at 1,409 unique sites in the study area (Jackson and Halford, 2020). Water levels were measured in 1,070 wells and 164 spring pools, with predevelopment levels available for 881 wells and 162 spring pools (table 10). Transmissivities were estimated from aquifer tests and specific capacities in 271 wells, with less than 40 percent of these wells also supplying water-level data. Site identifier, station name, location, and observation group for each unique site are reported in Jackson and Halford (2020).




Figure 48. Model-run process of the Death Valley version 3 model (DV3), which is an integrated stress-response model, in the study area, Nevada and California. DV3-AM-AFFCR, Death Valley version 3 model simulating groundwater development in the Ash Meadows, Alkali Flat–Furnace Creek Ranch, and Pahute Mesa–Oasis Valley groundwater basins; DV3-ER612, Death Valley version 3 model simulating pumping during the *ER-6-1-2 main* multiple-well aquifer test; DV3-PDVS, Death Valley version 3 model simulating groundwater development in the Pahrump to Death Valley South groundwater basin; DV3-SS, Death Valley version 3 steady-state model; *K*, hydraulic conductivity; *N*, recharge; *S*, storativity; *S_s*, specific storage; *S_y*, specific yield; and *T*, transmissivity.

Table 10. Summary of observations and Death Valley version 3 model (DV3) fit to simulated comparisons, in the study area, Nevada and California.

[**Model:** DV3-SS, Death Valley version 3 stress-response model simulating steady-state (predevelopment) conditions; DV3-AM-AFFCR, Death Valley version 3 stress-response model simulating groundwater development in the Ash Meadows, Alkali Flat–Furnace Creek Ranch, and Pahute Mesa–Oasis Valley groundwater basins; DV3-PDVS, Death Valley version 3 stress-response model simulating groundwater development in the Pahump to Death Valley South groundwater basin; DV3-ER612, Death Valley version 3 stress-response model simulating pumping during the well *ER-6-1-2 main* multiple-well aquifer test. **Sum-of-weights squared:** (ft/ft)², foot per foot squared; [ft/log(ft²/d)]², square of foot per log of square foot per day; (ft/acre-ft/yr)², foot per acre-foot per year squared; [ft/(gal/min)]², foot per gallon per minute squared. **RMS error:** Root-mean-square error; ft, foot; log(ft²/d), log of square foot per day; acre-ft/yr, acre-foot per year; gal/min, gallon per minute; ft³/s, cubic foot per second. **Abbreviation:** NA, not applicable]

Model	Observation group	Number of observations	Sum of squares of weighted residuals (foot squared)	Sum-of-weights squared	RMS error
DV3-SS	Water-level altitude in wells	881	2,005,251	9.E+2 (ft/ft) ²	49 ft
	Water-level altitude in evapotranspiration areas	1,657	20,027	2.E+1 (ft/ft) ²	35 ft
	Spring-pool altitude	162	114,580	3.E+1 (ft/ft) ²	64 ft
	Water-table altitude comparison to land surface	1,675	14,001	4.E+0 (ft/ft) ²	58 ft
	Water-level difference between sites	50	79,755	6.E+2 (ft/ft) ²	12 ft
	Transmissivity from aquifer tests	142	70,643	2.E+5 [ft/log(ft ² /d)] ²	0.6 log(ft ² /d)
	Transmissivity from specific capacities	129	57,367	8.E+4 [ft/log(ft ² /d)] ²	0.9 log(ft ² /d)
	Water budget volumes	23	169,317	1.E-2 (ft/acre-ft/yr) ²	30 acre-ft/yr
	Conceptual recharge volumes	31	546,236	3.E-3 (ft/acre-ft/yr) ²	110 acre-ft/yr
	Erroneous recharge from specified heads	3	1,475	7.E-6 (ft/acre-ft/yr) ²	120 acre-ft/yr
DV3-AM-AFFCR	Amargosa Desert drawdown	3,782	1,700,713	2.E+7 (ft/ft) ²	0.31 ft
	Ash Meadows drawdown	1,030	528,764	5.E+6 (ft/ft) ²	0.32 ft
	Drawdown from localized pumping centers	1,572	4,228	8.E+3 (ft/ft) ²	0.7 ft
	Ash Meadows spring capture	510	723,563	4.E+1 [ft/(gal/min)] ²	140 gal/min (0.3 ft ³ /s)
DV3-PDVS	PDVS drawdown	1,626	1,968,409	2.E+7 (ft/ft) ²	0.3 ft
	Pahump Valley spring capture	203	79,419	8.E+4 (ft/ft ³ /s) ²	1.0 ft ³ /s (444 gal/min)
DV3-ER612	Well <i>ER-6-1-2 main</i> drawdown	1,514	498,180	1.E+9 (ft/ft) ²	0.02 ft
Totals		14,990	8,581,929	NA	NA

Many more observations exist than unique sites primarily because water levels and discharges have been measured many times in wells and springs. About 11,600 observations from wells and springs are compared in the objective function (table 10), which is nearly 10 times greater than the number of unique sites. Water-level changes (drawdowns) and spring-discharge changes (capture) resulting from pumping were compared to simulated equivalents for more than 60,000 observations, but only about 10,000 observations had weights greater than 0 (table 10). More than 60,000 observations are reported by PEST because simulated hydrographs were sampled continuously regardless of measurement frequency. For example, well *Jeep Trail* has 15 water-level measurements from 1959 to 2015, but includes an additional 107 sampling observations (1 for each year from 1913 to 2018) to view a continuous simulated hydrograph from 1913 to 2018. These additional sampling observations were given weights of 0 and, therefore, did not affect the objective function. More observations than unique sites also exist because multiple

observations—such as a water-level altitude and water-level changes—were measured in a well. For example, *Tracer Well 3* has four types of observations: (1) water-level altitude; (2) water-level changes from groundwater development; (3) drawdowns from the well *ER-6-1-2 main* MWAT; and (4) a transmissivity estimate.

Simulated water levels were sampled from a single MODFLOW layer for comparison to measured water-level altitudes and changes. Open intervals are less than 246 ft (75 m) in length for 63 percent of the wells, which functionally precludes assigning more than a single MODFLOW layer. Open intervals penetrating multiple MODFLOW layers were assigned to the most transmissive layer, as conceptualized in the hydrogeologic framework. This is because water levels in wells most closely represent water levels in the most transmissive interval of a formation. Less than 17 percent of 1,070 wells fully penetrated multiple MODFLOW layers and were assigned to the most transmissive layer.

Simulated water levels at wells and springs were interpolated laterally between model cell centers in assigned layers, except where hydraulic discontinuities made lateral interpolation inappropriate. Simulated water levels mostly were interpolated from nodes of surrounding cells to points of measurement with MOD2OBS (Doherty, 2010b). Well locations of a small number of wells were shifted from their true locations to the model cell centers in MOD2OBS input files and the shifted locations are shown in spatial coverages of model results (Jackson and Halford, 2020). For example, instead of discretizing the model grid finer, locations of *Devils Hole* and *Devils Hole Well (AM-5)* were manually shifted from their true locations to attenuate the effect of an intervening discontinuity in shallow carbonate rocks on simulated water levels. This shift was an approximate difference of 400 ft west and 400 ft east from the true locations of *Devils Hole* and *Devils Hole Well (AM-5)*, respectively. Simulated spring pools in the Ash Meadows discharge area were sampled from cell centers because their conduits from carbonate rocks to land surface were simulated explicitly, and spring-pool cells were isolated hydraulically from adjoining cells.

Weights were assigned to observations to represent expected observation accuracy and importance of each observation to model fit. For example, water-level altitude observations were weighted progressively less as observations were more uncertain, which resulted in water levels in wells being weighted more than water levels in ET areas. Weights accounted for differences in the number of observations between wells, where a well with 100 water levels will be weighted more than a well with 10 water levels if all water levels are weighted equally. Weights also accounted for the range of measurement values between observation groups. For example, log-transmissivities from 142 aquifer-tests ranged from -4.7 to 5.6 log(ft²/d), whereas water-level altitudes in 881 wells ranged from -281 to 8,504 ft above NGVD29. Transmissivity observations would not affect calibration if log-transmissivities from aquifer-tests and water-level altitudes in wells were weighted equally.

Weights were adjusted iteratively so all observation groups affected model calibration. Mismatches in scatter plots of water-level altitudes and transmissivities, spatial distributions of water-level residuals, profiles of predevelopment water levels, and hydrographs of water-level changes and spring captures directly informed relative importance of observation groups on model calibration. Simulated water levels; drawdown extents; and transmissivity, specific-yield, specific-storage, and recharge distributions were examined for conceptual inconsistencies. For example, transmissivities exceeding 1,000 ft²/d in low-permeability rocks are conceptually problematic. This problem typically identified a misclassified hydrogeologic unit, a compensating error, or an insensitive parameter that drifted to an upper limit. Influence of each observation group on calibration was best summarized by sum-of-squares (table 10). This was because

the weighted sum-of-squares residuals for each observation group integrates the number of observations, range of measurement values, and relative weighting.

Predevelopment Observations—DV3-SS Model

Measurement observations used in the calibration of the DV3-SS model were categorized into 10 observation groups (table 10). The following sections describe: (1) the different types of measurement observations; (2) methods used to estimate observations, where appropriate; (3) reasoning for weight assignment during calibration; and (4) how measurements were implemented in the DV3-SS model and used in model calibration.

Water-Level Altitudes in Wells

Measured and simulated water-level altitudes were compared from 1,033 wells (fig. 46) in the study area, where 881 wells have weights greater than 1×10^{-6} (table 10). Most measured water levels were relatively shallow, with 961 wells being screened in layers 2, 3, or 4. Only 26 wells were screened in layer 6, 80 percent of which were in the NNSS. Small weights were assigned to water levels in 152 wells, which limited sensitivity of comparisons between measured and simulated water levels during parameter estimation. Small weights were assigned because water levels either were redundant or were affected by transient (nuclear testing or pumping) conditions. These water-level observations were assigned small weights, rather than excluded from the DV3 model, because these data provided censored information during calibration. For example, if a measured water level is affected by pumping, then the simulated predevelopment water level should be higher.

Water-Level Altitudes in Evapotranspiration Areas

Water-level altitudes were estimated at 1,657 ET locations (fig. 46; table 10) and compared to water levels simulated with the DV3-SS model. Water levels are within 30 ft of land surface in discharge areas. Water levels exceed land surface at spring pools and remain below land surface in ET areas. Water levels in ET locations were estimated with land-surface altitudes from a digital elevation model (DEM) that sampled 1:24,000-scale maps every 30 m and reported to the nearest whole meter (Gesch and others, 2009). DEM altitudes typically spanned 10 ft in model cells where discharge by ET_{GW} occurred. Water levels were assumed equal to average land-surface altitudes because variability of land surface exceeds measured differences between land surface and water levels. These observations are less certain than measured water-level altitudes in wells and were weighted less. During DV3-SS model calibration, if measured water-level data from wells exist in the discharge area, the measured water-level data have greater weights than DEM-averaged water levels in ET locations and parameters have greater sensitivity to the measured data.

Spring-Pool Altitudes

Measured and simulated spring-pool altitudes were compared from 162 springs in the study area (table 10). Altitudes were well known for 27 springs where discharges were simulated (table 9). Altitudes of springs in the Eleana Range, Groom Range, Sheep Range, Spring Mountains, and Black Mountains were less certain because altitudes were estimated from the DEM used to calculate water-level altitudes in ET areas. Spring altitudes estimated from the DEM were weighted less than springs where altitudes were known. Despite the low weight assigned to DEM-estimated spring altitudes, water-table altitudes in mountain ranges depended on these spring-pool altitudes because wells were absent (figs. 6 and 46).

Water-Table Altitude Comparisons to Land Surface

Simulated water-table altitudes were compared to land-surface altitudes to ensure that the simulated water table remained below land surface. Land-surface altitudes were sampled at 1,675 locations from the DEM used to calculate water-level altitudes in ET areas. Water-table altitudes were evaluated after each MODFLOW simulation and simulated altitudes either remained unchanged or were assigned to the land-surface altitude. The simulated water-table altitude was set equal to the land-surface altitude if the simulated water table was below land surface so that the residual equaled zero and did not affect model calibration. For example, a simulated water-table altitude that initially equaled 4,500 ft would be changed to 5,000 ft, where land-surface altitude is 5,000 ft, and the residual would be 0 ft. Alternatively, a simulated water-table altitude that initially equaled 5,500 ft at the same location would not be changed and the residual would be 500 ft. Water-table altitude comparisons to land surface had small weights because these observations are highly non-linear. Water-table altitude comparisons also had small weights, compared to water-level altitudes in wells and spring-pool altitudes, so that calibration was sensitive to measured water levels.

Water-Level Differences Between Measurement Sites

Measured and simulated water-level differences between wells (or between wells and spring pools) were compared to preserve vertical and lateral differences (fig. 49). Water-level differences between volcanic rocks at the water table and underlying low-permeability carbonate rocks beneath Rainier Mesa were the primary vertical differences of concern. The greatest vertical difference exceeded 1,800 ft between wells *ER-12-3 piezometer* and *ER-12-3 main* in Rainier Mesa. Small water-level differences in shallow carbonate rocks between Yucca Flat and the Ash Meadows discharge area were the

primary lateral differences of concern. Water levels decline 32 ft between well *ER-6-1-2 main* and *Devils Hole* and are separated by 42 mi (fig. 49).

Transmissivity Comparisons

Transmissivity estimates from aquifer-test results and specific capacities were compared to simulated transmissivities. Simulated transmissivities were computed by defining the area investigated by each aquifer test (fig. 50), averaging hydraulic conductivities of all model cells that occur within the area investigated, and then multiplying by the contributing thickness (Halford, 2016). The area investigated was defined where drawdowns exceeded 0.07 ft at the end of each aquifer test, but the radius of investigation was not allowed to exceed 6,600 ft. For aquifer tests where transmissivity was less than 1,000 ft²/d or small volumes of water were pumped, the contributing thickness was limited to the well screen length. For aquifer tests where transmissivity exceeded 1,000 ft²/d or large volumes (more than 100,000 gal) of water were pumped (Halford and others, 2006), the contributing thickness was the aquifer thickness from the DV3 hydrogeologic framework model. If the area investigated spanned multiple model layers, the simulated transmissivity was computed by averaging hydraulic conductivities in each model layer, multiplying by their respective model layer thicknesses, and then summing layer-averaged transmissivities (Halford, 2016, p. 10). Estimated transmissivities from aquifer tests and specific capacities are discussed herein as measured transmissivities for comparison to simulated transmissivities from the DV3-SS model.

Conceptual Preferences of Recharge, Predevelopment Discharge, and Groundwater-Basin-Boundary Flows

Expected and simulated groundwater-flow rates that were compared included recharge to groundwater basins, flow across divides between groundwater basins, interbasin flow through corridors between groundwater basins, and discharges from specified heads (table 11). Expected recharge to groundwater basins was the annual volume from the conceptual recharge distribution (fig. 16), which was estimated from predevelopment discharge. No flow was expected across boundaries that form divides between groundwater basins. Expected interbasin flows through corridors between groundwater basins were derived from Darcy estimates (fig. 6). Expected discharges from specified heads primarily are maximum estimated discharges from playas (table 11). Discharge south of Tecopa is an exception where a discharge of 1,100 acre-ft/yr was known, but simulated with a single, specified head for numerical stability. Simulated flow rates were sampled from the DV3-SS model with ZONEBUDGET (Harbaugh, 1990).




Figure 49. Lateral and vertical water-level difference observations used in the Death Valley version 3 steady-state model (DV3-SS), in the study area, Nevada and California.




Figure 50. Transmissivity observations from aquifer tests and specific capacities, in the study area, Nevada and California.

Table 11. Expected and simulated groundwater-flow rate observations, in the study area, Nevada and California.

[Groundwater basin: AFFCR, Alkali Flat–Furnace Creek Ranch; PDVS, Pahrump to Death Valley South; PMOV, Pahute Mesa–Oasis Valley. Flow volume component: Recharge and discharge flow volume components are colored blue and red, respectively. Symbol: <, less than.]

Groundwater basin	Flow volume component	Flow volume (acre-feet per year)	
		Expected	Simulated
PMOV	Recharge to PMOV	6,000	5,900
	Divide between PMOV and Ash Meadows	0	20
	Divide between AFFCR and PMOV	0	230
	Interbasin flow from PMOV to AFFCR	100	110
	Recharge to Bullfrog Hills	100	80
	Interbasin flow from Bullfrog Hills to PMOV	100	60
Ash Meadows	Recharge to Ash Meadows	21,100	21,600
	Divide between Ash Meadows and AFFCR north of well AD-4	0	50
	Interbasin flow from Ash Meadows to AFFCR near well AD-4	2,000–4,000	2,550
	Leakage from Ash Meadows to AFFCR south of well AD-4	200	270
	Divide between Ash Meadows and PDVS	0	70
AFFCR	Recharge to AFFCR	4,800	4,850
	Divide between AFFCR and PDVS	0	20
	Interbasin flow from AFFCR to PDVS near Eagle Mountain	<300	60
	Discharge from Franklin Lake	<700	440
	Discharge from specified heads on alluvial fan in Furnace Creek area	<300	300
	Discharge from floor of Death Valley in AFFCR	<200	120
PDVS	Recharge to PDVS	22,100	22,200
	Interbasin flow from PDVS to Ash Meadows north of Stewart Valley	<200	180
	Discharge from specified head south of Tecopa	1,100	1,000
	Discharge from Saratoga Spring area	800–1,100	950
	Discharge from floor of Death Valley in PDVS	<200	40

Expected annual volumes from the conceptual recharge distribution were divided into 31 zones (fig. 16) and compared to simulated annual volumes. Zones were small enough that the objective function was informed of expected spatial variability in annual volumes of recharge. Zones were large enough that annual volumes of recharge were minimally affected by displacement of infiltration by low-permeability rocks and delineation of zones. Four zones in Pahute Mesa, Sheep Range, and Spring Mountains generated more than 70 percent of all recharge. Annual volumes of recharge were limited elsewhere and less than 500 acre-ft/yr in 17 of 31 zones.

Penalizing simulated water-table altitudes higher than land surface (table 10), minimizing flow across groundwater-basin boundaries (table 11), and matching water-budget volumes were conceptual observations (table 11). These conceptual observations, which defined well-understood terms that were quantified poorly through other observation groups, were compared as measurement observations in the objective function. Conceptual observations were weighted minimally because expected values are uncertain.

Groundwater-Development Observations—DV3-AM-AFFCR and DV3-PDVS Models

Measurement observations used in the calibration of the DV3-AM-AFFCR and DV3-PDVS models were categorized into observation groups of water-level changes and captures (table 10). The following sections describe how (1) water-level change measurement observations were computed, implemented in groundwater-development models, and used in model calibration; (2) long-term natural fluctuations from variations in recharge were accounted for or removed from measured water-level changes; and (3) groundwater captures were computed in the groundwater-development models.

Water-Level Changes

Measurement times and water levels were averaged to a single value for each stress period prior to estimating water-level changes. Water levels were averaged in a total of 308 wells for the DV3-AM-AFFCR and DV3-PDVS models. For modeling purposes, each of the averages is referred to as a “measured water level”. Averaging eliminated high-frequency fluctuations that were not simulated. For example, water levels in well *ESB1* were averaged annually because 1-year stress periods were simulated in the DV3-PDVS model (fig. 51). Simulated water-level changes in well *ESB1* were fit to changes in these annually averaged water levels.

Measured and simulated water-level changes were compared relative to a reference water level in each well (fig. 52). Reference water levels established a time when simulated water levels were set equal to measured water levels. Simulated changes were relative to the reference water level and pivoted about the reference water level. This occurred during calibration as transmissivities, specific yields, and specific storages were estimated (fig. 52). Reference water levels were necessary because most water-level records began 10–50 years after groundwater development started and changes from predevelopment water levels generally were unknown. This approach has been applied previously to negate unknown effects of entry losses in pumping wells (Halford and Yobbi, 2006).

Reference water levels were established so that measured water-level changes from pumping primarily were compared. Initial water levels commonly were not used because these measurements frequently are from well logs and do not represent equilibrated conditions after drilling. Water levels that have not equilibrated in low-permeability rocks or are affected by crustal deformation from earthquakes also were not used as reference water levels and were assigned small weights. For example, water levels in well *Travertine Point 1* were affected by the Landers earthquake in 1992 (Fenelon and Moreo, 2002). A 2005 water level was the reference and water levels prior to 1997 were not compared in the objective function (fig. 52). Reference water levels also were established during the last 10 years of record, after pumping had ceased, to mitigate effects of pumping in supply wells such as *Army 1 WW* and *WW-8*.

Accounting for Temporal Variability in Recharge

Time-varying recharge was not simulated in the DV3 model because of the complexity of the groundwater system. The behavior of rising water-level trends from recharge is dependent on annual variations in precipitation, distance from the recharge source, unsaturated zone depth, and the hydraulic conductivity of unsaturated and saturated rocks. Instead of simulating time-varying recharge to account for rising water-level trends, the recharge component of the water-level trend was differentiated from the pumping component at selected sites using water-level models (Halford and others, 2012).

Long-term natural fluctuations from variations in recharge were removed from measured water-level changes in *Devils Hole* and nearby wells because they were substantial relative to pumping effects. This was most apparent from 1990 to 2018 when episodic recharge affected water levels in *Devils Hole* more than pumping (fig. 40). Long-term water-level fluctuations from recharge estimated in *Devils Hole* were assumed pervasive throughout the shallow carbonate because other nearby wells had water-level trends similar to *Devils Hole*. Therefore, long-term recharge trends also were removed from wells *AD-8*, *Point of Rocks North (AM-6)*, *Point of Rocks South (AM-7)*, *Devils Hole Well (AM-5)*, *North Crystal Well*,

SM-23-1, *Spring Meadows 12*, *Spring Meadows 9*, *Tracer Well 3 (AD-6)*, and *TW-5 (RV-1)* (fig. 53).

Wells along the periphery of pumping centers with small rising water-level trends are affected by episodic recharge and minimally are affected by pumping, if at all. These water-level rises have been attributed to recharge from multiple water-level trend studies (Elliott and Fenelon, 2010; Fenelon and Moreo, 2002; Fenelon and others, 2012; Jackson and Fenelon, 2018). Water levels typically have risen about 0.8 ft per decade since the 1980s in wells along the periphery of pumping centers, such as well *CF2* (fig. 32). Small water-level rises in these wells may have masked small water-level declines from pumping. Because water levels in these wells are rising and the magnitude of water-level declines from pumping is unknown, recharge could not be differentiated from pumping. Instead, measured and simulated water-level changes were inspected visually in wells with rising water levels, such as well *USFWS DR-1* (fig. 18), to determine whether pumping likely has been masked by rising trends. Observations from 51 wells with rising trends were weighted near zero, where the rising trend enforces a minimal drawdown boundary at these wells.

Measured water-level changes were assumed to be from pumping exclusively for wells within the main pumping centers. The pumping-only assumption likely was adequate where water-level declines exceeded 1 ft per decade, which includes most wells in the central Amargosa Desert and all 109 wells in the PDVS groundwater basin. The only exceptions were water levels in *Devils Hole* and in nearby wells open to shallow carbonate rocks.

Groundwater Capture from Springs and Evapotranspiration Areas

Measured and simulated captures were compared at 18 springs in the Ash Meadows discharge area and two springs in Pahrump Valley (table 9). Limited capture was simulated by combining the river and drain packages in MODFLOW (Harbaugh, 2005). Simulated captures were computed by subtracting the predevelopment discharge injected in the river package from the water removed in the drain package. Simulated flow rates from the river and drain packages were extracted with a variation of ZONEBUDGET (Harbaugh, 1990) to compute capture. Simulated capture could not be computed directly from ZONEBUDGET because only flows across zone faces and flows from individual MODFLOW packages for each zone are reported in ZONEBUDGET, and rates from multiple packages are not combined. The modified program, MOD2BUD, was used to compute capture by reading the output file from ZONEBUDGET. MOD2BUD sums rates from multiple packages, converts units, interpolates rates between time steps, and reports time series for each zone. Source code for MOD2BUD is provided in the data release for this report (Jackson and Halford, 2020).




Figure 51. “Raw” water-level measurements, measured water levels, which are annual averages of measured water-level data during an annual stress period, and simulated water levels in well *ESB1*, Nevada, 1910–2020.




Figure 52. “Raw” water-level measurements, measured (average) water-level changes, and simulated water-level changes in terms of depth to water level (top graph) and water-level change (bottom graph), at well *Travertine Point 1*, California, 1950–2018. DV3-AM-AFFCR, Death Valley version 3 model simulating groundwater development in the Ash Meadows, Alkali Flat–Furnace Creek Ranch, and Pahute Mesa–Oasis Valley groundwater basins.




Figure 53. Estimated transmissivity distribution from integrated Death Valley version 3 model, extent of megachannel, and wells with measured water levels noticeably affected by natural fluctuations from recharge, Nevada National Security Site and vicinity, Nevada.

Well *ER-6-1-2 main* Multiple-Well Aquifer Test—DV3-ER612 Model

Drawdowns from the well *ER-6-1-2 main* MWAT differed from water-level changes during groundwater development because drawdowns were attributed exclusively to pumping in well *ER-6-1-2 main*. This was possible because estimates of these drawdowns in observation wells were isolated from other water-level changes using water-level models (Halford and others, 2012). Water-level models removed effects of barometric and Earth tidal fluctuations, and effects of pumping from wells *WW-C-1* and *Army 1 WW* from measured water levels (Jackson and Halford, 2019). Estimated drawdowns solely were from pumping of well *ER-6-1-2 main*. Drawdowns from the MWAT could be isolated because they were not correlated with water-level changes from all other stresses.

Long-term trends in observation wells were not accounted for, but minimally affected drawdown estimates from the well *ER-6-1-2 main* MWAT. Effects of long-term trends were minimal because less than 1 year of water-level record was analyzed for each well, except in *Tracer Well 3*. Long-term trends were not estimated with water-level models because background water levels were unavailable. Long-term rising trends in wells *ER-7-1* and *ER-3-1-2 (shallow)* were both an increase of 0.07 ft/yr. These trends equate to rises of 0.04 ft during the period of analysis, which are small relative to drawdowns greater than 0.3 ft in these wells (Jackson and Halford, 2019). The long-term trend in *Tracer Well 3* was less than a 0.02-ft increase during 2004. Removing the long-term trend would increase the maximum drawdown in *Tracer Well 3* by less than 0.01 ft, which equals the root-mean-square (RMS) error in the drawdown estimates (Jackson and Halford, 2019).

Regularization Observations

Tikhonov regularization informed parameters insensitive to measurement observations (Doherty, 2010a). Parameters were values of hydraulic conductivity (foot per day), specific yield (decimal percent), specific storage (1 per foot), and recharge rate (foot per day) at pilot points.

Tikhonov regularization observations were equations that defined either a preferred value at a pilot point or a preferred relation between pilot points. In the preferred-value approach, a single equation is provided for each adjustable parameter (pilot point) that equates the parameter to the preferred value. Preferred relations between pilot points were specified as ratios of preferred (or expected) values between pilot points, which guided relative differences rather than absolute values. For example, preferred hydraulic conductivities of 0.3 and 30 ft/d at two pilot points would specify a preferred ratio of 100. Hydraulic-conductivity estimates of 5 and 500 ft/d at the two pilot points would perfectly agree with the preferred relation because the ratio is 100.

If the preferred relation is homogeneity, then pilot points within a zone are assigned the same initial preferred value and the preferred ratio between pilot points is 1. By invoking

homogeneity, Tikhonov regularization limits differences between pilot points by penalizing sharp differences, and thereby ensuring relatively continuous distributions (Doherty and Johnston, 2003). Contrasts within hydrogeologic units and recharge zones were penalized minimally in areas where data informed the objective function.

The preferred relation between pilot points for the recharge distribution was ratios of the conceptual average annual recharge (fig. 16). Initial recharge estimates at pilot points were sampled from the conceptual recharge distribution (fig. 16). Recharge rates were estimated independently at all pilot points, but preferred ratios of conceptual recharge rates did not change between pilot points during calibration. A maximum of 30,000 regularization observations initially constrained recharge estimates with these preferred relations.

For each hydrogeologic unit, zones of conceptualized homogeneous transmissivity were the preferred relation between pilot points for hydraulic-conductivity distributions. Preferred hydraulic conductivity equaled preferred transmissivity of a zone divided by thickness of the hydrogeologic unit at a pilot point. For example, conceptual transmissivity of shallow carbonate rocks was distributed with homogeneous zones (fig. 43). Simulated hydraulic conductivities were interpolated smoothly between zones throughout each hydrogeologic unit because zones of homogeneity were speculative. Homogeneous transmissivity zones were incorporated as regularization observations instead of as parameters, so transmissivity in a hydrogeologic unit could differ where dictated by measurement observations. About 30,000 regularization observations constrained hydraulic-conductivity estimates with these preferred relations.

Homogeneity was the preferred relation between pilot points for specific yield and specific storage. Preferred values of specific yield for basin fill and consolidated rocks were 0.1 and 0.02, respectively. Preferred values of specific storage were 2×10^{-6} 1/ft. About 2,000 regularization observations constrained specific-yield and specific-storage values with these preferred relations.

Regularization observations were weighted so that preferred relations were emphasized where measurement observations were few. Regularization observations were weighted relative to separation distances between pilot points and the nearest measurement sites. Regularization-observation weights between pilot-point pairs were equal to 1 where the distance between the two pilot points was less than the separation between a measured water level and the nearest pilot point. Weights between pilot-point pairs decreased as the distance between the pilot points was more than the distance between a measured water level and the nearest of the two pilot points. Distances between measurement sites were less than 1 mi through Pahute Mesa, Rainier Mesa, Yucca Flat, Oasis Valley, Yucca Mountain, Frenchman Flat, the central Amargosa Desert, Ash Meadows discharge area, and Pahump Valley, and exceeded 10 mi in northern Three Lakes Valley and the Black Mountains (fig. 46).

Unrealistic hydraulic-property distributions were avoided partially by preventing overfitting of measurement observations (Fienen and others, 2009). Goodness-of-fit was limited so that the weighted, sum-of-squares error could not be reduced to less than irreducible measurement and numerical model errors. This expected measurement error is a weighted, sum-of-squares error and is the variable PHIMLIM in a PEST control file (Doherty, 2010a). A PHIMLIM of 8,000,000 ft² was specified, which is equivalent to an RMS error of about 50 ft for water-level measurements and approximates the average allowable misfit between the simulated and measured water level at each well.

Goodness of Fit

Goodness of fit was evaluated with scatter plots, a map of residuals (simulated minus measured), water-level profiles, hydrographs, and hydraulic-property distributions. Steady-state calibration primarily was evaluated with scatter plots of simulated and measured water-level altitudes and transmissivities. A map of predevelopment (steady-state) water-level residuals identified systematic spatial biases. Agreement between vertical and lateral gradients was checked with profiles of measured and simulated water levels. Calibration of groundwater-development and MWAT models was evaluated by agreement between measured and simulated hydrographs of water-level changes in each well. Calibration of groundwater-development models also was evaluated by agreement between measured and simulated changes in spring discharges from pumping (table 9). Major hydrologic features have been identified in conceptual models from water-level profiles, hydrographs, transmissivity estimates, and a refined hydrogeologic framework. Simulation of these hydrologic features was evaluated qualitatively by comparing measured water-level profiles and hydrographs to simulated equivalents and examining simulated hydraulic-property distributions.

Predevelopment Observations

Simulated water levels compare favorably to measured water levels in the DV3-SS model (fig. 54). Average and RMS water-level errors of +1 and 49 ft, respectively, are not large relative to the 8,800-ft range of measured water levels (fig. 54). Measured water-level altitudes range from -281 to 8,504 ft in Death Valley playa and the Spring Mountains, respectively. Differences between simulated and measured water levels from the DV3-SS model have been reduced by about a factor of 5, compared to the DVRFS.v2 model (fig. 54).

Water-level residuals show little spatial pattern of significance, suggesting a good overall fit between simulated and measured water levels (fig. 55). Water-level residuals average about 20 ft in transmissive areas such as Jackass

Flats, the central Amargosa Desert, Ash Meadows discharge area, Furnace Creek area, and northern Pahrump Valley. Water-level residuals exceed 100 ft in high-altitude, high-relief, low-transmissivity areas such as Eleana Range, Groom Range, Sheep Range, and Spring Mountains. These residuals are interspersed positive and negative values that exhibit little spatial bias (fig. 55). Water-level residuals of more than 100 ft are expected in high-relief areas because simulated water levels are very sensitive to small amounts of recharge across low-permeability rocks, land-surface altitudes span more than 500 ft across these model cells, and the simulated water levels computed at cell centers are averages that are being compared to average land-surface altitudes across the model cell.

Spring-pool altitudes are underestimated and overestimated at perched springs in Groom Range, Sheep Range, and Spring Mountains, whereas nearby water-table altitude observations are overestimated (above land surface) (fig. 55). This occurred because land-surface altitudes span more than 500 ft across these model cells, water-table observations have disproportionate sensitivity, and recharge pilot points did not coincide with the locations of water-table observations. Water-table observations are inequalities, where water-table altitudes can be only overestimated because the altitudes were set equal to land surface for each optimization iteration if the water table was below land surface. This means that the water-table residual can be 0 ft after the first optimization iteration and 500 ft after the next iteration. The simulated water table is very sensitive to small changes in recharge in these areas of low-permeability rock, but parameter estimation only can “see” the parameters that overestimate the water table. Because recharge pilot points did not coincide with water-table observations, reductions or additions of recharge at pilot points lowered or raised the simulated water table near these spring pools while attempting to lower the water table at the water-table observations. Future modeling efforts should ensure that recharge pilot points and water-table observations occur at the same locations.

Simulated water levels in ET areas were within 50 ft of measured values at 86 percent of the sites. Spatial patterns generally were absent in simulated water levels in these ET areas, except in the Ash Meadows discharge area, Chicago Valley, and north and east of Tecopa (fig. 55). Simulated water levels in ET areas ranged from 50 to 60 ft greater than measured values in the Ash Meadows discharge area. Future modeling efforts should focus on better calibration to remove the spatial bias in the Ash Meadows discharge area. Simulated water levels are overestimated and underestimated in northern and southern Chicago Valley. Simulated water levels are underestimated east of Tecopa and overestimated north of Tecopa. Measured and simulated spring-pool altitudes differ by less than 30 ft around Tecopa (fig. 55). Spatial biases in Chicago Valley and near Tecopa are structural model errors that cannot be resolved with the limited data available.




Figure 54. Comparison of measured and simulated water-level altitudes from the calibrated Death Valley Regional Flow System version 2 model (DVRFS.v2) and Death Valley version 3 steady-state model (DV3-SS), in the study area, Nevada and California. Measured observations include estimated land-surface altitudes, estimated water-level altitudes in evapotranspiration areas, spring-pool altitudes, and measured water levels in wells. The four types of observations are combined from the DVRFS.v2 model and shown as one symbol.




Figure 55. Steady-state water-level altitude residuals in the Death Valley version 3 steady-state model (DV3-SS), in the study area, Nevada and California.

Simulated and measured transmissivities generally agree, with 76 percent of sites within the 95-percent confidence interval (fig. 56). Simulated and measured transmissivities geometrically average 440 and 650 ft²/d, respectively. The log standard deviation of residuals from all observations of aquifer-test transmissivity, which excludes specific-capacity estimates, is 0.9 or a multiplier of 8. Simulated transmissivities range from 6×10^{-4} to 1×10^6 ft²/d, or nine orders of magnitude. This is similar to measured transmissivities that range from 2×10^{-5} to 4×10^5 ft²/d, 10 orders of magnitude. Simulated transmissivities from the DV3-SS model agree with aquifer-test results an order of magnitude better than simulated transmissivities from the DVRFS.v2 model.

Simulated predevelopment discharge estimates totaled 54,700 acre-ft, which agree with expected discharge estimates from 53,600 to 54,900 acre-ft/yr (table 4). Simulated and measured discharges agree in rate and location because 52,500 acre-ft/yr or 97 percent, was specified. The remainder of discharges that were simulated with specified heads agreed with measured discharges or were within estimated ranges (table 11). South of Tecopa was the location of the greatest discharge simulated with a specified head in the DV3-SS model, where measured and simulated discharges were 1,100 and 1,000 acre-ft/yr, respectively.

Groundwater-Development Observations

Calibration of groundwater-development models primarily was evaluated with hydrographs and mapped extents of simulated drawdown. Differences between simulated and measured water-level changes in hydrographs were the quantitative measure of model fit. Measured and simulated hydrographs also were examined qualitatively for agreement between trends. Mapped extents of simulated drawdown (fig. 57) were compared to areas that were affected by groundwater development (figs. 29 and 32). Comparisons between previously estimated and simulated extents were necessarily qualitative but provided a useful guide for consistency between numerical and conceptual models of groundwater flow.

Measured and simulated water-level declines in the central Amargosa Desert pumping center closely match, with RMS errors of 3 ft (fig. 58). Measured water-level declines in well AD-5 were replicated closely except for the steeper measured declines after 2010. Departure between simulated and measured water-level changes could have resulted from erroneous pumping estimates or from effects of dewatering the basin fill that were not simulated. Unknown rates of pumping during 2011–18 were assumed equal to pumping estimates for 2010 (fig. 30). Transmissivity near well AD-5 likely is decreasing as basin fill is desaturated, but this process was not simulated. Potential desaturation seems a more likely reason for the poor fit at well AD-5, given consistent agreement between measured and simulated levels in TG Well and other wells where cumulative water-level declines were less than 30 ft (fig. 58). Simulated and measured water-level declines agree

within carbonate wells Inyo-BLM 1 (fig. 58C) and Travertine Point 1 (fig. 52), which are 7 and 15 mi, respectively, from maximum simulated drawdown in the central Amargosa Desert (fig. 57). Hydrograph fits improved with RMS errors of less than 1 ft as observation wells were more distant from pumping wells. This was because water levels were affected less by seasonal pumping and assignment of pumping well locations.

Measured and simulated hydrographs agree from wells at the perimeter of the area affected by the central Amargosa Desert pumping, with RMS errors of 0.05–0.5 ft (fig. 59). Simulated water-level declines in well AD-1 agree with the measured decline from 1990–2018. The simulated rate of water-level decline in well NC-EWDP-Washburn-1X (deep) is about 20 percent steeper than the measured decline from 2000–2015. A steeper simulated trend is conceptually acceptable because rising water-level trends exist in wells north of well NC-EWDP-Washburn-1X (deep). Naturally rising trends in these wells likely mask the northern extent of the area affected by pumping in the central Amargosa Desert (fig. 57). Slight declines were measured and simulated in wells DIVJ-02 and WRPMW-4 along the southern and western extents, respectively, of the area affected by pumping in the central Amargosa Desert (fig. 59). Water-levels in well WRPMW-4 also were affected by local pumping in the Furnace Creek area that began during 2009 and a recharge event in 2010 (fig. 59D). Both regional and local pumping effects are simulated correctly (fig. 59).

Measured and simulated water-level trends in Pahrump Valley match, with RMS errors of 5–10 ft in hydrographs near pumping wells. Misfits increased with proximity to assigned pumping wells, as observed in wells GSA, SD2, and JAW that were less than 1, 1.5, and 5 mi, respectively, from the nearest pumping well (fig. 60). Misfits were less than 1 ft in well JAW, which was farthest from pumping wells. Near the center of pumping, fits between measured and simulated water-level changes were sufficiently close relative to measured changes in excess of 80 ft, such as was observed in well ESB1 (fig. 51).

Better agreement exists between simulated and measured water levels in the central Amargosa Desert (fig. 58), compared to Pahrump Valley (fig. 60). Differences in model fit between pumping centers possibly were caused by differences in estimated pumping in the central Amargosa Desert and Pahrump Valley. About 30 percent of the volume pumped in Pahrump Valley occurred prior to the first pumpage inventory of Pahrump Valley in 1959 (Nevada Division of Water Resources, 2018). Multiyear periods of estimated uniform pumping indicate uncertainty of pumping estimates from Pahrump Valley prior to 1959 (fig. 30). Pumpage from the central Amargosa Desert was inventoried intermittently from 1965–1983 and verified with imagery after 1973 (Moreo and others, 2003). Pumpage was inventoried consistently in the study area after 1984, when pumping from the central Amargosa Desert increased generally and Pahrump Valley decreased (fig. 30).




Figure 56. Comparison of simulated and measured transmissivities from the Death Valley Regional Flow System version 2 model (DVRFS.v2) and Death Valley version 3 steady-state model (DV3-SS), in the study area, Nevada and California.




Figure 57. Maximum simulated drawdown and selected observation sites with hydrographs shown in this report, in the study area, Nevada and California, 2018.




Figure 58. “Raw” water-level measurements and simulated and measured (average) water-level declines in wells *AD-5* (A), *TG Well* (B), and *Inyo-BLM 1* (C), in the central Amargosa Desert, Nevada and California, 1950–2018.




Figure 59. “Raw” water-level measurements and simulated and measured (average) water-level declines in wells AD-1 (A), NC-EWDP-Washburn-1X (deep) (B), DVJ-02 (C), and WRPMW-4 (D) that result from pumping in the central Amargosa Desert, Nevada and California, 1950–2018.




Figure 60. “Raw” water-level measurements and simulated and measured (average) water levels in wells *GSA* (A), *SD2* (B), and *JAW* (C), in Pahrump Valley, Nevada, 1910–2020.

Measured and simulated hydrographs agree from wells at the perimeter of the area affected by Pahrump Valley pumping, with RMS errors between 0.1 and 1 ft (fig. 61). Measured water levels consistently declined from 2005 to 2015, with total declines of 3.3 and 2.5 ft in wells *BLM Stewart Valley Well* and *Last Chance Well*, respectively. Measured water-level decline and recovery of 15 ft were matched within 1 ft in well *Jeep Trail* (fig. 61). Water levels were not measured from 1976 to 2004 in well *Jeep Trail*, but the pattern of simulated water levels declining gradually and recovering rapidly after 1997 is similar to the measured water-level trend in well *ESB1* (fig. 51). Simulated and measured water-level declines from 1959 to 1975 were both 13 ft in well *021N010E04L01S*, which was the southernmost well in Pahrump Valley with water-level data (fig. 57). Simulated and measured water-level declines from 2005 to 2015 were both 0.6 ft in well *Hwy 127 MM21-1*, west of the Amargosa River.

Measured and simulated discharges from *Bennetts* and *Manse Springs* compare favorably, but goodness of fit is more qualitative (fig. 62). A 2,400 acre-ft/yr (3.3 ft³/s) increase in discharge from *Bennetts Spring* between 1927 and 1937 suggests an undocumented alteration occurred. The orifice of *Bennetts Spring* was cleaned and deepened in 1941 and discharge increased 1,400 acre-ft/yr (2 ft³/s) (Harrill, 1986). Simulating these alterations would require estimating multiple pool altitudes and drain conductances that the available dataset cannot reasonably inform. Simulated discharges from both *Bennetts* and *Manse Springs* were sensitive to poorly known pumping rates and locations (fig. 62). Pahrump Valley spring observations accordingly were weighted less than other observation groups and contributed less than 1 percent of the error in the objective function (table 10).

Measured and simulated water-level trends in wells near isolated pumping centers agree but measured water levels are noisier (fig. 63). RMS errors approach cumulative water-level declines. These water levels were measured less than 1 mi from the pumping well or in the pumped well itself. For example, wells *WW-4* and *WW-4A* are 1,200 ft apart and pumped alternately for water supply in CP basin (fig. 57). Measured water levels frequently are recovering from recent pumping, where pumping and recovery cause water levels to be 10s of feet lower than the long-term water-level trend (fig. 63). The long-term declining trend in well *WW-4* is caused by the slow dewatering of basin fill in CP basin (fig. 63). Head losses in the well from periods of pumping and recovery were not simulated, but yearly changes have been matched. Similar noise exists near other isolated pumping centers, such as in well *USAF Well 3* in Indian Springs (fig. 63).

Estimated specific-yield and specific-storage distributions are better informed when more information is available. Specific-yield estimates of basin fill in the central Amargosa Desert and Pahrump Valley ranged from 0.1 to 0.3 (fig. 64). Specific yields less than 0.05 generally were estimated where consolidated rocks occurred at the water table. Storage coefficients (specific storage times thickness of layers 2–6) generally ranged from 0.0001 to 0.01, where estimable

(fig. 65). Storage coefficients exceeded 0.01 in Pahrump Valley, where specific-storage estimates were constrained by an upper limit of 1×10^{-5} 1/ft and basin fill was thicker than 1,000 ft.

Overestimated specific yields and storage coefficients in Pahrump Valley are compensating errors that likely resulted from not explicitly simulating subsidence. Thick clay sequences occur in the basin fill of Pahrump Valley. These clays have compacted inelastically in response to declining water levels, which resulted in land subsidence (Harrill, 1986, p. 11). Inelastic specific storages of 4×10^{-5} to 1×10^{-3} 1/ft have been estimated for similar clays in Las Vegas Valley (Harrill, 1976; Pavelko, 2004). Overestimating a storage coefficient by 0.1 would be similar to explicitly simulating a 500-ft thick clay with an inelastic specific storage of 2×10^{-4} 1/ft.

Well *ER-6-1-2 main* Multiple-Well Aquifer Test

Heterogeneous transmissivity and specific-yield distributions in shallow carbonate rocks beneath Yucca Flat were required to match drawdowns from the well *ER-6-1-2 main* MWAT within the limits of measurement uncertainty. A maximum drawdown of 1.9 ft was estimated in well *ER-7-1* (fig. 66), with little attenuation or delay, 6 mi north of well *ER-6-1-2 main* (fig. 47). Maximum drawdown was limited to less than 0.3 ft in well *ER-3-1-2 (shallow)* (fig. 66), 4 mi northeast of well *ER-6-1-2 main* (fig. 47). Pumping 75 million gallons from well *ER-6-1-2 main* did not affect water levels in well *UE-1h* (fig. 67), about 4 mi west of well *ER-6-1-2 main* (fig. 47). Drawdowns in wells *ER-7-1*, *ER-3-1-2 (shallow)*, and *UE-1h* are consistent with a north-south trending corridor of transmissive, shallow carbonate rocks that are bounded on the east and west by low-transmissivity rocks (fig. 68).

Lack of drawdown in shallow carbonate rocks in western Yucca Flat was replicated in the DV3-ER612 model. Measured and simulated drawdowns in well *UE-1h* indicate no response to pumping well *ER-6-1-2 main*, where the RMS error of 0.01 ft can be attributed entirely to drawdown-estimation error (fig. 67). Lack of drawdown was created by the juxtaposition of high-transmissivity carbonate rocks near well *ER-6-1-2 main*, with low-transmissivity volcanic-sedimentary rocks and underlying deep carbonate rocks at well *UE-1h*.

Measurable drawdowns in *Tracer Well 3* (fig. 67), which are caused by pumping well *ER-6-1-2 main* (fig. 68), indicate that a hydraulic connection exists between Yucca Flat and *Tracer Well 3*. This hydraulic connection has been reproduced plausibly because simulated and measured drawdowns in *Tracer Well 3* agree with an RMS error of 0.01 ft (fig. 67). A high-transmissivity corridor extending from Yucca Flat to the Ash Meadows discharge area was conceptualized to exist to better simulate drawdowns in *Tracer Well 3*, more than 33 mi from pumping well *ER-6-1-2 main* (fig. 68). This estimated high-transmissivity corridor is a consistent extension of the previously postulated megachannel (fig. 68; Winograd and Pearson, 1976).




Figure 61. “Raw” water-level measurements and simulated and measured (average) water-level changes in wells BLM Stewart Valley Well (A), Last Chance Well (B), Jeep Trail (C), 021N010E04L01S (D), 022N007E13L01S (E), and Hwy 127 MM21-1 (F) that result from pumping in Pahrump Valley, in the study area, Nevada and California, 1910–2020.




Figure 62. Comparison of simulated and measured discharges from *Bennetts* (A) and *Manse* (B) Springs, Pahrump Valley, Nevada, 1910–2018.




Figure 63. “Raw” water-level measurements and simulated and measured (average) water-level changes in well *WW-4* in CP basin (*A*), and *USAF Well 3* in Indian Springs (*B*), Nevada, 1950–2018.




Figure 64. Estimated specific-yield distribution and pilot points from integrated Death Valley version 3 model, in the study area, Nevada and California.




Figure 65. Estimated storage-coefficient distribution, which is specific storage times thickness of model layers 2–6, and pilot points from integrated Death Valley version 3 model, in the study area, Nevada and California.




Figure 66. Periods when well *ER-6-1-2 main* pumped; simulated drawdowns from Death Valley version 3 model simulating pumping during the *ER-6-1-2 main* multiple-well aquifer test (DV3-ER612); and measured drawdowns, which were estimated from water-level models (Jackson and Halford, 2019), in wells *ER-3-1-2 (shallow)* (A), and *ER-7-1* (B), Nevada, 2004–05.




Figure 67. Periods when well *ER-6-1-2 main* pumped; simulated drawdowns from Death Valley version 3 model simulating pumping during the *ER-6-1-2 main* multiple-well aquifer test (DV3-ER612); and measured drawdowns, which were estimated from water-level models (Jackson and Halford, 2019), in wells *UE-1h* (A), and *Tracer Well 3* (B), Nevada, 2004–05.




Figure 68. Estimated transmissivity distribution from integrated Death Valley version 3 model (DV3), extent of megachannel, and observation sites during well *ER-6-1-2 main* multiple-well aquifer test, in the study area, California and Nevada.

Ash Meadows And Devils Hole

Simulated and measured predevelopment discharges, spring-pool altitudes, water-level changes from pumping, and spring captures were compared in the Ash Meadows discharge area to evaluate goodness of fit. Predevelopment discharges totaled 10,000 gal/min (16,150 acre-ft/yr) from all springs in the Ash Meadows discharge area, which is more than 60 percent of all predevelopment discharges from both AFFCR and Ash Meadows groundwater basins (table 4). Average and RMS spring-pool altitude errors of -8 and 32 ft, respectively, are acceptable errors, even though the errors are noticeable relative to a 160 ft head difference between *Devils Hole* and *Crystal Pool* (fig. 69). Distributions of simulated hydraulic conductivities in the Ash Meadows discharge area could be improved, but errors mostly affect simulated water-level changes and spring captures from local pumping.

Predevelopment spring-pool altitudes and discharges in the Ash Meadows discharge area were better simulated with the DV3-SS model than the DVRFS.v2 model (fig. 69). Measured and simulated discharges agreed perfectly for each spring in the Ash Meadows discharge area because discharges were specified in the DV3-SS model (fig. 69). However, measured and simulated discharges are dissimilar at each spring and in aggregate for the DVRFS.v2 model. Simulated discharges from the DVRFS.v2 model varied little between springs compared to measured spring discharges that ranged from 5 to 2,940 gal/min (0.01 and 6.55 ft³/s; table 9). Simulated discharge from *Crystal Pool* in the DVRFS.v2 model differed most and was 15 percent of measured discharge (fig. 69). Simulated discharges from the DVRFS.v2 model summed to slightly more than one-half of measured discharge from all springs in the Ash Meadows discharge area. Average and RMS spring-pool altitude errors of -54 and 68 ft from DVRFS.v2 are substantial errors. Misfits were larger where measured spring-pool altitudes exceeded 2,280 ft (fig. 69).

Water-level changes in *Devils Hole* and other wells in the megachannel (fig. 53) were evaluated differently during calibration from water-level changes in the remaining wells in the DV3-AM-AFFCR model. A different type of evaluation was required because long-term, natural water-level fluctuations were substantial in the Devils Hole area relative to effects of groundwater development. Simulated water-level changes in *Devils Hole* and nearby wells were fit in the objective function to measured water-level changes minus long-term, natural water-level fluctuations from recharge. The difference between measured and long-term natural fluctuations from recharge is assumed to represent pumping effects. Effects of pumping were simulated with the DV3-AM-AFFCR model and long-term, natural water-level fluctuations

were simulated with an analytical water-level model for *Devils Hole* (fig. 40) and other nearby wells (fig. 53). Hydrographs are presented with the original water-level measurements and simulated water levels that are the summation of numerical (DV3-AM-AFFCR) and analytical models (fig. 70).

Measured and simulated water-level changes in *Devils Hole* agree, with an RMS error of 0.2 ft (fig. 70). Overall, water-level trends and responses to pumping stresses agreed well throughout the nearly 70-year period of record. Misfits between measured and simulated water-level changes were greatest during initial recovery from cessation of pumping by Cappaert Enterprises after 1976 (fig. 38). This misfit most likely resulted from underestimating spring capture and overestimating specific yield in the Ash Meadows discharge area of the DV3-AM-AFFCR model (fig. 64). Errors in estimated long-term natural fluctuations from recharge also contributed to misfits between measured and simulated water-level changes in *Devils Hole*.

Measured water-level changes in wells *Spring Meadows 12*, *North Crystal Well*, and *Tracer Well 3* are similar to changes in *Devils Hole* and are matched by their respective simulated water-level changes in the DV3-AM-AFFCR model (figs. 53 and 70). A systematic decline of about 1 ft occurred in all wells between 1965 and 1995. Simulated water levels suggested that water levels in all wells responded to pumping by Cappaert Enterprises and declined prior to 1980. All wells were inferred to be affected strongly by the megachannel because water levels respond consistently to pumping and earthquake stresses. Simulated water-level changes in these wells agree with the conceptual model of the megachannel as an areally extensive, highly transmissive feature in the shallow-carbonate rocks (fig. 53).

Changes in measured and simulated spring discharges agree in the Ash Meadows discharge area of the DV3-AM-AFFCR model. Measured and simulated spring discharges in Ash Meadows agreed with an average RMS error of 120 gal/min (0.3 ft³/s). This error is similar to seasonal fluctuations in the absence of pumping (fig. 71) and is small relative to measured discharges that ranged from 5 to 2,900 gal/min (0.01 and 6.6 ft³/s). Periods of complete capture in *Jack Rabbit Spring* were simulated correctly during the summer from 1970 to 1977. Simulated recovery lagged behind measured recovery in *Jack Rabbit Spring* from 1978 to 1980 and likely resulted from locally overestimated specific yields. Capture was overestimated in *Point of Rocks Spring* but seasonal fluctuations were simulated correctly (fig. 71). Simulated changes in spring discharges in *Big Spring* replicated measured seasonal fluctuations and recovery within the uncertainty of measured discharges (fig. 71).




Figure 69. Measured, and DV3-SS- and DVRFS.v2-simulated pool altitudes (top graph) and spring discharges (middle graph), and total measured and simulated spring discharges (bottom graph), in the Ash Meadows discharge area, Nevada. DV3-SS, Death Valley version 3 steady-state model; DVRFS.v2, Death Valley Regional Flow System version 2 model; NGVD29, National Geodetic Vertical Datum of 1929; RMS, Root-mean-square error.




Figure 70. “Raw” water-level measurements, measured (average) water-level changes, and simulated water-level changes (summation of pumping from DV3-AM-AFFCR model and long-term natural fluctuations—recharge, steady discharge, and earthquakes—from analytical water-level model) in the megachannel, including wells *Tracer Well 3* (A), *North Crystal Well* (B), and *Spring Meadows 12* (C), and *Devils Hole* (D), Nevada, 1950–2018. DV3-AM-AFFCR, Death Valley version 3 model simulating groundwater development in the Ash Meadows, Alkali Flat–Furnace Creek Ranch, and Pahute Mesa–Oasis Valley groundwater basins.




Figure 71. Monthly pumping by Cappaert Enterprises; injection into *Devils Hole Well* (AM-5); total simulated capture in the Ash Meadows discharge area from DV3-AM-AFFCR model (A); and hydrographs showing measured and simulated (DV3-AM-AFFCR model) discharges from *Jack Rabbit* (B), *Point of Rocks* (C), and *Big* (D) Springs, Nevada, 1968–82. DV3-AM-AFFCR, Death Valley version 3 model simulating groundwater development in the Ash Meadows, Alkali Flat–Furnace Creek Ranch, and Pahute Mesa–Oasis Valley groundwater basins.

Groundwater flow in the Ash Meadows discharge area is better simulated with the DV3 model than the DVRFS.v2 model partly because the DV3 model was calibrated as an integrated stress-response model (fig. 48). Separately simulating predevelopment flow and changes from groundwater development constrained calibration and minimized compensating errors. For example, predevelopment discharge of 630 gal/min (1.4 ft³/s) from *Jack Rabbit Spring* was simulated correctly with the DV3-SS model, but the simulated spring pool was 22 ft lower than the measured altitude (fig. 69). Capture from *Jack Rabbit Spring* was simulated correctly with a 2 ft extinction depth in the DV3-AM-AFFCR model (fig. 71). Simulating these conditions with a drain in a single model would create compensating errors. Predevelopment discharge would be 0 with an extinction depth of 2 ft or little capture would be simulated with an extinction depth greater than 22 ft. Extinction depths seem overestimated in the DVRFS.v2 model because simulated capture from all springs in the Ash Meadows discharge area never exceeded 40 gal/min (0.09 ft³/s), whereas maximum measured capture totaled 3,800 gal/min (8.5 ft³/s).

Hydrologic Features

Major hydrologic features have been identified in the study area that the DV3 model must replicate (table 12). Simulated adequacy of these major hydrologic features was evaluated qualitatively because many aspects of these features remain conceptual. Conceptual models of these hydrologic features were developed from limited measurements from wells and springs, which limits the ability to quantify model misfit. Quantification was limited further where conceptual models depended on water quality and other measured quantities that were not simulated explicitly. For example, existence of a megachannel upgradient of the Ash Meadows discharge area was postulated primarily on anomalous ¹⁴C concentrations in discharge from *Crystal Pool* (Winograd and Pearson, 1976).

Agreement between numerical and conceptual models of major hydrologic features was evaluated with water-level profiles, transmissivity estimates, and hydrographs. Numerical model results were considered improved where measured and simulated gradients between wells along a profile agreed (fig. 72). Total simulated transmissivities along a profile explained water-level gradients, characterized groundwater-basin boundaries, and identified extremely transmissive and impermeable hydrologic features.

Water Table Beneath Rainier Mesa

Nuclear tests in tunnels beneath Rainier Mesa occurred within 300 ft of the shallow (perched and semi-perched) water table (U.S. Department of Energy, 2018), which makes the shallow water table a major hydrologic feature. Perched and semi-perched water-table mounds cause elevated water levels in the study area. Maximum altitude of the shallow water-table mound is about 6,200 ft above NGVD29 (fig. 73, A–A') and is within 0.5 miles of well *ER-12-3 piezometer* (shown as borehole ER-12-3 on fig. 72). Limited recharge to the shallow water table moves through volcanic rocks that primarily are zeolitized tuffs with hydraulic conductivities of 1×10^{-5} ft/d (0.004 ft/yr). This recharge ultimately will discharge in either the PMOV, AFFCR, or Ash Meadows groundwater basin (U.S. Department of Energy, 2018).

Measured and simulated water tables beneath Rainier Mesa generally agree (fig. 73, A–A'), which is a prerequisite for correctly associating recharge with the location of its ultimate discharge. Elevated water levels in the study area generally coincide with areas of low transmissivity, except beneath the perched water table where higher transmissivity occurs in deep carbonate rocks beneath the low-transmissivity volcanic rocks (fig. 73, A–A'). For example, the top of the perched water table near well *ER-12-3 piezometer* in zeolitized tuff is about 1,800 ft higher than water levels in well *ER-12-3 main* (shown as borehole ER-12-3 in fig. 72), open to underlying carbonate rocks. The perched water table is controlled by vertical movement through low-permeability volcanic tuff. Correctly simulating the perched water table beneath Rainier Mesa became an objective because this hydrologic feature had not been simulated adequately by the DVRFS.v2 model.

Boundary Between AFFCR and PMOV Groundwater Basins

The boundary between PMOV and AFFCR groundwater basins is a major hydrologic feature. The boundary between PMOV and AFFCR groundwater basins from Bare Mountain to Rainier Mesa (fig. 72) has been interpreted as a no-flow boundary along a groundwater-flow path (Fenelon and others, 2016), which has implications for radionuclide transport. If this boundary is a no-flow boundary, then contamination from nuclear testing beneath Pahute Mesa in the northwestern part of the NNSS will not migrate into the AFFCR groundwater basin. The boundary between PMOV and AFFCR groundwater basins was less certain than other PMOV boundaries because this boundary was defined based on predevelopment water levels and discharges, rather than a topographic or groundwater divide (Fenelon and others, 2016). This boundary was not simulated explicitly as a no-flow boundary; instead, predevelopment water levels and discharges were matched to simulated equivalents to determine whether a no-flow boundary is substantiated based on groundwater-flow paths.

Table 12. Summary of major hydrologic features simulated in the integrated Death Valley version 3 model (DV3), for the study area, Nevada and California.

[Abbreviations: AFFCR, Alkali Flat–Furnace Creek Ranch; PDVS, Pahrump to Death Valley South; PMOV, Pahute Mesa–Oasis Valley]

Significant hydrologic feature	Reason for significance	Relevant water-level profiles
Perched water-table mound beneath Rainier Mesa	Nuclear tests in tunnels beneath Rainier Mesa occur within 300 feet of the shallow (perched) water-table mound.	A-A'
Boundary between PMOV and AFFCR groundwater basins	Contamination from nuclear testing beneath Pahute Mesa potentially can migrate into AFFCR groundwater basin if the boundary is not a no-flow boundary. A no-flow boundary was determined in DV3 model based on fitting predevelopment water levels and discharges to simulated equivalents.	B-B' and C-C'
Megachannel in shallow carbonate rocks between northern Yucca Flat and Ash Meadows discharge area	Conceptual feature initially postulated immediately upgradient of Ash Meadows discharge area that explained hydrochemical variations between Ash Meadows springs. High hydraulic diffusivity of the shallow-carbonate megachannel causes drawdowns to propagate quickly and recover slowly.	D-D' and E-E'
Gravity fault in Ash Meadows discharge area	Gravity fault causes the juxtaposition of low-permeability basin fill (clay, silt, and fine-grained sand) in central Amargosa Desert with highly transmissive carbonate rocks in Ash Meadows discharge area. Gravity fault impedes groundwater flow and causes water to discharge from springs in Ash Meadows discharge area.	E-E'
Well AD-4 corridor	Well AD-4 corridor hydraulically connects Ash Meadows and AFFCR groundwater basins. Most of the flow that enters the AFFCR basin occurs through this corridor. Transmissive basin fill and carbonate rocks along the Gravity fault north of Ash Meadows discharge area allow for upwelling water in the carbonate to move into basin fill in the Amargosa Desert.	F-F' and G-G'
Furnace Creek Wash	Furnace Creek Wash allows regional groundwater flow to be conveyed to the alluvial fan on the Death Valley floor, where groundwater discharges by evapotranspiration from phreatophytes.	H-H'
Water table beneath Black Mountains and Greenwater Range	Black Mountains and Greenwater Range are interpreted as barriers to groundwater flow based on most recent water-table interpretations from all available data. The barrier impedes groundwater movement from central Amargosa Desert to Death Valley through the Black Mountains and Greenwater Range. In the PDVS groundwater basin, the barrier impedes groundwater flow beneath the Amargosa River to Death Valley through the Black Mountains.	I-I'
Continuous aquifer of carbonate rocks and basin fill between Spring Mountains and Amargosa River	Transmissive basin fill and carbonate rocks form a continuous aquifer between the principal recharge area in the Spring Mountains and discharge areas along the Amargosa River in the PDVS groundwater basin. Formation of a continuous aquifer has implications for pumping effects in Pahrump Valley, where drawdowns can propagate downgradient toward the Amargosa River.	J-J'




Figure 72. Estimated transmissivity distribution from integrated Death Valley version 3 model and traces of water-level profiles through major hydrologic features, in the study area, Nevada and California. See figures 73–79 for water-level profiles A–A' through J–J'.




Figure 73. Measured water-level profile and simulated water-level profiles from Death Valley Regional Flow System version 2 model (DVRFS.v2) and Death Valley version 3 steady-state model (DV3-SS) (top graph), and transmissivity profile from the DV3-SS model (bottom graph), through Rainier Mesa, Nevada. Trace of water-level profile A–A' is shown in figure 72.

Interpreting the boundary between PMOV and AFFCR groundwater basins as a no-flow boundary differs from previous conceptualizations (Waddell, 1982; Lacznia and others, 1996). In previous conceptualizations, groundwater flowed southward from Pahute Mesa, across the current boundary between PMOV and AFFCR groundwater basins, and towards Yucca Mountain (Lacznia and others, 1996). The conceptualization was developed with fewer wells and inaccurate predevelopment-discharge estimates from Oasis Valley and Franklin Lake of 2,000 and 10,000 acre-ft/yr, respectively (Walker and Eakin, 1963; Waddell, 1982; Czarnecki and Waddell, 1984). Current discharge estimates from Oasis Valley and Franklin Lake total about 6,200 and no more than 700 acre-ft/yr, respectively (table 4).

The DV3-SS model implicitly simulated a no-flow boundary between the PMOV and AFFCR groundwater basins from Bare Mountain to Rainier Mesa (fig. 72). The measured water-level profile perpendicular to the boundary in Buckboard Mesa shows a notable difference in lateral gradients from well ER-18-2 (fig. 74, B–B'), indicating groundwater movement to the north and south of the boundary. Measured and simulated water levels have similar altitudes perpendicular to the boundary south of Timber Mountain (fig. 74, C–C'), indicating a lack of potential for flow across the boundary. Simulated flow perpendicular

to the PMOV and AFFCR boundary is restricted by low transmissivity (fig. 74, B–B') or small lateral gradients (fig. 74, C–C') relative to gradients parallel to the boundary.

Megachannel

The megachannel (fig. 72) is a major hydrologic feature of the Ash Meadows groundwater basin because drawdowns within this feature propagate quickly and recover slowly. The megachannel initially was presented as a conceptual feature that explained hydrochemical variations between large springs in the Ash Meadows discharge area (fig. 72; Winograd and Pearson, 1976). The megachannel was delineated in this report as a contiguous extent of shallow carbonate rocks where transmissivity exceeds 20,000 ft²/d (fig. 72). The boundary of the megachannel was generalized around areas of low transmissivity in the Ash Meadows discharge area and extended into northern Yucca Flat (fig. 72). The northern extent includes well UE-10j (2232–2297 ft) because drawdowns from pumping well ER-4-1 m1 were detected 5.7 mi north in well UE-10j (2232–2297 ft) (fig. 68; Jackson, 2017). The megachannel as delineated in this report primarily differs from Winograd and Pearson (1976) by extending into Yucca Flat (fig. 72). This extension is well defined by measurable drawdowns in Tracer Well 3 from pumping well ER-6-1-2 main (figs. 67–68).




Figure 74. Measured and simulated water-level profiles (top graph and third graph from top), and transmissivity profiles from the Death Valley version 3 steady-state model (DV3-SS) (second and fourth graphs from top), through boundary between Pahute Mesa–Oasis Valley (PMOV) and Alkali Flat–Furnace Creek Ranch (AFFCR) groundwater basins, Nevada. NGVD29, National Geodetic Vertical Datum of 1929. Traces of water-level profiles B–B' and C–C' are shown in figure 72.

The megachannel is characterized by carbonate rock with high transmissivities and low storativities (specific yield plus storage coefficient). In unconfined areas of the shallow-carbonate megachannel, specific yields were spatially variable and averaged 0.04. In confined areas of the megachannel, confined storage coefficients averaged 0.0001. High transmissivities and low storativities resulted in broad areas with hydraulic diffusivities greater than 1,000,000 ft²/d. Hydraulic diffusivities increased where overlying saturated basin fill locally reduced hydraulic connection between carbonate rocks and the water table.

High hydraulic diffusivities caused relatively uniform declines of 2 ft in the megachannel between 1970 and 1980 from pumping by Cappaert Enterprises (fig. 70). About 20,000 acre-ft of water drained from 250,000 acres in the megachannel between 1970 and 1980, which about equals net pumpage from Cappaert Enterprises minus spring capture in the Ash Meadows discharge area (fig. 38). Water levels in the megachannel recovered slowly during the ensuing decades after 1980 because surrounding rocks had low hydraulic diffusivities and did not readily release additional water (fig. 70).

Measured and simulated water-level profiles through the megachannel agree closely (fig. 75). Measured and simulated gradients between wells WW-2 (3422 ft) and Tracer Well 3 both averaged 1.0 ft/mi between northern Yucca Flat and Amargosa Flat (fig. 75, D–D'). Simulated gradients between well Army 1 WW and Devils Hole averaged 0.9 ft/mi, but were not as flat as measured gradients of 0.3 ft/mi (fig. 75, E–E'). Corresponding simulated transmissivities of the megachannel ranged from 10,000 to 10,000,000 ft²/d. Maximum simulated transmissivities locally exceed aquifer-test results in the megachannel by twentyfold, which would seem troubling if transmissivities between wells were not considered. Simulated transmissivity results were questioned and compared to Darcy estimates of transmissivity between well Army 1 WW and Devils Hole. Darcy estimates of transmissivity ranged from 1,000,000 to 2,000,000 ft²/d, which is consistent with simulated transmissivities. Steep gradients between Devils Hole and Crystal Pool were simulated correctly with both simulated and measured gradients averaging 5 ft/mi (fig. 75, E–E'). Steepening gradients were simulated with a three-order-of-magnitude decrease in transmissivities.

Gravity Fault

Water levels and simulated transmissivities from Crystal Pool to Franklin Well are consistent with basin fill west of the Gravity fault in the Ash Meadows discharge area impeding groundwater flow (fig. 75, E–E'). Basin fill in this area consists of clay, silt, and fine-grained sand of lacustrine origin (Walker and Eakin, 1963). Clay content exceeds 80 percent through more than 1,000 ft of basin fill (Oatfield and Czarnecki, 1989), with extensive deposits of bentonite and zeolite being mined north and south of section E–E' (Castor and others, 2006). Simulated water levels, discharges, and transmissivities are

consistent with previous interpretations of the Gravity fault being a groundwater barrier that "...is caused by normal faulting of the poorly permeable Cenozoic rocks against the lower carbonate aquifer," (Winograd and Thordarson, 1975; p. C82).

Well AD-4 Corridor

The well AD-4 corridor is a major hydrologic feature that hydraulically connects Ash Meadows and AFFCR groundwater basins (fig. 72; fig. 76, F–F', G–G'). Most groundwater that flows from the Ash Meadows groundwater basin to the AFFCR groundwater basin flows through a 5-mi-wide corridor around well AD-4, where water upwells from underlying carbonate rocks to overlying basin fill. The area of upwelling water extends west to east about 2 mi between wells HA-AD68 and AD-4 (fig. 76, F–F') and south to north about 5 mi between wells HA-AD67 and NC-GWE-FELDERHOFF 25-01PA (fig. 76, G–G'). Water levels in the well AD-4 corridor are elevated 50–90 ft higher than water levels in wells immediately south, west, and north of the area of upwelling (fig. 76), which precludes all other sources of water other than flow from the underlying carbonate rocks.

Measured and simulated water levels through the well AD-4 corridor agree in profiles west to east and south to north (fig. 76). Simulated transmissivities are consistent with a corridor of limited lateral extent. Continuously transmissive rocks were simulated from west to east (fig. 76, F–F') and from south to north (fig. 76, G–G') through the 5-mi-wide corridor beneath well AD-4. These transmissivity profiles are qualitative and do not represent all hydraulic components because vertical flow is not depicted explicitly and flow through the well AD-4 corridor is limited by lower transmissivities of basin fill farther west of the F–F' profile. Simulated transmissivities west of well AD-4 ranged from 300 to 3,000 ft²/d, which are consistent with measured specific capacities of 3–5 ([gal/min]/ft).

Furnace Creek Wash

Furnace Creek Wash is a major hydrologic feature that allows regional groundwater flow to discharge from the alluvial fan on the Death Valley floor (fig. 9; fig. 72, H–H'). Measured and simulated water-level profiles closely agree (fig. 77), which was required to match the predevelopment water budget in the Furnace Creek area. The DV3-SS model simulated 5.8 ft³/s (4,170 acre-ft/yr) of groundwater entering Furnace Creek Wash, which is within a few percent of the predevelopment estimate of 5.6 ft³/s (4,100 acre-ft/yr) being conveyed into Furnace Creek Wash (fig. 77). Simulated, predevelopment-groundwater flow leaves Furnace Creek Wash either from diversions or as subsurface flow. Furnace Creek Wash buried tile and sump, and the Furnace Creek Inn Tunnel (fig. 77) diverted 2.0 ft³/s (1,500 acre-ft/yr). Subsurface flow of 3.8 ft³/s (2,700 acre-ft/yr) exits Furnace Creek Wash near Furnace Creek Inn Tunnel, flows downgradient, and discharges by ET_{GW} from the alluvial fan (fig. 77).




Figure 75. Measured and simulated water-level profiles (top graph and third graph from top), and transmissivity profiles from the Death Valley version 3 steady-state model (DV3-SS) (second and fourth graphs from top), through megachannel from Yucca Flat to the Ash Meadows discharge area, Nevada and California. NGVD29, National Geodetic Vertical Datum of 1929. Traces of water-level profiles *D–D'* and *E–E'* are shown in figure 72.




Figure 76. Measured and simulated water-level profiles (top graph and third graph from top), and transmissivity profiles from the Death Valley version 3 steady-state model (DV3-SS) (second and fourth graphs from top), through the well AD-4 corridor, Nevada and California. NGVD29, National Geodetic Vertical Datum of 1929. Traces of water-level profiles $F-F'$ and $G-G'$ are shown in figure 72.




Figure 77. Measured and simulated water-level profiles (top graph), and transmissivity profile from the Death Valley version 3 steady-state model (DV3-SS) (bottom graph), through the Furnace Creek area, California. NGVD29, National Geodetic Vertical Datum of 1929. Trace of water-level profile $H-H'$ is shown in figure 72.

Water Table Beneath Black Mountains and Greenwater Range

The Black Mountains and Greenwater Range are major hydrologic features that have been interpreted inconsistently. The water table beneath the Black Mountains and Greenwater Range was interpreted initially as a smoothly sloping surface from the Amargosa River on the east to the floor of Death Valley on the west (fig. 72) and originated from “...a hand-contoured ground-water elevation map interpreted by the Denver Office of the USGS and transferred to PNL on March 31, 1982” (Rice, 1984, p. 22). The sloping water table was simulated with the DVSS2 model (table 1; D’Agnese and others, 2002, p. 88).

The water table alternatively has been interpreted as a perched mound beneath the Black Mountains and Greenwater Range (D’Agnese and others, 1998, plate 1). Additional wells were inventoried in the Greenwater Range since 1982 and influenced the reinterpretation (Kilroy, 1991, plate 1). The mounded water table was the conceptual model for flow beneath the Black Mountains and Greenwater Range in DVRFS.v1 (Faunt, D’Agnese, and O’Brien, 2010, p. 139), but was simulated as a sloping water table. A mounded water table of limited north-south extent was simulated with the DVRFS.

v2 model (Belcher and others, 2017, p. 44), but the conceptual model was a sloping water table (Belcher and others, 2017, plate 1). In the DVRFS.v2 model, the limited north-south extent of the perched water-table mound did not preclude flow through the Black Mountains and Greenwater Range because about 5,000 acre-ft/yr of discharge was simulated from the Death Valley floor south of the Furnace Creek area. Simulated groundwater flow in the DVRFS.v2 model moved around the limited extent of the perched water-table mound. However, more recent data indicate that the Black Mountains and Greenwater Range more likely behave as hydraulic barriers.

The Black Mountains and Greenwater Range are interpreted in this study as barriers to groundwater flow based on the most recent water-table interpretations from all available data. The barrier impedes groundwater movement from the central Amargosa Desert to Death Valley through the Black Mountains and Greenwater Range. In the PDVS groundwater basin, the barrier also impedes movement of groundwater flow beneath the Amargosa River to Death Valley through the Black Mountains (fig. 72). The Black Mountains and Greenwater Range consist of bedded tuffs and clastic, crystalline, and intrusive rocks (Sweetkind and others, 2001, plate 3), which are typically impermeable rocks.

Steep hydraulic gradients and potential for limited local recharge indicate that the Black Mountains and Greenwater Range are low-transmissivity features. For example, water levels increase 2,475 ft between well *020N004E09K001S* and *Virgin Spring* in the Black Mountains (fig. 78, I–I'), which are a mapped distance of 8 mi apart (fig. 72), resulting in a hydraulic gradient greater than 300 ft/mi. Black Mountains and Greenwater Range are conceptualized as low-transmissivity features, which limits the amount of recharge. Local recharge rates do not exceed 0.001 ft/yr (fig. 16) and can generate no more than 9 acre-ft/yr/mi (0.2 ft³/d/ft) between well *KJ-2* and *021N004E15R002S*. This limits average transmissivity to less than 10 ft²/d in the Black Mountains and Greenwater Range and is consistent with simulated transmissivities (fig. 78, I–I').

Continuous Aquifer of Carbonate Rocks and Basin Fill in PDVS Groundwater Basin

Carbonate rocks and basin fill form a continuous aquifer between recharge in the Spring Mountains and discharge along the Amargosa River (fig. 72; fig. 79, J–J'). This conceptualization differs little from previous interpretations (Harrill, 1986, p. 27). Transmissive intervals primarily are hosted by carbonate rocks in the mountain blocks and basin fill in the valleys. *Bennetts* and *Manse* Springs occur at the contact between the alluvial fan and valley floor primarily because of a break in slope, not a reduction in transmissivity (fig. 79, J–J'). Transmissivity generally decreases from east to west between the Nopah Range and Amargosa River regardless of host rocks (fig. 72; fig. 79, J–J'). Measured and simulated water-level profiles from the Spring Mountains to the Amargosa River generally agree (fig. 79, J–J').

Simulated Predevelopment Groundwater Flow

Predevelopment groundwater flow was characterized with the calibrated DV3-SS model. Recharge-source areas were mapped for each major discharge area with particle tracking. Groundwater flow was simulated from the Ash Meadows groundwater basin to the Furnace Creek area through the well *AD-4* corridor. The Furnace Creek flow conceptualization is presented, which integrates results from previous investigations and compares the DV3 conceptualization to alternative conceptualizations. Simulated predevelopment water budgets were extracted for subareas in each groundwater basin. The simulated water budget also was extracted for the Rainier Mesa groundwater sub-basin because radionuclides from underground nuclear tests can migrate farther into the AFFCR, Ash Meadows, and (or) PMOV groundwater basins.

Recharge and Discharge Areas

Recharge and discharge areas were paired for predevelopment flow with particle tracking (Pollock, 2012). Particles were backward-tracked from *Bennetts*, *Manse*, and *Stump* Springs in Pahrump Valley and from discharge areas in Oasis Valley, Ash Meadows, Lower Amargosa, and Furnace Creek to contributing recharge areas. Particles were seeded on the faces of cells where simulated discharge occurred. Each particle represented 50 acre-ft/yr, where the number of particles apportioned to each cell face was based on the total simulated discharge from each cell. Discharge from all analyzed areas totaled 47,000 acre-ft/yr and was backward-tracked with 940 particles. Connections between the initial particle location in the discharge area and the terminus at the water table in a recharge area are shown with pathlines (fig. 80). Areas with greater pathline densities represented areas with higher groundwater-flow rates. Pathlines were generated using an assigned effective porosity of 10 percent for basin fill and volcanic-sedimentary rocks, and an assigned effective porosity of 1 percent for fractured carbonate, volcanic, and low-permeability rocks.

Recharge also was mapped and differentiated between five major discharge areas by forward-tracking from the water table to discharge areas. The five major discharge areas were Oasis Valley, Ash Meadows, Furnace Creek, Lower Amargosa, and Pahrump and Stewart Valleys. The contributing recharge area for Pahrump and Stewart Valleys included all discharge from springs and ET areas. Particles were seeded at the water table in model cell centers where simulated recharge rates exceeded 0.0001 ft/d (fig. 45). Each cell at the water table was mapped to one of the five discharge areas (fig. 80). Recharge areas were not mapped if they contributed to minor discharge areas, such as Death Valley, Franklin Lake, and Saratoga Spring area. Mapped recharge areas supply 86 percent of discharge from the study area. Groundwater-flow paths calculated by backward-tracking from discharge areas (pathlines) and forward-tracking from recharge areas (shading) are shown in figure 80.

Pahute Mesa is the primary recharge area contributing to discharge from Oasis Valley (fig. 80). Other highland areas that contribute recharge in the PMOV groundwater basin include Black Mountain, Timber Mountain, Cactus Range, and Kawich Range. Simulated contributing recharge areas for Oasis Valley generally agree with the previously delineated PMOV groundwater basin (Fenelon and others, 2016). Minor differences exist beneath Bare Mountain, east of the Belted Range, and north of Rainier Mesa (fig. 80).




Figure 78. Measured and simulated water-level profiles (top graph), and transmissivity profile from the Death Valley version 3 steady-state model (DV3-SS) (bottom graph), through the Black Mountains and Greenwater Range, California. NGVD29, National Geodetic Vertical Datum of 1929. Trace of water-level profile I-I' is shown in figure 72.




Figure 79. Measured and simulated water-level profiles (top graph), and transmissivity profile from the Death Valley version 3 steady-state model (DV3-SS) (bottom graph), from the Spring Mountains to the Amargosa River, Nevada and California. NGVD29, National Geodetic Vertical Datum of 1929. Trace of water-level profile J – J' is shown in figure 72.




Figure 80. Groundwater-flow paths to selected discharge areas and contributing recharge areas for discharge areas in Oasis Valley, Ash Meadows, Furnace Creek, Lower Amargosa, and Pahrump and Stewart Valleys, Nevada and California.

The Ash Meadows discharge area predominantly is recharged from the Spring Mountains and Sheep Range in the southern and eastern Ash Meadows groundwater basin (fig. 80). Less than 5 percent of the discharge is recharged from the Desert, Pintwater, Spotted, Pahrnatagat, and Groom Ranges. Between the Pahrnatagat and Groom Ranges (fig. 80), groundwater in shallow carbonate rocks contributes to discharge in the AFFCR groundwater basin, whereas groundwater in deep carbonate rocks contributes to discharge in Ash Meadows groundwater basin. Flow from basin fill in southeast Frenchman Flat into shallow carbonate rocks ultimately will discharge in the Ash Meadows discharge area. Simulated flow through shallow carbonate rocks is consistent with hydrochemical interpretations of calcium-magnesium-sodium-bicarbonate type waters that discharge from springs in the Ash Meadows discharge area (Winograd and Thordarson, 1975).

Bennetts and *Manse* Springs were primary discharges in Pahrump Valley prior to development and were recharged from the central Spring Mountains in the northern PDVS groundwater basin (fig. 80). *Stump* Spring is a relatively minor discharge of less than 300 acre-ft/yr that is recharged in the southwestern Spring Mountains (fig. 80). All recharge for springs in Pahrump Valley flowed through carbonate rocks prior to discharging from *Bennetts*, *Manse*, or *Stump* Springs.

Discharge in the Lower Amargosa area primarily is recharged in the Spring Mountains (fig. 80). Contributing recharge areas to the Lower Amargosa area extend north and south of the recharge areas for *Bennetts* and *Manse* Springs in the central Spring Mountains. About 10 percent of the discharge from the Lower Amargosa area is recharged in the Nopah, Resting Spring, and Greenwater Ranges. More flow was simulated through the northern Nopah Range into Chicago Valley than through the southern Nopah Range near California Valley (fig. 80).

Pathlines from recharge in the Spring Mountains to discharge along the Amargosa River show that carbonate rocks and basin fill form a continuous aquifer in the PDVS groundwater basin. Water recharges the carbonate rocks in the Spring Mountains, moves through basin fill and shallow carbonate rock beneath Pahrump Valley, and leaves Pahrump Valley through carbonate rocks in the Nopah Range (fig. 81). Groundwater flows through the northern part of the Nopah Range, Chicago Valley, and the southern part of the Resting Spring Range, and discharges near the Amargosa River. Groundwater flow functionally ceases west of the Amargosa River because of the exclusive occurrence of low-permeability rocks (fig. 32). Increasing occurrence of low-permeability rocks from east to west affects groundwater flow more than whether carbonate rocks or basin fill occur along the flow path.

Flow from Ash Meadows Groundwater Basin to the Furnace Creek Area

Discharge in the Furnace Creek area is atypical in the study area because a substantial part of the discharge is recharged in another groundwater basin (fig. 80). The Furnace Creek area is in Death Valley on the western edge of the AFFCR groundwater basin. More than 40 percent of the discharge in the Furnace Creek area is sourced from the Ash Meadows groundwater basin, with the remaining Furnace Creek discharge derived from the AFFCR groundwater basin (Fenelon and others, 2016).

Hydraulic connection between Ash Meadows groundwater basin and the Furnace Creek area has been explained with two alternative flow-path conceptualizations (fig. 82). The path through basin fill in the central Amargosa Desert is an alternative that has been presented piecemeal in previous investigations. This flow-path conceptualization assumes that most of the discharge sourced from the Ash Meadows groundwater basin passes through the well AD-4 corridor to reach the Furnace Creek area (figs. 80 and 82). The alternative path is flow through deep carbonate rocks that extend between the Ash Meadows discharge area and the southeastern Funeral Mountains, where flow moves northwest along the Furnace Creek fault zone to discharge areas in Furnace Creek (fig. 82; Hunt and Robinson, 1960; Belcher and others, 2009). These two alternatives will be discussed hereinafter as basin-fill and deep-carbonate flow paths. Lithology, hydraulic properties, chemical evidence, and numerical simulation results indicate that the basin-fill flow path is more likely than the deep-carbonate flow path.

Basin-Fill Flow Conceptualization

The basin-fill flow conceptualization assumes that basin fill in the central Amargosa Desert hydraulically connects the Furnace Creek area with carbonate rocks in Ash Meadows groundwater basin (fig. 83). Groundwater recharged in the Ash Meadows groundwater basin flows west-southwest through shallow carbonate rocks and converges on the well AD-4 corridor (fig. 80). Groundwater flows upward from carbonate rocks to basin fill in the well AD-4 corridor, moves west through the central Amargosa Desert, flows from basin fill to carbonate rocks in the Funeral Mountains, and continues to flow westward (fig. 83). Some of the westward-flowing groundwater discharges directly from carbonate rocks at *Nevares* Springs and the rest passes through shallow basin fill in the Furnace Creek area before discharging at land surface.




Figure 81. Cross section along a simulated groundwater-flow path from the Spring Mountains to the Amargosa River, Nevada and California.




Figure 82. Basin-fill and deep-carbonate flow-path conceptualizations from the Ash Meadows groundwater basin to discharge areas in Furnace Creek, Nevada and California.




Figure 83. Cross section along a simulated groundwater-flow path from the Ash Meadows groundwater basin to the Furnace Creek area through the well AD-4 corridor, Nevada and California.

Flow Potential Through Well AD-4 Corridor

Potential for flow from Ash Meadows groundwater basin into basin fill in the well AD-4 corridor has been recognized for 55 years, but estimated flow rates have differed greatly. Predevelopment water-level contours show a potentiometric high around the well AD-4 corridor that radially decreases into the central Amargosa Desert (Walker and Eakin, 1963, plate 3). A potentiometric high can occur from mounding from recharge, which is unlikely on a desert valley floor, or from groundwater upwelling. Upwelling of groundwater from carbonate rocks into overlying basin fill along the Gravity fault is supported by water-chemistry data. Water chemistry in wells open to basin fill within 0.4 mi of well AD-4 and springs in the Ash Meadows discharge area was classed as chemically similar (“Ash Meadows” and “East-central Amargosa Desert” in Winograd and Thordarson, 1975, p. C100). Winograd and Thordarson (1975, p. C87) dismissed substantial flow from carbonate rocks to basin fill near well AD-4 (figs. 82 and 83) because low-permeability siliciclastic rocks were assumed prevalent east of well AD-4. Claassen (1985 p. F19) analyzed drillers’ logs and additional wells, and concluded that, “[hydraulic] potential difference and the presence of more permeable sand and gravel in the valley fill in the vicinity of site 27 [well AD-4] support the presence of significant upward leakage from the carbonate aquifer.” About 2,000 acre-ft/yr of

flow through the corridor was estimated from transmissivity and hydraulic-gradient estimates in the basin fill west of well AD-4 (Fenelon and others, 2016).

Drilling history of wildcat oil and gas well *Felderhoff Federal 5-1* qualitatively supports the ability of shallow carbonate rock to transmit substantial flow through the well AD-4 corridor. *Felderhoff Federal 5-1* was drilled 1.6 mi northeast of well AD-4 (fig. 82), encountered carbonate rocks 850 ft below land surface, and reached a total depth of 1,466 ft below land surface (Carr and others, 1995). The well was abandoned before reaching its target depth of 5,000 ft below land surface because circulation using the mud-rotary drilling method could not be maintained. During October 22–25, 1991, less than 100 ft of hole was drilled near the bottom of the borehole (1,466 ft) while about 100,000 gal (2,500 barrels) of mud and cement were injected. Fluid-level altitudes of 2,354 ft were unchanged during injection and are consistent with expected water levels in shallow carbonate rocks at this location. Lack of circulation despite injection of large fluid volumes and unchanged water levels suggest hydraulic connection of the borehole with highly transmissive features in the carbonate rock. Geophysical measurements in the carbonate-rock sidewall of the borehole had bulk densities of 1.1 g/cm³, which is low compared to average bulk densities that typically exceed 2.6 g/cm³ for carbonate rocks. Low

measured bulk densities and a fully expanded caliper log between 1,410 and 1,445 ft below land surface are highly suggestive of large voids in the carbonate rocks (Carr and others, 1995).

Flow Potential Through Basin Fill in the Central Amargosa Desert

Transmissivities of basin fill in the central Amargosa Desert are sufficient to convey greater than 6,000 acre-ft/yr of groundwater to carbonate rocks in the Funeral Mountains. This groundwater is sourced from carbonate rocks east of the well AD-4 corridor, volcanic rocks at and upgradient of Yucca Mountain and Jackass Flats, and local recharge from the Amargosa River and Fortymile Wash (fig. 80). Specific capacities equal or exceed 20 gal/min/ft in 11 wells in the basin fill that overlie dense pathlines through the central Amargosa Desert (fig. 80). Pumping rates exceed 2,000 gal/min in five wells that were reported in Nevada well logs 4379, 4821, 7633, 9510, and 27276 (Nevada Division of Water Resources, 2018). Simulated transmissivities of basin fill in the central Amargosa Desert ranging from 10,000 to 100,000 ft²/d are consistent with empirical evidence from well logs (fig. 76, F–F').

Basin-Fill, Carbonate-Rock, and Volcanic-Rock Hydraulic Connections

The basin-fill flow conceptualization assumes basin fill, carbonate rocks, and volcanic rocks are hydraulically connected between recharge areas and the Furnace Creek discharge area. Recharge derived from Yucca Mountain and nearby upland areas in the AFFCR groundwater basin enters primarily volcanic rocks, moves downgradient into basin fill in the central Amargosa Desert, and passes through carbonate rocks in the Funeral Mountains (fig. 80). Recharge derived from Ash Meadows groundwater basin moves downgradient through carbonate rocks, enters basin fill in the central Amargosa Desert through the well AD-4 corridor, and moves into carbonate rocks in the Funeral Mountains (fig. 83). Recharge derived from the Amargosa River and Fortymile Wash infiltrates basin fill beneath the ephemeral channels and then moves into carbonate rocks in the Funeral Mountains. Water entering the Funeral Mountains from these different source areas moves westward to discharge in the Furnace Creek area (fig. 80).

Water-level data support west-southwest movement of groundwater through basin fill, carbonate rocks, and (or) volcanic rocks toward Furnace Creek. Predevelopment water-level contour maps show west-southwest groundwater flow toward the Furnace Creek area (Walker and Eakin, 1963, plate 3; Fenelon and others, 2010, plates 3–6; Fenelon and others, 2016, plate 1). Fenelon and others (2010, plates 3–4) show groundwater-flow potential between alluvial-volcanic and carbonate-rock aquifers based on lateral and vertical head gradients between wells.

Water-level declines with time in wells *Inyo-BLM 1* and *Travertine Point 1* confirm that basin fill in the central Amargosa Desert and carbonate rocks of the Funeral Mountains are connected hydraulically. The hydraulic connection was first reported in Fenelon and Moreo (2002, fig. 26). Both wells are completed in carbonate rocks, but on opposite sides of the Funeral Mountains (fig. 82). Well *Travertine Point 1* is more than 10 mi west of well *Inyo-BLM 1*, which is adjacent to basin fill in the central Amargosa Desert. Water levels declined 4 ft per decade in well *Inyo-BLM 1* (fig. 58C) and 3 ft per decade in well *Travertine Point 1* (fig. 52). In basin fill on the western side of the Amargosa Desert, water levels in *NA-9 Shallow Well* declined 5 ft/decade (Jackson and Halford, 2020). Consistent declines through the Funeral Mountains that diminish with distance from pumping in the Amargosa Desert (fig. 57) indicate a strong hydraulic connection with the central Amargosa Desert. Similar arguments confirm that basin fill in the central Amargosa Desert and volcanic rocks in Jackass Flats are hydraulically connected (fig. 57).

Geochemically Differentiated Sources of Furnace Creek Area Discharge

Major-ion and stable-isotope water chemistry can be used to identify potential source areas that contribute to Furnace Creek area discharge. Major-ion chemistry evolves from source areas to the discharge area, where dissolved-solid content typically increases along groundwater-flow paths (Drever, 1988). Stable isotopes of deuterium and oxygen-18 can be used to evaluate sources of Furnace Creek discharge. Deuterium and oxygen-18 concentrations are lighter (more negative) where recharge occurs at higher altitudes or cooler temperatures. Deuterium and oxygen-18 concentrations are affected minimally by water-rock interactions and evolve along flow paths by simple mixing (Thomas and others, 1997; p. C31).

Major Ions

The spatially variable, major-ion chemical character of groundwater across the study area results mostly from reaction with and dissolution of different rock types along flow paths. Groundwater in the Ash Meadows groundwater basin is characterized as a calcium-magnesium-sodium-bicarbonate type water (figs. 84 and 85). Well sites in Ash Meadows groundwater basin are open to carbonate rock and Ash Meadows springs are sourced from carbonate rock (fig. 84). The groundwater chemistry can be explained by long flow paths through carbonate rock that mix with groundwater derived from volcanic rocks. Calcium-magnesium-bicarbonate type groundwater is characteristic of carbonate rocks, whereas sodium-potassium-bicarbonate type groundwater is characteristic of volcanic rocks in the study area (Winograd and Thordarson, 1975). The addition of sodium likely is derived from downward leakage of groundwater through overlying volcanic rocks into carbonate rocks (Winograd and Thordarson, 1975, C104).




Figure 84. Water-chemistry sites in the Alkali Flat–Furnace Creek Ranch and Ash Meadows groundwater basins, Nevada and California. Water-chemistry data are compiled from Claassen (1973, 1985), Dudley and Larson (1976), and Thomas and others (1997), and are reported in Jackson and Halford (2020).




Figure 85. Major ion water chemistry for sites in the Alkali Flat–Furnace Creek Ranch and Ash Meadows groundwater basins, Nevada and California. Water-chemistry data are compiled from Claassen (1973, 1985), Dudley and Larson (1976), and Thomas and others (1997), and are reported in Jackson and Halford (2020).

Groundwater in the well AD-4 corridor is chemically similar to Ash Meadows springs (Winograd and Thordarson, 1975, p. C100). Wells 27 (also known as [230 S16 E50 07 1](#)) and 28 (also known as [HA-AD70](#)) in the well AD-4 corridor (fig. 84) are a calcium-magnesium-sodium-bicarbonate type (fig. 85), but have greater dissolved-solid concentrations (660 mg/L) compared to Ash Meadows springs (520–580 mg/L). Increased dissolved-solid concentrations are attributed to the addition of sodium and sulfate from mixing with groundwater in basin fill, where the likely source of sulfate is evaporite deposits, such as gypsum, within the basin fill (Winograd and Thordarson, 1975).

Major-ion chemistry varies spatially in the AFFCR groundwater basin because groundwater is derived from different sources (fig. 84). The chemical character of

groundwater from volcanic rocks in Yucca Mountain and Jackass Flats and groundwater near Fortymile Wash (fig. 84) is a dilute sodium-potassium-bicarbonate type (fig. 85; Winograd and Thordarson, 1975) with dissolved-solid concentrations ranging from 200 to 315 mg/L. This chemical character is similar to groundwater from wells farther south in the central Amargosa Desert, such as Well 4 (also known as [230 S16 E49 05ACC 1](#)) and Well 11 (also known as [HR Well](#)) in figure 84. Recharge derived from flood events along the Amargosa River infiltrates basin fill south of Bullfrog Hills and in western Amargosa Desert (fig. 84). Near the river channel, groundwater in underlying basin fill, carbonate rocks, and volcanic rocks is a sodium-chloride-sulfate-bicarbonate type (fig. 85) with dissolved-solid concentrations ranging between 700 and 950 mg/L.

A considerable fraction of discharge from the Furnace Creek area has long been attributed to recharge in Ash Meadows groundwater basin based on the water chemistry of Furnace Creek spring discharges (Hunt and Robinson, 1960; Hunt and others, 1966; Winograd and Thordarson, 1975; Steinkampf and Werrell, 2001; Belcher and others, 2009). Discharge from the Furnace Creek area also has been proposed to derive exclusively from basin fill in the Amargosa Desert. Winograd and Thordarson (1975, p. C112) concluded: *“Therefore, on the basis of chemical quality of water, the spring discharge at the Furnace Creek Wash-Nevares springs area seems to come from water in the valley-fill aquifer of the central and northwestern Amargosa Desert rather than directly from Pahrump Valley or from Pahrump Valley via Ash Meadows.”* The chemical character of discharge in the Furnace Creek area is a sodium-sulfate-bicarbonate type with dissolved-solid concentrations ranging from 760 to 820 mg/L (fig. 85), which is distinct from the water chemistry of Ash Meadows springs (fig. 84). This discharge is a mixture of calcium-magnesium-sodium-bicarbonate type groundwater with additional sulfate and chloride (Winograd and Thordarson, 1975, p. C99).

Examination of the available major-ion data plausibly suggests that Furnace Creek area discharge is a chemical evolution, or mixture, of groundwater derived from both the Ash Meadows and AFFCR groundwater basins (fig. 84). The component coming from the Ash Meadows groundwater basin is calcium-magnesium-sodium-bicarbonate type water moving from shallow carbonate rocks west of well *Army 1* WW into the AFFCR groundwater basin through the well *AD-4* corridor (fig. 84). The components coming from the AFFCR groundwater basin are dilute sodium-potassium-bicarbonate type groundwater originating near Yucca Mountain and Jackass Flats and a higher dissolved-solid, sodium-chloride-sulfate-bicarbonate type groundwater near the Amargosa River in the western Amargosa Desert (fig. 85). Continued mineral dissolution along flow paths is observed in the increase of dissolved-solid content from the well *AD-4* corridor (660 mg/L) and Yucca Mountain and Jackass Flats area (200–315 mg/L), to west-central Amargosa Desert (700–950 mg/L) and springs at Furnace Creek (760–820 mg/L) (figs. 84 and 85). Furthermore, the central Amargosa Desert groundwater has a chemical character that is intermediate between springs in the Furnace Creek and Ash Meadows discharge areas (fig. 85).

Based on major-ion compositions, Furnace Creek area discharge also could result from chemical evolution of Ash Meadows springs discharge. Limited data are available to evaluate the chemical evolution of groundwater from Ash Meadows springs to the Furnace Creek discharge area by way of a deep-carbonate flow path. *Inyo-BLM 1* is the only well open to carbonate rocks in the central Amargosa Desert (fig. 84), but this 2,900-ft-deep well should represent

conditions along the deep-carbonate flow path (fig. 82). Water from well *Inyo-BLM 1* has a higher dissolved-solids concentration (995 mg/L) than Furnace Creek area discharge, which means that groundwater near this well would have to mix with a considerable fraction of more-dilute groundwater to result in the chemical composition of groundwater observed in the Furnace Creek area. In the deep-carbonate flow conceptualization, mixing between concentrated and dilute groundwater would have to occur in only carbonate rocks. This scenario seems less likely than the basin-fill flow conceptualization, which postulates that Furnace Creek area discharge originates from Ash Meadows groundwater basin through the well *AD-4* corridor and from the Amargosa Desert. However, major-ion compositions in carbonate rocks beneath the Amargosa Desert are insufficient to conclusively exclude a flow path between Ash Meadows springs and Furnace Creek discharge.

Stable Isotopes

Deuterium and oxygen-18 concentrations in Furnace Creek cannot be differentiated from the Ash Meadows discharge area, Yucca Mountain–Jackass Flats wells, or Amargosa Desert wells. Deuterium concentrations of -104.0, -102.0, and -102.0 permil from *Nevares*, *Travertine*, and *Texas* Springs, respectively, are bracketed by potential sources from Ash Meadows and AFFCR groundwater basins (fig. 86). Deuterium concentrations range from -104.0 to -103.0 in the Ash Meadows discharge area, from -108.0 to -93.2 permil in the Yucca Mountain–Jackass Flats area, from -104.0 to -97.5 permil in the central Amargosa Desert, and from -105.0 to -92.5 permil from carbonate sites in Ash Meadows groundwater basin (fig. 86). Oxygen-18 concentrations of -13.6, -13.7, and -13.7 permil from *Nevares*, *Travertine*, and *Texas* Springs, respectively, also are within the range of sites in the Ash Meadows discharge area, Yucca Mountain–Jackass Flats area, and the western and central Amargosa Desert (fig. 86).

The wide range of isotopic values representing Yucca Mountain–Jackass Flats groundwaters indicate the large size and range of altitude covered by this area. The range of isotopic values in the central Amargosa Desert likely occurs because of groundwater mixing. Pumping in the central Amargosa Desert generally has increased between 1950 and 2010 (fig. 30). Irrigation pumping has withdrawn about 555,000 acre-ft of groundwater from storage during 1950–2010, when about 94,000 acre-ft of water re-infiltrated as return flow. Samples with oxygen-18 concentrations ranging from -13.2 to -12.4 permil in the central Amargosa Desert wells (sites 3, 13–16, 18, and 20 in fig. 86) appear evaporatively enriched, which may be attributed to pumping and return flow.



The deep-carbonate flow conceptualization assumes that deep carbonate rocks beneath the central Amargosa Desert hydraulically connect the Furnace Creek area with the Ash Meadows discharge area (fig. 82). This conceptualization principally was developed using hydrochemical data with limited hydrologic evidence. Hydrochemical evidence from previous investigations is reiterated and followed by hydrologic and hydrochemical results from subsequent investigations that contradict the deep-carbonate flow path conceptualization.

The deep-carbonate flow path has been conceptualized as a permeable feature in IT, DVRFS.v1, and DVRFS.v2 models (table 1). Conceptualization and implementation of the deep-carbonate flow path was articulated clearly for the IT model: “*The Furnace Creek fault is interpreted to act as a conduit to groundwater flow from the Amargosa Desert to Death Valley.*” (IT Corporation, 1997, p. 6-15; fig. 82).

conceptualized as a conduit through deep carbonate rocks from the Ash Meadows discharge area to Furnace Creek (Hunt and Robinson, 1960). The flow path was postulated in a quarter-page of text, based solely on hydrochemical similarities of spring waters between the Furnace Creek and Ash Meadows discharge areas. This argument was reiterated and expounded upon by assuming Furnace Creek discharge was sourced from Pahrump Valley, based on hydrochemical similarities and decreasing hydraulic potential from Pahrump to the Ash Meadows discharge area and to Furnace Creek (Hunt and others, 1966, p. B40). Arguments for flow from Pahrump to the Furnace Creek area through Ash Meadows were dismissed with a more exhaustive hydrochemical analysis and observation that a thick clastic confining unit isolates Pahrump Valley from Ash Meadows discharge area (fig. 29; Winograd and Thordarson, 1975, p. C91, C112). Furthermore, analysis of major-ion water chemistry (fig. 85) shows that springs in the Furnace Creek area are hydrochemically distinct from springs in the Ash Meadows discharge area (fig. 84). Therefore, no hydrologic or hydrochemical data exist to support the Furnace Creek fault zone as a conduit to groundwater flow.

Hydrochemical Evidence

The basis for incorporating the deep-carbonate flow path in the DVRFS.v1 model was as follows: “Hydrochemical data indicate that spring flow in the major springs at the Furnace Creek area likely derives from the carbonate-rock aquifer (Winograd and Thordarson, 1975, p. C95). Similar hydrochemistry between spring waters at Ash Meadows and the Furnace Creek area (Czarnecki and Wilson, 1991; Steinkampf and Werrell, 2001) indicate a hydraulic connection between these two discharge areas through the regional carbonate-rock aquifer by way of large-scale fractures or channels in the carbonate-rock aquifer (Winograd and Pearson, 1976)” (Faunt, D’Agnese, and O’Brien, 2010, p. 151). Previous arguments were accepted for the DVRFS.v2 model with the statement, “DVRFS v. 2.0 is consistent with the accepted hydrogeologic interpretations of groundwater flow from Ash Meadows to the Furnace Creek springs through the southern Funeral Mountains...” (Belcher and others, 2017, p. 53).

The argument that “[h]ydrochemical data indicate that spring flow in the major springs at the Furnace Creek area likely derives from the carbonate-rock aquifer” (Faunt, D’Agnese, and O’Brien, 2010, p. 151) is not evidence for a deep-carbonate flow path. Springs in the Furnace Creek area are sourced from carbonate rocks. However, the fact that Furnace Creek springs are sourced from carbonate rocks does not mean that groundwater flow from recharge areas to the Furnace Creek discharge area is solely through carbonate rocks. Winograd and Thordarson (1975, p. C113) state clearly that “[f]low from the central Amargosa Desert into Death Valley is the most likely source of the major spring discharge in east-central Death Valley.” Winograd and Thordarson (1975, p. C112) also concluded as follows: “Therefore, on the basis of chemical quality of water, the spring discharge at the Furnace Creek Wash-Nevares springs area seems to come from water in the valley-fill aquifer of the central and northwestern Amargosa Desert.”

The argument that “[s]imilar hydrochemistry between spring waters at Ash Meadows and the Furnace Creek area...indicate a hydraulic connection between these two discharge areas through the regional carbonate-rock aquifer” (Faunt, D’Agnese, and O’Brien, 2010, p. 151) is not valid based on available data. The chemical character of Furnace Creek discharge is a sodium-sulfate-bicarbonate type that is distinct from Ash Meadows springs, which are a calcium-magnesium-sodium-bicarbonate type. Central Amargosa Desert groundwater has a chemical character that is intermediate between springs in the Furnace Creek and Ash Meadows discharge areas. Chemical evolution of groundwater from Ash Meadows springs to Furnace Creek by way of a deep-carbonate flow path is less plausible, based on the limited data available, compared to a basin-fill flow path. The source of discharge in Furnace Creek is inconclusive based on stable-isotope results. Furthermore, an argument of similar

hydrochemistry between springs does not, by itself, indicate a hydraulic connection between the two discharge areas.

The basin-fill flow path was excluded previously because water chemistry of the central Amargosa Desert was characterized with limited numbers of wells. For example, in a rare earth element study to characterize the source of Furnace Creek springs (Johannesson and others, 1997), water chemistry of the central Amargosa Desert was characterized using only two wells (sites 3 and 35 in [fig. 84](#)). Characterization of all central Amargosa Desert groundwater using only two wells is not representative because the water chemistry varies greatly ([fig. 84](#)). Using limited data from the central Amargosa Desert resulted in the conclusion that “...[rare earth element] signatures of Ash Meadows ground waters are similar to those of springs in the Furnace Creek region of Death Valley but different from shallow ground waters from predominantly tuffaceous alluvial deposits in the Amargosa Desert, perched ground waters from felsic volcanic rocks, and ground waters that have only flowed through the regional Paleozoic carbonate aquifer” (Johannesson and others, 1997, p. 807). Heterogeneous water chemistry and complex flow fields in the Amargosa Desert indicate that a comprehensive and integrated hydrologic and geochemical analysis is necessary to conclusively characterize flow to Furnace Creek springs.

Contradictory Results from Drilling and Numerical Simulation

Wells *Inyo-BLM 1* and *Inyo-BLM 2* ([fig. 19](#)) were intended to characterize the deep-carbonate flow path beneath the Amargosa Desert (Inyo County Yucca Mountain Repository Assessment Office, 2005). Well *Inyo-BLM 1* was drilled to a depth of 2,900 ft below land surface and penetrated 450 ft of carbonate rocks. A small transmissivity of 100 ft²/d was estimated from a tidal-forcing analysis (Cutillo and Bredehoeft, 2011). Well *Inyo-BLM 2* was drilled to a depth of 3,340 ft below land surface without encountering carbonate rocks (Inyo County Yucca Mountain Repository Assessment Office, 2007). Results from targeted drilling in the Amargosa Desert contradicted expectations that permeable carbonate rocks occur at depth.

Similar results also occurred with other wells in the study area, where transmissive carbonate rocks at depth were targeted. Wells *ER-5-3-2* and *UE-25p1 (JF-2a)* ([fig. 19](#)) were drilled to depths of 5,683 and 5,923 ft below land surface, respectively, and penetrated low-transmissivity (100–900 ft²/d) carbonate rocks. Wells *ER-5-4-2* and *ER-8-1 (recompleted)* ([fig. 19](#)) were drilled to depths of 7,000 and 2,863 ft below land surface, respectively, and penetrated low-transmissivity (less than 1 ft²/d) volcanic and granitic rocks, respectively, instead of carbonate rocks. Even though a rigorous evaluation of deep carbonate rocks is not possible, failed attempts to find transmissive intervals in deep carbonate rocks indicate that a deep flow path through carbonate rocks is unlikely.

The deep-carbonate flow path was not simulated by the DVRFS.v2 model (fig. 87), despite being discussed as the preferred conceptual model (Belcher and others, 2017, p. 53). No discharge in the Furnace Creek area originated in the Ash Meadows groundwater basin as simulated with the DVRFS.v2 model. The DV3-SS model simulated groundwater flow to the Furnace Creek area from the Yucca Mountain area in the AFFCR groundwater basin and predominantly from Yucca Flat and the Groom Range in Ash Meadows groundwater basin (fig. 87).

Basin-Fill Flow Path More Probable

The basin-fill flow path between Ash Meadows groundwater basin and the Furnace Creek area is more plausible, based on available data, than a deep-carbonate flow path for discharge in the Furnace Creek area. The basin-fill flow path, which extends from the well AD-4 corridor, through the central Amargosa Desert, and into the Funeral Mountains, is consistent with hydraulic and hydrochemical evidence. The deep-carbonate flow path is not supported by hydraulic or geochemical evidence. The water chemistry of discharge in the Furnace Creek area clearly has evolved from the chemistry in the Ash Meadows discharge area and requires mixing with water from a non-carbonate source. Conceptual and numerical models of the basin-fill flow path are consistent in this study. In contrast, the deep-carbonate flow path conceptualization for the DVRFS.v2 study is not consistent with the DVRFS.v2 model (fig. 87).

Predevelopment Water Budgets

Groundwater basins were subdivided to simulate water budgets where estimated flow rates were needed. Groundwater-flow estimates generally are needed to constrain groundwater-velocity estimates from underground nuclear tests in CAUs at the NNSS. Estimated flow rates also inform water availability in subareas. Groundwater basins were divided into subareas, where flow across subarea divides was minimal, to minimize sensitivity of flow-rate estimates to specific divides (fig. 88). These divisions were suggested by mapped pathlines (fig. 80), water-level contours, and existing mapped groundwater-basin boundaries. Flow rates were simulated and balanced using zones that extended vertically from the water table to the model base in each subarea. Simulated recharge, discharge, and net flows between subareas were totaled with ZONEBUDGET (Harbaugh, 1990) and reported for each subarea.

Pahute Mesa–Oasis Valley Groundwater Basin

Most of the recharge in the PMOV groundwater basin is derived from Pahute Mesa (fig. 45). Total simulated recharge in the PMOV groundwater basin is 5,900 acre-ft/yr (table 11; fig. 88). Simulated recharge in the Pahute Mesa and Timber

Mountain areas is 4,130 acre-ft/yr, whereas simulated recharge in the northwestern subarea is 1,060 acre-ft/yr. A smaller amount (600 acre-ft/yr) of recharge occurs in Kawich Valley from the Belted and Kawich Ranges. A small amount of recharge also is generated locally in the Oasis Valley discharge area (110 acre-ft/yr).

More than 90 percent of the groundwater discharging in Oasis Valley is derived from recharge sourced at Pahute Mesa and Timber Mountain (fig. 88). Total simulated discharge in Oasis Valley is 6,130 acre-ft/yr. The 5,530 acre-ft/yr of groundwater inflow from Pahute Mesa and Timber Mountain areas accounts for locally derived recharge and inflows from the north, west, and east. Bullfrog Hills contributes a small amount (60 acre-ft/yr) of groundwater flow to Oasis Valley.


Ash Meadows Groundwater Basin

Total simulated recharge in the Ash Meadows groundwater basin is about 21,600 acre-ft/yr (table 11; fig. 88). About 80 percent (17,400 acre-ft/yr) of the recharge in Ash Meadows groundwater basin occurs in the Spring Mountains and Sheep Range, which are the highest altitude ranges in the study area. Less than 20 percent (3,670 acre-ft/yr) of the total recharge is derived from highland areas in the northern part of the Ash Meadows groundwater basin.

Less than 3 percent of predevelopment flow in Ash Meadows groundwater basin moves through Yucca Flat (fig. 88). About 190 acre-ft/yr of groundwater moves into northern Yucca Flat from Emigrant Valley. Groundwater flow through the Eleana Range into western Yucca Flat is about 60 acre-ft/yr, whereas groundwater flow through the Halfpoint Range into eastern Yucca Flat is about 10 acre-ft/yr. Simulated recharge derived from highland areas that bound Yucca Flat totals 230 acre-ft/yr. Total simulated groundwater flow from southern Yucca Flat through carbonate rocks is about 530 acre-ft/yr.

Groundwater flow in the Ash Meadows groundwater basin converges near the Specter Range (fig. 88). About 17,000 acre-ft/yr moves westward from recharge areas spanning from the Spring Mountains in the south to the Sheep Range in the east. About 3,700 acre-ft/yr of groundwater moves south-southwest from Yucca Flat and the Pahrnagat and Groom Ranges.

Simulated water budgets indicate that the Ash Meadows discharge area receives groundwater primarily from the Ash Meadows groundwater basin, with a minor contribution from the PDVS groundwater basin (fig. 88). About 18,290 acre-ft/yr of groundwater moves southwest into the Ash Meadows discharge area. Simulation results indicate that about 180 acre-ft/yr of groundwater moves northward from Pahrump Valley to the Ash Meadows discharge area. This result is speculative and uncertain because of a lack of water-level data in wells to constrain flow between Pahrump Valley and the Ash Meadows discharge area.






Figure 88. Predevelopment water budgets within and between geographic areas in the study area from the Death Valley version 3 steady-state model (DV3-SS), Nevada and California.

Alkali Flat–Furnace Creek Ranch Groundwater Basin

Total simulated recharge in the AFFCR groundwater basin is less than 5,000 acre-ft/yr (table 11; fig. 88). Slightly more than one-half (2,840 acre-ft/yr) of the recharge occurs on Timber, Yucca, and Shoshone Mountains (fig. 45). About 1,800 acre-ft/yr infiltrates along the Amargosa River and Fortymile Wash during ephemeral flows in the Amargosa Desert (figs. 45 and 88).

Groundwater moves laterally into the Amargosa Desert across six of the eight boundaries between adjacent zones (fig. 88). Simulated flow into the Amargosa Desert (AFFCR groundwater basin) principally comes from the Ash Meadows groundwater basin (2,790 acre-ft/yr) and Yucca and Shoshone Mountain areas (2,570 acre-ft/yr). Flow from the PMOV groundwater basin near Beatty, Bullfrog Hills, the Gravity Fault south of the well AD-4 corridor, and Greenwater Range are minor and contribute less than 400 acre-ft/yr to the Amargosa Desert.

Most groundwater that enters the Amargosa Desert moves westward toward the Furnace Creek area (fig. 88). Total simulated discharge in the Furnace Creek area is 6,430 acre-ft/yr. About 6,380 acre-ft/yr of groundwater moves from the Amargosa Desert through the Funeral Mountains to discharge at Furnace Creek. About 50 acre-ft/yr is recharged locally in the Funeral Mountains near Furnace Creek.

Groundwater movement into Franklin Lake occurs from the Amargosa Desert, Greenwater Range, and Ash Meadows discharge area (fig. 88). Total simulated discharge at Franklin Lake is 440 acre-ft/yr, with most of this discharge sourced from the Amargosa Desert. The Greenwater Range and Ash Meadows discharge area directly contribute less than 10 percent of the discharge at Franklin Lake.

Pahrump to Death Valley South Groundwater Basin

Simulated recharge in the PDVS groundwater basin totals 22,930 acre-ft/yr (fig. 88), but net recharge totals 22,210 acre-ft/yr (table 11) after 720 acre-ft/yr of re-infiltrated surface flow near Dumont Dunes is subtracted. Most of the recharge occurs in the Spring Mountains. About 400 acre-ft/yr is recharged in the Nopah and Resting Spring Ranges, with most recharge occurring in the Nopah Range (fig. 45). Most of the discharge from the Saratoga Spring area is re-infiltrated surface flow near Dumont Dunes (fig. 45), and the functional terminus of the PDVS groundwater system is the Lower Amargosa area.

More than 60 percent of the groundwater entering Pahrump and Stewart Valleys is discharged locally at springs and in evapotranspiration areas (fig. 88). Groundwater inflow to Pahrump and Stewart Valleys from local recharge and upgradient flow from the Spring Mountains totals 20,280 acre-ft/yr. Total simulated discharge in Pahrump and Stewart Valleys is slightly more than 13,000 acre-ft/yr.

Less than 40 percent (7,740 acre-ft/yr) of groundwater entering Pahrump and Stewart Valleys moves southwest to discharge areas downgradient of the Nopah Range (fig. 88). Most of the groundwater moves through the Nopah Range into Chicago Valley. This groundwater either discharges in Chicago Valley or moves southward to discharge along the Amargosa River. Groundwater that enters California Valley either discharges at springs locally in the valley or moves downgradient to discharge areas near Tecopa, California.

Simulation results indicate that groundwater discharging in the Saratoga Spring area is derived from California Valley and from re-infiltrated surface flow near Dumont Dunes (fig. 88). More than 70 percent of the discharge in the Saratoga Spring area is local recharge from re-infiltrated surface flow from the Amargosa River. California Valley contributes about 40 acre-ft/yr of groundwater flow to the Saratoga Spring area.

Rainier Mesa Groundwater Sub-Basin

Recharge to Rainier Mesa is limited to 100 acre-ft/yr across a 50 mi² area (fig. 88), even though Rainier Mesa receives high rates of precipitation. Most of the precipitation is not recharged locally because of low-permeability rocks, which cause most recharge to be redistributed downslope (fig. 16). Recharge rates in Rainier Mesa averaged 0.003 ft/yr and were limited by low permeabilities of the zeolitized tuffs. This in-place recharge moves downgradient and about 30, 60, and 10 acre-ft/yr moves into the PMOV, Ash Meadows, and AFFCR groundwater basins, respectively.

Effects of Groundwater Development

Effects of groundwater development were characterized with calibrated DV3-AM-AFFCR and DV3-PDVS models. Extents of water-level declines from pumping were mapped throughout the study area. Sources of pumped water were differentiated between groundwater-storage depletion, capture of discharge from springs and ET areas, and return flow. Reductions in natural discharges from predevelopment to 2018 were quantified by discharge areas in Oasis Valley, Ash Meadows, Furnace Creek area, Pahrump Valley, and Lower Amargosa area. Effects of pumping centers and local injection on water levels in *Devils Hole* were differentiated between 1950 and 2018.

Extent of Water-Level Declines

Extents of water-level declines throughout the study area in 2018 are shown where simulated declines equaled or exceeded 1 ft (fig. 57). Using simulation results to estimate the extent of pumping effects was necessary where effects have not been measured or are obscured. For example, simulated water levels declined in California Valley where no wells have been inventoried or drilled (fig. 57). Simulated declines of 1–2 ft in Jackass Flats likely occurred (fig. 57) but are masked by water-level rises from recharge that exceed declines from pumping (fig. 36). Estimating extents of pumping-affected areas with simulated water levels is less certain than measuring water levels in wells and primarily suggests where monitoring is needed.

Drawdowns from pumping in the central Amargosa Desert, Jackass Flats, eastern NNSS, and Indian Springs have coalesced into a 2,200 mi² area (fig. 57). This area extends west to east from the Furnace Creek area to the base of the Sheep Range and south to north from the southern Funeral Mountains to northern Yucca Flat. Drawdowns from multiple pumping centers have combined because relatively contiguous areas have transmissivities greater than 10,000 ft²/d (fig. 68). Basin fill of the central Amargosa Desert, volcanic and carbonate rocks of Jackass Flats, and the carbonate-rock megachannel are three notable areas where simulated transmissivities are high and empirically confirmed with aquifer-test results.

Drawdowns from pumping in Pahrump Valley have affected most, if not all, transmissive basin fill and carbonate rocks in the PDVS groundwater basin, where drawdowns extend over an area of 1,400 mi² (fig. 57). Drawdowns were constrained to the southwest by low-permeability rocks that bound transmissive rocks between the Amargosa River and the Spring Mountains (fig. 32). Simulated drawdowns north of Shoshone and in Chicago Valley are relatively accurate based on comparisons with measured declines in wells 022N007E13L01S and Hwy 127 MM21-1 (fig. 61). Simulated drawdowns do not extend into the Tecopa area (fig. 57). This result is less certain because groundwater levels have not been measured near Tecopa.

Drawdowns from isolated areas of groundwater development have limited extents of less than 5 mi (fig. 57). Drawdowns in Emigrant Valley, Pahute Mesa, and south of Bullfrog Hills are typical examples of isolated pumping. Drawdowns greater than 1 ft were not simulated around Furnace Creek area pumping wells. These pumping wells are close to *Travertine* and *Texas Springs*, which has resulted in most of the pumped water being derived from captured spring discharge rather than groundwater storage. Effects from pumping in Indian Springs are not isolated, as conceptualized, and contribute to water-level declines in the megachannel (fig. 57).

Sources of Pumped Water

Simulation results for sources of pumped water were differentiated between groundwater-storage depletion, return flow, and capture of discharge from springs and ET areas. Cumulative pumping volumes totaled 50, 19, and 31 percent from storage depletion, return flow, and capture, respectively, during groundwater development between 1910 and 2018. Sources differed considerably by groundwater basin as groundwater development occurred (fig. 89). Cumulative capture (1913–2018) exceeded cumulative storage depletion in the PDVS groundwater basin, but storage depletion annually exceeded capture during peak pumping between 1952 and 1985. Storage depletion supplied greater than 90 percent of pumped water from AFFCR and Ash Meadows groundwater basins (fig. 89A). These groundwater basins were combined because pumping from either basin can capture predevelopment discharges in both basins. Return flow consisted of water from storage depletion and capture that had been pumped during previous years. Storage depletion and capture constituted 61 and 39 percent of cumulative return flow in the study area, respectively.

Capture was substantial where groundwater development occurred near springs in Pahrump Valley and the Ash Meadows discharge area. Pumping wells in Pahrump Valley mostly were within 5 mi of *Bennetts* and *Manse* Springs prior to 1946 (figs. 29 and 32) and pumped water principally was captured spring discharge (fig. 89). Pumping by Cappaert Enterprises was within 5 mi of springs in the Ash Meadows discharge area and about one-half of the pumped water was capture.

Reductions in Natural Discharges

Discharges from springs and ET areas decreased in response to declining groundwater levels from pumping (table 13). Simulated discharges in 2018 were less than 80 percent of discharges prior to development. More than 80 percent of the simulated decline in predevelopment discharge occurred in Pahrump Valley and primarily was capture of discharges from *Bennetts* and *Manse* Springs (fig. 62).

Simulated captures in the Franklin Well area and Chicago Valley were both more than 80 percent of predevelopment discharge (table 13), indicating that extinction depths were underestimated. These ET areas were assigned a uniform extinction depth of 5 ft. Simulated water levels in the Franklin Well area and Chicago Valley declined between 10 and 15 ft after 1993, but vegetation appears little changed between 1994 and 2018. Simulating capture of discharge by ET_{GW} with a fixed extinction depth is an approximation that does not account for growth of roots.




Figure 89. Total annual groundwater withdrawals by groundwater-storage depletion, return flow, and capture of discharge from springs and evapotranspiration areas by groundwater basins Alkali Flat–Furnace Creek Ranch and Ash Meadows (A), Pahute Mesa–Oasis Valley (B), and Pahrump to Death Valley South (C), in the study area, 1910–2018, with withdrawal estimates from 2010 projected to 2018.

Table 13. Simulated discharges by discharge area for predevelopment (DV3-SS model), 2018 (DV3-AM-AFFCR or DV3-PDVS model), and projected future conditions in 2100 (DV3-PRED model), in the study area, Nevada and California.

[**Groundwater basin:** AFFCR, Alkali Flat–Furnace Creek Ranch; PDVS, Pahrump to Death Valley South; PMOV, Pahute Mesa–Oasis Valley. **Annual simulated discharge—2018 and 2100:** Pumping rates from 2010 were either projected through 2018 or 2100. **Abbreviations:** DV3-AM-AFFCR model, Death Valley version 3 stress-response model simulating groundwater development in the Ash Meadows, Alkali–Furnace Creek Ranch, and Pahute Mesa–Oasis Valley groundwater basins; DV3-PDVS model, Death Valley version 3 stress-response model simulating groundwater development in the Pahrump to Death Valley South groundwater basin; DV3-PRED model, Death Valley version 3 predictive model; DV3-SS model, Death Valley version 3 stress-response model simulating steady-state (predevelopment) conditions]

Groundwater basin	Discharge area	Annual simulated discharge (acre-feet)		
		Predevelopment	2018	2100
AFFCR	Furnace Creek area ^{1,2}	6,300	6,100	5,900
	Franklin Well area ³	330	50	10
	Franklin Lake ¹	300	300	200
	Death Valley playa ¹	100	100	100
Ash Meadows	Ash Meadows with Amargosa Flat	18,500	18,000	17,400
	Indian Springs	700	580	530
PMOV	Oasis Valley ⁴	6,100	6,000	6,000
PDVS	Pahrump Valley with Stewart Valley ⁵	13,200	3,300	4,900
	Chicago Valley ³	400	10	0
	Shoshone area	2,100	2,000	2,000
	Tecopa/California Valley area	6,300	6,100	6,100
	Saratoga Spring area—NET ⁶	310	310	310
	Death Valley playa ¹	40	40	40
TOTAL		54,700	42,900	43,500

¹ Simulated predevelopment discharges from playas assume groundwater-evapotranspiration rates of 0.001 foot per year.

² Simulated discharges from Furnace Creek Wash include diversions.

³ Simulated discharges in 2018 and 2100 are biased low because extinction depths are underestimated.

⁴ Simulated drawdowns of less than 0.5 feet in Beatty captured about 100 acre-feet of discharge in Oasis Valley.

⁵ Simulated discharges include *Bennetts* and *Manse* Springs and evapotranspiration areas in Pahrump and Stewart Valleys.

⁶ Net discharge subtracts 720 acre-feet per year (1 cubic foot per second) of return flow from Amargosa River downstream of Dumont Dunes streamgage (USGS 10251375).

Simulated discharge in 2018 from the Ash Meadows discharge area decreased by 3 percent, or 500 acre-ft/yr, with more than 300 acre-ft/yr from springs. Captured spring discharges supplied about one-half of the pumpage for Cappaert Enterprises, but capture varied markedly between springs (fig. 71). Pumping captured all discharge from *Jack Rabbit Spring* during summer months from 1972 to 1977. However, average discharge from *Big Spring* decreased by 20 percent and seasonally fluctuated 10 percent owing to pumping by Cappaert Enterprises (fig. 71). Maximum capture of all spring discharge occurred in August 1971 when well *Spring Meadows 6* pumped 1,400 gal/min (3.0 ft³/s) (figs. 37 and 38). More than 90 percent of the water pumped from well *Spring Meadows 6* was captured discharge from *Crystal Pool*, which is within 1,000 ft of well *Spring Meadows 6* (Dudley and Larson, 1976).

Pumping in the central Amargosa Desert minimally affected discharges from *Travertine* and *Texas Springs* in the Furnace Creek area (fig. 90). Combined simulated discharges from *Travertine* and *Texas Springs* decreased by a total of 0.24 ft³/s (170 acre-ft/yr) between predevelopment and 2018. Nearly all simulated capture from these springs were caused by local pumping in the Furnace Creek area that started in 2009. Measured discharges were not easily interpreted because of missing records and shifts from earthquakes that introduced ambiguity. Combined measured discharges from *Travertine* and *Texas Springs* decreased from 2.4 ft³/s (1,740 acre-ft/yr) to 2.0 ft³/s (1,450 acre-ft/yr) between 1964 and 1990. The observed decrease is difficult to attribute to a particular stress because discharges only were measured once during this 25-year period. Discharges were measured continuously for less than 3 years during the 1990s before earthquakes perturbed spring discharges (fig. 90). Combined discharge from *Travertine* and *Texas Springs* increased 0.3 ft³/s (220 acre-ft/yr) in response to the Landers/Little Skull Mountain earthquake and earthquake effects dissipated after a decade (Cuttillo and Ge, 2006). Restoration activities, such as restoring spring runs from *Travertine* and *Texas Springs*, in the Furnace Creek area also perturbed discharges between 2006 and 2008.

Ash Meadows and Devils Hole

Effects of individual pumping centers on water levels in *Devils Hole* were estimated with calibrated DV3-AM-AFFCR and DV3-PDVS models. Pumping wells were grouped into 11 pumping centers by geography and NNSS operational units (table 14). The central Amargosa Desert, Pahrump Valley, and Cappaert Enterprises were grouped as major pumping centers (fig. 91). Pumping from Ash Meadows groundwater basin was differentiated further between *Crystal*, *Indian Springs*, and the megachannel (fig. 91). Pumping from wells in the megachannel was grouped separately from nearby wells outside the megachannel because of disproportionate effects

of pumping on water levels in *Devils Hole*. Net pumpage from pumping centers and its effect on water levels in *Devils Hole* between 1968 and 2018 are shown in table 14. Simulated results are not shown prior to 1969 because limited data are available in *Devils Hole* prior to 1969 and measurable water-level declines occurred after 1969.

Water-level changes in *Devils Hole* were simulated 11 times with pumping and return flows from a single pumping center in each simulation. Individual water-level changes from 11 simulations were summed and compared to the total simulated change from all pumping in the calibrated DV3-AM-AFFCR model. The summation of individual simulations did not equal total simulated changes from the calibrated DV3-AM-AFFCR model (fig. 92). Results differed because captures from springs and ET areas were non-linear and depended on total pumpage. The fact that *Jack Rabbit Spring* went dry during summer from 1970 to 1977 is an example of a non-linear response (fig. 71). Individual water-level changes were scaled so that the summation of individual simulations equaled simulated changes from the calibrated DV3-AM-AFFCR model. Scaling fractions varied with time and ranged from 1.15 to 0.72 during 1984 and 2018, respectively (fig. 92).

Only pumping centers in the central Amargosa Desert and Ash Meadows groundwater basin measurably affected water levels in *Devils Hole* (table 14). Pumping from Beatty, Pahrump Valley, and Pahute and Buckboard Mesas did not affect water levels in *Devils Hole* because areas of low transmissivity intervene (figs. 29 and 72). Jackass Flats did not affect water levels in *Devils Hole* because pumping was distant and pumped volumes were small relative to aquifer storage (table 14). Furnace Creek area did not affect water levels in *Devils Hole* because pumping was distant and pumped wells captured nearby discharge from *Travertine* and *Texas Springs*.

Pumping by Cappaert Enterprises and the NNSS inside the megachannel predominantly affected water levels in *Devils Hole* between 1969 and 1980 (fig. 92). However, residual effects of pumping from the megachannel have persisted for decades after pumping ceased. Maximum water-level declines of 2.5 ft occurred during the 1970s, where 80 percent of the decline was due to pumping by Cappaert Enterprises. Pumping by Cappaert Enterprises accounted for 25 percent of the anthropogenic water-level decline in *Devils Hole* in 2018, 40 years after pumping ceased. Pumping by the NNSS inside the megachannel accounted for, on average, 20 percent of the anthropogenic water-level decline in *Devils Hole* during the 1970s. Although most of the pumping in the NNSS occurred prior to 1993, NNSS pumping inside the megachannel accounted for 25 percent of the water-level decline in *Devils Hole* from 1993 to 2018. Water-level declines in 2018 of less than 0.1 ft from *Crystal* are small (fig. 92), but disproportionately large for average pumping rates of 40 acre-ft/yr (table 14). Pumping in *Crystal* exaggeratedly affected water levels in *Devils Hole* because pumpage came from the megachannel (fig. 91).




Figure 90. Measured and simulated discharges from *Travertine* (A) and *Texas* (B) Springs in the Furnace Creek area, California, 1950–2018. Simulated discharges do not account for earthquake effects.

Table 14. Pumping centers; net pumpage volumes, 1969–2018; and effect of pumping centers on water levels in *Devils Hole*, in the study area, Nevada and California.

[Groundwater basin: AFFCR, Alkali Flat–Furnace Creek Ranch; PDVS, Pahrump to Death Valley South; PMOV, Pahute Mesa–Oasis Valley. Symbols: <, less than; –, not applicable because simulated drawdown was not estimated]

Groundwater basin	Pumping center	Volume of net pumpage, 1969–2018 (acre-feet)	Simulated water-level decline in Devils Hole (feet)		Year of maximum water-level decline in Devils Hole
			2018	Maximum	
Ash Meadows	Cappaert Enterprises	40,000	0.36	2.09	1972
AFFCR	Central Amargosa Desert	540,000	0.48	0.48	2018
Ash Meadows	Inside megachannel	15,000	0.31	0.46	1995
Ash Meadows	Crystal	2,000	0.06	0.23	1987
Ash Meadows	Outside megachannel	38,000	0.12	0.14	2007
Ash Meadows	Indian Springs	28,000	0.08	0.08	2018
AFFCR	Jackass Flats	6,000	<0.01	<0.01	–
AFFCR	Beatty	26,000	<0.01	<0.01	–
PMOV	Pahute and Buckboard Mesas	11,000	<0.01	<0.01	–
PDVS	Pahrump Valley	1,064,000	<0.01	<0.01	–
AFFCR	Furnace Creek area	2,000	<0.01	<0.01	–




Figure 91. Pumping centers analyzed for affecting water levels in *Devils Hole*, Nevada and California.




Figure 92. Annual net pumpage by pumping center (A) and water-level changes in *Devils Hole* by pumping center, as simulated with the Death Valley version 3 stress-response model simulating groundwater development in the Ash Meadows, Alkali Flat–Furnace Creek Ranch, and Pahute Mesa–Oasis Valley groundwater basins (B), Nevada and California, 1950–2018.

Water levels in *Devils Hole* declined rapidly in the early 1970s, recovered through the 1980s, and have declined slowly and steadily since the 1990s from pumping in the central Amargosa Desert (fig. 92). Pumped volumes from the central Amargosa Desert were an order of magnitude greater than pumped volumes from Cappaert Enterprises (table 14), but effects on water levels in *Devils Hole* were attenuated by limited hydraulic connection through the well AD-4 corridor. Water levels in *Devils Hole* have declined at a rate of 0.1 ft per decade from pumping in the central Amargosa Desert during 1998–2018. Pumping in the central Amargosa Desert accounted for a third of anthropogenic water-level decline in *Devils Hole* during 2018 (fig. 92).

Injection in *Devils Hole Well (AM-5)* elevated water levels in *Devils Hole* about 0.5 ft prior to the discontinuation of injections in 1977 (fig. 93). Effects of injection in *Devils Hole Well (AM-5)* were estimated by removing injection from the calibrated DV3-AM-AFFCR model and simulating water-level changes in *Devils Hole*. Results from the model simulating injection were subtracted from model results without injection to estimate effects of injection in *Devils Hole Well (AM-5)* on water levels in *Devils Hole*. Differences in fit between measured and simulated water levels in *Devils Hole* prior to and during injection suggest that injection rates were more variable than reported (Larson, 1975). This is because measured and simulated monthly water-level changes track well prior to injection and poorly during simulated injection. Water levels in *Devils Hole Well (AM-5)* also vary greatly (fig. 39), which suggests that the injection rate was not constant with time.

Potential Effects of Future Groundwater Development

Potential effects of future groundwater development on water levels and spring discharges were estimated with the DV3-PRED model (Jackson and Halford, 2020). Pumping history and temporal discretization in the DV3-PRED model differed from the DV3-AM-AFFCR and DV3-PDVS models. Pumping changed annually in all groundwater basins from 1913–2010 in the DV3-PRED model. Annual pumping rates during 2011–2018 were projected from pumping rates in 2010 (Elliott and Moreo, 2018). All pumping scenarios simulated pumping, water-level changes, and capture of discharges from 1913–2018 before solving for predicted changes. Simulated water-level changes in *Devils Hole* from DV3-AM-AFFCR (fig. 92) and DV3-PRED (fig. 94) models differ because of use of monthly and annual stress periods during pumping by Cappaert Enterprises, respectively. These temporal pumping differences dissipated during recovery between 1980 and 2000, and simulated water levels from both DV3-AM-AFFCR and DV3-PRED models were quite similar between 2000 and 2018 (fig. 94).

Water-level changes in *Devils Hole* from pumping were simulated with steady-pumping and no-pumping scenarios that simulated changes from 2019–2100 (fig. 94). Pumping rates from 2010 were projected from 2019–2100 in the steady-pumping scenario. All pumping ceased in 2019 and recovery was simulated in the no-pumping scenario. Simulated water levels in *Devils Hole* declined 1.5 ft and rose 0.1 ft from 2019–2100 in the steady-pumping and no-pumping scenarios, respectively (fig. 94).

Prolonged water-level recovery responses in *Devils Hole* were observed from Cappaert pumping during 1980–2018 and from results of the hypothetical no-pumping scenario during 2019–2100. Prolonged water-level recovery responses to pumping are typical in the megachannel. For example, prolonged recovery also has been observed in *Tracer Well 3* during recovery from Cappaert pumping (fig. 70) and recovery from the *ER-6-1-2 main MWAT* (fig. 67). Prolonged recovery occurs because large volumes of groundwater were withdrawn from carbonate rocks in the megachannel. Pumping minimally decreases water levels and induces little extra flow from surrounding rocks to offset storage depletion in the megachannel. Substantial groundwater-storage depletion from the Ash Meadows groundwater basin (fig. 89) has resulted in a 2-ft water-level decline throughout the carbonate-rock megachannel by 2018 (fig. 57).

Water-level changes in *Devils Hole* simulated with the DV3-PRED model likely are biased towards minimum change for given pumping rates because of assumptions regarding natural fluctuations. Water levels are affected by long-term natural fluctuations; however, simplified assumptions were made to quantify this natural variability so that hydraulic properties could be estimated (fig. 40). Long-term natural fluctuations in *Devils Hole* were not estimated uniquely and were biased toward a minimum rise of 1 ft between 1973 and 2018. A rise of 1.5 ft between 1973 and 2018 could have been estimated in *Devils Hole*, which would have caused drawdown estimates to be 0.5 ft greater or total 2 ft in 2018, instead of the 1.5 ft of drawdown currently simulated in 2018 (fig. 94). Simulated water levels in *Devils Hole* would have declined 2 ft between 2018 and 2100, or 4 ft from predevelopment conditions, in the steady-pumping scenario had an alternative long-term natural fluctuation with a rise of 1.5 ft between 1973 and 2017 been used.

Natural discharges are projected to increase by 1,600 acre-ft/yr in Pahrump Valley and decrease slightly or not change in all other discharge areas between 2018 and 2100 if pumping remains at 2010 rates in the steady-pumping scenario (table 13). Increased discharges were simulated in *Manse Spring* and are a response to locally rising water levels (fig. 51) that are projected to continue. Simulated discharges in Chicago Valley decreased by 10 acre-ft/yr between 2018 and 2100, whereas simulated discharges in the Shoshone and Tecopa/California Valley areas are projected to remain unchanged from 2018 to 2100. Simulated discharges in the Ash Meadows and AFFCR groundwater basins decreased by about 1,000 acre-ft/yr between 2018 and 2100 (table 13).




Figure 93. Groundwater withdrawals and injections (top graph); and measured water levels, and simulated water levels with and without injections (bottom graph), in Devils Hole Well (AM-5) (bottom graph), Nevada, 1960–2000.




Figure 94. Measured water levels without long-term natural fluctuations from recharge, and simulated water levels from DV3-AM-AFFCR and DV3-PRED models, in Devils Hole, Nevada, 1950–2100. DV3-AM-AFFCR, Death Valley version 3 stress-response model simulating groundwater development in the Ash Meadows and Alkali Flat–Furnace Creek Ranch groundwater basins; DV3-PRED, Death Valley version 3 predictive model.

Groundwater-Basin Boundary Uncertainty

Boundary uncertainty was addressed for all internal groundwater-basin boundaries in the study area. Predevelopment groundwater-flow paths, water-level declines from groundwater development, and hydraulic properties were used to determine whether groundwater-basin boundaries are barriers to flow.

The PMOV groundwater basin mostly is isolated from neighboring AFFCR and Ash Meadows groundwater basins. A net rate of 20 acre-ft/yr moves from the Ash Meadows groundwater basin into the PMOV groundwater basin (fig. 88). Limited flow occurs through the Belted Range along this boundary because of low-permeability rocks that form a barrier to flow (fig. 32). The southeastern boundary of the PMOV groundwater basin between Bare Mountain and Rainier Mesa is a good approximation of the groundwater divide (fig. 88). A small number of flow paths cross the southeastern PMOV boundary (fig. 80). However, the amount of simulated groundwater flow across this boundary is small (230 acre-ft/yr; fig. 88) and accounts for less than 4 percent of total discharge in Oasis Valley. Water-level declines from pumping in the PMOV groundwater basin also are isolated from declines associated with pumping centers in the AFFCR and Ash Meadows groundwater basins.

Low-permeability rocks (fig. 32) hydraulically isolate PDVS groundwater basin from the AFFCR and Ash Meadows groundwater basins (fig. 68). These low-permeability rocks cause pumping in Pahrump Valley to minimally affect water levels in Ash Meadows and AFFCR groundwater basins (fig. 57) because hydraulic connections to PDVS groundwater basin are limited to two locations of saturated basin fill. Saturated basin fill beneath the Amargosa River near Eagle Mountain connects AFFCR and PDVS groundwater basins (fig. 32), where simulated interbasin flow is about 60 acre-ft/yr (fig. 88). Saturated basin fill between Stewart Valley and the Ash Meadows discharge area connects PDVS and Ash Meadows groundwater basins (fig. 32), where simulated interbasin flow is about 180 acre-ft/yr (fig. 88).

Ash Meadows and AFFCR groundwater basins are coupled and are better considered as a single groundwater basin. The basin boundary extending from the well AD-4 corridor northward to Jackass Flats is a groundwater divide that was delineated based on water-level altitudes in wells (Fenelon and others, 2016). Acreally extensive drawdowns from pumping in both groundwater basins have coalesced into a 2,200 mi² area (fig. 57), where these drawdowns have propagated across this boundary. Hydraulic continuity principally occurs through the well AD-4 corridor, where predevelopment groundwater flow is about 2,550 acre-ft/yr (fig. 88).

Boundary uncertainty was not addressed for external groundwater-basin boundaries, which bound the study area. External groundwater-basin boundaries were simulated as

no-flow boundaries in the integrated DV3 model because the study area primarily is isolated from surrounding groundwater basins by low-permeability rocks and groundwater divides (Fenelon and others, 2016). Potential groundwater flow is expected to be limited from north of Kawich, Emigrant, Tikaboo, and Pahranaagat Valleys (Winograd and Thordarson, 1975; Harrill and others, 1988; Heilweil and Brooks, 2011; Fenelon and others, 2016). Potential groundwater flow across external boundaries was not precluded by no-flow boundaries because potential lateral flow was accommodated in simulated recharge estimates. Differentiating recharge from lateral flow along the study-area boundary was not possible because little data exist.

Evaluation of Advective Flow from Corrective Action Units

Advective-flow distances (and velocities) from underground nuclear tests are used to evaluate flow rates and boundary conditions in the (regional) DV3 model. Flow rates and boundary conditions from the DV3 model need to be evaluated because they support local-scale CAU models of groundwater flow and radionuclide transport. Flow rates and boundary conditions extracted from the DV3 model and used in a local-scale model highly influence the Darcy velocities of the local-scale model, which affect advective transport calculations. Evaluating advective movement along flow paths is a relevant way to determine the reasonableness of simulated flow rates near nuclear tests in the DV3 model.

Groundwater-flow paths were simulated from all underground nuclear tests detonated near or below the water table at the NNSS using the DV3-SS model. Advective-flow distances and velocities were computed along flow paths using the DV3-SS model. Computing advective velocities along simulated flow paths is a straight-forward calculation that requires an estimated effective porosity of the rocks along the flow path and hydraulic-conductivity and hydraulic-gradient values derived from the calibrated model. The advective velocity was used to calculate the distance a water particle would move in 165 years, which is the time necessary for tritium in a nuclear test cavity to decay to below the Safe Water Drinking Act (SDWA) standard of 20,000 pCi/L (U.S. Environmental Protection Agency, 2017), assuming an initial concentration of 2.2×10^8 pCi/L (Pawloski and others, 2001). An advective-flow distance based on tritium decay is used because tritium is a conservative radionuclide. Computed 165-year advective-flow distances are qualitatively compared to tritium data from wells downgradient from nuclear tests to ensure that the computed distances are consistent with known transport distances. Because the DV3-SS model was not calibrated to measured tritium concentrations, simulated groundwater-flow paths from nuclear tests are not expected to coincide with exact pathways of known tritium plumes.

Predevelopment groundwater-flow paths were not simulated for all 828 underground nuclear tests on the NNSS (U.S. Department of Energy, 2015). Flow paths were simulated only for the 296 underground nuclear tests (fig. 95) that were detonated below the water table or less than 328 ft (100 m) above the water table (Stoller-Navarro Joint Venture, 2004b, 2005b; Navarro-Intera, LLC, 2013; U.S. Department of Energy, 2018). These 296 tests are considered to have the potential to introduce radionuclides directly into the saturated zone (Finnegan and others, 2016). Flow paths originated from model layer 1 for nuclear tests detonated above the water table, whereas flow paths originated in model layer 2, 3, 4 or 5 for nuclear tests detonated below the water table. Model layer selection for each nuclear test detonated in the saturated zone was based on detonation depth below the simulated water table. Vertical locations of nuclear tests were checked to ensure that they intersected the correct hydrogeologic unit in the DV3 model. Flow paths were simulated by assigning an effective porosity of 0.01 to fractured volcanic and carbonate rocks, and an effective porosity of 0.1 to basin fill and volcanic-sedimentary rocks, which include the volcanic tuffs in Yucca Flat, Frenchman Flat, and Rainier Mesa.

The 165-year period used to calculate advective-flow distances along simulated flow paths from 296 underground nuclear tests was based on estimated initial tritium concentrations in nuclear-test cavities and the decay (half-life) coefficient for tritium of 12.3 years (Lucas and Unterweger, 2000). Initial tritium concentration, in picocuries per liter, was estimated for each nuclear test using methods described in Stoller-Navarro Joint Venture (2005b) for tests in Frenchman Flat CAU, Stoller-Navarro Joint Venture (2004b) for tests in Pahute Mesa CAU, Navarro-Intera, LLC (2013) for tests in Yucca Flat–Climax Mine CAU, and U.S. Department of Energy (2018b) for tests in Rainier Mesa–Shoshone Mountain CAU. Initial concentrations ranged from 1.5×10^4 to 2.2×10^8 pCi/L and averaged 8.5×10^7 pCi/L. For each nuclear test, the elapsed time was computed for tritium to radioactively decay from the initial concentration to the SDWA standard of 20,000 pCi/L (U.S. Environmental Protection Agency, 2017). The elapsed time ranged from 7 to 165 years and averaged 120 years. The upper bound of elapsed time was used to calculate the distance traveled from each test, which resulted in calculated distances for tests with low initial concentrations to be overestimated.

The 165-year advective-flow distances from each nuclear-test location are shown in figure 95. Advective-flow distances less than 400 ft are not shown on the figure because distances are too short to easily discern. Calculated advective-flow distances may be greater than actual tritium migration distances because the calculated distances do not account for dispersive effects. For example, not accounting for dispersion and matrix diffusion will overestimate downgradient migration distances. Because of potential for overestimation from using the upper bound of elapsed time and not accounting for dispersive effects, calculated advective-flow distances likely are biased high relative to the maximum extents of tritium transport above the SDWA standard.

Calculated 165-year advective-flow distances from underground nuclear tests are consistent with tritium migration distances, as determined from well samples and from radionuclide transport studies in Frenchman Flat, Yucca Flat–Climax Mine, and Rainier Mesa–Shoshone Mountain CAUs. Calculated advective-flow distances extend less than 0.5 mi from all underground nuclear tests in these CAUs, which is consistent with actual tritium migration distances between nuclear-test cavities and sampled wells. Tritium at concentrations greater than SDWA standards (20,000 pCi/L) has been measured only in wells within 300 ft of nuclear tests and in post-shot holes drilled into nuclear-test cavities or chimneys in Frenchman Flat and Yucca Flat–Climax Mine CAUs (Smith, 2002)³. In the Rainier Mesa–Shoshone Mountain CAU, tritium at concentrations greater than SDWA standards has been measured only in water from flooded tunnels where the tests were detonated (U.S. Department of Energy, 2018). Measured tritium migration distances are expected to be shorter than calculated 165-year advective-flow distances because only 25–60 years have elapsed from present (2018) since nuclear tests were detonated in these CAUs. Detailed, smaller-scale, model analyses, using conservative assumptions, have been published that support limited downgradient migration from Frenchman Flat, Yucca Flat–Climax Mine, and Rainier Mesa–Shoshone Mountain CAUs. Simulated tritium at concentrations greater than SDWA standards remained within NNSS boundaries over a 1,000-year period for underground nuclear tests in Frenchman Flat (Navarro Nevada Environmental Services, LLC, 2010), Yucca Flat–Climax Mine (Navarro-Intera, LLC, 2013), and Rainier Mesa–Shoshone Mountain CAUs (U.S. Department of Energy, 2018). These simulated results are consistent with computed advective-flow distances from this study.

Pahute Mesa has known tritium plumes migrating from BENHAM/TYBO (Wolfsberg and others, 2002), CHESHIRE (Pawloski and others, 2001), and HANDLEY (Navarro-Intera, LLC, 2015) nuclear tests. The longest measured plumes to date (2018) occur downgradient of the BENHAM/TYBO and HANDLEY tests. Tritium at concentrations greater than the SDWA standard has moved at least 2.6 mi in 50 years from the BENHAM/TYBO test and 1.9 mi in 48 years from the HANDLEY test (Mission Support and Test Services, LLC, 2018). Tritium data indicate that advective transport velocities range from at least 205 ft/yr from the HANDLEY test to 276 ft/yr from the BENHAM/TYBO test. Assuming uniform advective transport velocities along flow paths from these nuclear tests and initial tritium concentrations of 2.2×10^8 pCi/L, maximum tritium migration at concentrations greater than the SDWA standard ranges from 6.4 to 8.6 mi from HANDLEY and BENHAM/TYBO tests, respectively.

³ Tritium concentrations greater than the SDWA standard only were considered from sites where tritium migrated from the source in the groundwater system through either predevelopment flow or induced flow from pumping. Well UE-5n in Frenchman Flat was not included because tritiated groundwater withdrawn from well RNM-2S was discharged into an unlined ditch, infiltrated basin fill beneath the ditch, and contaminated groundwater in the vicinity of well UE-5n (Smith, 2002).




Figure 95. Simulated 165-year advective-flow paths from 296 underground nuclear tests detonated near or below the water table, in the study area, Nevada National Security Site, Nevada. Simulated flow paths do not coincide with tritium plumes and do not represent tritium plumes.

Calculated 165-year advective-flow distances from underground nuclear tests are consistent with downgradient extents of measured tritium plumes in the Pahute Mesa CAU. Advective-flow distances from nuclear tests range from less than 0.1 to 12.6 mi and average 1.8 mi. Advective velocities range from 0.03 to 400 ft/yr and average 60 ft/yr. These calculated advective-flow distances and velocities are within the range of estimated tritium migration distances from HANDLEY and BENHAM/TYBO tests.

Simulated groundwater-flow paths do not coincide with known tritium plumes in the Pahute Mesa CAU. Discrepancies are attributed to DV3-SS model limitations. Computed advective-flow distances from HANDLEY and BENHAM/TYBO tests are shorter than measured transport distances because advective velocities in the DV3 model are controlled by low (less than 50 ft²/d) transmissivities in wells near these tests and the DV3-SS model was not calibrated to tritium concentrations in downgradient wells. Despite these model errors, computed advective-flow distances for all tests suggest that a limited number of plumes with tritium concentrations greater than SDWA standards exist and that these plumes will migrate only a few miles. This is consistent with the number and migration distance of identified tritium plumes on Pahute Mesa. Furthermore, although simulated flow paths locally do not match observed tritium plumes, simulated flow paths from all tests end in Oasis Valley, which is consistent with the expected discharge location (Fenelon and others, 2010, 2016).

Boundary conditions and flow rates from the DV3 model can be applied to local-scale CAU transport models, where tritium transport migration results can be refined. Advective-flow distances in Frenchman Flat, Yucca Flat–Climax Mine, and Rainier Mesa–Shoshone Mountain CAUs are consistent with expected tritium transport distances based on data and previous numerical studies. Advective velocities from nuclear tests in Pahute Mesa CAU are within the range of actual tritium migration velocities from HANDLEY and BENHAM/TYBO tests. Similarities between measured transport velocities and calculated advective velocities indicate that flow rates in the DV3 model are reasonable.

A steady-state assumption is appropriate for simulation of flow and transport within CAU-scale models. Advective-flow distances from underground nuclear tests in Frenchman Flat, Yucca Flat–Climax Mine, and Rainier Mesa–Shoshone Mountain CAUs are less than 0.5 mi. These flow paths do not extend into shallow carbonate rocks of the regional carbonate aquifer and, therefore, effects of regional pumping on advective transport are negligible. Advective-flow distances are more than 5 mi from several nuclear tests in the Pahute Mesa CAU. However, the PMOV groundwater basin is a hydraulically isolated basin. Water-level declines from pumping in AFFCR and Ash Meadows groundwater basins do not extend into the PMOV groundwater basin (fig. 57). Pumping within the PMOV groundwater basin has withdrawn about 26,000 acre-ft of groundwater from storage between 1945 and 2010 (fig. 89), which has affected water levels only locally (Jackson and Fenelon, 2018).

Model Limitations

The DV3 model addresses questions about predevelopment groundwater flow, groundwater development, and advective-flow rates in the study area. Veracity of simulated results depends on how well the DV3 model approximates the actual system. Simplification of underlying conceptual models, uncertainty in estimates of predevelopment groundwater discharges, and errors in pumping estimates are major limitations. These limitations result from insufficient measurements to fully account for variations in hydraulic properties and stresses throughout the model area. Spatial and temporal discretization also affect results, but these numerical limitations are minor relative to data limitations.

Groundwater discharges substantially affect numerical model results but remain poorly defined from Furnace Creek and Lower Amargosa discharge areas. Predevelopment groundwater discharge from the Furnace Creek area totals 8.5 ft³/s (6,100 acre-ft/yr) in this investigation, but likely is overestimated. Measured discharges from springs and diversions were not concurrent and discharge from the alluvial fan below Furnace Creek Wash was estimated with extrapolated ET_{GW} rates. Average simulated transmissivities of 30,000 ft²/d through Furnace Creek Wash are biased high and suggest that discharge from the alluvial fan was overestimated. Groundwater discharge from the Lower Amargosa area was estimated exclusively with extrapolated ET_{GW} rates. Uncertainty of groundwater discharge from the Furnace Creek and Lower Amargosa areas can be reduced by appropriate investigations.

Simulated effects of pumping from the central Amargosa Desert on water levels in *Devils Hole* depend greatly on the well AD-4 corridor. Water-level profiles confirm the existence of the well AD-4 corridor, but the degree of hydraulic connection has not been estimated independently. Pumping from carbonate rocks east of well AD-4 and observing drawdowns in basin fill around well AD-4 would confirm the magnitude of hydraulic connection through the well AD-4 corridor.

The area north and east of the NNSS remains poorly defined because less than 24 wells were available (fig. 46). This 3,300 mi² area encompasses Gold Flat in the northwest, the Pahranaagat Range in the northeast, and the Sheep Range in the southeast, and covers 30 percent of the study area. Estimated hydraulic properties of carbonate rocks east and north of well USAF R65N (fig. 49) mostly were uninformed by data. Hydraulic properties of basin fill and carbonate rocks between well Army 1 WW and Indian Springs were minimally informed by water levels (figs. 29 and 46) and aquifer-test results (fig. 19).

Measured groundwater levels and discharges were not matched perfectly by their simulated equivalents, even after calibration, because errors cumulatively affect model results. These irreducible errors result from simplification of the conceptual model, grid scale, and insufficient measurements. Simulated and measured quantities should be compared to estimate uncertainty of specific simulated results. Plausibility of predicted drawdowns in a well should be evaluated by similarity between simulated and measured water-level changes prior to prediction. For example, simulated water levels in ET areas within Chicago Valley and near Tecopa (fig. 55) show spatial biases because there is a structural model error that cannot be resolved with the limited data available. Clayey Tecopa Lake beds and underlying China Ranch beds remain undifferentiated in the hydrogeologic framework. This conceptual model was not incorporated because differences cannot be defined without wells and well logs. The structural model error does not affect the timing of capture between Pahrump and Shoshone because drawdowns in well *Hwy 127 MM21-1* provide information about the hydraulic connection between these areas (fig. 57). However, data are unavailable to provide information about the timing and magnitude of drawdown and capture near Tecopa from pumping in Pahrump.

Simulation results indicate that about 180 acre-ft/yr of groundwater moves northward from Pahrump Valley to the Ash Meadows discharge area (fig. 88). This result is speculative and uncertain because of a lack of water-level data in wells to constrain flow between Pahrump Valley and the Ash Meadows discharge area. For example, measured water levels in well *GS-1 Well (AD-12)* (fig. 6) have declined about 0.5 ft since 1996. The DV3-PDVS model simulated less than 0.1 ft of water-level decline from 1913 to 2018 in response to pumping from Pahrump Valley. Most of the water-level decline in well *GS-1 Well (AD-12)* may be attributed to poor well construction or slow water-level equilibration following well construction (Fenelon and Moreo, 2002). Well *GS-1 Well (AD-12)* is a recompleted borehole that initially was drilled for mineral exploration. The USGS cased the existing borehole in 1986, where monitoring well *GS-1 Well (AD-12)* is a 10-ft interval at the bottom of the borehole open to low-permeability calcareous mudstone (Fenelon and Moreo, 2002). Slow water-level recovery following well completion likely explains most of the water-level decline in this well.

Lateral discretization of the study area into a rectangular grid of cells and vertical discretization into layers forced an averaging of hydraulic properties. Each cell was assumed to represent a homogeneous block or some volumetric average of the aquifer medium. Discretization errors occurred in every model cell, which includes the smallest model cells. Bedding structures in the alluvium and fracture networks in the bedrock were averaged even in the smallest cells, which were 820 ft on

a side and 160 ft thick. Flow paths were averaged over lengths of about 0.3 mi because hydraulic properties are averaged.

Errors in hydraulic diffusivity inversely affect the timing of groundwater capture. Hydraulic diffusivity is transmissivity divided by storativity, which functionally is specific yield for unconfined aquifer conditions. Groundwater capture will occur sooner as hydraulic diffusivity increases and will be delayed as hydraulic diffusivity decreases. Errors in hydraulic-diffusivity estimates of 50 percent in the DV3-PRED model are not unexpected, so 50-percent errors in timing of groundwater-capture estimates can occur.

The spatial distribution of simulated recharge minimally affects model results. Simulated recharge refines hydraulic-conductivity estimates; however, most recharge occurs upgradient of areas of interest. For example, hydraulic-diffusivity estimates in the Furnace Creek area, central Amargosa Desert, megachannel, and Pahrump Valley primarily were defined by fitting to measured water-level declines from pumping and water-level altitudes from predevelopment discharges. In these areas where hydraulic-diffusivity estimates affect predictions of pumping on water levels, the effect of upgradient recharge is minimal. The total volume of recharge is more important. For example, in Pahute Mesa, the total volume of recharge is well defined because total discharge in Oasis Valley is defined well from detailed micrometeorological measurements (Laczniak and others, 1999; Reiner and others, 2002). The simulated recharge distribution may be nonunique, but most recharge occurs upgradient of nuclear tests that define the leading edge of transport from Pahute Mesa. Total subsurface flow downgradient of Pahute Mesa should be simulated correctly, and this flow is constrained by ensuring a water balance between recharge and discharge in the PMOV groundwater basin. The spatial recharge distribution is most important for Rainier Mesa; however, total recharge is limited by low-permeability volcanic rocks (tunnel beds).

Changes in recharge in response to climate change were not considered in this study. The steady-state (DV3-SS) model assumes recharge remains unchanged over a timescale of more than a century. Water-level changes from changes in recharge are assumed small, such that transmissivity is not a function of thickness. Therefore, changes in recharge do not affect the hydraulic properties of the groundwater system. Groundwater development (DV3-AM-AFFCR and DV3-PDVS) models and the predictive (DV3-PRED) model do not simulate time-varying changes in recharge and temporal recharge trends were removed from well hydrographs, where appropriate. If future recharge decreases within the next 100 years, then drawdowns will increase. The DV3-AM-AFFCR, DV3-PDVS, and DV3-PRED models simulate water-level declines from pumping only. The estimation of spatially distributed water-level changes from historical variations in recharge and likely future changes were beyond the scope of this study.

Summary

The study area consists of the Pahute Mesa–Oasis Valley (PMOV), Alkali Flat–Furnace Creek Ranch (AFFCR), Ash Meadows, and Pahrump to Death Valley South (PDVS) groundwater basins in Nevada and California. Radionuclides were introduced into the groundwater system of the study area by underground nuclear testing beneath the Nevada National Security Site (NNSS). Pumping by Cappaert Enterprises in the Ash Meadows discharge area during the 1970s directly affected water levels in *Devils Hole*, the exclusive habitat of the endangered Devils Hole pupfish, *Cyprinodon diabolis*. Pumping for irrigation in the central Amargosa Desert and Pahrump Valley can adversely affect federally protected groundwater-dependent ecosystems. Groundwater-basin boundaries were uncertain, which affects potential radionuclide migration directions and the degree of hydraulic connection between pumping centers and groundwater-dependent ecosystems.

To address the above stated problems, the five purposes of this report were to:

1. Characterize predevelopment groundwater flow;
2. Evaluate effects of historical (1913–2018) groundwater development on water levels and discharges;
3. Estimate potential future (2019–2100) effects of groundwater development on water levels and spring discharges;
4. Evaluate advective flow from selected underground nuclear tests to determine if boundary conditions and flow rates from the regional model in this study are reasonable for local-scale flow and transport models; and
5. Address groundwater-basin boundary uncertainty in the study area.

Characterization of predevelopment groundwater flow required conceptual models for recharge, discharge, and hydraulic-conductivity distributions within hydrogeologic units. Conceptual models integrated water-level data, transmissivity estimates, geologic data, water availability in recharge areas, and locations and estimates of predevelopment discharge. A hydrogeologic framework was used to distribute hydraulic properties within hydrogeologic units during simulation of predevelopment and groundwater development.

Regional discharge areas were analyzed critically because hydraulic-property estimates and predictions of groundwater capture depend greatly on specified locations and rates of discharges. Virtually all discharge from the Ash Meadows discharge area was attributed directly to springs. The predevelopment water budget from the Furnace Creek area included diversions from Furnace Creek Wash, a major hydrologic feature that conveys groundwater to the alluvial fan at Furnace Creek. Discharges from Pahrump and Stewart Valleys likely totaled 13,300 acre-feet per year (acre-ft/

yr) prior to development, with 9,800 acre-ft/yr (13.5 cubic feet per second) discharging from *Bennetts* and *Manse* Springs. Discharge from the Lower Amargosa area ceased 2 miles south of Tecopa, where China Ranch beds above the Amargosa River were eroded or unsaturated. Saratoga Spring area is supplied primarily by base flow in the Amargosa River that infiltrates basin fill below Dumont Dunes. Playas were interpreted as low-permeability features that discharged very little groundwater.

Relations between transmissivity, rock type, and depth in the study area were investigated with transmissivity estimates from 271 aquifer tests and specific capacities. Rocks were categorized into four hydraulically distinct hydrogeologic units: (1) basin fill; (2) carbonate rocks; (3) volcanic rocks; and (4) low-permeability granitic and siliciclastic rocks. Thicknesses of hydrogeologic units and their transmissivities were not correlated regardless of rock type. More than 90 percent of estimated transmissivity in carbonate and volcanic rocks occurred within 1,600 feet (ft) of the water table. Contributing intervals composed less than 10 percent of open holes in carbonate and volcanic rocks and did not occur predictably with depth.

A hydrogeologic framework was developed with simplified hydrogeologic units that were appropriate for extrapolating hydraulic conductivities. The hydrogeologic framework was divided into five layers and extended from the water table to 3,300 ft below the National Geodetic Vertical Datum of 1929 (NGVD29). Thick sequences of carbonate and volcanic rocks were divided into shallow and deep intervals based on analysis of hydraulic conductivity with depth. Hydrogeologic interpretations from the Underground Test Area project were incorporated in the framework because drilling 34 new boreholes and completing 119 new wells during 2000–2016 reduced geologic and hydrologic uncertainties. Major hydrologic features, such as Furnace Creek Wash and China Ranch beds, were incorporated explicitly in the hydrogeologic framework.

Pumping in the study area averaged 46,000 acre-ft/yr from 1960–2010 and totaled 38,000 acre-ft/yr in 2010. The 46,000 acre-ft/yr of pumping averaged 80 percent of the predevelopment discharge, which totaled about 55,000 acre-ft/yr. Annual pumping in the PDVS groundwater basin peaked at 46,000 acre-ft/yr in 1968 and exceeded the basin predevelopment discharge of 22,400 acre-ft/yr between 1955 and 2000. Pumping from AFFCR and Ash Meadows groundwater basins gradually increased from 700 acre-ft/yr in 1950 to 21,000 acre-ft/yr in 2010 and has not exceeded the predevelopment discharge of 26,000 acre-ft/yr. Pumping by Cappaert Enterprises in the Ash Meadows discharge area totaled 42,000 acre-ft during 1969–1977. Water levels declined 2.3 ft in *Devils Hole* in response to this pumping. Return flows from irrigation, domestic, and metered pumping in the study area averaged 20 percent of the pumping, with a 2-year delay between application and recharge to the water table.

The central Amargosa Desert and Pahrump Valley were the two primary pumping centers and affected water levels in areas of 300 and 600 square miles (mi²), respectively. These broad areas were delineated using dozens of wells, where water levels declined at rates greater than 0.1 ft per decade. Delineation of areas affected by pumping were more tenuous in the Funeral Mountains and Lower Amargosa area because observation wells were few or non-existent there. Groundwater levels distant from pumping centers rose between 1980 and 2018 throughout most of the study area in response to a wetter-than-average period from 1970 to 2018.

Water-level changes in *Devils Hole* have been influenced measurably by long-term natural fluctuations in addition to pumping. These long-term natural fluctuations appear as multiple-decade periods of declining or rising water levels and result from differences between episodic recharge and steady discharge. Water levels in *Devils Hole* were simulated with an analytical water-level model so that long-term, natural fluctuations from recharge could be estimated and differentiated from pumping effects. Estimated long-term, natural fluctuations suggest that water levels in *Devils Hole* would have risen about 1 ft between 1973 and 2018 in the absence of pumping.

Recharge and hydraulic-property distributions in the study area were estimated by simultaneously calibrating four numerical, groundwater models. Predevelopment (steady-state) conditions (DV3-SS model); groundwater development in Ash Meadows, AFFCR, and PMOV groundwater basins (DV3-AM-AFFCR model); groundwater development in PDVS groundwater basin (DV3-PDVS model); and the well *ER-6-1-2 main* multiple-well aquifer test (DV3-ER612 model) were simulated with four stress-response models. Stress-response pairs were isolated with separate models so that fewer errors were introduced compared to simulating all responses with a single generalized model. For example, discharge rates were specified at nearly all springs and evapotranspiration areas in the DV3-SS model, whereas discharge was simulated using capture-limited boundaries in DV3-AM-AFFCR, DV3-PDVS, and DV3-ER612 models, which prevented simulated captures from exceeding measured discharges.

Hydraulic-conductivity, specific-yield, specific-storage, and recharge distributions, as well as extinction depths from springs with known captures were estimated by minimizing a weighted composite, sum-of-squares objective function that included measurement and Tikhonov regularization observations. Measured observations included water-level altitudes, water-level differences between wells, transmissivities, selected flow rates, temporal water-level changes, and spring captures. Simulated responses from all four groundwater models were compared to measured observations and the comparisons simultaneously informed revised parameter estimates. Hydraulic conductivity, specific yield, specific storage, and recharge were distributed with pilot points in the groundwater models so that observed spatial variability could be simulated in hydrogeologic

units. Simulated responses compare favorably to measured observations for all quantifiable observations.

Simulated water-level changes in *Devils Hole* were the summation of pumping changes that were simulated with the DV3-AM-AFFCR model and long-term, natural fluctuations from episodic recharge and steady discharge that were simulated with an analytical water-level model. Measured and simulated (numerical + analytical model) water levels in *Devils Hole* agreed with a root-mean-square error of 0.2 ft. Overall shape of water levels and responses to pumping stresses in *Devils Hole* agreed through the nearly 70-year period of record.

Eight major hydrologic features were identified in the study area and were simulated correctly:

1. The perched water-table mound beneath Rainier Mesa, which allows for numerical simulation of groundwater flow from nuclear tests in Rainier Mesa.
2. The boundary between PMOV and AFFCR groundwater basins, which affects rates and directions of radionuclide migration from Pahute Mesa.
3. The megachannel—a high hydraulic diffusivity feature that causes drawdowns to propagate quickly and recover slowly. The megachannel extends from Ash Meadows discharge area to Indian Springs and from the southernmost part of the NNSS to northern Yucca Flat.
4. The Gravity fault, which forms a flow barrier that juxtaposes low-permeability basin fill downgradient of highly transmissive carbonate rocks. The Gravity fault causes groundwater to move upward and discharge from springs in the Ash Meadows discharge area.
5. The well *AD-4* corridor, which hydraulically connects Ash Meadows and AFFCR groundwater basins.
6. Alluvial deposits along Furnace Creek Wash, which transmit groundwater above *Travertine* Springs to the alluvial fan on the floor of Death Valley.
7. Black Mountains and Greenwater Range forming flow barriers, which isolate Death Valley from the central Amargosa Desert and Amargosa River.
8. Carbonate rocks and basin fill forming a continuous aquifer between the Spring Mountains and the Amargosa River.

Predevelopment (DV3-SS model) results indicate that the recharge source or sources for most of the major discharge areas are derived from the same groundwater basin. Oasis Valley, Ash Meadows discharge area, *Bennetts* and *Manse* Springs, and Lower Amargosa area primarily discharge groundwater that was recharged in the same groundwater basin. Discharge from the Furnace Creek area was atypical because more than 40 percent of the discharge was recharged in another groundwater basin.

The well AD-4 corridor is an area of considerable interbasin flow (2,550 acre-ft/yr) that hydraulically connects AFFCR and Ash Meadows groundwater basins. The longest flow paths in the study area pass through the well AD-4 corridor. Groundwater flows upward from carbonate rocks in Ash Meadows groundwater basin to basin fill in the well AD-4 corridor, moves west through the central Amargosa Desert, flows from basin fill to carbonate rocks in the Funeral Mountains, and continues to flow westward to the Furnace Creek area before discharging. This flow path is consistent with hydraulic and hydrochemical evidence. Results from the DV3-SS model also are consistent with this conceptual model of connecting recharge and discharge areas through basin fill in the central Amargosa Desert. An alternative conceptual model connects recharge and discharge areas through deep carbonate rocks along the Furnace Creek fault zone, but this conceptual model is less probable based on hydraulic and hydrochemical data.

Water budgets were simulated for subareas of groundwater basins in the study area to estimate groundwater-flow rates from corrective action units (CAUs) at the NNSS and to inform water availability in subareas. More than 90 percent of the groundwater discharging in Oasis Valley is derived from recharge sourced at Pahute Mesa and Timber Mountain. About 80 percent (17,400 acre-ft/yr) of recharge in Ash Meadows groundwater basin is derived from the Spring Mountains and Sheep Range. Less than 3 percent of the predevelopment flow in Ash Meadows groundwater basin moves through Yucca Flat. Slightly more than one-half (2,840 acre-ft/yr) of the recharge in AFFCR groundwater basin is derived from Timber, Yucca, and Shoshone Mountains. Most groundwater that enters the Amargosa Desert moves westward toward Furnace Creek. Total simulated discharge at Franklin Lake is 440 acre-ft/yr, with most of this discharge sourced from the Amargosa Desert. Most recharge to the PDVS groundwater basin occurs in the Spring Mountains.

Ash Meadows and AFFCR groundwater basins are coupled and are better considered as a single groundwater basin. Areal extensive drawdowns from pumping in both groundwater basins have coalesced into a 2,200-mi² area. Hydraulic continuity principally occurs through the well AD-4 corridor. The PDVS groundwater basin functionally is limited to transmissive rocks between the Lower Amargosa area and the Spring Mountains and is hydraulically isolated from other groundwater basins in the study area. The PMOV groundwater basin also is hydraulically isolated from other basins and the DV3 model supports the previously mapped boundary.

Groundwater development in the study area principally has removed water from storage because most of the pumping has been relatively distant from discharge areas. Cumulative pumping volumes totaled 50, 31, and 19 percent from storage depletion, capture, and return flow, respectively, during groundwater development between 1910 and 2018. Sources differed considerably by groundwater basin. Storage depletion supplied greater than 90 percent of pumped water from AFFCR and Ash Meadows basins. Storage depletion annually exceeded capture during peak pumping between 1952 and

1985 in the PDVS groundwater basin. Capture was substantial where groundwater development occurred near springs in Pahrump Valley and the Ash Meadows discharge area.

Only pumping centers in the central Amargosa Desert and Ash Meadows groundwater basin measurably affected water levels in *Devils Hole*. Pumping by Cappaert Enterprises and the NNSS inside the megachannel have most affected water levels in *Devils Hole* and accounted for 50 percent of the anthropogenic water-level decline in 2018. Water levels in *Devils Hole* have declined slowly and steadily from pumping in the central Amargosa Desert, which accounted for a third of the anthropogenic water-level decline in 2018.

Future depths to water below the reference in *Devils Hole* depend on pumping and long-term natural fluctuations. Water levels in *Devils Hole* likely will decline between 0.1 and 0.2 ft per decade during the next 80 years, assuming future pumping rates are similar to 2010 rates. Analytically simulated natural fluctuations between 1900 and 2018 have ranged from declines of 0.1 ft per decade to rises of 0.3 ft per decade. Natural fluctuations depend on future precipitation and are functionally unknown, but likely will be bound by historical rates of change for the next few decades.

Advective-flow distances and velocities from underground nuclear tests in the DV3 model are within the range of advective transport calculations from tritium data and previous radionuclide transport investigations. This result indicates that boundary conditions and flow rates from the (regional) DV3 model are reasonable for local-scale CAU transport models. Simulated 165-year groundwater-flow paths also do not extend into pumping areas and effects of regional pumping on advective transport are negligible. This result indicates that a steady-state (predevelopment) assumption is appropriate for local-scale CAU flow and transport models.

The DV3 model is a major improvement compared to previous regional models of the study area, such as the Death Valley Regional Flow System version 2 (DVRFS.v2) model. Veracity of simulated results depends on how well a model approximates the actual system. Compared to the DVRFS.v2 model, the DV3 model has a better fit between measured and simulated water-level altitudes, water-level differences between wells, transmissivities, discharges, temporal water-level changes, and spring captures. The DV3 model also is consistent with conceptual models of predevelopment flow through groundwater-discharge areas and major hydrologic features, unlike the DVRFS.v2 model, which had inconsistencies between conceptual models and numerical results.

Results from the DV3 model can support future investigations of radionuclide transport and pumping effects in the study area. Boundary conditions and flow rates from the DV3 model can support boundary conditions applied to local-scale models of flow and radionuclide transport from the Pahute Mesa and Yucca Flat–Climax Mine CAUs. The DV3 model also can estimate potential effects of groundwater development on water levels in *Devils Hole* and other federally protected groundwater-dependent ecosystems in the study area.

Acknowledgments

The authors gratefully acknowledge John Klenke of the Nuclear Waste Repository Project Office in Nye County, Nevada, for providing Pahrump Valley and Amargosa Desert water-level data. The authors also gratefully acknowledge the following U.S. Geological Survey personnel:

- Steven R. Reiner and Peggy E. Elliott for data processing,
- Donald S. Sweetkind for providing geologic insights and technical guidance to revise the Death Valley version 3 (DV3) hydrogeologic framework,
- Nora Nelson for assisting with documentation of the model archive of the data release,
- Rebecca Frus for quality assurance and documentation of transmissivity estimates in Appendix B of the data release,
- Philip Gardner and Steve Van Denburgh for providing technical guidance in evaluation of water-chemistry data, and
- Joseph M. Fenelon for providing conceptual guidance of hydrologic principles developed in this report and for quality assurance of water-chemistry data in Appendix G of the data release.

The authors gratefully acknowledge the reviewers of this report, model archive, and data release appendixes for their helpful comments:

- Karl Pohlmann and Chuck Russell of the Desert Research Institute;
- Edward M. Kwicklis of Los Alamos National Laboratory;
- Peter Martian of Navarro, LLC;
- Richard Waddell and Guy Roemer of Tetra Tech;
- Sue Braumiller of the U.S. Fish and Wildlife Service;
- Paula A. Cutillo of the U.S. National Park Service; and
- Joseph M. Fenelon, Philip Gardner, Leonard Konikow, and Stanley Leake of the U.S. Geological Survey.

References Cited

- Allander, K.K., Smith, J.L., and Johnson, M.J., 2009, Evapotranspiration from the Lower Walker River Basin, west-central Nevada, water years 2005–07: U.S. Geological Survey Scientific Investigations Report 2009-5079, 62 p., <https://pubs.er.usgs.gov/publication/sir20095079>.
- Anderman, E.R., and Hill, M.C., 2000, MODFLOW-2000, the U.S. Geological Survey modular ground-water model—Documentation of the Hydrogeologic-Unit Flow (HUF) package: U.S. Geological Survey Open-File Report 2000-342, 89 p., <https://doi.org/10.3133/ofr00342>.
- Bechtel Nevada, 2002, A hydrostratigraphic model and alternatives for the groundwater flow and contaminant transport model of Corrective Action Units 101 and 102—Central and western Pahute Mesa, Nye County, Nevada: U.S. Department of Energy Report DOE/NV/11718–706, 383 p., <https://www.osti.gov/biblio/799777>.
- Bechtel Nevada, 2005a, A hydrostratigraphic framework model and alternatives for the groundwater flow and contaminant transport model of Corrective Action Unit 98: Frenchman Flat, Clark, Lincoln and Nye Counties, Nevada: U.S. Department of Energy Report DOE/NV/11718-1064, 240 p., <https://www.osti.gov/biblio/859292>.
- Bechtel Nevada, 2005b, Completion report for well cluster ER-5-3: U.S. Department of Energy Report DOE/NV/11718-1093, 202 p.
- Bechtel Nevada, 2005c, Completion report for well cluster ER-5-4: U.S. Department of Energy Report DOE/NV/11718-998, 159 p.
- Bechtel Nevada, 2006, A hydrostratigraphic model and alternatives for the groundwater flow and contaminant transport model of Corrective Action Unit 97—Yucca Flat—Climax Mine, Lincoln and Nye Counties, Nevada: U.S. Department of Energy Report DOE/NV/11718-1119, 288 p., <https://www.osti.gov/biblio/878649>.
- Bedinger, M.S., and Harrill, J.R., 2006, Analytical regression stage analysis for Devils Hole, Death Valley National Park, Nevada: *Journal of the American Water Resources Association*, v. 42, no. 4, p. 827–839, <https://doi.org/10.1111/j.1752-1688.2006.tb04497.x>.
- Belcher, W.R., ed., 2004, Death Valley regional ground-water flow system, Nevada and California—Hydrogeologic framework and transient ground-water flow model: U.S. Geological Survey Scientific Investigations Report 2004-5205, 408 p., <https://pubs.er.usgs.gov/publication/sir20045205>.
- Belcher, W.R., Bedinger, M.S., Back, J.T., and Sweetkind, D.S., 2009, Interbasin flow in the Great Basin with special reference to the southern Funeral Mountains and the source of Furnace Creek springs, Death Valley, California, U.S.: *Journal of Hydrology*, v. 369, nos. 1–2, p. 30–43, <https://doi.org/10.1016/j.jhydrol.2009.02.048>.

- Belcher, W.R., Elliott, P.E., and Geldon, A.L., 2001, Hydraulic property estimates for use with a transient ground-water flow model of the Death Valley regional ground-water flow system, Nevada and California: U.S. Geological Survey Water-Resources Investigations Report 2001-4210, 28 p., <https://doi.org/10.3133/wri014210>.
- Belcher, W.R., and Sweetkind, D.S., eds., 2010, Death Valley regional ground-water flow system, Nevada and California—Hydrogeologic framework and transient ground-water flow model: U.S. Geological Survey Professional Paper 1711, 398 p., <https://doi.org/10.3133/pp1711>.
- Belcher, W.R., Sweetkind, D.S., and Elliott, P.E., 2002, Probability distributions of hydraulic conductivity for the hydrogeologic units of the Death Valley regional ground-water flow system, Nevada and California: U.S. Geological Survey Water-Resources Investigations Report 2002-4212, 24 p., <https://doi.org/10.3133/wri024212>.
- Belcher, W.R., Sweetkind, D.S., Faunt, C.C., Pavelko, M.T., and Hill, M.C., 2017, An update of the Death Valley regional groundwater flow system transient model, Nevada and California: U.S. Geological Survey Scientific Investigations Report 2016-5150, 74 p., 1 pl., <https://doi.org/10.3133/sir20165150>.
- Belcher, W.R., Sweetkind, D.S., Hopkins, C.B., and Poff, M.E., 2019, Hydrogeology of Lower Amargosa Valley and groundwater discharge to the Amargosa Wild and Scenic River, Inyo and San Bernardino Counties, California, and adjacent areas in Nye and Clark Counties, Nevada: U.S. Geological Survey Scientific Investigations Report 2018-5151, 131 p., 1 pl., <https://doi.org/10.3133/sir20185151>.
- Berger, D.L., Mayers, C.J., Garcia, C.A., Buto, S.G., and Huntington, J.M., 2016, Budgets and chemical characterization of groundwater for the Diamond Valley flow system, central Nevada, 2011–12: U.S. Geological Survey Scientific Investigations Report 2016-5055, 83 p., <https://doi.org/10.3133/sir20165055>.
- Blankennagel, R.K., and Weir, J.E., Jr., 1973, Geohydrology of the eastern part of Pahute Mesa, Nevada Test Site, Nye, County, Nevada: U.S. Geological Survey Professional Paper 712-B, 35 p., <https://doi.org/10.3133/pp712BBredehoeft>.
- Blankennagel, R.K., and Weir, J.E., Jr., 2002, The water budget myth revisited—Why hydrogeologists model: *Groundwater*, v. 40, no. 4, p. 340–345, <https://doi.org/10.1111/j.1745-6584.2002.tb02511.x>.
- Bredehoeft, J., 2007, It is the discharge: *Groundwater*, v. 45, no. 5, p. 523.
- Buqo, T., 2004, Nye County water resources plan: Tonopah, Nevada, Nye County Department of Natural Resources and Federal Facilities, 136 p., <http://www.nyecounty.net/DocumentCenter/View/145/Nye-County-Water-Resources-Plan?bidId=>.
- Byers, F.M., Jr., Carr, W.J., Orkild, P.P., Quinlivan, W.D., and Sargent, K.A., 1976, Volcanic suites and related cauldrons of the Timber Mountain-Oasis Valley caldera complex, southern Nevada: U.S. Geological Survey Professional Paper 919, 70 p., <https://doi.org/10.3133/pp919>.
- Carr, W.J., Grow, J.A., and Keller, S.M., 1995, Lithologic and geophysical logs of drill holes Felderhoff Federal 5-1 and 25-1, Amargosa Desert, Nye County, Nevada: U.S. Geological Survey Open-File Report 95-155, 14 p., <https://doi.org/10.3133/ofr95155>.
- Carson, R.L., 1979, Water-resources data collected in the Devils Hole area, Nye County, Nevada, 1976–77: U.S. Geological Survey Open-File Report 79-742, 22 p.
- Castor, S.B., McLaurin, B.T., Ludington, S., and Flynn, K.S., 2006, Mineral resource potential of the Ash Meadows and Amargosa Mesquite Trees Areas of Critical Environmental Concern, Nye County, Nevada, chap. F of Ludington, S., ed., Mineral resource assessment of selected areas in Clark and Nye Counties, Nevada: U.S. Geological Survey Scientific Investigations Report 2006-5197, p. F1–F13, <http://pubs.usgs.gov/sir/2006/5197/>.
- Christiansen, R.L., Lipman, P.W., Carr, W.J., Byers, F.M., Jr., Orkild, P.P., and Sargent, K.A., 1977, Timber Mountain-Oasis Valley caldera complex of southern Nevada: *Geological Society of America Bulletin*, v. 88, no. 7, p. 943–959, [https://doi.org/10.1130/0016-7606\(1977\)88<943:TMVCCO>2.0.CO;2](https://doi.org/10.1130/0016-7606(1977)88<943:TMVCCO>2.0.CO;2).
- Claassen, H.C., 1973, Water quality and physical characteristics of Nevada Test Site water-supply wells: U.S. Geological Survey Report 474-158, 145 p.
- Claassen, H.C., 1985, Sources and mechanisms of recharge for ground water in the west-central Amargosa Desert, Nevada; a geochemical interpretation: U.S. Geological Survey Professional Paper 712-F, 31 p., <https://doi.org/10.3133/pp712F>.
- Cooper, H.H., and Jacob, C.E., 1946, A generalized graphical method for evaluating formation constants and summarizing well field history: *Transactions, American Geophysical Union*, v. 27, no. 4, p. 526–534. <https://doi.org/10.1029/TR027i004p00526>.
- Craig, R.W., and Robison, J.H., 1984, Geohydrology of rocks penetrated by test well UE-25p#1, Yucca Mountain area, Nye County, Nevada: U.S. Geological Survey Water-Resources Investigations Report 84-4248, 57 p.
- Cuttillo, P.A., and Bredehoeft, J. D., 2011, Estimating aquifer properties from the water level response to earth tides: *Groundwater*, v. 49, no. 4, p. 600–610, <https://doi.org/10.1111/j.1745-6584.2010.00778.x>.

- Cuttillo, P.A., and Ge, S. 2006, Analysis of strain-induced ground-water fluctuations at Devils Hole, Nevada: *Geofluids*, v. 6, p. 319–333, <https://doi.org/10.1111/j.1468-8123.2006.00150.x>.
- Czarnecki, J.B., and Stannard, D.I., 1997, Geohydrology and evapotranspiration at Franklin Lake playa, Inyo County, California, with a section on estimating evapotranspiration using the energy-budget eddy-correlation technique by Stannard, D.I.: U.S. Geological Survey Water-Supply Paper 2377, 75 p., <https://doi.org/10.3133/wsp2377>.
- Czarnecki, J.B., and Waddell, R.K., 1984, Finite-element simulation of ground-water flow in the vicinity of Yucca Mountain, Nevada-California: U.S. Geological Survey Water-Resources Investigations Report 84-4349, 38 p., <https://doi.org/10.3133/wri844349>.
- Czarnecki, J.B., and Wilson, W.E., 1991, Conceptual models of the regional ground-water flow and planned studies at Yucca Mountain, Nevada: *Hydrological Science and Technology*, v. 7, nos. 1–4, p. 15–25.
- D’Agnese, F.A., Faunt, C.C., and Turner, A.K., 1998, An estimated potentiometric surface of the Death Valley region, Nevada and California, using geographic information systems and automated techniques: U.S. Geological Survey Water-Resources Investigations Report 97–4052, 15 p., 1 pl., <https://doi.org/10.3133/wri974052>.
- D’Agnese, F.A., Faunt, C.C., Turner, A.K., and Hill, M.C., 1997, Hydrogeologic evaluation and numerical simulation of the Death Valley regional ground-water flow system, Nevada and California: U.S. Geological Survey Water-Resources Investigations Report 96-4300, 124 p., <https://doi.org/10.3133/wri964300>.
- D’Agnese, F.A., O’Brien, G.M., Faunt, C.C., Belcher, W.R., and San Juan, Carma, 2002, A three-dimensional numerical model of predevelopment conditions in the Death Valley regional ground-water flow system, Nevada and California: U.S. Geological Survey Water-Resources Investigations Report 2002-4102, 114 p., <https://doi.org/10.3133/wri024102>.
- DeMeo, G.A., Lacznik, R.J., Boyd, R.A., Smith, J.L., and Nylund, W.E., 2003, Estimated ground-water discharge by evapotranspiration from Death Valley, California, 1997–2001: U.S. Geological Survey Water-Resources Investigations Report 2003-4254, 27 p., <https://doi.org/10.3133/wri034254>.
- Doherty, J., 2010b, Addendum to the PEST manual: Brisbane, Australia, Watermark Numerical Computing, 235 p.
- Doherty, J., 2010a, PEST, Model-independent parameter estimation—User manual (5th ed., with slight additions): Brisbane, Australia, Watermark Numerical Computing, 336 p.
- Doherty, J., and Johnston, J.M., 2003, Methodologies for calibration and predictive analysis of a watershed model: *Journal of the American Water Resources Association* 39, no. 2, p. 251–265. [Also available at <https://doi.org/10.1111/j.1752-1688.2003.tb04381.x>.]
- Drever, J.I., 1988, The geochemistry of natural waters (2d ed.): Prentice Hall, Upper Saddle River, New Jersey, 437 p.
- Dudley, W.W., Jr., and Larson, J.D., 1976, Effect of irrigation pumping on Desert Pupfish habitats in Ash Meadows, Nye County, Nevada: U.S. Geological Survey Professional Paper 927, 52 p., <https://doi.org/10.3133/pp927>.
- Elliott, P.E., and Fenelon, J.M., 2010, Database of groundwater levels and hydrograph descriptions for the Nevada Test Site area, Nye County, Nevada: U.S. Geological Survey Data Series 533, version 7.0, October 2016, 16 p., <https://doi.org/10.3133/ds533>.
- Elliott, P.E., and Moreo, M.T., 2011, Groundwater withdrawals and associated well descriptions for the Nevada National Security Site, Nye County, Nevada, 1951–2008: U.S. Geological Survey Data Series 567, 126 p., <https://doi.org/10.3133/ds567>.
- Elliott, P.E., and Moreo, M.T., 2018, Update to the groundwater withdrawals database for the Death Valley regional ground-water flow system, Nevada and California, 1913–2010: U.S. Geological Survey data release, <https://doi.org/10.5066/F75H7FH3>.
- Faunt, C.C., D’Agnese, F.A., and O’Brien, G.M., 2010, Hydrology, chap. D of Belcher, W.R., and Sweetkind, D.S., eds., Death Valley regional ground-water flow system, Nevada and California—Hydrogeologic framework and transient ground-water flow model: U.S. Geological Survey Professional Paper 1711, p. 161–249, <https://doi.org/10.3133/pp1711>.
- Faunt, C.C., Blainey, J.B., Hill, M.C., D’Agnese, F.A., and O’Brien, G.M., 2010, Transient numerical model, chap. F of Belcher, W.R., and Sweetkind, D.S., eds., Death Valley regional ground-water flow system, Nevada and California—Hydrogeologic framework and transient groundwater flow model: U.S. Geological Survey Professional Paper 1711, p. 251–344, <https://doi.org/10.3133/pp1711>.
- Faunt, C.C., Sweetkind, D.S., and Belcher, W.R., 2010, Three-dimensional hydrogeologic framework model, chap. E of Belcher, W.R., and Sweetkind, D.S., eds., Death Valley regional ground-water flow system, Nevada and California—Hydrogeologic framework and transient ground-water flow model: U.S. Geological Survey Professional Paper 1711, p. 161–249, <https://doi.org/10.3133/pp1711>.

- Fenelon, J.M., Halford, K.J., and Moreo, M.T., 2016, Delineation of the Pahute Mesa–Oasis Valley groundwater basin, Nevada (ver. 1.1, May 2016): U.S. Geological Survey Scientific Investigations Report 2015–5175, 40 p., <https://doi.org/10.3133/sir20155175>.
- Fenelon, J.M., Lacznia, R.J., and Halford, K.J., 2008, Predevelopment water-level contours for aquifers in the Rainier Mesa and Shoshone Mountain area of the Nevada Test Site, Nye County, Nevada: U.S. Geological Survey Scientific Investigations Report 2008–5044, 38 p., <https://pubs.er.usgs.gov/publication/sir20085044>.
- Fenelon, J.M., and Moreo, M.T., 2002, Trend analysis of ground-water levels and spring discharge in the Yucca Mountain region, Nevada and California, 1960–2003: U.S. Geological Survey Water-Resources Investigations Report 2002–4178, 97 p., <https://doi.org/10.3133/wri024178>.
- Fenelon, J.M., Sweetkind, D.S., Elliott, P.E., and Lacznia, R.J., 2012, Conceptualization of the predevelopment groundwater flow system and transient water-level responses in Yucca Flat, Nevada National Security Site, Nevada: U.S. Geological Survey Scientific Investigations Report 2012–5196, 61 p., <https://doi.org/10.3133/sir20125196>.
- Fenelon, J.M., Sweetkind, D.S., and Lacznia, R.J., 2010, Groundwater flow systems at the Nevada Test Site, Nevada—A synthesis of potentiometric contours, hydrostratigraphy, and geologic structures: U.S. Geological Survey Professional Paper 1771, 54 p., <https://pubs.usgs.gov/pp/1771/>.
- Fienen, M., Muffels, C., and Hunt, R., 2009, On constraining pilot point calibration with regularization in PEST: Groundwater, v. 47, no. 6, p. 835–844, <https://doi.org/10.1111/j.1745-6584.2009.00579.x>.
- Finnegan, D.L., Bowen, S.M., Thompson, J.L., Miller, C.M., Baca, P.L., Olivas, L.F., Geoffrion, C.G., Smith, D.K., Goishi, W., Esser, B.K., Meadows, J.W., Namboodiri, N., and Wild, J.F., 2016, Nevada National Security Site underground radionuclide inventory, 1951–1992—Accounting for radionuclide decay through September 30, 2012: Los Alamos National Laboratory Report LA-UR-16-21749, 53 p., <https://www.osti.gov/biblio/1242909>.
- French, R. H., Jacobson, R.L., and Lyles, B.F., 1996, Threshold precipitation events and potential ground-water recharge: Journal of Hydraulic Engineering, v. 122, no. 10, p. 573–578, [https://doi.org/10.1061/\(ASCE\)0733-9429\(1996\)122:10\(573\)](https://doi.org/10.1061/(ASCE)0733-9429(1996)122:10(573)).
- Frus, R.J., and Halford, K.J., 2018, Documentation of single-well aquifer tests and integrated borehole analyses using transmissivity estimates, Pahute Mesa and vicinity, Nevada: U.S. Geological Survey Scientific Investigations Report 2018–5096, 22 p. [Also available at <https://doi.org/10.3133/sir20185096>.]
- Garcia, C.A., Fenelon, J.M., Halford, K.J., Reiner, S.R., and Lacznia, R.J., 2011, Assessing hydraulic connections across a complex sequence of volcanic rocks—Analysis of U-20 WW multiple-well aquifer test, Pahute Mesa, Nevada National Security Site, Nevada: U.S. Geological Survey Scientific Investigations Report 2011–5173, 24 p. [Also available at <https://doi.org/10.3133/sir20115173>.]
- Garcia, C.A., Halford, K.J., and Lacznia, R.J., 2010, Interpretation of flow logs from Nevada Test Site boreholes to estimate hydraulic conductivity using numerical simulations constrained by single-well aquifer tests: U.S. Geological Survey Scientific Investigations Report 2010–5004, 28 p., <https://doi.org/10.3133/sir20105004>.
- Garcia, C.A., Huntington, J.M., Buto, S.G., Moreo, M.T., Smith, J.L., Andraski, B.J., 2014, Groundwater discharge by evapotranspiration, Dixie Valley, west-central Nevada, March 2009–September 2011: U.S. Geological Survey Professional Paper 1805, 90 p., <https://doi.org/10.3133/pp1805>.
- Garcia, C.A., Jackson, T.R., Halford, K.J., Sweetkind, D.S., Damar, N.A., Fenelon, J.M., and Reiner, S.R., 2017, Hydraulic characterization of volcanic rocks in Pahute Mesa using an integrated analysis of 16 multiple-well aquifer tests, Nevada National Security Site, 2009–14: U.S. Geological Survey Scientific Investigations Report 2016–5151, 62 p., <https://doi.org/10.3133/sir20165151>.
- Gesch, D., Evans, G., Mauck, J., Hutchinson, J., and Carswell Jr., W.J., 2009, The national map—Elevation: U.S. Geological Survey Fact Sheet 2009–3053, 4 p.
- Geter, T., 2015, Amargosa Desert (Hydrographic Basin 14-230) groundwater pumpage inventory—Water year 2015: State of Nevada Department of Conservation and Natural Resources, 126 p.
- Greene, L.W., and Latschar J.A., 1981, Death Valley National Monument historic resource study—A History of Mining: National Park Service, Denver, Colorado: Online book, accessed August 14, 2019, at https://www.nps.gov/parkhistory/online_books/deva/index.htm.
- Halford, K., Garcia, C.A., Fenelon, J., and Mirus, B., 2012, Advanced methods for modeling water-levels and estimating drawdowns with SeriesSEE, an Excel add-In, (ver. 1.1, July 2016): U.S. Geological Survey Techniques and Methods, book 4, chap. F4, 28 p., <https://dx.doi.org/10.3133/tm4F4>.

- Halford, K.J., 2016, T-COMP—A suite of programs for extracting transmissivity from MODFLOW models: U.S. Geological Survey Techniques and Methods, book 6, chap. A54, 17 p., <https://dx.doi.org/10.3133/tm6A54>.
- Halford, K.J., and Plume, R.W., 2011, Potential effects of groundwater pumping on water levels, phreatophytes, and spring discharges in Spring and Snake Valleys, White Pine County, Nevada, and adjacent areas in Nevada and Utah: U.S. Geological Survey Scientific Investigations Report 2011-5032, 52 p., <https://doi.org/10.3133/sir20115032>.
- Halford, K.J., Weight, W.D., and Schreiber, R.P., 2006, Interpretation of transmissivity estimates from single-well pumping aquifer tests: *Groundwater*, v. 44, p. 467–471, <https://doi.org/10.1111/j.1745-6584.2005.00151.x>.
- Halford, K.J., and Yobbi, D.K., 2006, Estimating hydraulic properties using a moving-model approach and multiple aquifer tests: *Groundwater*, v. 44, no. 2, p. 284–291, <https://doi.org/10.1111/j.1745-6584.2005.00109.x>.
- Harbaugh, A.W., 1990, A computer program for calculating subregional water budgets using results from the U.S. Geological Survey modular three-dimensional ground-water flow model: U.S. Geological Survey Open-File Report 90-392, 46 p., <https://doi.org/10.3133/ofr90392>.
- Harbaugh, A.W., 2005, MODFLOW-2005, the U.S. Geological Survey modular ground-water model—The ground-water flow process: U.S. Geological Survey Techniques and Methods, book 6, chap. A16, <https://doi.org/10.3133/tm6A16>.
- Harrill, J.R., 1976, Pumping and ground-water storage depletion in Las Vegas Valley, Nevada, 1955–74: Nevada Division of Water Resources Bulletin 44, 70 p., <http://images.water.nv.gov/images/publications/water%20resources%20bulletins/Bulletin44.pdf>.
- Harrill, J.R., 1986, Ground-water storage depletion in Pahrump Valley, Nevada-California, 1962–75: U.S. Geological Survey Water Supply Paper 2279, 53 p., <https://doi.org/10.3133/wsp2279>.
- Harrill, J.R., Gates, J.S., and Thomas, J.M., 1988, Major ground-water flow systems in the Great Basin region of Nevada, Utah, and adjacent states: U.S. Geological Survey Hydrologic Atlas 694-C, pls. 1–2.
- Heilweil, V.M., and Brooks, L.E., eds., 2011, Conceptual model of the Great Basin carbonate and alluvial aquifer system: U.S. Geological Survey Scientific Investigations Report 2010-5193, 191 p. [Also available at <https://doi.org/10.3133/sir20105193>].
- Hershey, R.L., Paces, J.B., Singleton, M.J., Kwicklis, E.M., Decker, D.L., Fryer, W.M., and Earman, S., 2008, Geochemical and isotopic evaluation of groundwater movement in Corrective Action Unit 99—Rainier Mesa and Shoshone Mountain, Nevada Test Site: U.S. Department of Energy Report DOE/NV/26383-10, Publication No. 45229, 173 p., <https://www.osti.gov/opennet/detail?osti-id=944749>.
- Hsieh, P.A., and Freckleton, J.R., 1993, Documentation of a computer program to simulate horizontal-flow barriers using the U.S. Geological Survey modular three-dimensional finite-difference ground-water flow model: U.S. Geological Survey Open-File Report 92-477, 32 p., <https://doi.org/10.3133/ofr92477>.
- Hunt, C.B., and Robinson, T.W., 1960, Possible interbasin circulation of ground water in the southern part of the Great Basin: U.S. Geological Survey Professional Paper 400-B, p. B273–B274, <https://doi.org/10.3133/pp400B>.
- Hunt, C.B., Robinson, T.W., Bowles, W.A., and Washburn, A.L., 1966, Hydrologic basin, Death Valley, California: U.S. Geological Survey Professional Paper 494-B, 138 p., <https://doi.org/10.3133/pp494B>.
- Interagency Wild and Scenic Rivers Coordinating Council, 2018, National Wild and Scenic Rivers System—Amargosa River, California: National Wild and Scenic Rivers System web page, accessed January 2, 2018, at <http://www.rivers.gov/rivers/amargosa.php>.
- Inyo County Yucca Mountain Repository Assessment Office, 2005, Death Valley lower carbonate aquifer monitoring program—Wells down gradient of the proposed Yucca Mountain nuclear waste repository: U.S. Department of Energy Cooperative Agreement DE-FCO8-02RW12162 Final Project Report, 39 p., <http://www.inyoyucca.org/LSNRroot/documents/iny5.pdf>.
- Inyo County Yucca Mountain Repository Assessment Office, 2007, Inyo County final project report from 2002–2005—Death Valley lower carbonate aquifer monitoring program—Wells down gradient of the proposed Yucca Mountain nuclear waste repository: U.S. Department of Energy Cooperative Agreement DE-FCO8-02RW12162 Final Project Report, 39 p., Nuclear Regulatory Commission Accession Number ML081070545, <http://pbadupws.nrc.gov/docs/ML0810/ML081070525.html>.
- IT Corporation, 1995, Pre-completion hydrologic testing documentation package for well UE-10j: IT Corporation Report prepared for U.S. Department of Energy Nevada Operations Office, 336 p.

- IT Corporation, 1997, Regional groundwater flow and tritium transport modeling and risk assessment of the underground test area, Nevada Test Site, Nevada: Report DOE/NV-477 prepared by the IT Corporation, Las Vegas, Nevada, for the U.S. Department of Energy Nevada Operations Office [variously paged], <https://www.osti.gov/biblio/788792>.
- IT Corporation, 1999, Preliminary water level contours and topographic map of western Pahute Mesa and Oasis Valley: Las Vegas, Nevada, IT Corporation, 1 pl.
- Jackson, T.R., 2017, AQUIFER TEST PACKAGE—Drawdown estimation and analysis of the ER-4-1 m1 multiple-well aquifer test of the lower carbonate aquifer, Yucca Flat, Nevada National Security Site: U.S. Geological Survey, aquifer test package, accessed June 1, 2017, at <https://nevada.usgs.gov/aquifertests/ER-4-1m1.cfm?studyname=ER-4-1m1>.
- Jackson, T.R., and Fenelon, J.M., 2018, Conceptual framework and trend analysis of water-level responses to hydrologic stresses, Pahute Mesa–Oasis Valley groundwater basin, Nevada, 1966–2016: U.S. Geological Survey Scientific Investigations Report 2018-5064, 89 p., <https://doi.org/10.3133/sir20185064>.
- Jackson, T.R., and Halford, K.J. 2019, Estimation of groundwater flow through Yucca Flat based on a multiple-well aquifer test at well *ER-6-1-2 Main*, Nevada National Security Site: U.S. Geological Survey Scientific Investigations Report 2019–5038, 27 p., <https://doi.org/10.3133/sir20195038>.
- Jackson, T.R., and Halford, K.J. 2020, MODFLOW-2005 model and supplementary data used to characterize groundwater flow and effects of pumping in the Death Valley regional groundwater flow system, Nevada and California, with special reference to Devils Hole: U.S. Geological Survey data release, <https://doi.org/10.5066/P9HIYVG2>.
- Jackson, T. R., Halford, K. J., Gardner, P. M., and Garcia, C.A., 2018, Evaluating micrometeorological estimates of groundwater discharge from Great Basin desert playas: *Groundwater*, v. 56, no. 6, p. 909–920, <https://doi.org/10.1111/gwat.12647>.
- Johannesson, K.H., Stetzenbach, K.J., Hodge, V.F., Kreamer, D.K., and Zhou, X., 1997, Delineation of ground-water flow systems in the southern Great Basin using aqueous rare earth element distributions: *Groundwater*, v. 35, p. 807–819, <https://doi.org/10.1111/j.1745-6584.1997.tb00149.x>.
- Kilroy, K.C., 1991, Ground-water conditions in Amargosa Desert, Nevada–California, 1952–87: U.S. Geological Survey Water-Resources Investigations Report 89-4101, 93 p., <https://doi.org/10.3133/wri894101>.
- Konikow, L.F., and Leake, S.A., 2014, Depletion and capture—Revisiting “the source of water derived from wells”: *Groundwater*, v. 52, p. 100–111, <https://doi.org/10.1111/gwat.12204>.
- Kunkel, F., and Robinson, T.W., 1966, A geohydrologic reconnaissance of the Saratoga Spring area, Death Valley National Monument, California: U.S. Geological Survey Open-File Report 66-74, 25 p., <https://doi.org/10.3133/ofr6674>.
- Laczniak, R.J., Cole, J.C., Sawyer, D.A., and Trudeau, D.A., 1996, Summary of hydrogeologic controls on ground-water flow at the Nevada Test Site, Nye County, Nevada: U.S. Geological Survey Water-Resources Investigations Report 96-4109, 59 p., <https://doi.org/10.3133/wri964109>.
- Laczniak, R.J., DeMeo, G.A., Reiner, S.R., Smith, J.L., and Nylund, W.E., 1999, Estimates of ground-water discharge as determined from measurements of evapotranspiration, Ash Meadows Area, Nye County, Nevada: U.S. Geological Survey Water-Resources Investigations Report 99-4079, 70 p., <https://doi.org/10.3133/wri994079>.
- Laczniak, R.J., Smith, J.L., and DeMeo, G.A., 2006, Annual ground-water discharge by evapotranspiration from areas of spring-fed riparian vegetation along the eastern margin of Death Valley, 2000–02: U.S. Geological Survey Scientific Investigations Report 2006-5145, 36 p., <https://doi.org/10.3133/sir20065145>.
- Laczniak, R.J., Smith, J.L., Elliot, P.E., DeMeo, G.A., Chatigny, M.A., and Roemer, G.J., 2001, Ground-water discharge determined from estimates of evapotranspiration, Death Valley regional flow system, Nevada and California: U.S. Geological Survey Water-Resources Investigations Report 2001-4195, 51 p., <https://doi.org/10.3133/wri014195>.
- Larson, J.D., 1974a, Water-resources data collected in the Devils Hole area, Nevada, 1972–73: U.S. Geological Survey Water-Resources Investigations Report 73-61, 20 p. [Also available at <https://doi.org/10.3133/wri7361>.]
- Larson, J.D., 1974b, Water-resources data collected in the Devils Hole area, Nevada, 1973–74: U.S. Geological Survey Open-File Report 74-330, 12 p. [Also available at <https://doi.org/10.3133/ofr74330>.]
- Larson, J.D., 1975, Water-resources data collected in the Devils Hole area, Nevada, 1974–75: U.S. Geological Survey open-file report, 12 p.
- Leake, S.A., Reeves, H.W., and Dickinson, J.E., 2010, A new capture fraction method to map how pumpage affects surface water flow: *Groundwater*, v. 48, p. 690–700, <https://doi.org/10.1111/j.1745-6584.2010.00701.x>.

- Lucas, L.L., and Unterwieser, M.P., 2000, Comprehensive review and critical evaluation of the half-life of tritium: *Journal of Research of the National Institute of Standards and Technology*, v. 105, no. 4, p. 541–549, <https://doi.org/10.6028/jres.105.043>.
- Malmberg, G.T., 1967, Hydrology of the valley-fill and carbonate-rock reservoirs, Pahump Valley, Nevada-California: U.S. Geological Survey Water Supply Paper 1832, 47 p., <https://doi.org/10.3133/wsp1832>.
- Maxey, G.B., and Eakin, T.E., 1951, Ground water in Railroad, Hot Creek, Reveille, Kawich, and Penoyer Valleys, Nye, Lincoln, and White Pine Counties, Nevada, in Eakin, T.E., Maxey, G.B., Robinson, T.W., Fredericks, J.C., and Loeltz, O.J., Contributions to the hydrology of eastern Nevada: Nevada Water Resources Bulletin No. 12, p. 127–171.
- Maxey, G.B., and Jameson, C.H., 1948, Geology and water resources of Las Vegas, Pahump, and Indian Springs Valleys, Clark and Nye Counties, Nevada: Nevada Water Resources Bulletin No. 5, 121 p. plus 2 appendixes, <http://images.water.nv.gov/images/publications/water%20resources%20bulletins/Bulletin5.pdf>.
- Miller, G.A., 1977, Appraisal of the water resources of Death Valley, California–Nevada: U.S. Geological Survey Open-File Report 77–728, 68 p., <https://doi.org/10.3133/ofr77728>.
- Mirus, B.B., Halford, K.J., Sweetkind, D.S., and Fenelon, J.M., 2016, Testing the suitability of geologic frameworks for extrapolating hydraulic properties across regional scales: *Hydrogeology Journal*, v. 24, p. 1133–1146, <https://doi.org/10.1007/s10040-016-1375-1>.
- Mission Support and Test Services, LLC, 2018, Nevada National Security Site—Environmental report 2017: U.S. Department of Energy Report DOE/NV/03624-0270, 264 p., https://www.nnss.gov/docs/docs_LibraryPublications/2017%20NNSER.pdf.
- Moreo, M.T., Halford, K.J., La Camera, R.J., and Lacznia, R.J., 2003, Estimated ground-water withdrawals from the Death Valley regional flow system, Nevada and California, 1913–98: U.S. Geological Survey Water-Resources Investigations Report 2003-4245, 28 p., <https://doi.org/10.3133/wri20034245>.
- Moreo, M.T., and Justet, L., 2008, Update to the ground-water withdrawals database for the Death Valley regional ground-water flow system, Nevada and California, 1913–2003: U.S. Geological Survey Data Series 340, 10 p., <https://pubs.er.usgs.gov/publication/ds340>.
- Moreo, M.T., Lacznia, R.J., and Stannard, D.I., 2007, Evapotranspiration rate estimates of vegetation typical of ground-water discharge areas in the Basin and Range carbonate-rock aquifer system, Nevada and Utah, September 2005–August 2006: U.S. Geological Survey Scientific Investigations Report 2007–5078, 36 p., <https://doi.org/10.3133/sir20075078>.
- Morrison, R.B., 1999, Lake Tecopa—Quaternary geology of Tecopa Valley, California, a multimillion-year record and its relevance to the proposed nuclear waste repository at Yucca Mountain, Nevada, in Wright, L.A., and Troxel, B.W., eds., Cenozoic basins of the Death Valley region: Boulder, Colorado, Geological Society of America Special Paper 333, <https://doi.org/10.1130/0-8137-2333-7.301>.
- Naranjo, R.C., Welborn, T.L., and Rosen, M.R., 2013, The distribution and modeling of nitrate transport in the Carson Valley alluvial aquifer, Douglas County, Nevada: U.S. Geological Survey Scientific Investigations Report 2013-5136, 51 p., <https://doi.org/10.3133/sir20135136>.
- National Climatic Data Center, 2017, 1981–2010 normals data access: National Oceanic and Atmospheric Administration National Climatic Data Center web page, accessed July 2017, at <http://www.ncdc.noaa.gov/data-access/land-based-station-data/land-based-datasets/climate-normals/1981-2010-normals-data>.
- National Security Technologies, LLC, 2007, A hydrostratigraphic model and alternatives for the groundwater flow and contaminant transport model of Corrective Action Unit 99—Rainier Mesa—Shoshone Mountain, Nye County, Nevada: U.S. Department of Energy Report DOE/NV/25946-146, 302 p., <https://www.osti.gov/biblio/934454>.
- Navarro, 2016b, Pahute Mesa well development and testing analyses for Well ER-20-11, Nevada National Security Site, Nye County, Nevada: Navarro Report N/0002653-028-REV. 0, 175 p. [Also available at <https://www.osti.gov/biblio/1464519-pahute-mesa-well-development-testing-analyses-well-er-nevada-national-security-site-nye-county-nevada-revision>.]
- Navarro, 2016a, Response to external peer review team report for Corrective Action Unit 97—Yucca Flat/Climax Mine, Nevada National Security Site, Nye County, Nevada: Navarro Report N/0002653-031-REV. 1, 272 p., <https://www.osti.gov/biblio/1465146>.
- Navarro-Intera, LLC, 2013, Phase I flow and transport model document for Corrective Action Unit 97—Yucca Flat/Climax Mine, Nevada National Security Site, Nye County, Nevada, Rev. 1: Las Vegas, Nevada, Navarro-Intera Report N-I/28091-080, <https://www.osti.gov/scitech/biblio/1094979>.

- Navarro-Intera, LLC, 2015, Evaluation of PM-3 chemistry data and possible interpretations of 3H observations: Navarro-Intera Report N-I/28091-092, 159 p.
- Navarro Nevada Environmental Services, LLC, 2010, Phase II transport model of Corrective Action Unit 98—Frenchman Flat, Nevada Test Site, Nye County, Nevada: Navarro Nevada Environmental Services Report N-I/28091-004, 843 p.
- Nevada Division of Water Resources, 2018, Well log database query tool: Nevada Division of Water Resources web page, accessed January 2018, at <http://water.nv.gov/>.
- Nevada State Engineer, 1979, State Engineer's Order No. 724—Designating and describing the Amargosa Desert ground water basin, Nye County, Nevada: Carson City, Office of the State Engineer of the State of Nevada, 5 p., <http://images.water.nv.gov/images/Orders/724o.pdf>.
- Nevada State Engineer, 2008a, State Engineer's Order No. 1197: Carson City, Office of the State Engineer of the State of Nevada, 2 p., <http://images.water.nv.gov/images/Orders/1197o.pdf>.
- Nevada State Engineer, 2008b, State Engineer's Ruling 5902—In the matter of applications 69836, 69837, 70383, 72012, 72239, 72962, 73862, 74531, 74532, 74533, 74534, and 74535, filed to change the point of diversion, place of use and manner of use of underground water previously appropriated under permit 60437 certificate 14999, permit 63235, permit 17417 certificate 5888, permit 31727 certificate 9318, permit 66057, permit 20352 certificate 5764, permit 66370, application 70383, application 69837, application 69836, permit 67957, and permit 67956, within the Amargosa Desert hydrographic basin (230), Nye County, Nevada: Carson City, Office of the State Engineer of the State of Nevada, 24 p., <http://images.water.nv.gov/images/Rulings/5902r.pdf>.
- Noble, D.C., Anderson, R.E., Ekren, E.B., and O'Connor, J.T., 1964, Thirsty Canyon tuff of Nye and Esmeralda Counties, Nevada, Article 126—Short papers in geology and hydrology: U.S. Geological Survey Professional Paper 475-D, p. 24–27.
- Noble, D.C., Vogel, T.A., Weiss, S.I., Erwin, J.W., McKee, E.H., and Younker, L.W., 1984, Stratigraphic relations and source areas of ash-flow sheets of the Black Mountain and Stonewall Mountain volcanic centers, Nevada: *Journal of Geophysical Research*, v. 89, p. 8593–8602. [Also available at <https://doi.org/10.1029/JB089iB10p08593>.]
- Oatfield, W.J., and Czarnecki, J.B., 1989, Hydrogeologic inferences from drillers' logs and from gravity and resistivity surveys in the Amargosa Desert, southern Nevada: U.S. Geological Survey Open-File Report 89–234, 29 p., <https://doi.org/10.3133/ofr89234>.
- Osterkamp, W.R., Lane, L.J., and Savard, C.S., 1994, Recharge estimates using a geomorphic/distributed-parameter simulation approach, Amargosa River basin: *Water Resources Bulletin*, v. 30, no. 3, p. 493–507, <https://doi.org/10.1111/j.1752-1688.1994.tb03308.x>.
- Pavelko, M.T., 2004, Estimates of hydraulic properties from a one-dimensional numerical model of vertical aquifer-system deformation, Lorenzi site, Las Vegas, Nevada: U.S. Geological Survey Water-Resources Investigations Report 2003-4083, 35 p., <https://doi.org/10.3133/wri034083>.
- Pawloski, G.A., Tompson, A.F.B., and Carle, S.F., 2001, Evaluation of the hydrologic source term from the underground nuclear tests on Pahute Mesa at the Nevada Test Site—The CHESHIRE Test: Lawrence Livermore National Laboratory Report UCRL-ID-147023, 507 p.
- Pistrang, M.A., and Kunkel, F., 1964, A brief geologic and hydrologic reconnaissance of the Furnace Creek Wash area, Death Valley National Monument, California: U.S. Geological Survey Water-Supply Paper 1779–Y, 35 p., <https://doi.org/10.3133/wsp1779Y>.
- Pollock, D.W., 2012, User guide for MODPATH version 6—A particle-tracking model for MODFLOW: U.S. Geological Survey Techniques and Methods, book 6, chap. A41, 58 p., <https://pubs.usgs.gov/tm/6a41/>.
- PRISM Climate Group, 2012, PRISM climate data, 30-year normal, Norm81m data set, created July, 2012: Oregon State University PRISM Climate Group web page, accessed May 2014, at <http://prism.oregonstate.edu>.
- Prothro, L.B., and Drellack, S.L., Jr., 1997, Nature and extent of lava-flow aquifers beneath Pahute Mesa, Nevada Test Site: U.S. Department of Energy Report DOE/NV/11718-156, 50 p., <https://www.osti.gov/biblio/653925>.
- RamaRao, B.S., de Marsily, G., and Marietta, M.G., 1995, Pilot point methodology for automated calibration of an ensemble of conditionally simulated transmissivity fields—I, Theory and computational experiments: *Water Resources Research*, v. 31, no. 3, p. 475–493, <https://doi.org/10.1029/94WR02258>.
- Reiner, S.R., Lacznik, R.J., DeMeo, G.A., Smith, J.L., Elliott, P.E., Nylund, W.E., and Fridrich, C.J., 2002, Ground-water discharge determined from measurements of evapotranspiration, other available hydrologic components, and shallow water-level changes, Oasis Valley, Nye County, Nevada: U.S. Geological Survey Water-Resources Investigations Report 2001-4239, 65 p., <https://doi.org/10.3133/wri014239>.

- Rice, W.A., 1984, Preliminary two-dimensional regional hydrologic model of the Nevada Test Site and vicinity: Albuquerque, New Mexico, Sandia National Laboratories Report SAND83-7466, 89 p., <https://www.nrc.gov/docs/ML0330/ML033070362.pdf>.
- Russell, C.E., 1987, Hydrogeologic investigations of flow in fractured tuffs, Rainier Mesa, Nevada Test Site: Las Vegas, University of Nevada, M.S. thesis, <https://www.nrc.gov/docs/ML0330/ML033010264.pdf>.
- Savard, C.S., 1998, Estimated ground-water recharge from streamflow in Fortymile Wash near Yucca Mountain, Nevada: U.S. Geological Survey Water-Resources Investigations Report 97-4273., 30 p., <https://doi.org/10.3133/wri974273>.
- Sawyer, D.A., Fleck, R.J., Lanphere, M.A., Warren, R.G., Broxton, D.E., and Hudson, M.R., 1994, Episodic caldera volcanism in the Miocene southwestern Nevada volcanic field—Revised stratigraphic framework, $^{40}\text{Ar}/^{39}\text{Ar}$ geochronology, and implications for magmatism and extension: Geological Society of America Bulletin, v. 106, no. 10, p. 1304–1318, [https://doi.org/10.1130/0016-7606\(1994\)106<1304:ECVITM>2.3.CO;2](https://doi.org/10.1130/0016-7606(1994)106<1304:ECVITM>2.3.CO;2).
- Sheets, R.A., Hill, M.C., Haitjema, H.M., Provost, A.M., and Masterson, J.P., 2015, Simulation of water-table aquifers using specified saturated thickness: Groundwater, v. 53, no. 1, p. 151–157, <https://doi.org/10.1111/gwat.12164>.
- Simonds, F.W., 1989, Geology and hydrothermal alteration at the Calico Hills, Nye County, Nevada: Boulder, University of Colorado, unpublished M.S. thesis, 136 p.
- Slate, J.L., Berry, M.E., Rowley, P.D., Fridrich, C.J., Morgan, K.S., Workman, J.B., Young, O.D., Dixon, G.L., Williams, V.S., McKee, E.H., Ponce, D.A., Hildenbrand, T.G., Swadley, W.C., Lundstrom, S.C., Ekren, E.B., Warren, R.G., Cole, J.C., Fleck, R.J., Lanphere, M.A., Sawyer, D.A., Minor, S.A., Grunwald, D.J., Lacznia, R.J., Menges, C.M., Yount, J.C., and Jayko, A.S., 2000, Digital geologic map of the Nevada Test Site and vicinity, Nye, Lincoln, and Clark Counties, Nevada, and Inyo County, California: U.S. Geological Survey Open-File Report 99-554A, 53 p, scale 1:120,000, <https://pubs.usgs.gov/of/1999/ofr-99-0554/>.
- Smith, D.K., 2002, Evaluation of the radiochemistry of near-field water samples at the Nevada Test Site applied to the definition of a hydrologic source term: Lawrence Livermore National Laboratory Report UCRL-ID-149049, 55 p.
- Smith, D.W., Moreo, M.T., Garcia, C.A., Halford, K.J., and Fenelon, J.M., 2017, A process to estimate net infiltration using a site-scale water-budget approach, Rainier Mesa, Nevada National Security Site, Nevada, 2002–05: U.S. Geological Survey Scientific Investigations Report 2017-5078, 22 p., <https://doi.org/10.3133/sir20175078>.
- Smith, J.L., Lacznia, R.J., Moreo, M.T., and Welborn, T.L., 2007, Mapping evapotranspiration units in the Basin and Range carbonate-rock aquifer system, White Pine County, Nevada, and adjacent parts of Nevada and Utah: U.S. Geological Survey Scientific Investigations Report 2007-5087, 20 p., <https://doi.org/10.3133/sir20075087>.
- Stallman, R.W., 1971, Aquifer-test design, observation, and data analysis: U.S. Geological Survey Techniques of Water-Resources Investigations, book 3, chap. B1, 31 p., <https://pubs.usgs.gov/twri/twri3-b1/>.
- Starkey, H.C., and Blackmon, P.D., 1979, Clay mineralogy of Pleistocene Lake Tecopa, Inyo County, California: U.S. Geological Survey Professional Paper 1061, 40 p., <https://doi.org/10.3133/pp1061>.
- Steinkampf, W.C., and Werrell, W.E., 2001, Ground-water flow to Death Valley, as inferred from the chemistry and geohydrology of selected springs in Death Valley National Park, California and Nevada: U.S. Geological Survey Water-Resources Investigations Report 98-4114, 37 p., <https://doi.org/10.3133/wri984114>.
- Stoller-Navarro Joint Venture, 2004a, Phase II hydrologic data for the groundwater flow and contaminant transport model of Corrective Action Unit 98—Frenchman Flat, Nye County, Nevada: Las Vegas, Nevada, Stoller-Navarro Joint Venture Report S-N/99205-032, Rev. 0 [variously paged], <https://www.osti.gov/biblio/840959>.
- Stoller-Navarro Joint Venture, 2004b, Unclassified source term and radionuclide data for the groundwater flow and contaminant transport model of Corrective Action Units 101 and 102, central and western Pahute Mesa, Nye County, Nevada: Las Vegas, Nevada, Stoller-Navarro Joint Venture Report S-N/99205-022, 171 p.
- Stoller-Navarro Joint Venture, 2005a, Analysis of hydraulic responses from the ER-6-1 multiple-well aquifer test, Yucca Flat FY 2004 testing program, Nevada Test Site, Nye County, Nevada: Las Vegas, Nevada, Stoller-Navarro Joint Venture Report S-N/99205-051, 84 p., <https://doi.org/10.2172/840943>.
- Stoller-Navarro Joint Venture, 2005b, Unclassified source term and radionuclide data for Corrective Action Unit 98—Frenchman Flat, Nevada Test Site, Nevada: Las Vegas, Nevada, Stoller-Navarro Joint Venture Report S-N/99205-058, 498 p.
- Stoller-Navarro Joint Venture, 2009, Phase I transport model of Corrective Action Unit 101 and 102—Central and western Pahute Mesa, Nevada Test Site, Nye County, Nevada: Las Vegas, Nevada, Stoller-Navarro Joint Venture Report S-N/99205-111, Rev. 1, 696 p.

- Stonestrom, D.A., Prudic, D.E., Walvoord, M.A., Abraham, J.D., Stewart-Deaker, A.E., Glancy, P.A., Constantz, J., Lacznik, R.J., and Andraski, B.J., 2007, Focused ground-water recharge in the Amargosa Desert basin, chap. E. of Stonestrom, D.A., Constantz, J., Ferre, T.P.A., and Leake, S.A., eds., *Ground-water recharge in the arid and semiarid southwestern United States*: U.S. Geological Survey Professional Paper 1703-E, 136 p., <https://doi.org/10.3133/pp1703E>.
- Sweetkind, D.S., Belcher, W.R., Faunt, C.C., and Potter, C.J., 2010, *Geology and hydrogeology*, chap. B of Belcher, W.R., and Sweetkind, D.S., eds., *Death Valley regional ground-water flow system, Nevada and California—Hydrogeologic framework and transient ground-water flow model*: U.S. Geological Survey Professional Paper 1711, p. 19–94, <https://doi.org/10.3133/pp1711>.
- Sweetkind, D.S., Dickerson, R.P., Blakely, R., and Denning, P.D., 2001, *Interpretive geologic cross sections for the Death Valley regional flow system and surrounding areas, Nevada and California*: U.S. Geological Survey Miscellaneous Field Studies Map MF-2370, 3 pls., 32 p., <http://pubs.usgs.gov/mf/2001/mf-2370/>.
- Taylor, E.M., and Sweetkind, D.S., 2014, *Three-dimensional geologic mapping of the Cenozoic basin fill, Amargosa Desert basin, Nevada and California*: U.S. Geological Survey Scientific Investigations Report 2014–5003, 40 p., 2 appendixes, accessed September 7, 2017, at <http://dx.doi.org/10.3133/sir20145003>.
- Theis, C.V., 1940, The source of water derived from wells—Essential factors controlling the response of an aquifer to development: *Civil Engineering*, v. 10, p. 277–280, <https://water.usgs.gov/ogw/pubs/Theis-1940.pdf>.
- Thomas, J.M., Welch, A.H., and Dettinger, M.D., 1997, *Geochemistry and isotope hydrology of representative aquifers in the Great Basin region of Nevada, Utah, and adjacent States*: U.S. Geological Survey Professional Paper 1409-C, 100 p., <https://pubs.er.usgs.gov/publication/pp1409C>.
- Thomasson Jr., H.G., Olmsted, F.H., and LeRoux, E.F., 1960, *Geology, water resources and usable ground-water storage capacity of part of Solano County, California*: U.S. Geological Survey Water-Supply Paper 1464, 693 p., <https://doi.org/10.3133/wsp1464>.
- U.S. Department of Energy, 2010, *Environmental restoration*: U.S. Department of Energy Fact Sheet DOE/NV-537, Rev. 4, 2 p., accessed September 2013, at http://nnss.gov/docs/fact_sheets/DOENV_537.pdf.
- U.S. Department of Energy, 2015, *United States nuclear tests, July 1945 through September 1992*: U.S. Department of Energy Report DOE/NV-209 REV 16, 129 p. [Also available at https://www.nnss.gov/docs/docs_LibraryPublications/DOE_NV-209_Rev16.pdf.]
- U.S. Department of Energy, 2018, *Rainier Mesa/Shoshone Mountain flow and transport model report—Nevada National Security Site, Nevada, Rev. 1*: U.S. Department of Energy Report DOE/NV-1588, <https://www.osti.gov/biblio/1465819-rainier-mesa-shoshone-mountain-flow-transport-model-report-nevada-national-security-site-nevada-revision>.
- U.S. Environmental Protection Agency, 2017, *National Primary Drinking Water Regulations: Code of Federal Regulations, title 50, part 141*, <https://www.govinfo.gov/content/pkg/CFR-2017-title40-vol25/xml/CFR-2017-title40-vol25-part141.xml>.
- U.S. Geological Survey, 2018b, *Aquifer tests: Carson City, Nevada*, U.S. Geological Survey, Nevada Water Science Center web site, accessed June 2018, at <http://nevada.usgs.gov/water/aquifertests/index.htm>.
- U.S. Geological Survey, 2018a, *USGS National Water Information System—Web Interface*: U.S. Geological Survey National Water Information System database, accessed December 2018, at <https://waterdata.usgs.gov/nwis>.
- Waddell, R.K., 1982, *Two-dimensional, steady-state model of ground-water flow, Nevada Test Site and vicinity, Nevada-California*: U.S. Geological Survey Water-Resources Investigations Report 82-4085, 72 p., 1 pl., <https://doi.org/10.3133/wri824085>.
- Walker, G.E., and Eakin, T.E., 1963, *Geology and ground water of Amargosa Desert, Nevada-California*: Nevada Department of Conservation and Natural Resources, Water Resources—Reconnaissance Series Report 14, 45 p., http://images.water.nv.gov/images/publications/recon%20reports/rpt14-Amargosa_valley.pdf.
- Waring, G.A., 1921, *Ground water in Pahrump, Mesquite, and Ivanpah Valleys, Nevada and California*: U.S. Geological Survey Water-Supply Paper 450-C, p. 51–86., <https://doi.org/10.3133/wsp450C>.
- Wells, S.G., McFadden, L.D., Renault, C.E., and Crowe, B.M., 1990, *Geomorphic assessment of late Quaternary volcanism in the Yucca Mountain area, southern Nevada—Implications for the proposed high-level radioactive waste repository*: *Geology*, v. 18, no. 6, p. 549–553. [Also available at [https://doi.org/10.1130/0091-7613\(1990\)018<0549:GAOLQV>2.3.CO;2](https://doi.org/10.1130/0091-7613(1990)018<0549:GAOLQV>2.3.CO;2).]

- Westenburg, C.L., 1993, Water-resources data for the Devils Hole area, Nye County, Nevada, July 1978–September 1988: U.S. Geological Survey Open-File Report 90-381, 13 p., <https://doi.org/10.3133/ofr90381>.
- Williams, O.R., Albright, J.S., Christensen, P.K., Hansen, W.R., Hughes, J.C., Johns, A.E., McGlothlin, D.J., Pettee, C.W., and Ponce, S.L., 1996, Water rights and Devil's Hole pupfish at Death Valley National Monument, *in* Halvorson W.L. and Davis, G.E. eds., Science and ecosystem management in the national parks: Tucson, University of Arizona Press, p. 161–183.
- Winograd, I.J., and Pearson, F.J., Jr., 1976, Major carbon-14 anomaly in a regional carbonate aquifer—Possible evidence for megascale channeling, south-central Great Basin: *Water Resources Research*, v. 12, p. 1125–1143, <https://doi.org/10.1029/WR012i0006p01125>.
- Winograd, I.J., Riggs, A.C., and Coplen, T.B., 1998, The relative contributions of summer and cool-season precipitation to groundwater recharge, Spring Mountains, Nevada, USA: *Hydrogeology Journal*, v. 6, no. 1, p. 77–93, <https://doi.org/10.1007/s100400050135>.
- Winograd, I.J., and Thordarson, W., 1975, Hydrologic and hydrochemical framework, south-central Great Basin, Nevada-California, with special reference to the Nevada Test Site: U.S. Geological Survey Professional Paper 712-C, p. C1–C126. <https://doi.org/10.3133/pp712C>.
- Western Regional Climate Center, 2016, Recent climate in the West: Western Regional Climate Center web page, accessed May 2016, at <http://www.wrcc.dri.edu/>.
- Wolfsberg, A., Glascoe, L., Lu, G., Olson, A., Lichtner, P., McGraw, M., Cherry, T., and Roemer, G., 2002, TYBO/BENHAM—Model analysis of groundwater flow and radionuclide migration from underground nuclear tests in southwestern Pahute Mesa, Nevada: Los Alamos National Laboratory Report LA-13977, 490 p.
- Yager, R.M., Maurer, D.K., and Mayers, C.J., 2012, Assessing potential effects of changes in water use with a numerical groundwater-flow model of Carson Valley, Douglas County, Nevada, and Alpine County, California: U.S. Geological Survey Scientific Investigations Report 2012–5262, 73 p., <https://doi.org/10.3133/sir20125262>.

Publishing support provided by the U.S. Geological Survey
Science Publishing Network, Tacoma Publishing Service Center

For more information concerning the research in this report, contact the
Director, Nevada Water Science Center
U.S. Geological Survey
2730 N. Deer Run Road
Carson City, Nevada 89701
<https://www.usgs.gov/centers/nv-water>



ERM HAS OVER 140 OFFICES ACROSS THE FOLLOWING
COUNTRIES AND TERRITORIES WORLDWIDE

Argentina	Mozambique
Australia	Netherlands
Belgium	New Zealand
Brazil	Panama
Canada	Peru
China	Poland
Colombia	Portugal
Denmark	Romania
France	Singapore
Germany	South Africa
Hong Kong	South Korea
India	Spain
Indonesia	Switzerland
Ireland	Taiwan
Italy	Thailand
Japan	UAE
Kazakhstan	UK
Kenya	US
Malaysia	Vietnam
Mexico	

ERM's Irvine Office

1920 Main Street
Suite #300
Irvine, CA 92614
T +1 949 623 4700

www.erm.com